

34m
C-74-15
0.2

LS2K
#

TA7
W34m
no.
C-74-15
c.2



MISCELLANEOUS PAPER C-74-15

COST AND FEASIBILITY STUDY; ALTERNATE DESIGNS TO PERMIT USE OF SLIP FORM AND OTHER TECHNIQUES TO MAXIMIZE ECONOMIES, TRUMBULL LAKE DAM, PEQUONNOCK RIVER BASIN, CONNECTICUT


by

J. F. Camellerie, Consulting Engineer
23 Green St., Huntington, New York 11743

August 1974

Final Report

Approved For Public Release; Distribution Unlimited



Prepared for U. S. Army Engineer Division, New England
Waltham, Massachusetts 02154

Published by Concrete Laboratory
U. S. Army Engineer Waterways Experiment Station
P. O. Box 631, Vicksburg, Miss. 39180

LIBRARY BRANCH
TECHNICAL INFORMATION CENTER
US ARMY ENGINEER WATERWAYS EXPERIMENT STATION
VICKSBURG, MISSISSIPPI

REPORT DOCUMENTATION PAGE

READ INSTRUCTIONS
BEFORE COMPLETING FORM

1. REPORT NUMBER Miscellaneous Paper C-74-15		2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) COST AND FEASIBILITY STUDY; ALTERNATE DESIGNS TO PERMIT USE OF SLIP FORM AND OTHER TECHNIQUES TO MAXIMIZE ECONOMIES, TRUMBULL LAKE DAM, PEQUONNOCK RIVER BASIN, CONNECTICUT		5. TYPE OF REPORT & PERIOD COVERED Final report	
7. AUTHOR(s) J. F. Camellerie		6. PERFORMING ORG. REPORT NUMBER	
9. PERFORMING ORGANIZATION NAME AND ADDRESS J. F. Camellerie, Consulting Engineer 23 Green Street Huntington, N. Y. 11743		8. CONTRACT OR GRANT NUMBER(s)	
11. CONTROLLING OFFICE NAME AND ADDRESS U. S. Army Engineer Division, New England 424 Trapelo Road Waltham, Mass. 02154		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) U. S. Army Engineer Waterways Experiment Station P. O. Box 631 Vicksburg, Miss. 39180		12. REPORT DATE August 1974	
		13. NUMBER OF PAGES 509	
		15. SECURITY CLASS. (of this report)	
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE	
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.			
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)			
18. SUPPLEMENTARY NOTES			
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Concrete Slip form techniques Concrete costs Trumbull Lake Dam Dam construction			
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The ten books incorporated in this report were prepared by J. F. Camellerie, P.E., Consulting Engineer, Huntington, New York, under contract to the U. S. Army Engineer Division, New England. The primary purpose in this study was to determine the feasibility of the use of slip form techniques to dam construction; however, the report includes cost studies of other types of conventional dam construction.			

FOREWORD

The ten books incorporated in this report were prepared by J. F. Camellerie, P.E., Consulting Engineer, Huntington, New York, under contract to the U. S. Army Engineer Division, New England. The primary purpose in this study was to determine the feasibility of the use of slip form techniques to dam construction; however, the report includes cost studies of other types of conventional dam construction.

INDEX

BOOK C	Conventional Construction
CA	Appendix: Illustrations and Cost Sheets
R	Rapid Construction Utilizing Slip Form Techniques
RA	Appendix: Illustrations and Calculations
RC	Appendix: Cost Study Sheets
A	Alternate Dam Design
AC1	Appendix: Composite Dam
AC2	Appendix: Massive Head Buttress Dam
AC3	Appendix: Ambursen Dam
AC4	Appendix: Cellular Dam

**COST AND FEASIBILITY STUDY
ALTERNATE DESIGNS TO PERMIT USE
OF SLIP FORM AND OTHER TECHNIQUES
TO MAXIMIZE ECONOMIES**

BOOK C

CONVENTIONAL CONSTRUCTION

BOOK C - CONVENTIONAL CONSTRUCTION

Page C	General Description of Dam Structure
Page C-2	Factors Affecting Construction and Methodology
Page C-18	Construction Costs and Analysis
Page C-29	Comments and Recommendations

Plates, Drawings, and Sketches

- 1 Plates 2-4 through 2-6
- 2 Drawings 209-C-1 through C-3
- 3 Drawings 270-C-2 (Probably should be 209-C-2)
Drawings 290-C-3 (Probably should be 209-C-3)
- 4 Sketches 209-SC-1 and SC-2 (in Book CA)
- 5 Sketches 209-SC-19 through SC-22 (in Book CA)
- 6 Sheets EC-S, EC-1, EC-2, EC-2A, EC-3


GENERAL DESCRIPTION OF DAM


GENERAL DESCRIPTION OF DAM STRUCTURE

Gravity Dam Section - The dam section, both overflow and nonoverflow, will be constructed of concrete materials founded on rock. Length of dam at elevation 280 will be 915 feet between rock abutments. From the right abutment the non-overflow section is 410 feet long followed by a 350-foot overflow section (ungated) and ending with a 155 foot non-overflow section to the left abutment. From elevation 280 the valley depresses on the base line such that the deepest monolith is approximately 150 feet deep. There are 16 monoliths, 10 non-overflow and 6 overflow; they are 60 feet wide between vertical bulkhead joints except monoliths No. 1 and No. 13 are 50 feet wide and monolith No. 16 is 35 feet wide. (SEE PLATES 2-4, 2-5, & 2-6.) All monoliths will have an upstream face sloped at 1/12 and downstream face sloped at 9/12 except monolith No. 2 has a multiple step upstream face of 1/12 to 7.5/12 and monolith No. 14 and No. 15 have a downstream slope of 1/1. An 8' x 6' drainage gallery will be provided within the dam near the heel for all monoliths except monolith No. 1, No. 14, No. 15 and No. 16, and a 14' x 14' water supply gallery 87 feet long will be provided in monoliths No. 6 and No. 7.


Pumping Station - Non-overflow monolith No. 6 will house the pumping station which is 30 feet wide, 52 feet long, (14 feet into gravity section at El. 199 and 31.25 feet into gravity section at elevation 167) and 32 feet high from elevation 167. The exterior portion of the pumping station will terminate over the downstream toe such that it is wholly cradled by the dam section. The exterior portion of the roof will be a formed concrete structure to take the surcharge of ice and snow sliding off the downstream slope of the dam.

Access Gallery - Non-flow monolith No. 7 will provide at station 4-40 a 10' x 10' access gallery from the downstream parking area to the control chamber, water supply and drainage gallery at elevation 167. An entrance gallery is provided at top of dam in monolith No. 2.







SECTION AT STA 5+00




SECTION AT STA 7+40



SECTION AT STA 8+30




TYPICAL DRAIN PROFILE
SCALE 1" = 10'




TYPICAL GROUT CURTAIN PROFILE
SCALE 1" = 10'

NOTE
For sect A-A, see Plate 2-4



SECTION AT STA 6+80



DEPARTMENT OF THE ARMY ENGINEERING DISTRICT CORPS OF ENGINEERS WATER RESOURCES DEVELOPMENT PROJECT TRUMBULL LAKE TYPICAL SECTIONS NO 2 CONNECTICUT JULY 1957	
SCALE 1" = 10'	SHEET

**FACTORS AFFECTING CONSTRUCTION
AND METHODOLOGY**

CLIMATE CONSIDERATIONS

The site of this project is in southwestern Connecticut just 5 miles north of Bridgeport, an area of temperate to cool climate with temperatures ranging from -20 to +100 degrees Fahrenheit with a mean annual temperature of 50°. Freezing temperatures may be expected mid-October to mid-April with a mean temperature of 37 degrees Fahrenheit. The construction season is generally mid-March thru mid-November with a range of 10 to 100 degrees Fahrenheit and a mean temperature of 60 degrees. During the hottest months of July and August the temperature will run 40 to 100 degrees with a mean of about 72 degrees.

Precipitation is uniform throughout the year at a mean of 4 inches per month. The precipitation may go as high as 18 inches per month and it is possible to have a month in which there is no rain at all. Snow cover on the ground may be expected from mid-December to mid-March.

Concrete work performed prior to March 15th and after November 15th will require winter protection.

HYDROLOGICAL CONSIDERATIONS, STREAM DIVERSION AND CONSTRUCTION SEQUENCE

The river basin is subject to flooding which is most likely to occur during the hurricane season. Droughts are frequent with flow of stream down to nothing. Existing stream invert at the dam site is approximately 159 feet.

During construction, provisions must be made for passing the 10-year all-season peak discharge of 1,700 cfs. A two phase scheme is conceived which employes diversion through open or partially completed monoliths and through the flood

control conduit. First phase diversion will utilize an open monolith for passing both normal and floodflows; the second phase will use the flood control conduit for passing normal flows (50 cfs or 3⁺ csm) with excess flows passing over a partially completed monolith.

In this study we select the first river diversion through monolith No. 8, utilizing a channel having a minimum area of 350 square feet below elevation 165.0 and coinciding partially with the permanent channel for the intake structure. For the flow of 1700 cfs this channel will result in an upstream water level of less than 170.0 feet mean sea level. The top of cofferdams was therefore set at 172.0 feet.

The diversion preparations include the construction of a cellular cofferdam just east of monolith No. 7, up and down stream, parallel to the future retaining wall. (SEE DRAWING 270-C-2). The cofferdam will be extended up and downstream towards the west bank of the river.

During this diversion stage, excavation will be completed for monoliths No. 4, 5, 6, 7, and 9 and for the retaining wall. Concrete placement will be started in these structures and expedited in monoliths No. 4, 6, and 7. Monolith 5 will be raised to elevation 162.5 to pass possible flood flows during the second diversion stage together with two diversion conduits in monolith 7. If necessary, the placing of monolith 6 and 7 will be delayed at elevation 174.0 to allow for installation of mechanical equipment directly from above. Monolith No. 9 will be raised to elevation 192.5. During highwater periods concrete placement will shift to the abutment blocks, with emphasis on monoliths 1, 2, and 3. (SEE DRAWING 209-C-3).

In the second stage diversion, the first stage cofferdam will be levelled and the second stage cofferdam will be placed upstream and downstream of blocks 8 to 10. (SEE SKETCHES 209-SC-1 & 2).

The upstream cofferdam will be constructed to elevation 172.0.

Equipment for the pump station and water supply gallery will be installed to allow for further placement of concrete in monoliths 6 and 7.

The water will be ponded to allow higher waterflows to pass through the diversion conduits and over monolith 5. The downstream cofferdam will be constructed to elevation 170.0 for protection from tailwater.

Excavation under monolith No. 8 will be completed and concrete placed to elevation 170.0

Concrete placement will be finished in monoliths 1 to 4 and expedited in monoliths 6 and 7.

Concrete placement will continue in various abutment monoliths on the east bank.

After monoliths 6 and 7 reach elevation 200.0, monolith No. 8 will be raised to elevation 185.0 and held until all monoliths with the exception of monolith No. 5, reach the elevation 207.5.

Monolith 5 will be raised a minimum of 15 ft. behind monolith No. 8. Monolith 8 will be raised 15 ft. behind all other monoliths.

A flume diversion was considered in lieu of cofferdams. It is our opinion that the flume may best be placed on the west bank of the river along the railroad bed and passing through monolith No. 4 or 5. Placing the flume along the east bank would result in a much longer run due to the topography and complications caused by the borrow operations. The railroad bed will facilitate flume construction on the west bank.

Because of the width of the valley upstream of the dam site and the low gradient of the valley floor, the flume will have to run about 3000 feet upstream with a cross section of approximately 45 by 8 feet. A short, low dam, about 200 feet long, will be needed at the upstream end of the flume to provide a settling basin and collection point for the water before it enters the flume. Down stream the flume will have to be extended approximately 2000 feet to protect the work from tail waters in periods

of heavy flow. As an alternate to extending the flume downstream, a cofferdam may be built just downstream of the dam site where the valley is still narrow, thereby protecting the work from tail waters. The construction of the flume downstream of the dam site is probably not acceptable for ecological reasons.

This flume must be cut into rock side hill and/or built up with fill and since sheet piling cannot be driven into rock, in effect one side of the flume will have to be constructed to take full hydrostatic pressure. As an alternate, the flume may be constructed entirely on fill with sides and bottom of waterproof construction.

In the light of the above considerations, we have based this study on cofferdam solutions as shown on drawing No. 209-C-2.

SOIL CONDITIONS AND GEOLOGY

Bed rock consisting of foliated metamorphic rock underlies the dam site out-cropping on the east side of the valley except for the shelf under monoliths Nos. 13, 14 and 15 where a shallow mantle of silt and sand varying in depth from nothing to ten feet covers the rock.

The west side of the valley slopes rather uniformly at 25 to 30 degrees to the horizontal with a mantle of talus deposits approximately 12 feet thick. Rock and gravel spoil from previous construction underlies monolith No. 4 to a depth up to 20 feet.

The valley floor underlying monoliths Nos. 5 through 8 has a sedimentary pervious fill of silty sand, gravel and boulders up to thirty feet deep at the thickest point. The present stream is channelized in this relatively flat valley floor.

Both east and west abutments are heavily foliated with trees and shrubs.

Sand and gravel deposits in layers to forty feet deep, and having characteristics satisfactory for use as concrete aggregate, are to be found in the valley floor approximately

2000 feet upstream of the dam. The location of these deposits is shown on drawing 209-C-1 and is designated as areas "A" and "B". Area "A" is a mix of sand and gravel whereas area "B" is primarily sand. Approximately 750,000 yards of material are available in these two areas with one-third of it above the water table. By controlling the borrow operation, between areas "A" and "B", the mixture of sand and gravel may be kept fairly close to the job requirements of the concrete mix.

These borrow pits as well as areas further upstream may also be used to furnish fill for stream diversion and other work.

ENVIRONMENTAL PROTECTION

Generally speaking, great care will be taken not to disturb area appearance or, when appearance is disturbed, to restore the area to its original appearance, or at least an appearance that is harmonious with the rest of the environs. This includes preservation of flora, fauna and terrain features. In order to accomplish this, no operations will be permitted downstream of the dam site and operations at the abutments will be very restricted. In keeping with this requirement, the tail tower will be erected by helicopter, thereby avoiding the defacement resulting from bringing heavy equipment into this area overland. Actually, this may very well be the most economical method of erection. The head tower, cableway pick-up point and cement air slide head will be placed on the relatively flat and sparsely treed knoll overlooking the west abutment in the area to be developed as a recreational area. (SEE DRAWING 209-C-2).

In order to reduce activity in this area, as well as for reasons of economy, it is planned to quarry and process the aggregates in the valley. The batch plant will also be located in the valley and fed cement via an air slide from the upper access area. Cement, forms, chemicals, equipment, etc., are delivered at this area or as an alternate, may be delivered utilizing the lower access roads. The cableway, as planned in this study, is capable of picking up only from the upper area. It is

possible to bring the head tower track nearer the abutments and increase the arc of travel to pick up from the lower access road, but this will involve some difficulty and expense due to less favorable ground contours.

Prevention of water pollution requires ponding and settling of diverted waters. Drawing 209-C-2, showing the stream diversion, shows a settling basin just south east of the downstream cofferdam. During the second phase, ponding will be effected by the dam itself. Waste water from washing, jetting, curing, etc, must be processed before release into the river.

It is planned that all cement and materials handling equipment is equipped with dust collector systems and that roads and other trafficked areas will be sprinkled or treated as required. The granular soil to be found in the stream bed should not give much trouble in this respect. Costing includes carting away all debris except selected materials which may be buried within the reservoir area as no burning is permitted on site. Chipping of tree trunks and other wood debris is anticipated as an economical method of disposal by recycling.

ACCESS TO SITE

There are only three directions of access to the site:

- a) Improvement and widening of the old railroad road bed connecting with Whitney Avenue from the north (upstream).
- b) Improvement and widening of the old railroad road bed connecting with Church Hill Road to the south (downstream). The railroad bed is continuous but will be severed in half when the west abutment monoliths are constructed.
- c) Construction of the upper access road connecting with Valdemere Avenue to the west of the west abutment, plus a temporary extension to the cableway head tower area.

There is no access from the east. The only approach to the east bank will be across the river by constructing a small bridge.

In this study it is planned to receive shipments mainly from the Valdemere Avenue approach, transferring the materials and equipment via the cableway directly to the dam construction. An air slide carries cement directly to the cement storage bins. Heavy equipment and some shipments and personnel will reach the job site via the lower access road.

An access road is planned connecting the railroad bed road (lower access road) with the batch plant and borrow areas on the east bank (SEE DRAWING 209-C-1 & 2.)

LABOR SUPPLY

This is an area of good labor availability and no problem is anticipated in number and skill of workers required, particularly since it is long range employment. Labor costs in this area run about 5% higher than the national mean and an escalation of 8% per year is assumed. It is anticipated that neither travel pay nor camp facilities will be required.

CONCRETE

For the purposes of this study, it has been determined that the concrete required for this dam is of four types as follows and in following quantities. All concrete will be air entrained:

a) INTERIOR MASS CONCRETE
(all areas except as listed below)

Total Quantity Required:	93,000	CY
Mix Design:		
Portland Cement, Type II	1.40	cwt
Fly Ash	1.10	cwt
Coarse Aggregate 6" Max.	29.32	cwt
Fine Aggregate	8.14	cwt
Water	1.62	cwt
1-1/2" slump		
Air Entrainment		

b) EXTERIOR MASS CONCRETE

(All upstream faces, downstream face of spillway monoliths.)

Total Quantity Required: 26,000 CY

This quantity is based on an average face thickness of 6 feet.

Mix Design:

Portland Cement, Type II	1.83	cwt
Fly Ash	.78	cwt
Coarse Aggregate 6" Max.	29.32	cwt
Fine Aggregate	8.14	cwt
Water	1.62	cwt

c) 3,000 psi Concrete
(pumping station)

Total Quantity Required: 5,000 CY

d) 4,000 psi Concrete
(flood control conduit)

Total Quantity Required: 3,000 CY

Mass concrete will be cooled to 50° F. by means of a 130 ton capacity refrigeration plant which will furnish either flaked ice or chilled water or both as required. Introduction of flaked ice into the mix in lieu of equal weights of water will be sufficient during most of the year. Sprinkling of the aggregates with chilled water will be required June through mid September. Hot weather concreting procedures will also have to be carefully adhered to in the hot summer months to insure placing at temperatures no greater than 50° F.

CONCRETE PRODUCTION

Economy, environment and job control all point to in-situ concrete production on this job. This study is

based on a quarry operation in borrow areas A and B, aggregate processing using portable equipment and batch facilities to provide a rated capacity of 160 yards per hour of concrete. The minimum capacity required by EM 1110-2-2000 is 80 yards per hour based on preventing cold joints in the concrete. It is our judgment that although one 4 yard mixer just meets the above minimum requirement, the higher capacity will give optimum economy in the placing operation. Further, two mixers furnish the necessary safety if one mixer becomes inoperable.

QUARRY OPERATION

The potential aggregate sources are glacio-fluvial deposits which do not require any drilling or blasting.

A geological report indicates that a major part of the deposits will be found below water-table.

It is therefore suggested using a dragline in view of possible wet excavation.

It seems that the hourly demand of the aggregate plant, which is 225 tons or 135 bank cubic yards, can be met with a 2-1/2 cubic yard dragline which could be crawler mounted.

The output of a 2-1/2 cubic yard dragline would be approximately 165 cubic yards per hour, assuming 70% efficiency and 50% optimum working condition.

In order to service the loading equipment and the aggregate plant in an economical way, we suggest using 6 cubic yard rear dump trucks.

The standard 7 cubic yard hopper of the grizzly is sufficient but could be extended to receive approximately 24 cubic yards if needed.

Calculations indicate that the four - 6 cubic yard dump trucks operating on 5 to 6 cycles per hour will satisfy the aggregate plant and the dragline output.

It will be required to build an all-weather gravel surfaced road between the loading area and the discharge point of the trucks. The grade will be in the vicinity of 3 to 4%.

CRUSHING PLANT OPERATION

A preliminary investigation of data available indicates that an aggregate plant with a primary, secondary and tertiary crusher will be required in order to produce aggregate of the desired gradation.

A portable aggregate plant was selected because of its bigger resale value as compared to a stationary plant. With a construction project of this relatively moderate concrete demand this will be an important factor in keeping the cost per yard within limits. The location of the aggregate plant is shown between the aggregate borrow areas and the mix plant at a high enough elevation to remain in the dry. Handling equipment will convey the excavated material to a ramp alongside the primary crushing plant and dump it into a vibrating grizzly feeder to screen out oversize material. The screened stone will be fed into a 2036 jaw crusher to produce the first reduction in size.

A portable conveyor will feed the material to the vibrating screen at the secondary crusher unit for further reduction by a gyratory type crusher. Thence a conveyor will transport the aggregate to a vibrating screen, equipped with a single screw classifier. This unit supplies via conveyor the tertiary crushing plant, which will be operating in closed circuit with the aforementioned vibrating screen.

A conveyor belt will discharge the first aggregate size from the above unit onto a stockpile.

The remainder of the material will be conveyed to two consecutive portable screening plants for further distribution to individual stockpiles according to aggregate sizes. The stockpiled material will occupy an area of approximately 200 feet long by 40 feet wide. A tunnel conveyor, supplied by short belt feeders will run under the whole length of the aggregate stockpile and feed the individual aggregate sizes to the top bins of the mixing plant.

All portable plant units will be installed without running gear on concrete foundations.

BATCH PLANT

Since various mixes are required for this project, we suggest using a selector system with provisions for pre-set automatic batching. Individual scales and hoppers for all materials as well as graphic recording for the amount of material entering each batch will be needed.

We have planned to use two - 4 cubic yard tilting mixers with weigh batchers sized accordingly. The mixers will retain the batch for a total of 2 minutes mixing time plus approximately one minute charging, discharging and contingency for a complete cycle of 3 minutes. This cycle will enable the two - 4 cubic yard mixers to furnish a maximum of 160 cubic yards of concrete per hour.

We envision the batch plant having the following characteristics:

- 1 - One - 270 cy. five aggregate compartment bin with equally divided central cement compartment for cement and fly ash and total aggregate storage of approximately 260 tons (3000 # heap per cubic yard of material). The cement compartment to include high and low level indicator switches with signal lights and pneumatic fill pipe assembly; aggregate compartments to include hi-lo signals only.
- 2 - A motorized distributor assembly on top of the overhead storage bins will distribute the aggregates from the aggregate charging equipment to the various aggregate storage compartments. Bin selector switch mounted in control panel will be utilized to control this operation.
- 3 - One fully automatic cement weigh batcher with weigh hopper and cone discharge gate, controlled by pneumatic ram with solenoid operated air control valve, scale levers and linkage for central dial unit.
- 4 - Four fully automatic aggregate weigh batchers for sand, fine, intermediate and coarse aggregate and one fully automatic cobble batcher for 6" material, all air operated and tied into a central recording unit.

- 5- One fully automatic water batcher with weighing and recording equipment.
- 6- Fully automatic air entraining and water reducing agent admixture dispensers tied in with the water batcher and equipped with weighing and recording units.
- 7- In order to control all batchers collectively and individually, a control panel is required with indicating lights, automatic batch and discharge buttons and a discharge sequence timer for discharging materials in any desired sequence.
- 8- Charging the two - 4 cubic yard mixers will be done by means of a two-way air operated mixer charging chute.
- 9- One central electric motor control panel to service miscellaneous motors layed out for 440 V, 3 phase 60 hz. and including a 110 V transformer.
- 10- The refrigeration equipment will include two compressors with three ice machines and ice handling equipment such as ice screws, elevator, daily use tank, weigh batcher and controls to record the amount of ice entering each batch.
- 11- Dust control equipment for the batching plant should include two dust collectors for the cement tank and mixers and a batcher vent.
- 12- Two silos will provide storage for cement and flyash at 300 tons and 230 tons respectively. Both units will include a pumping system for reclaiming the material to the center compartments of the overhead bind and a dust collecting system.

CONCRETE PLACEMENT

A radial cableway seems to be the most economical method of concrete placement for this site. The cableway selected has a 6 cy capacity with a 3 minute cycle or an hourly placing rate of 120 cy. Effective placing time during an

8 hour shift will be 6 hours or 720 cy per shift, (see sketch 209-C-3) which means that overtime placing at 120 yards per hour will be required on a few of the larger blocks.

The fixed tower of the cableway will be installed on the east bank; the movable tower, which is the head tower and includes the hoisting machinery will operate on the west abutment. The concrete or bucket transfer point is projected into the area at monolith 13 on the east abutment, this point being approximately 120 feet from the mixing plant at elevation 245.0 ± .

The concrete placing sequence envisioned in this study will be as shown on drawing 290-C-3. Phase I, performed during the first stream diversion will take 62 days to complete with a placement of 51,000 yards of concrete. Phase II, which will be performed after the stream is diverted through the flood control conduits, will take 123 days and involve the placement of 74,500 yards of concrete. Four months must be allowed between phases to allow for cofferdam levelling and installation of additional cofferdams and sheet piling.

Pour scheduling allows for a slow start since considerable time is spent on rock cleanup and building or adjusting foundation forms. Between lifts, time will be required for concrete cleanup, moving and setting forms, installation of embedded items, etc.

The full capacity of the concrete placing system will only come into play after a major number of monoliths have reached the cantilever form stage.

Placements shown are based on seven and one-half foot lifts with concrete demand as shown on sketches 209-SC-13 thru 18. This sequence results in a plant utilization factor of 42 percent obtained by dividing average concrete placement per hour by rated batch plant capacity of 160 yards per hour. 425,650 square feet of horizontal joints and 51,600 square feet of transverse vertical joints will be required.

FORMING SYSTEM

The form system included in this study is the normal cantilever type form universally used in dam construction for 7'-6" lifts and including a hinged section on the downstream side to facilitate concrete placement from buckets, as shown on sketch 209-SC-19. The forms are brought to the monolith via the cableway or a crawler crane operating on the valley floor and handled in place from lift to lift by a small hydraulic boom crane. The types of formwork required are as follows:

- Foundation Forms
- Lift Starter Forms
- Cantilever Forms
- Monolith Bulkhead Forms
- Gallery Forms
- Wall and Slab Forms (Power station and top slab)
- Stair Forms.

SEE SKETCH 209-SC-20 for FORM REQUIREMENTS in each category.

The first concrete lift placed on the rock surface will utilize built-in-place forms which are anchored to and braced against the bedrock.

Lift starter forms will be used until the concrete is raised high enough to provide anchorage space for the legs at the cantilever forms.

Inverted cantilever forms may be used for this phase of construction with the bolts installed at the top of each started form lift to serve as anchors for the legs of the first regular cantilever forms. SEE DRAWING 209-C-3 for disposition of foundation and lift starter forms.

Cantilever forms and inverted cantilever forms may serve as bulkheads. When cantilever forms are used in the normal position, a 15-foot differential elevation will be required in order to allow for cantilever anchorage clearance.


CONSTRUCTION SCHEDULE

It is anticipated that the contract for this work will be let by October 1st, 1972 and that procurement and stripping will actually start at this time. Procurement can be continued over the winter in order to start plant erection in the Spring. As much stripping as possible must be done in the fall of 1972 in order to finish up in April of 1973, with a lay-off in the winter. This will allow start of diversion work and plant erection on April 1st of 1973. SEE CONSTRUCTION SCHEDULE Sketch 209-SC-21 showing items on critical path only. Concreting is started in late 1973 and completion in 1974. It is suggested that the winter of 1974-1975 be allowed the contractor for demobilization, cleanup, testing, environmental work and contingency time. Because of the tightness of this schedule, the penalty clause should not be effective earlier than April 1st, 1975. This is admittedly a very tight schedule but it is entirely feasible. If work cannot start by October 1st of this year, in effect a full construction season will be added to the construction schedule as shown on Sketch 209-SC-22 with an escalation cost of 6 to 7 percent to the entire project.

Because of design considerations, extraordinary care must be taken in executing the foundation grouting. This will require progressive grouting from one abutment to the other or from a central point towards the abutments. This parameter has not actually been integrated into the construction sequence shown, but it is felt that with little change in sequencing this requirement may be met without change in over-all time or construction cost.


NUMBER DESIGNATIONS

- 1 RADIAL CABLEWAY
- 2 COFFERDAM
- 3 CEMENT AIR SLIDE
- 4 CONCRETE BATCH PLANT
- 5 CEMENT BINS
- 6 AGGREGATE STOCK PILES
- 7 AGGREGATE CRUSHERS AND SCREENS
- 8 ACCESS ROADS
- 9 BORROW AREA A
- 10 BORROW AREA B



GENERAL PLAN OF DAM SITE

SCALE 1" = 200'




UPSTREAM ELEVATION


SCALE




DEPARTMENT OF THE ARMY ENGINEERING CENTER WASHINGTON, D. C. 20315	
WATER RESOURCE DEVELOPMENT PROJECT TRUSSVILLE LAKE PEQUONNOK RIVER BASIN, CONNECTICUT	
GENERAL SITE PLAN AND ELEVATION LAYOUT	
DATE: _____ DRAWN BY: _____ CHECKED BY: _____ APPROVED BY: _____	SCALE: _____ SHEET NO.: _____ TOTAL SHEETS: _____
209-C-1	



J.F. CAMELLERE, P.E. CONSULTING ENGINEER <small>100 WEST 17th ST. NEW YORK, N.Y.</small>		DEPARTMENT OF THE ARMY <small>100 HULLYARD DRIVE</small> CORPS OF ENGINEERS <small>WATER RESOURCES DIVISION</small>	
WATER RESOURCES DEVELOPMENT PROJECT TRUMBULL LAKE REDUCTION OF RIVER BASIN CONNECTICUT			
CONSTRUCTION SITE LAYOUT			
209-C-2		1957	



LAYOUT OF FOUNDATION & STARTER FORMS
DOWNSTREAM ELEVATION



NOTE:
TOTAL NUMBER OF LIFTS REQUIRED
IN PHASE II = 120

CONCRETE PLACEMENT SEQUENCE
DOWNSTREAM ELEVATION



PROJECT TITLE WATER RESOURCES DEVELOPMENT PROJECT TRUMBULL LAKE PERFORMANCE RIVER BASIN CONNECTICUT	
CONSTRUCTION SEQUENCE PHASE I FIRST DIVERSION	
SHEET NO. 202-C-3	SHEET 1 OF 1

CONSTRUCTION COSTS
AND ANALYSIS

ESTIMATED COSTS

It is estimated that with construction starting by October 1st, 1972 the cost of the concrete dam will be slightly over seven million dollars as shown on Cost Sheets EC-1 thru EC-4. The direct costs are distributed as follows:

Cementitious Materials	\$ 347,000	9.9%
Plant & Plant Operation	1,699,608	48.8%
Cooling	100,600	2.9%
Concrete Placing & Vib.	134,634	3.8%
Joint Treatment, Finish., and Curing	207,364	6.0%
Forms	535,658	15.4%
Miscellaneous Inserts	460,418	13.2%
<hr/>		
TOTAL DIRECT COSTS	3,485,282	100.0%

Additional cost for environmental control is estimated at \$280,000 including reasonable water turbidity, dust and noise control and landscape renewal. This is 8% of the direct costs. Sitework and field overhead are estimated at \$2,310,000 or 67 percent of direct cost.

To these costs have been added escalation for the period during which purchasing and construction will be in progress and appropriate percentages for general overhead, profit, contingency and bid bond.

The methods and materials used are in conformity with current Corps of Engineers specifications without modification and the costs were carefully arrived at by appropriate analysis based on quotations, rentals, crew studies, salvage values and cost experience. Labor rates, benefits, insurances, taxes and attitudes were all given full consideration. The methods used are methods in common use in the industry, utilizing cableway transport and cantilever forming raised by mechanized equipment. The production anticipated is consistent with a well organized aggressively managed operation free of unusual delays due to labor, environment enthusiasts, climatic problems or material shortages. Normal delays, costs and inefficiencies have been included in the estimated cost.

J.F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

DATE JUN 1, 1972
REVISED APRIL 1, 1974

SHEET NO. EC-1

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGLAND DIV. CORPS/ENGR.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
ITEM 04 DAM						
CLEARING & GRUBBING	360,000	S.F.	.05	18,000	-	SUB
DISPOSAL	250,000	S.F.	.03	7,500	-	SUB
EXCAV., UNCLASS	36,000	CY	2.00	72,000	-	SUB
EXCAV., ROCK	10,000	CY	10.	100,000	-	SUB
EXCAV., TALUS	14,000	CY	3.00	42,000	-	SUB
HAND CLEANING	70,000	S.F.	.75	52,500	-	SUB
CULVERT PIPE	-	L.F.	4.50	-	1.50	----
CHAIN LINK FENCE	850	L.F.	3.50	3,000	2.00	1,700
FOUNDATION GROUTING	50,000	S.F.	.90	45,000	-	----
DIVERSION STAGE I	-	L.S.	-	547,000	-	SUB
DIVERSION STAGE II	-	L.S.	-	167,000	-	SUB
CEMENT	10,755	TONS	27.20	292,000	-	----
FLY ASH	6,115	TONS	9.00	55,000	-	----
BORROW OPERATION	240,000	TONS	.30	72,000	.29	69,500
AGGREGATE PRODUCTION	231,000	TONS	.53	128,000	.34	78,500
BATCH PLANT OPER	127,000	C.Y.	3.44	437,360	1.75	222,300
CABLEWAY OPER	127,000	C.Y.	2.00	254,000	.61	77,470
CONCRETE PLACING	127,000	C.Y.	.06	8,000	.52	66,000
VIBRATION	127,000	C.Y.	.35	44,400	.41	52,100
HOR JOINT TREATMENT	425,650	S.F.	.05	22,000	.15	63,850
FINISHING	146,000	S.F.	.05	7,300	.28	41,000
CURING	430,800	S.F.	.01	4,310	.01	4,310
FORMS: FDN.	18,300	CA	.80	14,640	3.00	55,000
LIFT STARTERS	12,830	CA	.55	7,100	1.17	15,000
CANTILEVER	107,270	CA	.55	59,800	1.17	125,600
BULKHEAD	51,600	CA	.55	28,400	1.17	60,400
STAIRS	1,300	CA	.30	390	1.25	1,625
SPRAY WALL	800	CA	.30	240	1.50	1,200
SLAB (P.H.)	2,470	CA	.75	1,850	1.00	2,470
SLAB (TOP)	2,350	CA	.25	590	.75	1,760
WALLS (P.H.)	7,080	CA	.75	5,310	2.00	14,160
DAM (TOP)	12,400	CA	.25	3,100	1.50	18,600
RET. WALLS	7,450	CA	.25	1,860	1.00	7,450
CURBS	3,300	CA	.50	1,650	1.50	4,950
GALLERY	16,500	CA	.65	10,720	1.75	28,875
				2,514,020		1,013,820

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUN 1, 1972 REV.

SKETCH# EC 1

TRUMBUELL LAKE DAM

NEW ENGLAND DIVISION CORPS OF ENGINEERS

HYDRAULIC PACKAGE

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Estimated Amount</u>
Gate Valves 16" Manual	2	Ea	\$1,000	2,000.00
Gate Valves 16" Automatic	4	Ea	1,600	6,400.00
Gate Valves 24" Manual	4	Ea	3,600	14,400.00
Gate Valves 24" Automatic	4	Ea	4,800	19,200.00
Gate Valves 36" Automatic	1	Ea	6,700	6,700.00
Water Supply Pipe 16"	225	LF	18.00	4,050.00
Water Supply Pipe 24"	200	LF	26.00	5,200.00
Water Supply Pipe 36"	600	LF	48.00	28,800.00
Blow Off Pipe 36"	90	LF	50.00	4,500.00
Double 3' x 4' Gates	1	Job	LS	70,000.00
Intake Screen, 24"	4	Ea	2,000.00	8,800.00
Bulkhead Gate	1	Ea	5,000.00	5,000.00
Gate Vent System	1	Job	LS	5,000.00
Float Well & Accessories	1	Job	LS	3,000.00
Heating & Vent. System	1	Job	LS	5,000.00
Crane & Hoist	1	Job	LS	7,140.00
Diesel Engine	1	Job	LS	10,000.00
Sump Pumps	1	Job	LS	5,000.00
Electric Systems	1	Job	LS	30,000.00
Grounding System	1	Job	LS	4,000.00
Tile Gage	1	Job	LS	4,000.00
Log Boom	1	Job	LS	10,000.00
Water Quality Control	1	Job	LS	3,300.00
Instrumentation	1	Job	LS	15,000.00
Downstream Measuring Weir	1	Job	LS	10,000.00
TOTAL COST - 1971				286,490.00
ESCALATION to 1972 @ 6%				17,189.40
COST IN 1972				303,679.40

LABOR RATES

The labor rates used for making this study are as follows and include fringe benefits but not payroll taxes and insurance.

Carpenters	\$ 9.00
Bricklayers	8.90
Ironworker	10.20
Crusher Operator	7.75
Crane Operator	8.60
Oiler	6.85
Cableway Operator	8.10
Conveyor Operator	7.75
Mechanics	7.90
Rescreen Operator	7.75
Maintenance Engineer	7.90
Air Tool Operator	6.85
Laborer	5.60

SALVAGE RATES

Salvage rates used are as follows:

Mobile Aggregate Plant	75%
Mixing Plant	33%
Cementveyor	40%
Cableway	50%
High Pressure Hoses	50%
Dragline	60%
Trucks	40%
Concrete Buckets	33%

These salvage values are based on brand new equipment and represent reasonable values in an active industry. Doubts on the part of the contractors and others concerned as to the future availability or profitability of this type of work will result in lower salvage estimates or none at all. In this respect, mobile equipment and equipment of universal use will fare best. Appropriate monies have been incorporated for proper maintenance of the equipment during its use.

The difficulty of reducing crew sizes below certain minimums, and in fact reducing crew sizes at all, has been given full consideration in this study as regards smaller placements.

FINANCING COSTS

No provision was made for the cost of financing to the contractor. The burden of financing equipment, materials and subcontracts usually falls upon the shoulders of the vendors and the prices used include this consideration. Payroll costs are, of course, the burden of the contractor and he may well consider these costs in the face of the prospect of payment delays and retentions.

76952

COST ESCALATION

Escalation assumes a continued inflation on a decelerated rate, therefore percent cost increases have not been projected mathematically but have been tempered by our best judgement based on present attitudes and economic indicators. The escalation used is actually as follows:

Labor	1973.....	8%
	1974.....	6%
	1975.....	4%
Materials	1973.....	8%
	1974.....	4%
	1975.....	4%

In making calculations the labor was assumed to be divided equally between 1973 and 1974 so that:

1/2 of labor in 1973 @ 8% escalation	4%
1/2 of labor in 1974 @ 8% plus 6% escalation	7%
<hr/>	
<u>TOTAL ESCALATION FOR LABOR.....</u>	<u>11%</u>

Materials and subcontracts are made earlier and are subject to less escalation:

3/4 of purchases in 1972 @ no escalation	0%
1/4 of purchases in 1973 @ 8% escalation	2%
<hr/>	
TOTAL ESCALATION FOR MATERIALS	2%

It is interesting to note if the contract is not let until 1973 the escalation may be as follows:

30% of labor in 1973 @ 8% escalation	2.4%
50% of labor in 1974 @ 8 + 6%	7.0%
20% of labor in 1975 @ 8 + 6 + 4%	3.6%

13.0%

1/2 of purchases in 1973 @ 8%	4.0%
1/2 of purchases in 1974 @ 8% + 4%	6.0%

10.0%

This represents an additional cost of:

2% of \$2,000,000	\$40,000
8% of \$4,000,000	320,000

\$ 360,000 or 6%

CONCLUSION

It is our opinion that this is a very realistic cost estimate and makes an excellent base for comparison with any other construction innovations that may require analysis as to actual savings that may be achieved.

COMMENTS AND RECOMMENDATIONS

COMPRESSED SCHEDULES AND CONSTRUCTION ORIENTED DESIGN

It is obvious that compressed construction schedules will result in significant savings in the areas of overhead costs, funding, environmental control, field inspection, accounting and inflationary escalation. This is, therefore, a prime area for reasarch in order to cut construction costs. Construction oriented design cannot be over-estimated in this regard; in-house construction experts or outside consultants must be used early in the design process. The designer cannot wait for contractor input; this comes too late. Those designs which minimize foundation work and volume of material handled offer maximum promise.

EARLIER CONTRACT AWARDS

As long as we are in an inflationary era, early start of construction will be as important as compressed schedules. With costs escalating at one-half percent per month or so, design must be implemented as aggressively as the construction. Phased contracts are desirable in this respect. Contract awards should not be delayed unless the risks considerably out-weigh the cost of monthly escalation.

FINANCING COSTS

The cost of financing the work eventually falls on the Owner. Since the Owner can generally finance work at several percent less than the contractor, it is advisable to make mobilization payments, avoid unnecessary delays in payments and keep retention to a minimum.

CONTINGENCY

It almost always pays the Owner to take as much of the contingency as possible. When the contractor takes the contingency, the Owner pays all of it whether it ever develops or not. When the Owner takes the contingency, he pays only for those unexpected costs that do arise.

STREAM DIVERSION

The incorporation of stream diversion into and through the dam by extending and gating the overflow conduit will save considerable money in diversion work and should be made part of this design.

CONSTRUCTION ECONOMY STUDIES

It is interesting to note that the highest percentage of direct cost is in the area of plant. Assuming that the plant is efficiently designed to the construction requirements of a particular dam construction, the cost is pretty well a function of volume and offers little promise for savings induced by technological changes in the plant itself. Considerable savings may, however, be achieved by making the concrete demand as nearly equal on a daily basis as possible. The desirability of equal concrete placements offers maximum incentive for study to reduce construction costs.

For this dam, cementitious materials comprise 10 percent of direct cost. The cost here may be reduced by either reducing cement content, substituting more flyash, using less concrete volume, or a combination of all.

Formwork constitutes a significant percentage of the direct costs and offers a good target for study.

It is interesting to note that placing and vibration combined comprise less than four percent of the direct cost and offer little promise for savings.

COST AND FEASIBILITY STUDY
ALTERNATE DESIGNS TO PERMIT USE
OF SLIP FORM AND OTHER TECHNIQUES
TO MAXIMIZE ECONOMIES

BOOK CA

CONVENTIONAL CONSTRUCTION

APPENDIX: ILLUSTRATION AND COST SHEETS

BOOK CA - CONVENTIONAL CONSTRUCTION

APPENDIX: ILLUSTRATION AND COST SHEETS

Page CA-2 Illustration

Page CA-25 Cost Study Sheets

1 Sketches 209-SC-1 through SC-22

2 Sketches EC-S1 through S38

ILLUSTRATIONS


J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

LATE JUNE 1, 1972 REV.

SKETCH# 209-SC-1

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.
STREAM DIVERSION, STAGE-I



STAGE - 1

LAYOUT OF CELLULAR COFFER DAM

J. F. CAMELLERIE, P.E.
25 GREEN STREET
HUNTINGTON, N. Y.


DATE JUNE 1, 1972 REV.

SKETCH # 209-SC-2

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN

STREAM DIVERSION, STAGE II



STAGE - II

LAYOUT OF CELLULAR COFFER DAM

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUN. 1, 1972 REV.

SKETCH # 209-50

TRUMBULL LAKE DAM

REGUONNOCK RIVER BASIN, CONN

CABLEWAY CYCLE STUDY

ASSUME CENTER OF MASS ~ 500 FT FROM PICKUP HOIST
160 " BELOW " VER

CABLEWAY-BUCKET CYCLE

LOAD BUCKET 30 SEC
HOIST CLEAR OF DOCK 10 "

HORIZ. TRAVEL

ACCELERATE ~100' 10 SEC
TRAVEL ~300' 12 "
RETARD ~100' 10 "

32 "

VERT. TRAVEL

ACCELERATE ~30' 10 SEC
LOWER ~110' 17 "
RETARD ~30' 10 "

37 "

VERTICAL TRAVEL CONTROLS: 37 "
SPOT & DUMP BUCKET. 40 " 30
RETURN TO DOCK 37 "
LAND BUCKET 15 "

169 SEC
2 MIN 49 SEC
SAY 3 MIN.

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1/72 REV. APR 11/72 SKETCH # 209-SC-4

TRUMBULL LAKE DAM

REGUONNOCK RIVER BASIN, CONN.

CONC. OPERATION STUDY

IT IS ASSUMED THAT THE CABLEWAY AVAILABILITY WILL BE 75%.

START-UP PRODUCTION WILL BE REDUCED TO ALLOW FOR GETTING OFF THE ROCK.

PRODUCTION WILL ALSO BE REDUCED AT THE END OF THE JOB TO ALLOW FOR SMALL POURS IN THE TOP OF THE DAM.

THE MIXING PLANT CAPACITY FOR A CABLEWAY WITH A POURING RATE OF 120 CY PER HR. SHOULD BE APPROX. $1.5 \times 120 \text{ CY} = 180 \text{ CY/HR}$.

FOR A 3 MIN. MIX CYCLE $180/20 = 9 \text{ CY}$. USE 2-4 CY MIXERS.


MIN. CAPACITY OF CONC. MIXERS REQUIRED IN ACCORDANCE WITH EM 1110-2-2000:

MAX. SIZE OF PLACEMENT = 4 CY

AVERAGE LIFT = 18"

MONOLITH WIDTH = 60'

MAX. TIME BETWEEN PLACEMENTS : 2 HRS



40 PLACEMENTS REQ.
FOR COMPLETE
2 HR CYCLE

PLACEMENT PROFILE

PLACEMENT AREA = $108 \text{ CF}/1.5 = 72 \text{ SF} = 8.5 \times 8.5$

$60/8.5 = 7^+$ PLACEMENTS ACROSS. SAY 8 PLACEMENTS.

TOTAL NO OF PLACEMENTS = $8 \times 5 = 40$ EA ACROSS 60 FT

MIN. CONC. REQUIRED PER HR = $\frac{40 \times 4}{2} = 80 \text{ Yd/HR}$

MIXER CYCLE:

CHARGING	20 SEC
MIXING	120 "
DISCHARGE	15 "
CONTINGENCY	15 "
TOTAL	<u>170 SEC</u>

NO OF BATCHES MIXED PER HR. = $3600/170 = 21$

MIXER CAPACITY REQ. = $80/21 = 3.8 \text{ cy}$.

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1/72 REV.

SKETCH# 209-SC-5

TRUMBULL LAKE DAM

PERQUONNOC K RIVER BASIN, CONN.

CONC. OPERATION STUDY

ASSUME AVERAGE MIXER OUTPUT OF 120 CY/HR
REQUIRED CEMENT & FLYASH SUPPLY /HR

C.: $120 \text{ CY} \times 192'' = 23,000'' = 6166\text{L} = 11,5 \text{ TONS}$

F.A.: $120 \text{ CY} \times 79'' = 9500'' = 33'' = 4,75''$

ASSUME 6 HR PRODUCTION PER DAY OR SHIFT.

REQUIRED SUPPLY / DAY

CEMENT: $11,5 \text{ TONS} \times 6 = 69,0 \text{ TONS}$

FLYASH: $4,75'' \times 6 = 28,5''$

MIX FOR INT. CONCRETE PER CY.

P.C.		192''		
F.A.		79''		
FINE AGG. #4-	29%	940''	5,64 CF	64,5 TONS/HR
3/4" - #4	17,8%	674''	4,06 "	39,5 "
1/2" - 3/4"	17,8%	674''	4,00 "	39,5 "
6" - 1/2"	35,6%	1348''	8,00 "	79,0 "
	100%	4078''	21,70 CF	222,5 TONS/HR

REQ. AGGREGATE PRODUCTION PER HR.

$120 \text{ CY} \times 1,85 \text{ TONS} = 222 \text{ TONS/HR}$

$127,000 \text{ yd Conc.} \times 1,85 \text{ TONS.} = 231,000 \text{ Tons Total}$

PLUS COFFER DAM ETC 9,000

240,000 Tons Prod.

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1/72 REV.

SKETCH# 209-SC-6

TRUMBULL LAKE DAM
PEQUONNOK RIVER BASIN, CONN
QUARRY OPERATION STUDY

AGGREGATE PLANT PRODUCTION: 225 TONS/HR OR
150 CY LOOSE

LOOSE CY = 1.5 TONS/CY
BANK CY = 1.7 " "

AGGREGATE PLANT DEMAND PER MINUTE = $\frac{225}{60} = 3.75$ TONS

LOOSE CY REQ. = $\frac{3.75}{1.5} = 2.5$ CY

BANK CY REQ. = $\frac{3.75}{1.7} = 2.2$ CY

2 1/2 CY DRAGLINE OUTPUT = 195 cy

ASSUME 50% OF OPTIMUM OUTPUT WHICH IS A
FACTOR OF 0.85

ACTUAL OUTPUT = 165 cy

TRUCK CYCLE

WAIT	0.5 MIN
LOAD	3.0 "
PULL OUT	0.25 "
HAUL	
2000 FT 5% UP	2.00 "
WAIT	0.5 "
DUMP	1.0 "
PULL OUT	0.25 "
RETURN	1.5 "
<u>TOTAL</u>	<u>9.0 MIN</u>

NO OF CYCLES IN 50 MIN = $\frac{50}{9} = 5.5$

5.5 x 7 BANK YARDS/TRUCK = 38.5 cy

4 TRUCKS WILL DELIVER $4 \times 38.5 \text{ cy} = 154 \text{ cy/HR}$

(7150 cy)


J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1/72 REV.

SKETCH# 209-SC-7

TRUMBULL LAKE DAM
REGUONNOCK RIVER BASIN, CONY.
AGGREGATE OPERATION

PROPOSED PORTABLE
AGGREGATE PLANT



J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE

REV.

SKETCH# 289-SC

TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CON
CONC. PLACEMENT STUDY

THICKNESS OF CONC. LAYERS FOR A 2 HR
CAPACITY OF 160 CY & 240 CY

(4 CY)

(6 CY)

LIFT #	$Y = \frac{\text{AREA}^{\text{SF}}}{27}$	$\frac{160 \text{ YD/HR}}{Y \text{ YD/FT}}$	$\frac{240 \text{ YD/HR}}{Y \text{ YD/FT}}$
1	256 yd/ft	0,63 FT/HR	0,94 FT/HR
2	242	0,66	1,00
3	228	0,70	1,05
4	214	0,75	1,12
5	200	0,80	1,20
6	186	0,86	1,30
7	172	0,93	1,40
8	158	1,03	1,57
9	145	1,10	1,65
10	131	1,22	1,83

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE: JUNE 11, 1972 REV. 07/11/72 SKETCH# 209-5C-10

TRUMBULL LAKE DAM

REGUONNOCK RIVER BASIN, CONN.

COST STUDY

PRODUCTION TIME AND QUANTITIES

STAGE	TOTAL CY	AVERAGE CY DAILY POUR	DAYS	MONTHS
1	52,500	850	62	3.1
2	74,500	600	123	6.2
TOTAL	<u>127,000</u>		<u>185</u>	<u>9.3</u>

AVERAGE PRODUCTION PER SHIFT = 577 CY *

" " " WEEK 3,430 cy

" " " MONTH = 13,700 cy

" " " HOUR = 72 cy

" " " " = 96 cy **

* TOTAL NO OF SHIFTS = 185 + 35 OT SHIFTS
= 220 SHIFTS TOTAL

** BASED ON 6 HRS ACTIVE PLACEMENT PER SHIFT.

PRODUCTION PER "PAY SHIFT" FOR COST BASIS @ 220 SHIFTS
+ 17 SHIFTS (35/2 FOR OTIME PAY)
237 SHIFTS

$$\frac{127,000}{237} = 536 \text{ YDS } \left\{ \begin{array}{l} \text{EXTRA PAY} \\ \text{FOR SHIFT} \\ \text{WORK} \end{array} \right.$$

$$\frac{127,000}{220} = 577 \text{ YDS (NO PREMIUM PAY)}$$

USE 550 YDS/SHIFT

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.


DATE JUN 1, 1972 REV.

SKETCH # 209-SC-11

TRUMBULL LAKE DAM

PERQUONNOC RIVER BASIN, CONN.

CONCRETE VOLUMES



$\frac{1}{12} = \frac{d}{120}$
 $d = 10'-0"$

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.


DATE JUN 1, 1972 REV.

SKETCH # 209-8

TRUMBULL LAKE DAM

PEQUONNOC RIVER BASIN, CONN.

CONCRETE VOLUMES



VOLUME A = VOLUME OF CENTER STRIP OF LIFT
VOLUME B = VOLUME OF LIFT.

2.22

LIFT	LENGTH	HT	X	Y	(X+Y)/2	VOLUME A C.Y.	VOLUME B C.Y.		
16	60'	7.5'	15.0	21.25	18.13	40.3	302		
15			21.25	27.50	24.38	54.2	406		
14			27.50	33.75	30.63	68.2	512		
13			33.75	40.00	36.88	82.	615		
12			40.00	46.25	43.13	95.7	718		
11			46.25	52.50	49.38	109.8	823		
10			52.50	58.75	55.63	125.	937		
9			58.75	65.00	61.88	137.5	1032		
8			65.00	71.25	68.13	152.	1140		
7			71.25	77.50	74.38	165	1238		
6			77.50	83.75	80.63	179.	1340		
5			83.75	90.00	86.88	193.	1440		
4			90.00	96.25	93.13	207.	1550		
3			96.25	102.50	99.38	221.	1660		
2			102.50	108.75	105.63	234.	1755		
1	60'	7.5'	108.75	115.0	111.88	248.	1860		

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 11 1972 REV.

SKETCH # SC-13

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, COIN.

CONV. CONSTRUCTION

CONCRETE DEMAND SCHEDULE				
MONTH-				
WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE $\frac{Yds}{HR}$	REMARKS
1	1	250	40	BASE LIFT
2	2	115	20	"
3x2 SHIFTS	3	540	45	"
4x2	4	650	55	"
5x2	5	730	60	"
6	6	350	60	"
7	7 8	385	75	"
		60		
8x2	9	1080	90	"
9x3	10	1860	105	
10x2	11	1000	85	
11x2	12	900	75	

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1, 1972 REV.

SKETCH 90-17

TRUMBULL LAKE DAM

DEQUONNOCK RIVER BASIN, CONN.

CONV. CONSTRUCTION

CONCRETE DEMAND SCHEDULE

MONTH -

WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE ^{Yds} / _{HR}	REMARKS
12	13	615	105	
13	14	615	105	
14	15	175	30	
15 x 2	16	1180	100	
16 x 3	17	1670	95	
17 x 3	18	1875	105	
18 x 2	19	1120	95	
19	20	900	120	
20	21	700	115	
21 x 2	22	1440	115	
22 x 3	23	1650	95	

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11 1972 REV.

SKETCH # SC-15

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

CONV. CONSTRUCTION

CONCRETE DEMAND SCHEDULE

MONTH-

WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE $\frac{Yds}{HR}$	REMARKS
23 x 3	24	1710	95	
24 x 2	25	1350	115	
25 +	26	900	120	
26	27	600	100	
27 x 2	28	1490	120	
28	29	440	75	BASE
29 x 3	30	1760	100	
30 x 2	31	1220	105	
31	32	340	60	
32	33	795	120	
33 x 2	34	960	80	

CA-17-

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11 1972 REV.

SKETCH# SC-16

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

CONV. CONSTRUCTION

CONCRETE DEMAND SCHEDULE

MONTH-

WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE $\frac{Yds}{HR}$	REMARKS
34	35	485	80	
35	36	660	110	
36 x 2	37	1500	115	
37	38	700	120	
38 x 2	39	1220	105	
39 x 2	40	1340	115	
40	41	690	115	
41 +	42	940	120	
42	43	380	65	
43	44	300	50	
44 x 2	45	1300	110	

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11 1972 REV.

SKETCH # SC-17

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

CONV. CONSTRUCTION

CONCRETE DEMAND SCHEDULE				
MONTH -				
WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE ^{Yds} / _{HR}	REMARKS
45	46	600	100	
46 x 2	47	1180	100	
47 x 2	48	1140	95	
48 x 2	49	1040	90	
49	50	615	105	
50	51	280	50	
51	52	285	50	
52 x 2	53	1180	100	
53	54	350	60	
54 x 2	55	1130	95	
55	56	185	30	


J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 11 1972 REV. SKETCH # 00-10
 TRUMBULL LAKE DAM
 PEQUONNOCK RIVER BASIN, CONN.
 CONV. CONSTRUCTION

CONCRETE DEMAND SCHEDULE				
MONTH -				
WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE ^{Yds} / _{HR}	REMARKS
56 x 2	57	1020	85	
57	58	205	35	
58	59	65	11	BASE
59	60	90	15	"
60	61	320	55	"
61	62	104	20	"
62	63	135	25	
63 TO 185	TOTAL 123	74,500	75 AV.	
	(185 + 35 O'TIME SHIFTS	21.5 TIME =	237 pay days)	
TOTAL PLACEMENT:		125,389 CY		
CONCRETE PER DAY:		680 CY AVERAGE		
CONCRETE PER PAY DAY:		530 CY AVERAGE		
PLANT UTILIZATION:		530 / 1280	= 42 %	

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM,
PEQUONNOCK RIVER BASIN, CONN.
STEEL FORMS.



TYPICAL STEEL CANTILEVER FORM
FOR UPSTREAM FACE

J. F. CAMELLERIE, P.E.

23 GREEN STREET

HUNTINGTON, N. Y.

DATE JUNE 11/77 REV. APR. 11/74 SKETCH# 204-36-60

TBUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

FORM COST STUDY

FORM AREAS

	TOTAL AREAS	REQ.	FORM MATERIAL
<u>FOUNDATION</u>			
UPSTREAM FACE	5,562 SF	1,800	SF
DOWNSTREAM FACE	6,221 "	2,200	"
BULKHEAD	6,500 "	2,500	"
TOTAL	18,283 SF	6,500	SF
<u>STARTER FORMS</u>			
UPSTREAM	6,430 SF	1,400	SF
DOWNSTREAM	6,400 "	1,400	"
TOTAL	12,830 SF	2,800	SF
<u>GALLERY & OTHER</u>	16,500 SF	3,000	SF
<u>INT. FORMS</u>			
<u>PUMP STATION FORMS</u>	9,550 SF	5,000	SF
<u>WATER GALLERY FORMS</u>	2,200 SF	1,500	SF
<u>CANTILEVER FORMS</u>	107,270 SF	4,800	SF
10 SETS REQ.			
10' x 60' x 8'			
<u>BULKHEAD FORMS</u>	51,600 SF	6,720	SF
7 SETS REQ.			
7' x 120' x 8'			
<u>CREST FORMS</u>			
2 SETS REQ.	18,100 SF	5,200	SF
2600 x 2			
<u>RETAINING WALL</u>	7,450 SF	2,500	SF

CONSTRUCTION SCHEDULE - DELAYED CONSTRUCTION START

J. F. CAVELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE: JULY 1, 1972, REV. APRIL 1, 1974 SKETCH # 107 - S.C. 515
TRUMBULL LAKE DAM
PERUONNOCK RIVER BASIN CONN.
CONSTRUCTION SCHEDULE - DELAYED CONST. START

MONTH YEAR	JAN.	FEB.	MAR.	APR.	MAY	JUNE	JULY	AUG.	SEPT.	OCT.	NOV.	DEC.
1973	PROCUREMENT								CONC. PHASE I			
		STRIPPING			PLANT ERECTION							
			DIVERSION - STAGE I									
1974			CONC. PHASE I		DIVERSION - STAGE II							
							CONCRETE - PHASE II					
1975						C. D. & E.*						
			CONC. PHASE II									

* CLEAN-UP, DEMOBILIZATION & ENVIRONMENT
CONTRACTURAL COMPLETION DATE SEP 15, 1975

Revised

COST STUDY SHEETS

J. F. CAMELLERIE, P.E.
 23, GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 17 1972 REV.

SKETCH # EC - S1

TRUMBULL LAKE DAM

REQUONNOCK RIVER BASIN, CONN.

CONCRETE ESTIMATE

	CY	CEMENT	FLYASH
INT. CONC	93000	$\times 1.40 = 130,000$ CWT $\div 376 = 34,500$ bbl	$\times 1.10 = 102,000$ CWT $\div 286 = 35,600$ bbl
EXT	26000	$\times 1.83 = 47,500$ CWT $\div 376 = 12,600$ bbl	$\times .78 = 20,300$ CWT $\div 286 = 7,100$ bbl
3000 PSI 4000 PSI	8000	$\times 4.70 = 37,600$ CWT $\times 1.25$ bbl = <u>10,000</u> bbl	
		57,100 bbl	42,700 bbl
		215,100 CWT	122,300 CWT
		57100 42700	
		<u>TOTAL 99,800 bbl</u>	

$215,100 / 20 = 10,755$ TONS (CEMENT)

$122,300 / 20 = 6,115$ TONS (FLYASH)

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
DEQUENNOCK RIVER BASIN, CONT
AGGREGATE OPERATION

QUARRY OPERATION 1600 TONS / SHIFT

COST PER SHIFT		LABOR	SUPPLIES	TOTAL
1 FOREMAN		8 ⁶⁰ 76.00	-	76.00
1 DRAGLINE OPERATOR		68.80	-	68.80
1 OILER		55.20	25.00	80.20
1 SPOTTER		44.80	-	44.80
TOTAL / SHIFT		244.80	25.00	269.80

TOTAL / TON				.17
MISC. TOOLS ETC.			15.00	.01

AGGREGATE HAUL

4 TRUCK DRIVERS	169.50		169.50
TOTAL / TON			.11

<u>EQUIPMENT</u>	EQUIPM.	SALVAGE	NET
1 2 1/2 CY DRAGLINE	100.000	60.000	40.000
4 6 CY REAR DUMP TRUCKS	52.000	20.000	32.000
			72.000

RENTAL \$ 4000/MO x $\frac{240,000}{22 \times 1600}$ = 27,500

\$ 3,200/MO x " = $\frac{22,000}{49,500}$ + MOBILIZ & APPL TIME

SAY 10 Mos x 7,200 = $\frac{72,000}{}$ USE

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1/72 REV.

SKETCH # EC-

TRUMBULL LAKE DAM

REQUONNOCK RIVER BASIN, CONN.

COST STUDY - DIRECT COST

231

OPERATION OF AGGREGATE PLANT

COST PER SHIFT (1580 TONS/SHIFT)

	LABOR	SUPPLIES	TOTAL
1 FOREMAN	9 ⁵⁰ 76 ⁵⁰	—	76.00
1 PR. GRUSHER OPERATOR	7 ⁸⁰ 62 ⁵⁰	—	62.50
1 OPER. FOR OTHER CRUSHERS	7 ⁸⁰ 62 ⁵⁰	—	62.50
1 OILER	6 ⁷⁵ 54 ⁰⁰	—	54.00
1 WELDER	10 ²⁰ 81 ⁶⁰	—	81.60
1 MECHANIC	7 ⁸⁰ 62 ⁵⁰	—	62.50
1 CRANE OPER.	—	—	—
1 OILER	—	—	—
1 CONV. OPERATOR	8 ⁵⁵ 64 ⁰⁰	—	64.00
POWER / HR	—	10.00	10.00
REPAIR PARTS	—	60.00	60.00
OIL, GREASE & MISC.	—	10.00	10.00
TOTAL COST/SHIFT			543.10
① COST / TON			.34
② COST / CY (① x 1.9)			.64

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 11/72 REV. SKETCH# EC-34
TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN
COST STUDY-DIRECT COST

MIX PLANT CHARGING RESCREENING , CEMENT HANDLING & CONCRETE MIXING

MASS CONCRETE PLACEMENT WILL BE DONE 1 SHIFT PER DAY TOTALING 231 DAYS & SHIFTS. DURING THIS PERIOD APPROX. 127000 CY OF CONCRETE WILL BE POURED. AVERAGE PRODUCTION PER SHIFT = 550 CY

COST PER SHIFT

	LABOR	SUPPLIES	TOTAL
1 SUPER OR FOREMAN	9 ⁵⁰ 76.00	—	76.00
1 PLANT OPERATOR	7 ⁵⁰ 62.50	—	62.50
1 RESCREEN OPER.	7 ²⁵ 62.00	—	62.00
1 ASSIST RESCREEN OPER	7 ²⁵ 62.00	—	62.00
1 CONC. DISPATCHER	5 ⁶⁰ 44.80	—	44.80
1 LABORER	5 ⁵⁰ 44.80	—	44.80
2 MAINTENANCE LAB.	6 ⁸⁰ 109.00	—	109.00
POWER	—	10.00	10.00
REPAIR PARTS \$ 25,000	—	150.00	150.00
OIL , SUPPLIES	—	30.00	30.00
TOTAL COST PER SHIFT			651.10
TOTAL COST PER CY			1.18

CEMENT LOSS & ADMIXTURE COST

CEMENT LOSS 1.5% OF COST/CY .02

1.20 /cy

23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CO
COST STUDY-DIRECT COST

350 cy / SHIFT

CONCRETE COOLING
COST PER SHIFT

	LABOR	SUPPLIES	TOTAL
1 OPERATOR OF REFRIG. EQUIPMENT	⁷⁸⁰ 62.50	—	62.50
1 MAINTENANCE LABOR	⁶⁸⁰ 54.50	—	54.50
POWER, WATER	—	30.00	30.00
REPAIR PARTS	—	30.00	30.00
MISC.	—	25.00	25.00
TOTAL COST PER SHIFT			202.00
COST PER CY			<u>.36</u>

CONC. HAUL
COST PER SHIFT

1 BELT OPERATOR	⁷⁸⁰ 62.50	—	62.50
1 MAINT. LABOR	—	—	—
POWER	—	2.00	2.00
REPAIR PARTS	—	10.00	10.00
MISC.	—	5.00	5.00
TOTAL COST PER SHIFT			79.50
COST PER CY			<u>.15</u>

TOTAL BATCH OPERATION = 1.20
.36
.15

1.71/cy. YP. say 1.71

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE QUOTE 11/12 REV.

SKETCH# EC-36

TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CONN.
COST STUDY - PLANT & EQUIPMENT

CONCRETE

	LABOR	EQUIP- MENT	SALVAGE	NET
<u>QUARRY & HAUL TO AGGREGATE PLANT COST / CY</u>	SHEET EC-52	SHEET EC-52		
<u>CONC. DELIVERY</u>				
1 CONVEYOR ON A-FRAME COST / CY	SHEET EC-53	INCL. IN AGG. PLANT		
<u>MIXING PLANT</u>				
CONTAINING 175 CY AGGREGATE STORAGE, 2-4CY MIXERS, ICE PLANT, 2 CEM. SILOS & RECLAIMING SYSTEM, DUST CONTROL INSTALLATION + MISC.		432,000	150,000	282,000
<u>CEMENT HANDLING</u>				110,000
CEMENT VEYOR INSTALLATION		60,360	25,000	35,360
				<u>10,000</u>
				437,360
<u>AGGREGATE PLANT INSTALLATION INCL. EXCAV. & GRADING</u>				10,000
GRIZZLY & PRIMARY CRUSHER.		490,000	380,000	110,000
SCREEN & SECONDARY GYRASHERE CRUSHER.				
SCREEN & TERTIARY GYRASHERE IN CLOSED CIRCUIT.				

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1/72 REV.

SKETCH# EC-57

TRUMBULL LAKE DAM
 PEQUONNICK RIVER BASIN, CONN.
 COST STUDY - PLANT & EQUIPMENT

CONC. CONT.

	LABOR	EQUIP- MENT	SALVAGE	NET
2 RINSING SCREENS				
1 CLASSIFIER				
5 STOCKPILES WITH TUNNEL RECLAIM- CONVEYOR				
WATER DISTRIB. ELECTRIC SYSTEM	3000.00	5000.00		8000.00
TOTAL				128.000
COST PER CY				1.01
COST PER TON				.53

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 11, 1972 REV.

SKETCH # EC-58

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CORP.

COST STUDY - DIRECT COST

CABLE WAY OPERATION
COST PER SHIFT

THE CABLEWAY WILL HANDLE APPROX 127,000 CY OF CONCRETE

CABLE REPLACEMENTS

	LABOR	SUPPLIES	TOTAL
HOISTING LINE	---	---	---
	NOT	REQUIRED	

CABLEWAY OPERATION

1 OPERATOR	⁸⁶⁰ 68.80	---	68.80
1 OILER	⁶²⁰ 55.20	---	55.20
1 RIGGER	⁶⁹⁵ 63.20	---	63.20
1 BELLBOY	44.80	---	44.80
1 MAINTENANCE ENG.	⁷⁹⁰ 63.20	---	63.20
POWER	---	10.00	10.00
REPAIR PARTS & SUPPLIES	---	30.00	30.00
TOTAL PER SHIFT			335.20
COST PER CY.			<u>.61</u>

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1/72 REV. _____ SKETCH # EC-59
TRUMBULL LAKE DAM
REGUONACK RIVER BASIN, CONN.
COST STUDY - PLANT & EQUIPMENT

CABLEWAY

<u>FACILITY PURCHASE</u>	LABOR	EQUIP- MENT	SALVAGE	NET
6 CY CABLEWAY		395.000	200.000	195.000
CABLES	—	—	—	INCL. REV.
<u>INSTALLATION</u>				
EXCAV. & GRADING	—	—	—	15,000
TIES & RAILS	—	—	—	5,000
COUNTERWEIGHT CONC. 170 CY	—	—	—	8,000
ELECTRICAL	—	—	—	5,000
MISC. (AIR LIFT ETC.)	—	—	—	25,000
TOTAL				263,000
TOTAL / CY				\$ 2.00

CONCRETE PLACEMENT

2- 6 CY BUCKETS	—	12,000	4,000	8,000 ^①
AIR & WATER CUTTING	—	20,000	10,000	10,000 ^②
FINISHERS	—	3,000	—	3,000 ^③
TOTAL				21,000
TOTAL / CY				\$ 0,17

① IN PLACING .06 / CY
 ② IN HOR ST. .08 / CY
 ③ IN FINISHING .03 / CY + .02 TIE HOLES = .05

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 11/72 REV.

SKETCH# EC-510

TRUMBULL LAKE DAM

REGUONNOCK RIVER BASIN, CONN.

COST STUDY - DIRECT COST

PLACEMENT CREW (COST PER SHIFT)

	LABOR	SUPPLIES	TOTAL
1 FOREMAN	6 ^{hr} 48.80	—	48.80
4 LABORERS	179.20	—	179.20
1 BUCKET DUMPER	44.80	—	44.80
MISC. SUPPLIES	—	25.00	25.00
1 CARPENTER (CHARGED TO FORMS)	—	—	—
TOTAL			297.80
COST PER CY			<u>.55</u>
4 VIBRATOR MEN	179.20	—	179.20
VIBRATORS PER SHIFT	—	55.00	55.00
TOTAL			234.20
COST PER CY			<u>.42</u>

SEE SHEET EC-511

23 GREEN STREET
HUNTINGTON, N. Y.

PEQUONNOKT RIVER BASIN, CONN.
COST STUDY - DIRECT COST.

CONCRETE PLACING

PICK-UP POINT
SPREADING
FOREMAN

1 MAN
4 MEN
1 MAN

6 MEN @ 5.60 = 36.60
+ .50 Foreman = .50
\$ 37.10
per hour

Cost per DAY = 37.10 x 8 = 296.10/day

CONCRETE PLACED PER DAY = $\frac{127,000}{222} = 575$ yds

COST PER YD. = $\frac{296.10}{575} = .52$ ¢

CONCRETE VIBRATION

4 MEN @ 5.60 = \$ 22.40 /hr

COMP. OPER @ 7.40 = 7.40 /hr

\$ 29.80 x 8 = 238.00

VIBRATORS (4 INCL 2 SPARES) 50.00

COMPRESSOR (ADD'L) 150.00

\$ 438.00

Cost Per YD = $\frac{438.00}{575} = .76$ (.41 + .35)

FINISHING

2 MEN @ 8.87 = 17.74

1 HELPER @ 7.15 = 7.15

Foreman .50 = .50

\$ 25.39/hr = \$ 204/day

Cost Per SqFT = $\frac{204.00}{7.5 \times 120} = .225$ ¢

23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CONN.
COST STUDY - DIRECT COST

CLEANUP & CURE
COST PER SHIFT

	LABOR	SUPPLIES	TOTAL
1 FOREMAN	⁷³⁵ 58.80	—	58.80
2 AIR-TOOL OPERATORS	⁶²⁵ 109.60	—	109.60
2 LABORERS	89.90	—	89.90
PARTS & SUPPLIES	—	30.00	30.00
TOTAL COST / SHIFT			288.30
COST / CY			.52 (.17/ft')
AIR TOOLS / CY			.05 (.02/ft')
			.08 (.03/ft')
FROM SHEET EC-59			
<u>WEEKEND SHIFT (FOR 45 WEEKENDS)</u>			

2 LABORERS	90 DAYS		
COST / CY			
SATURDAY x 12			6,050.00
SUNDAY x 2			8,060.00
			14,110.00
COST / CY			.11

PATCH & FINISH
COST PER SHIFT

1 FOREMAN (WORKING)	⁸⁷⁵ 70.00	—	70.00
1 FINISHER	⁸²⁵ 66.00	—	66.00
1 LABORER	44.80	—	44.80
SUPPLIES		30.00	30.00
COST / SHIFT			210.80
COST / CY			.38 (.33L .05M)

COST PER 50 FT = $.38 \times \frac{127,000}{146,000} = .33$ Sheet EC-511
 $\frac{.23}{.56/2} = .28$ AV.

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE 00/00/12 REV.

SKETCH NO. 010

TRUMBULL LAKE DAM
DEQUONNOCK RIVER BASIN, CONN.
COST-STUDY, PLANT & EQUIPMENT

UTILITIES & SERVICE FACILITIES

SHOPS & BLDG'S.

	<u>ESTIM. NET COST</u>
SHOP	12,000
ELEC. SHOP	5,000
PIPE & RIGGING SHOP	5,000
TIRE SHOP	2,000
FORM DECK	2,000
TOOL SHEDS	3,000
WATER, SANITATION	3,000
MISC.	5,000
GRADING	5,000
	\$ 42,000

INCL IN FIELD OHD

SERVICE EQUIPMENT & FACILITIES

1-90TON CRAWLER	90,000	F/O
2 FORKLIFTS	24,000	F/O
1 GRADER	10,000	F/O
2 PICKUPS	8,000	F/O
2 AIR COMPRESSORS	25,000	F/O
ELEC. SUBSTATION	15,000	CORPS
POWER DISTRIBUTION, LIGHT	20,000	F/O
AIR DISTRIB. & WATER	30,000	SHEET-EC-S9
WELDING MACHINES	1,500	F/O
COMMUNICATION SYSTEM	10,000	F/O
	\$ 233,500	

DEWATERING

PUMPS	\$ 10,000	F/O
-------	-----------	-----

TOTAL \$ 285,500

J. F. CAMELLEKIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CONN.
HORIZONTAL JOINTS

AREA OF MONOLITH SURFACES.

1.	115' x 93'	= 10700	S.F.
2.	108.5' x 162'	= 17560	S.F.
3.	102.5' x 216'	= 22200	"
4.	96.25' x 245'	= 23470	"
5.	90' x 300'	= 27000	"
6.	83.75' x 354'	= 29600	"
7.	77.5' x 460'	= 35600	"
8.	71.25' x 480'	= 34200	"
9.	65' x 515'	= 33500	"
10.	58.75' x 535'	= 31500	"
11.	52.5' x 565'	= 29650	"
12.	46.25' x 605'	= 28000	"
13.	40' x 632'	= 25280	"
14.	33.75' x 648'	= 21800	"
15.	27.5' x 726'	= 20000	"
16.	21.25' x 746'	= 15500	"
17.	15' x 794'	= 11900	"
18.	405' x 10'	= 4050	"
19.	414' x 10'	= 4140	"

TOTAL - 425650 S.F.

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1, 1973 REV.

SKETCH# EC-S/5

TRUMPULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

EXCAVATION - COST STUDY

HAND CLEANED BED ROCK SURFACE.

1.	300'-0" x 60'-0"	=	18,000 S.F.
2.	230'-0" x 42'-0"	=	9,660 S.F.
3.	60'-0" x 50'-0"	=	3,000 S.F.
4.	106'-0" x 110'-0"	=	11,660 S.F.
5.	40'-0" x 10'-0"	=	400 S.F.
6.	155'-0" x 18'-0"	=	2,790 S.F.

45510 S.F.

10% EXTRA FOR SLOPE

4551 S.F.

TOTAL AREA 50061 S.F.

ADDITIONAL HAND CLEANING -

420'-0" x 50'-0" = 21,000

TOTAL AREA - 71,061 S.F.

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1, 1972^{REV.}

SKETCH# EC-510

TRUMBULL LAKE DAM,

PEQUONNOCK RIVER BASIN, CO.

EXCAVATION-COST STUDY

LIMIT OF CLEARING SURFACE -

- | | | |
|----|---------------------|---------------|
| 1. | 230'-0" x 112'-0" | = 25400 S.F. |
| 2. | 235'-0" x 53'-0" | = 12500 S.F. |
| 3. | 27'-0" x 115'-0" | = 3105 S.F. |
| 4. | 355'-0" x 350'-0" | = 124500 S.F. |
| | 10% EXTRA FOR SLOPE | = 12450 S.F. |
| 5. | 300'-0" x 320'-0" | = 96000 S.F. |
| 6. | 210'-0" x 300'-0" | = 63000 S.F. |
| | 5% EXTRA FOR SLOPE | = 3150 |
| 7. | 135'-0" x 100'-0" | <u>13500</u> |

TOTAL AREA = 353605 S.F.

J. F. CAMELERIE, P.E.

23 CAYEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 11/72 REV. APR. 11/74 SKETCH # EC-5 17

TRUMBULL LAKE DAM

DEQUONNOCK RIVER BASIN, CONN.

FORM COST STUDY

FORM AREAS

	TOTAL AREAS	REQ. FORM MATERIAL
<u>FOUNDATION</u>		
UPSTREAM FACE	5,562 SF	1,800 SF
DOWNSTREAM FACE	6,221 "	2,200 "
BULKHEAD	6,500 "	2,500 "
TOTAL	18,283 SF	6,500 SF
<u>STARTER FORMS</u>		
UPSTREAM	6,430 SF	1,400 SF
DOWNSTREAM ~	6,400 "	1,400 "
TOTAL	12,830 SF	2,800 SF
<u>GALLERY & OTHER</u>	16,500 SF	3,000 SF
<u>HNT. FORMS</u>		
<u>PUMP STATION FORMS</u>	9,550 SF	5,000 SF
<u>WATER GALLERY FORMS</u>	2,200 SF	1,500 SF
<u>CANTILEVER FORMS</u>	107,270 SF	4,800 SF
10 SETS REQ. 10' x 60' x 8'		
<u>BULKHEAD FORMS</u>	51,600 SF	6,720 SF
7 SETS REQ. 7' x 120' x 8'		
<u>CREST FORMS</u>		
2 SETS REQ 2600 x 2	18,100 SF	5,200 SF
<u>RETAINING WALL</u>	7,450 SF	2,500 SF

Revised

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1st 1972 REV.

SKETCH# EC-5/8

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONN.

FORM COST.

UPSTREAM FACE FORMS (FOUND. FORMS)

POUR	LENGTH (F)	HEIGHT (F)	AREA (S.F.)
1. a)	9	6	54
b)	7	6.67	46.69
c)	13	7.5	97.5
d)	6	7.5	45
e)	10	7.5	75
f)	7	7.5	52.5
g)	6	7	42
2. a)	10	7.5	75
b)	10	7.5	75
c)	16	7.5	120
d)	14	5	70
3. a)	30	7	210
b)	11	7.5	82.5
c)	15	7.5	112.5
d)	5	5	25
4. a)	10	7.5	75
b)	10	7.5	75
c)	12	7.5	90
d)	10	7.5	75
e)	12	7.5	90
5. a)	30	7.5	225
	11	7	77
			1880.69

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1, '72 REV.

SKETCH# EC-5

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CO

FORM COST

UPSTREAM FACE FORMS (FOUND. FORMS)

POUR	LENGTH (F)	HEIGHT (F)	AREA (S.F.)
			B.F. 1889.69
6	60	6	360
7 a)	10	7.5	75
b)	30	7.5	225
c)	12	7.5	90
8 a)	10	7.5	75
b)	20	7.5	150
c)	15	6	90
9. a)	30	6	180
b)	19	6	114
10.	60	3	180
11 a)	10	7.5	75
b)	11	7.5	82.5
c)	40	7.5	300
12. a)	40	6	240
b)	6	7.5	45
c)	12	7.5	90
d)	7	7.5	52.5
e)	12	7.5	90
f)	8	7.5	60
g)	5	3.	15
13. a)	20	7.5	150

4628.69

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1st '72 REV.

SKETCH# EC-520

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

FORM COST.

UPSTREAM FACE FORMS(FOUND. FORMS.)

POUR	LENGTH (F)	HEIGHT (F)	AREA CS.F.
			B.F. 4628.69
13 b)	50	6	30
14 a)	10	6.67	66.7
b)	25	7.5	187.5
15:	40	10	400
16:	25	10.	250
		TOTAL	5562.89 SF
			5563.14 = 1400

DOWN STREAM FACE FORMS
(FOUND FORMS)

	POUR	LENGTH (FE)	HEIGHT (FE)	AREA
	1. a)	7.5	6	45
	b)	4	6.67	26.68
	c)	7.5	7.5	56.25
	d)	11	7.5	82.5
	e)	13	7.5	97.5
	f)	14	7.5	105
	g)	4.5	5	22.5
	2. a)	24.5	7.5	183.75
	b)	33	7.5	247.5
	c)	8.5	7.5	63.75
	3. a)	10	7.5	75
	b)	18	7.5	135
	c)	16.5	7.5	123.75
	d)	11	7.5	82.5
	4. a)	15.5	7.5	116.25
	b)	16	7.5	120
	c)	17	7.5	127.5
	d)	25	7.5	187.5
	e)	8.5	6	51
	5. a)	20	7.5	150
	b)	43	7.5	322.5

2421.43

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 15 1964

PROJECT NO. 327

TRUMBULL LAKE DAM
 PEQUONNOCK RIVER BASIN, CONN
 FORM COST.

DOWN STREAM FACE FORMS
 (FOUND. FORMS)

	POUR	LENGTH (FE)	HEIGHT (FL)	AREA (S.F.) B.F. 2421'43
	5. c)	30	1.5	45
	6.	60	3	180
	7 a)	40	7.5	300
	b)	25	7.5	187.5
	8. a)	30	7.5	225
	b)	25	7.5	187.5
	c)	12	2	24
	9. a)	20	7.5	150
	b)	35	7.5	262.5
	c)	15	1.5	22.5
	10.	60	7.5	450
	11. a)	20	7.5	150
	b)	12	7.5	90
	c)	10	7.5	75
	d)	31	4.5	139.5
	13. a)	13	7.5	97.5
	b)	34	2.	68
	14. a)	37	6.67	246.79
	b)	23	2	46
	15. a)	53	6.67	353.51
	b)	30	1.5	45
	16.	25	5.	125

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1st '72 REV.

SKETCH # EC-S23

TRUMBULL LAKE DAM,

PEQUONNOCK RIVER BASIN, CONN.
FORM COST.

DOWN STREAM FACE FORMS
(FOUND. FORMS)

POUR	LENGTH (FT)	HEIGHT (FT)	AREA (S.F.) B.F. 5891.73
12. a)	40	3	120
b)	5	7.5	37.5
c)	8	7.5	60
d)	11	7.5	82.5
e)	4	7.5	30
TOTAL			6221.73 (SF)

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1ST 72 REV.

TRUMBULL LAKE DAM.

SKETCH# EC-S 227-

PEQUONNOK RIVER BASIN, CONN.

FORM COST:

LIFT STARTER FORMS (UP-STREAM)

POUR	LENGTH (F)	HEIGHT (F)	AREA (S.F.)
1 a)	10	6.67	66.7
b)	10	7.5	75
c)	10	7.5	75
d)	10	7.5	75
2 a)	10	7.5	75
b)	10	7.5	75
c)	20	7.5	150
d)	20	7.5	150
3. a)	30	7.5	225
b)	10	7.5	75
c)	20	7.5	150
4. a)	10	7.5	75
b)	10	7.5	75
c)	10	7.5	75
d)	10	7.5	75
e)	20	7.5	150
5. a)	30	7.5	225
b)	30	7.5	225
6. a)	60	7.5	450
7. a)	10	7.5	75
b)	40	7.5	300
c)	10	7.5	75

2991.7

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11, 72 REV. APR. 11, 74 SKETCH# EC-520

TRUMBULL LAKE DAM

DEQUONNOCK RIVER BASIN, CONN

FORM COST

CANTILEVER FORMS SHALL BE USED FOR STARTER FORMS

ACTUAL FORM MATERIAL REQUIRED:

CANT. FORMS 4800 SF

BULKHEADS 6720 "

11520 SF x 7.20 = 82,900

CANT. FORM DELIVERED WITH PLATFORM + 2 ANCHOR BOLTS,
10 FT MODULES = 720 / SF

TOTAL FORM COST 82,900

25% SALVAGE - 20,700

\$ 62,200

PIGTAILS 5600 EA 9,000

SHEBOLTS 2000 EA 16,860

BRACKETS 290 EA 3,000

\$ 28,860

FORMS TO BE USED FOR

STARTERS 12,830 SF

CANTILEVERS 107,270 "

BULKHEADS 51,600 "

171,700 SF

FORM COST PER SF

FORMS LESS SALVAGE 62.200

SHEBOLTS, PIGTAILS 28.860

TOTAL 91.060 / 171,700 SF = .53

SAY .55 \$ / SF

Revised

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE

REV.

SKETCH# EC-S27

TRUMBULL LAKE DAM

DEQUONNOCK RIVER BASIN, CONN.

STAIR FORMS

FORM SURFACE AREA FOR THE

① STAIRS OF INSPECTION GALLERY.

TREAD = 11" → WIDTH, 6'-0" → LENGTH.

RISERS = 7'5"

332 NOS. OF STEPS, NOS. OF RISERS = 334.

AREA OF FORM = $6'-0" \times \left(\frac{7.5'}{12}\right) \times 334$

TOTAL AREA = 1240 S.F.

② STAIRS OF WATER SUPPLY GALLERY.

RISERS - 8" HT. →
3'5' LONG
15 NOS.

$15 \times 3'5" \times \left(\frac{8}{12}\right)' = 35 \text{ S.F.}$

TOTAL AREA 1275 S.F.

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11, 1972 REV.

SKETCH# EC-5-83

TRUMBULL LAKE DAM.

PEQUONNOCK RIVER BASIN, CONN.

FORM AREA FOR STAIR OF STAIR TOWER.

TOTAL HEIGHT $26' - 8''$

RISERS - $8''$ HEIGHT

TRADES - $3' - 6''$ LONG, WIDTH - $10''$

TOTAL RISERS = 40 NOS.

TOTAL TRADES = 35 NOS.

FORM FOR RISERS = $3.5 \times \frac{8}{12} \times 40 \approx 94$ S.F.

FORM FOR BOTTOM

OF STAIR SLAB = $5 \times 3.5 \times 7.8 = 137$ S.F.

SIDE WALLS STRAIGHT - $2 \times 2 \times 6.5 \times 26.67 = 694$ S.F.

CURVED - $2 \times 2 \times 3.14 \times 3.5 \times 26.67 = 1170$ S.F.

RAILINGS - $2 \times 3.5 \times 39' - 0'' = 273$ S.F.

TOTAL - 2368 S.F.

J. F. C. MELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUL 15, 71 REV.

SKETCH# EC-52

TRUSS BULL LAKE DAM

PEAK MATCH CYCLE BASIN, CO

3 1/2" PIPE

3 1/2" I. D. B. S. PIPE.

NO. OF MONO. TUBES	LENGTH OF 3 1/2" PIPE Av.	NO OF PIPE IN EACH MONO.	TOTAL L.F. OF 3 1/2" PIPE
2	29'	6	174
3	117'	6	102
4	11'	6	66
5	13'	6	78
6	15'	6	90
7	17'	6	102
8	16'	6	96
9	14'	6	84
10	14'	6	84
11	17'	6	102
12	17'	6	102
13	12'	6	72
	192'	72	1,152 L.F.

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUN 1 1972 REV.

SKETCH# EC-S30

TRENT BULL LAKE DAM.
 PEAVOONOCK RIVER BASIN COLL.
 2 1/2" Ø PIPE

2 1/2" Ø I. D. B. S. PIPE

NO OF MONOLITH	LENGTH OF 2 1/2" Ø PIPE/MONO. AV.	NOS. OF PIPE IN EACH MONO.	TOTAL L.F. OF 2 1/2" Ø PIPE
2	27'	12	
3	15'	13	
4	9'	13	
5	11'	13	
6	13'	13	
7	15'	13	
8	14'	13	
9	12'	13	
10	12'	13	
11	15'	13	
12	15'	13	
13	10'	12	
	168'	154	2147 L.F.

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1, 1972 REV.

SKETCH# EC-331

TIMM BULL LAKE DAM.

PEQUONNICK RIVER BASIN COM.

DRAIN HOLES

3" Ø DRAIN HOLES

NO. OF MONO.	AV. LENGTH OF 3" Ø DRAIN HOLES.	NO. OF HOLES IN EACH MONO.	TOTAL LF. OF 3" Ø DRAIN HOLES.
2	40'	6	
3	40'	6	
4	40'	6	
5	40'	6	
6	40'	6	
7	40'	6	
8	40'	6	
9	40'	6	
10	40'	6	
11	40'	6	
12	40'	6	
13	40'	6	
		72	2,880 LF.

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1, 11-REV.

SKETCHED BY S. B. C.

TRUMBULL LAKE DAM.

PEQUONNOK RIVER BASIN, CONN.

GROUT HOLES

1 1/2" Ø GROUT HOLES.

NO. OF MONO.	AV. LENGTH OF 1 1/2" Ø GROUT HOLES.	NO. OF HOLES IN EACH MONO.	TOTAL L.F. OF 1 1/2" Ø HOLE.
2	60'	12	
3	60'	13	
4	60'	13	
5	60'	13	
6	60'	13	
7	60'	13	
8	60'	13	
9	60'	13	
10	60'	13	
11	60'	13	
12	60'	13	
13	60'	12	
		154	9,240 LF

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1, 72 REV.

SKETCH# 60-5133

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

6" DRAINS

6" ϕ DRAINS 12' O.C. \pm

NO. OF NO. NO.	AV. LENGTH OF DRAIN.	NO. OF DRAINS	TOTAL L.F.
2	8'	2	16
3	27'	5	135
4	61'	5	305
5	88'	5	440
6	88'	5	440
7	76'	5	380
8	69'	5	345
9	54'	5	270
10	48'	5	240
11	39'	5	195
12	3'	1	3
		TOTAL	2769 L.F.

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM.

PEQUONNICK RIVER BASIN, COM.

8' DRAIN WELL

8" DIA FORMED DRAIN WELL.

NO. OF MONOLITH STATION	LENGTH OF DRAIN WELL	
2, 1+15	33'	
3, 1+70	61'	
4 2+30	93'	
5 2+90	129'	
6 3+50	135'	
7 4+10	135'	
8 4+70	116'	
9 5+30	98'	
10 5+90	85'	
11 6+50	83'	
12 7+10	56'	
13 7+70	23'	
14 8+05	23	

1070 L.F.

COPPER SEAL

NO. OF MONOLITH	STATION		LENGTH OF SEAL LF	TOTAL
2	1+10		54	
3	1+70		80	
4	2+30		103	
5	2+90		147	
6	3+50		150	
7	4+10		148	
8	4+70		133	
9	5+30		116	
10	5+90		106	
11	6+50		103	
12	7+10		85	
13	7+70		40	
14	8+20		40	
15	8+80		25	
	9+40		15	
			1345 x 2	2690

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1, 77 REV.

SKETCH# EC-526

TRUMBULL LAKE DAM.

PERQUOINOCK RIVER BASIN, CONN.

COPPER SEAL AT CONTR. JOINTS. GALLERY

LENGTH $2 \times [(3+2+2) + (6+2+2)]$ FT.

= 44 FT.

NO. OF JOINTS = 11.

TOTAL LENGTH OF SEAL = $44 \times 11 = 484$ L.F.

MISC. SEALS ~ 500 LF

TOTAL - 2690 LF

484 "

500 "

3674 LF

SAY 4000 LF

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1, 72 REV.

SKETCH# EC-537

TRUMP BULL LAKE DAM
PEQUANNOCK RIVER BASIN CO.

INSIDE VOL. OF PUMPING STATION.

LENGTH - 49'-0"

WIDTH - 24'-0"

HEIGHT - 32'-0"

$$\text{VOLUME} = 49'-0" \times 24'-0" \times 32'-0" = 37,632 \text{ C.F.}$$

$$\text{LESS FLOOR SLAB} = 1 \times 49' \times 24' = 1176 \text{ C.F.}$$

$$36,456 \text{ C.F.}$$

$$\text{LESS CONC. AT BASE} = 3' \times 9' \times 24' = 648 \text{ C.F.}$$

$$35,808 \text{ C.F.}$$

ACCESS ROADS

480' x 16' = 7,350 SF - ACCESS TOP
 14900 x 13' = 268,200 SF - RAILROAD
 3600 x 20' = 72,000 SF - VALLEY ROAD

ENVIRONMENTAL CONTROL

a) WATER TURBIDITY CONTROL

METERING DEVICES & FLOCCULANT DISPENSERS --

MONTHLY OPERATION:

18 Mos @ 3,000 -- 54,000

\$ 35,000

 \$ 89,000

b) DUST CONTROL ON ROADS --- \$1,000 Chemicals

c) NOISE ABATEMENT (EQUIPMENT)

Cleaving & Grubbing	\$ 9,000
EXCAV	135,000
DIVERSION	80,000
DRAGLINE & TRUCKS	162,000
AGGREGATE PLANT	490,000
MIXING PLANT	432,000
CABLEWAY	395,000
AIR TOOLS	80,000
GEN'L EQUIP	243,000

TOTAL EQUIP 2,036,000

5% Equip \$ 100,000

d) Landscape Renewal

1000 Plants @ \$ 25⁰⁰ = \$ 25,000

**COST AND FEASIBILITY STUDY
ALTERNATE DESIGNS TO PERMIT USE
OF SLIP FORM AND OTHER TECHNIQUES
TO MAXIMIZE ECONOMIES**

**BOOK R
RAPID CONSTRUCTION UTILIZING
SLIP FORM TECHNIQUE**

BOOK R - RAPID CONSTRUCTION UTILIZING SLIP FORM TECHNIQUES

Page R-1	Feasibility Factors Affecting Construction Methodology
Page R-19	Construction Costs and Analysis
Page R-38	Cost Analysis
Page R-44	Summary, Recommendations, and Discussions of Additional Modifications

Drawings, Sketches, Sheets, and Tabulations

1	Drawings 209-R-S, R-1 through R-10
2	Drawings 209-RM-1 through RM-4
3	Sketches 209-R-1 through R-8
4	Sketches 209-RS-15 (in Book RA)
5	Sketches 209-SR-1 through SR-8 (in Book RA)
6	Sketches 209-W-4 and W-5
7	Sketches ER-A1 through A21 (in Book RA)
8	Sheets ECR-1 through 10
9	Sheets W-4 and W-5 (in Book RA)
10	Sheets EM-F1, F-2 (in Book RA)
11	Sheets EM-S17 through S22 (in Book RA)
12	Sheets 209-CR-1 through CR-10 (in Book RA)
13	Tabulations 209-SR-18, SR-13

FEASIBILITY
FACTORS AFFECTING CONSTRUCTION
METHODOLOGY

STREAM DIVERSION AND CONSTRUCTION SEQUENCE

The stream diversion for constructing the dam utilizing slip form techniques is essentially the same as for construction by traditional methods. The work is divided again into two phases related to the two stages of stream diversion. Placements 1 thru 37 as shown on drawing 209-R-1 will be placed during Phase I, bringing monoliths 4 thru 11 to elevation 177'-6" with the exception of monolith 5 which will be kept low for storm overflow and monoliths 10 and 11, which will be as shown to elevation 185'-0". If further study indicates that monolith 5 should be kept lower than elevation 170, this can be easily accomplished without appreciable effect on this study. Elevation 170 was selected as weir height for monolith 5 in order to provide sufficient head for good flow through the flood control and blow-off conduits during the second stage diversion. It seems necessary, however, to maintain this weir height at elevation 162'-6" in order that upstream water levels be kept down to acceptable limits. Placing the weir height at this level presents no problem and will have no significant effect on this study which is based on the 170'-0" elevation. If necessary, the concrete over the water supply gallery can be kept down to elevation 176'-0" to allow installation of piping in the open.

During Phase II. (See Drawing 209-R-2) slip form and fixed form operations will be intermixed together and in the order shown on concrete demand schedule, Sketches 209-R1 thru R8, starting with placement 38 on the 38th working day; slip form operations are indicated by Roman numerals and except for monolith 5, will be continuous placement to elevation 260, working around the clock on a 24 hour basis and taking a week to

complete, including some work into the weekend. During slip form placements it is not anticipated that concrete will be placed in the 7'-6" lifts. The 7'-6" lifts have been spaced at 7 calendar days (5 working days) except in one or two instances near the top. Retaining walls and minor miscellaneous placements can be made during the same period of time without interfering with the main operation or overloading the concrete plant. Monolith number 5 will be kept low until all other slip formed monoliths are up to elevation 260, the east abutment monoliths up to elevation 237'-6" and the west abutment monoliths to 222'-6". Monolith 5 is then slipped in two operations stopping for the weekend. Work will then continue simultaneously on the abutments and top of dam to completion. Since these last placements are small, lost time may be picked up during this period if necessary.

ENVIRONMENTAL PROTECTION AND ACCESS TO SITE

Since this construction scheme will not utilize a cableway system and since concrete production is kept in the valley, work above the east and west abutments will not be required, leaving these areas untouched. Traffic from Valdamere Avenue access and activity in the populated area above the west abutment will be greatly reduced. In order to further reduce this traffic, the cement unloading station has been removed to the lower access road (SEE DRAWING 209-R-10), and all shipments will be received at this lower level.

Night operations during slip forming (a total of 8 weeks) will result in activities and noises that may be objectionable. Unloading, aggregate production, and as many other activities as possible must be accomplished during normal working hours to reduce night activities.

LABOR CONSIDERATION

The availability and attitude of labor towards shift work is extremely important to the economy of the slip form operations. Actually, a continuous 24 hour operations is not essential to this technique. The slide may be made in daily lifts based on an eight hour operation or in daily lifts of any predetermined height, say 7'-6",

running into some overtime if necessary. Even with daily operations, some premium time must be paid because of the necessity of freeing the forms at the end of each day's work. This will involve a skeleton form crew for two to three hours after placing is completed. Since preliminary inquiries indicate that shifting is possible and economical in this area, and since a continuous slip will eliminate the costly horizontal joint treatment, as well as have some beneficial effect in reducing thermal shock, we have based this study on a continuous 24 hour placement except in monolith No. 5. It was elected to take a stop and horizontal joint over the weekend in lieu of the premium time involved in running monolith No. 5 through the weekend.

Shift work is generally done in one of two ways, depending on the availability of labor and on union agreements, three 8 hour shifts or two 12 hour shifts. Three 8 hour shifts are, of course, the most economical and have the advantage of not overtiring the men by too long and grueling a day. When eight hour shifts are used, supervision is usually placed on twelve hour shifts to provide overlap across the shift changes and a better degree of continuity. The pay for three 8 hour shifts is 27 hours for 24 hours work. Sometimes the men are asked to work the half hour lunch-time in which case they are paid 30 hours for 24 hours work. It is better to give the men the lunch half hour as they will normally take it in any case and charge the double time for it anyway. The lunch periods are usually staggered by the foremen to maintain continuity. Pay for the twelve hour shifts is usually 34 or 30 hours for 24 hours work, depending on whether overtime is at double time or at time-and-a-half.

The cost impact of premium time for the various methods of shifting as compared to an eight hour day without overtime is approximately as follows:

One 8-hour shift with overtime skeleton crew to free the forms	1.25
Three 8-hour shifts	1.125
Two 12-hour shifts.....	1.33
One straight time shift with two shifts overtime.....	1.55
Sunday operation for 8-hour day.....	2.00

In considering labor costs, the above premium costs must be balanced against the labor savings that accrue from form reuse (height of slip divided by form height), elimination of erection and stripping of forms at each lift, reduction in form cleaning, elimination of scaffold erection handling and dismantling and tie hole patching.

Slip forming has a good impact in areas where unemployment is temporarily high as it will concentrate work for three times as many men in a short period of time. When labor supply is low and competition for men exists between projects, two twelve-hour shifts has a great appeal to the men because of the premium pay involved.

Due to the automated repetitious nature of slip forming techniques, a minimum of skill is required among the main labor force, making the use of unskilled labor (especially among minority groups) possible without loss of efficiency. The supervision and some of the skilled trades, however, must be highly skilled and an experienced technician will be needed to work with the supervision until they acquire skill in the technique. The technician will be needed during form construction and for about two slips.

CONCRETE

The mass concrete used in the construction of this dam presents problems in the use of slip forming techniques. These problems result from the low cement content, substitution of fly-ash and low temperatures of the concrete, all of which add up to an extremely low rate of hydration and strength pick-up. At tests conducted at the Waterways Experiment Station in Vicksburg, Mississippi during April and May, 1972, it was found that with concrete temperatures of 70 degrees Fahrenheit and an ambient temperature of 73 degrees, the exterior mass concrete picked up 3 degrees Fahrenheit in 12 hours and an additional 12 degrees in the next 12 hours for a total of 15 degrees in 24 hours. The low temperature pick-up in the first 12 hours is the significant item.

The tests conducted in Vicksburg indicated that this concrete placed at temperatures from 57 to 70 degrees Fahrenheit in a 73 degree environment successfully held

vertical surfaces emerging from the forms at ages as low as 2 to 4 hours. SEE TABLE 209-SR-17. Using a four foot high slip form, 4 hour old concrete emerging from the form may be translated into a slide rate of 12 inches per hour.

During the tests, monoliths 3 feet by 6 feet in plan and ten feet high were slip formed at rates of 3 inches, 6 inches and 12 inches per hour respectively, without any problems; as long as the forms were kept full. Slips at 18 inches per hour were marginal. It is predictable that if the forms are allowed to run empty, the heavy vibrators used in this type of work will push the concrete out from under the form. This situation actually occurred during the test and it was necessary to stop vibration until the forms were filled to the top. With the forms running full, no problem was encountered with the use of 6 inch vibrators.

Both data and visual inspection indicate that this concrete placed at 57 to 70 degrees Fahrenheit in a mild environment of 70 to 75 degrees can be slip formed at rates considerably lower than 3 inches per hour and higher than 12 inches per hour without problems. The upstream and downstream faces of the dam are actually sloped so that the danger of "fall out" or bulging of concrete from under the form is almost nil, if the forms are kept full. It was also observed that the slip formed surfaces were in excellent condition for finishing and remained so for many hours after they were exposed.

The slow set of cement will not cause serious problems as far as slipability is concerned. The rate of slide can be kept down and the forms can be made longer than four feet if necessary. It is to be noted that because of the prolonged plasticity of the concrete, contact with the form is maintained two to three times as long as with normal structural concrete thus increasing the drag forces by an amount somewhat higher than this ratio. Test showed the drag loads per lineal foot of forms to run between 100 and 600 pounds for wood forms and 150 to 250 pounds for steel forms. Our best judgement is that drag forces must be designed at three times those used for structural concrete work. It is interesting to note, too, that although drag forces for mass concrete are much higher

than for structural concrete under normal operating conditions, they will not tend to increase to the high drag values (infinity) that structural concrete can reach when concrete sets too rapidly. This indicates that the chances of the forms binding to the concrete, (which requires dismantling and re-assembly, causes tearing of the concrete) are nil over long periods of time. During the test at the Waterways Experimentation Station, the forms were left in contact with the concrete overnight and were broken away in the morning without any damage to the forms nor to the concrete.

The major problem connected with the slow rate of hydration and low strength pick-up of cool mass concrete is the development of sufficient strength to enable anchoring of the forms (whether it be slip or fixed cantilever forms). For this reason a special type of anchor has been developed by this office having precast concrete block at the surface to give good strength at the actual insert face and a bearing plate effect for transmitting compressive and shear loadings to the low strength at the actual insert face and a bearing plate effect for transmitting compressive and shear loadings to the low strength mass concrete. This system also provides a means of spacing and holding the inserts in position relative to each other and to the concrete surface. The inserts must develop high resistance to pull-out at strengths well below the traditional value of 300 psi. The solution to this problem lies in using inserts that go deeper into the concrete (at some cost) so that the action is more like that obtained by burying deadmen deep in a granular material.

At tests conducted at Vicksburg on May 5th, three inserts were tested in 50 degree Trumbull mass concrete having an age of eight hours. It is estimated that the tensile strength of this concrete was between 1 and 2 psi. (SEE TABLE 209-SR-18). Two of the anchors tested were of the composite type described above and shown on Sketch 209-W-4 and one of the composite type utilizing a conventional anchor as shown on Sketch 209-W-5. The two "deep" anchors were pulled out at 5100# and 6000#; the standard anchor was pulled out at 2500#. It is to be noted that the depth of the test monolith (3'-0") limited

the depth of embedment of the first two anchors. Actually the length of the bars may be extended as necessary in the actual construction. It is noted also that the edge distance and spacing of the three inserts did not allow full development of cone normally to be expected under such conditions. Lastly, the pipe support between inserts adds to the strength of the anchor by adding projected bearing surface and by cantilever action down to concrete of greater age.

During tests conducted on May 19th, anchors of the "deep" type were tested by pulling them up from the top of the monolith allowing the test of anchors 5'-0" long, twice as long as the ones tested May 5th. The capacity was doubled, but again monolith dimensions prevented full strength development.

It is planned to conduct additional anchor and early concrete strength tests to develop data for determining the length of anchors actually required based on age and temperature parameters. For the purpose of this cost study, ten foot long anchors were used.

A problem develops in planning the rate of placement of large size aggregates related to three parameters, maximum rate of slipping; minimum thickness of placements, maximum time between placements. It has been traditional to make the thickness of concrete placements a minimum of three times the largest aggregate size. For 6 inch aggregate such as planned for this project, the minimum placement thickness is 18 inches. Allowing two hours maximum between successive placements results in a minimum placing rate of 9 inches per hour. If the strength pick-up is not sufficient to support this rate of slide, the form must be designed higher than four feet. If this solution is not viable, then either slipforming must be abandoned or the size of aggregate must be reduced.

The minimum concrete mixing and placing capacity required in accordance with EM 1110-2-2000 is slightly under 150 yards per hour. The two 4 yard mixers provided for the purposes of this study have a rated capacity of 160 yards per hour, the same as was provided for the purposes of the conventional methods study. Although the number of days of placing is reduced, (see sketches 209-SR-1 thru SR-8), the number of shifts is increased. This will improve the plant utilization factor for the quarry and aggregate production operations but will reduce the average placement of concrete per shift to 516 yards with a plant utilization

factor of 40% arrived at by dividing total concrete in the monoliths by the number of 8 hr. shifts by a daily plant capacity of 1280 yards (160 yards per hour times 8 hours). This results in a decrease in the batch plant utilization factor of 2 percent.

Because of the strength pick-up and other qualities necessary to support a good rate of slide, a minimum cement content will be required. In order to provide this minimum cement factor we must use exterior concrete in both upstream and downstream faces of the dam, but not the transverse (inter-monolith) faces. This will result in an increase in exterior mass concrete and a decrease in interior mass concrete on 19,400 square feet of downstream face or 4300 cubic yards.

CONCRETE PLACEMENT

Concrete placement by belt conveyors offers a rapid flexible method of placing concrete on this project. Conveyors are adaptable to both the fix form and slip form operations and are capable of much higher rates of concrete delivery if other limitations were removed. Since the great majority of placements are over 200 yards and require rates of placement of over 50 yards per hour, experience indicates the conveyors are the most economical method of placing the concrete.

Belt conveyors are limited and inefficient in the vertical transport of concrete. This requires integration of another piece of concrete placing equipment to be used in conjunction with the belts for raising the concrete to the higher lifts. For the basis of this study, we selected a two-well materials hoist tower (SEE DRAWING 209-R-3) which has a capacity of 160 yards per hour plus a long history of dependability. Because the hoist tower is between two belt conveyors (continuous feed equipment) two hoisting buckets of three yd. capacity each will be needed with surge hoppers of eight yard capacity top and bottom to smooth out the delivery and feeding of the concrete. The two-well system also gives a safety margin to maintain operations in the event of a malfunction of one of the hoists. Please note that the upper surge and receiving hopper is supported on the tower and suspended in such a manner that it will be hydraulically synchronized to maintain the same level as the slip form operation. Discharge of the skip buckets into a common surge hopper is automatic. The use of other types of elevating machinery such as bucket elevators is not recommended because of problems in keeping

-the equipment clean and preventing concrete build-up and fouling of the machinery.

Pumping the concrete has been considered as this placing method is capable of pumping concrete vertically as well as horizontally, eliminating the necessity of integrating the materials tower into the handling system. Since concrete pumping depends on maintaining a rich film of cement, sand and water to provide lubrication between the pipe walls and the moving concrete, the minimum cement content must be about 450 lbs/yd with a relatively high percentage of well graded fines and a slump of 2 inches or more. Mass concrete mixes now in vogue will not support concrete pumping.

The maximum size of aggregate can also be a deterrent to the use of concrete pumping. The size of the pumps and pipes are related to the size of the aggregate. Six inch maximum aggregate, which can have dimensions considerably more than 6 inches, will require pipe lines of at least 12 inches, probably more; the pumps must be sized accordingly. Equipment of this size will have capacities and weight ten times that of equipment now in use. The weight of a 12 inch pipe full of concrete will be approximately 175 lbs. per lineal foot. Pipes of this weight are acceptable for main lines and can be hydraulically hooked up to the slip form hydraulics to maintain a fixed position relative to the work. The final concrete distribution must, however, be by other means since such pipes cannot be readily handled.

Crane handling is not considered economical in this type of placing except possibly for some of the smaller placements at the top of the dam, retaining walls and miscellaneous concrete.

The conveyor operations are divided roughly into three groups:

- 1- A fairly typical system where trains of feeder and/or side discharge conveyors run along the ground, on the trestle runway or on the monoliths themselves and deliver concrete directly from the plant to the point of deposit.

2- An automated conveyor system supported on the slip form, fed by a materials tower and distributing the concrete to any point on the leading monoliths.

3- An automated conveyor system supported from the slip forms and distributing the concrete to trailing monoliths.

The conveyor train system is shown on Drawings 209-R-1 and 209-R-2. A timber trestle runway has been provided as a working area for the crane and conveyors; semi-permanent conveyor rail can be mounted on this runway and feeder conveyors of 30 to 100 foot lengths may be used in various combinations to service any particular monolith. Sixteen inch belt conveyors have the capacity to meet the concrete requirements of this job. The use of six inch aggregates, however, necessitates the use of 24 inch conveyors at an equipment first cost premium of 40 to 50 percent.

Concrete is transported from the batch plant via a radially moveable feeder conveyor to either a run along the trestle to the west, a similar run to the east, or an elevated conveyor feeding directly to monolith 13 on the east abutment. Side discharge conveyors then transport the concrete to the particular monolith being placed. The side discharge conveyors are stationary; the feeder conveyors are rearranged daily, utilizing the crane to effect these movements. Actual distribution within the monolith is effected using radial spreaders or side discharge conveyors.

The conveyor system for placing the concrete in the slip formed lead monoliths consists of a main line conveyor supported on the upstream and downstream slip forms and rising with them and a distributing conveyor. A steel support bracket is provided to cater to the overhang condition that develops in the main line conveyors as the placing progresses. This conveyor is tied to the material tower and maintains a constant relation to it and the surge hopper. These conveyors are side discharge conveyors of a 160 yard per hour total capacity. The distributing conveyors are shown riding on rails supported on the transverse slip forms each serving any point in the monolith. Using the one conveyor with reversible

belt and a two way plow is more economical than using two one-way conveyors. The capacities needed will almost always be considerably less than 160 yards per hour. It should be noted that jack capacities must be increased to 6 tons at points of conveyor support; actually 6 ton jacks were used throughout.

The conveyor system for the trailing monoliths as shown on Drawing 209-R-2, monolith No. 7, consists of a main line side discharge conveyor on one side of the monolith supported on a double truss which is supported on the face slip forms. A similar truss is on the other side of the monolith. The distributing conveyor capable of reaching any point in the monolith runs on rails supported from the two double trusses. The materials towers from the lead monoliths are used to feed the conveyors either by elephant trunk from the top of the monolith or directly via a suspended conveyor running directly from the suspended surge bin to the main line conveyor. Monoliths 1, 2, 3, and 11 may be placed using the lead monolith materials tower, elephant trunk and conveyor system as shown for monolith 11.

FORMING SYSTEM

The forming system envisioned in this study consists of a combination of fixed and sliding forms as required to cater to the varying conditions that occur in the different parts of the dam. Basically, the height of monoliths slip formed are those that can be formed by conventional cantilevered forms allowing for starting a level lift with room for anchoring of the strongbacks. Monoliths 1, 2 and 12 thru 16 do not have sufficient height to justify setting up a slip form operation. Monolith 3 would support a slide of 37-1/2 feet; monolith 11 would support a slide of 45 feet. These monoliths can be economically slid and may have been included in the group of monoliths we planned to slide. Actually this study is based on sliding monoliths 4 thru 10 on an alternate basis as shown on Drawing 209-R-2. This particular group was selected due to alternate arrangement of lead and trail monoliths and orientation to monolith 5, which must be kept down as last monolith slid to provide a stream overflow weir.

The forming of the areas below and on the abutment sides of the slip formed monoliths is effected by traditional forming methods, that is to say foundation forms, lift starter forms and cantilever forms. Concrete placements have been spaced at a minimum of five calendar days between placements. It is obvious that a long flat valley or a deep gorge with vertical sides would give maximum opportunity for use of slip forms.

The basic concept for the slip form system is as shown on Drawings 209-R-3 and 4. This system is capable of sliding a complete monolith with two faces and two transverse bulkheads. By mounting a double truss on each side of the monolith perpendicular to the base line, all conveyors can be supported from these trusses which are, in turn, supported on the face slip forms only (SEE MONOLITH No 7 and Detail A on Drawing 209-R-2). This latter system can be used with a lead monolith, a trail monolith, or with an end trailing monolith (one transverse bulkhead) as transverse bulkheads are not required for supporting the conveyor system.

The form is a hybrid between the conventional cantilever form and the conventional slip form having the capabilities of both (See Drawing 209-R-4). All forces parallel to the formed face are transmitted through the jack to the jack rod which can take only axial loads and no bending. All axial loads are transmitted directly to the bottom of the slide through the jack rods with the concrete preventing buckling. The jack rods run continuously from the bottom of the slide, being extended in ten foot lengths as the work progresses; the jack rod platform as shown providing a placing deck and template to hold the jack rods. A base plate may be used under the first section of jack rod if this is considered necessary to keep compressive strength on the concrete within limits. Off-the-shelf jacks in capacities up to 25 tons are available on a rental basis, higher capacities being obtainable on a special order basis if necessary.

Loads perpendicular to the formed surface are transmitted through the trailing cantilever legs and then through wheels capable of taking no loads parallel to the formed surface. Wheel support brackets are attached to the dam

on previously set inserts as the forms clear these inserts (See Sketch 209-SR-10). These brackets are composed of three pieces to allow for side erection and removal to the yoke legs; quick connection hardware and some adjustability are very desirable in these brackets. The loadings due to gravity loads, eccentricity, hydrostatic concrete pressure, form drag and wind produce overturning moment resulting in maximum pull-out forces of 18 kips.

(See Calculation Sheets 209-CR-1 thru 10). Actually, this pull-out force can be substantially reduced by using counterweights or tying the yokes to each other across the monolith. Tying across the jack level will not directly interfere with the concrete placing system, but it does offer impediments in a general way such that it should be looked at as a low priority alternate solution. We have actually slip formed one dam in upstate New York using steel drums filled with water for counterweights. This worked very well and allowed for easy adjustment of the counterweights. Taking care of the overturning moments through the concrete anchors seems feasible and will present a minimum of interference with placing operations.

Three ton jacks are sufficient for raising and supporting these forms as shown. If counterweights are used, and in sections of form supporting conveyors, the capacity of the jacks and jack rods must be increased, probably doubled. For this reason it was conservatively decided to use 6 ton jacks throughout. The conveyors may be so supported as to decrease rather than increase the overturning moments of the forms.

The proposed form shown on Drawing 209-R-4 is a wood form composed of tongue and groove fir floor boards with 3 ply 2 x 10 wales and 2 x 6 diagonal trussing. Wood forms of this type have had a long and successful service record over many years. Because of the spaces between the boards, this form reacts very well to dimensional changes caused by varying moisture conditions. Wood forms also have a great deflection flexibility, can endure grooving from aggregate projections without serious damage, are easily repaired by replacing individual boards by driving a new one through and are very economical. Plywood forms have been used successfully, but the plys tend to tear off and there is a serious tendency to buckle. The backing for the plywood

has to be heavier and removal of a damaged plywood sheet is very difficult to achieve. Finnform plywood, a very strong plywood with many more plies than are usually obtainable and a very hard plastic surface has a very good service record. It was tested at the Waterways Experimentation Station together with board and steel surfaces and gave satisfactory results. Although finnform was used for a 525 foot slide in Baltimore very successfully and without any wear problems, the large aggregate caused significant damage to the plank tested at the Experimentation Station.

Steel forms, fiberglas reinforced plastics and combinations with wood may all be used as forming material. Steel and fiberglas may turn out to be the most economical if good reuse is developed, particularly over more than one project. In addition, steel forms reduce drag forces by 50 percent as compared to board forms. It must be noted at this point that the fiberglas reinforced plastic forms have only been tested once to our knowledge on a hundred and sixty foot slide.

Platforms and scaffolds have been integrated into the slip form system to provide placing and template platforms as well as a finishing platform and a platform for removing the guide wheel brackets and patching the insert holes. Scaffolds are handrailed as necessary with ladders providing access between platforms and personnel stair towers, providing access to the ground. Lateral bracing trusses provide for longitudinal stability.

The system for forming vertical and nearly vertical surfaces is shown on Drawing 209-R-6. This system is used on the upstream face and transverse bulkheads.

Like the traditional cantilever form system, a problem exists with finding enough room for anchoring the trailing cantilever legs. This is accomplished as shown on Drawing 209-R-7 by means of an intermediate form which takes the place of the lift starter form in the conventional system. The slip form is erected with the bottom of the form 7'-6" above the first lift that has a level surface the full length of the monolith. It is supported on the bottom of the legs and shored as required.

Fixed forms may be installed to cover this 7'-6" lift using the yoke legs as strong backs and taking the hydrostatic concrete pressure by ties into hard concrete. Two lifts are shown in the drawing but the placement will probably be made in one lift. Once the concrete is up to the bottom of the slip form, filling of the slip form may commence and the forms moved upon the concrete reaching sufficient strength.

It is planned to stop the slip form at elevation 260'-0", since at this elevation a change in slope occurs on the upstream face. The bottom wheel anchor is replaced by a fixed support capable of taking loads parallel to the formed surface and the top section of the yoke is removed together with the jacking equipment. The placing platform remains in place to provide a deck for erecting vertical panel forms for casting the remainder of the work in the conventional manner using form ties. 6'-8" is then cast using the slip forms on the downstream face and fixed form on the upstream face. At the top of this placement conventional panel forms are installed on the downstream face supported on the modified slip form system and platform. In the slip form placing sequence shown on Drawing 209-R-3 alternate monoliths are placed so that the lead monolith has in effect face forms for casting the transverse dam faces. The trailing monoliths require no transverse forms as the concrete is placed directly against the previously placed monoliths. If adjacent monoliths are to be slip formed simultaneously, premolded joint fillers may be installed to maintain separation between monoliths. A modification of the slip form system may be used to accomplish this using jacks synchronized with the jacks controlling the slip form movement; panels of rigid joint filler are fed into a moving jig as the placing progresses, using little sheet metal clips to align and hold the panels together. This method is shown on Drawing 209-R-8. On this drawing are also shown some suggestions for handling a monolith system which for one reason or another utilizes concrete filler sections placed between the monoliths after the monoliths are completed.

Drawing 209-R-9 shows some of the ways in which the intersections between transverse and face sliding forms may be handled including corner details for both lead and trailing monoliths and intersection between face forms

and premolded joints.

The slip forming system used here involves only hydraulic connections between the face forms and the transverse forms. Actually, the various face forming systems can be mechanically tied together supporting some system of platforms spanning between forms. Such a system would provide support for construction equipment, storage areas and access ways. The size, height and configuration of this dam is such that it is felt that such a "space platform" is not required and that there is some advantage to the flexibility obtained with the system shown.

Copper water stops may be placed as shown on Sketch 209-RS-15 utilizing a continuous keyway guided by the slip form and a bend-out leg.


The drain wells at the transverse joints may be slip formed in two halves as shown on drawing Sketch 209-SR-16.

The transverse bulkheads will slide past the fixed form gallery forms with no problems.


CONSTRUCTION SCHEDULE

The construction schedule for this work is shown on Sketch 209-SR-12. The schedule is based on work starting in the fall of 1972 with Phase I of concrete placing being completed late in the summer of 1973. Phase II of concrete placing is completed during the prime time of the construction season.

If work is delayed until the beginning of 1973, (SEE SKETCH 209-SR-13), concreting Phase I will be pushed into the late fall of 1973 but placing of Phase II will not be effected and completion by the end of 1974 will be adhered to.




PLAN




DOWNSTREAM ELEVATION



TRANSVERSE SECTION AT MONOLITH 6



P. H. CABELLERIE, P. CONTRACTING ENGINEER 1000 14TH ST. N.W. WASHINGTON, D.C. 20005		DEPARTMENT OF THE ARMY WASHINGTON, D.C. 20315	
WATER RESOURCES DEVELOPMENT PROJECT TRUMBULL LAKE REGUENOUCH RIVER BASIN, CONNECTICUT CONTINUOUS SLIP FORM OPERATION PHASE I (PRE-SLIP)			
DRAWN BY: [] CHECKED BY: [] DATE: []		SHEET NO. 209-R OF 209-R	




DOWNSTREAM ELEVATION




PARTIAL PLAN




J.F. CAMELLERE, P.E. LICENSE NO. 10100 STATE OF CONNECTICUT		DEPARTMENT OF THE ARMY CONSTRUCTION DIVISION WASHINGTON, D.C.
WATER RESOURCES DEVELOPMENT PROJECT TRUMBULL LAKE PELDONNOCK RIVER BASIN, CONNECTICUT		
CONTINUOUS SLIP FORM OPERATION PHASE II (SLIP & CANTILEVER)		
DRAWN BY: J.F. CAMELLERE CHECKED BY: J.F. CAMELLERE DATE: 10/15/64		SHEET NO. 2087-4 SHEET



SECTION THRU MONOLITH NO. 6



PLAN




SECTION A-A




STRENGTH THROUGH PAYMENTS

J. F. CAMELLERIE, PE CONSULTING ENGINEER 100 NORTH MAIN STREET WASHINGTON, D. C. 20004		DEPARTMENT OF THE ARMY 5100 BENTLEY AVENUE CAMP BUNNING WASHINGTON, D. C. 20315	
WATER RESOURCES DEVELOPMENT PROJECT TRUMBULL LAKE REGUONNOCK RIVER BASIN CONNECTICUT		DATE: _____ DRAWN BY: _____ CHECKED BY: _____ APPROVED BY: _____	
SCALE: NONE (SEE DET.) 209-R-3		SHEET NO. _____ TOTAL SHEETS _____	




WATER RESOURCE DEVELOPMENT PROJECT TRUMBULL LAKE CANTILEVERED SLIP FORM SYSTEM DOWNSTREAM FACE	
J. F. CAMBERLIE, P.E. CONSULTING ENGINEER NEW YORK	DRAWN BY: [] CHECKED BY: [] DATE: 209




FRONT VIEW OF SLIPFORM & SCAFFOLDING
DOWNSTREAM FACE

		WATER RESOURCE DEVELOPMENT PROJECT	
		TRUMBULL LAKE	
		CANTILEVERED SLIP FORM SYSTEM	
		DOWNSTREAM FACE	
DATE	REVISIONS	SCALE NONE	DATE: JUNE 1 1978
		DRAWN: B.E.C.	CHECKED: J.P.C.
		JOB NO. 209	FORM NO. R-5




SECTION THROUGH FORM



FRONT ELEVATION

J. F. CAMELLERIE, P.E. CONSULTING ENGINEER HARTFORD NEW YORK		WATER RESOURCES DEVELOPMENT PROJECT TRUMBULL LAKE CANTILEVERED SLIP FORM SYSTEM UPSTREAM FACE	
		SCALE: NONE	DATE: JUNE 1, 1978
DRAWING NO. 209		SHEET NO. 1 OF 1	
REVISIONS		DRAWING NO. 209	






INTERMEDIATE FORMING
DOWNSTREAM FACE
UPSTREAM FACE SIMILAR


FIX FORMING
TOP OF SLIP FORM
DOWNSTREAM FACE

FIX FORMING
TOP OF SLIP FORM
UP STREAM FACE


REVISIONS	WRITER RESOURCE DEVELOPMENT PROJECT	
	TRUMBULL LAKE	
	CANTILEVERED SLIP FORM SYSTEM	
	START & TOP	
DATE	DESIGNED BY	CHECKED BY
	J. F. CAMELIERNE, P.E.	ZAKI I. 1/27/74
	CONSULTING ENGINEER	DATE 4/7/74
	HARTFORD NEW YORK	JOB NO. 209
		DWG NO. R-7



CORNER DETAIL
TRAILING MONOLITH



ELEV. A-A
DOWNSTREAM OR UPSTREAM
ELEVATION




ELEV. B-B
ELEVATION AT TRANSVERSE FORM

CORNER DETAIL
LEAD MONOLITH



GRAPHIC SCALE

DESIGN	DATE	REVISIONS	BY
J. F. CAMELLERIE, P.E. CONSULTING ENGINEER 100 WEST STREET NEW YORK		DEPARTMENT OF THE ARMY WATER RESOURCES DIVISION CORPS OF ENGINEERS WASHINGTON, D.C.	
PROJECT: WATER RESOURCES DEVELOPMENT PROJECT			
LOCATION: TRUMBULL LAKE			
REGION: PEGUONNOCK RIVER BASIN CONNECTICUT			
OPERATION: CONTINUOUS SLIP FORM OPERATION			
INTERSECTION: SLIP FORM INTERSECTIONS			
APPROVED	DATE	BY	
SCALE: NONE			
SHEET: 209-R-9			



GRAPHIC SCALE

DATE		SCALE		BY	
J. J. WAMILLER, P.E. DISTRICT ENGINEER DISTRICT NO. 10 WATER RESOURCES DIVISION				UNIT OF THE ARMY TRUMBULL LAKE, CONNECTICUT	
PROJECT TITLE WATER RESOURCES DEVELOPMENT PROJECT TRUMBULL LAKE PEQUONNOC RIVER BASIN, CONNECTICUT				DRAWING TITLE CONTINUOUS SLIP FORM OPERATION CONSTRUCTION SITE LAYOUT	
DESIGNED BY	CHECKED BY	APPROVED BY	DATE		
SCALE 1" = 200' (SEE SHEET 209-R-10)				SHEET NO. 209-R-10 SHEET	

CONSTRUCTION COSTS

AND ANALYSIS

CONSTRUCTION COSTS

The cost of constructing the dam at Trumbull Pond using slip forms and belt conveyors and applying the same rates and pricing methods as used for conventional construction is \$6,830,000 - slightly less than that for conventional construction. Actually, the difference is about \$185,000 or 2-1/2 percent of the total dam cost.

SEE Cost and Summary Sheets ER-S and ER-1 thru ER-4.

Cost Analysis Sheets ECR-1 thru ECR-10 give a rearranged breakdown of the costs according to work groupings with payroll taxes and insurance included. These cost analysis sheets show both conventional and rapid construction costs and breakdown of direct costs by percentages.

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE July 1, 1972 REV.

SKETCH# E12-3A

TRUMBUEL LAKE DAM

NEW ENGLAND DIVISION CORPS OF ENGINEERS

HYDRAULIC PACKAGE

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Estimated Amount</u>
Gate Valves 16" Manual	2	Ea	\$1,000	2,000.00
Gate Valves 16" Automatic	4	Ea	1,600	6,400.00
Gate Valves 24" Manual	4	Ea	3,600	14,400.00
Gate Valves 24" Automatic	4	Ea	4,800	19,200.00
Gate Valves 36" Automatic	1	Ea	6,700	6,700.00
Water Supply Pipe 16"	225	LF	18.00	4,050.00
Water Supply Pipe 24"	200	LF	26.00	5,200.00
Water Supply Pipe 36"	600	LF	48.00	28,800.00
Blow Off Pipe 36"	90	LF	50.00	4,500.00
Double 3' x 4' Gates	1	Job	LS	70,000.00
Intake Screen, 24"	4	Ea	2,000.00	8,800.00
Bulkhead Gate	1	Ea	5,000.00	5,000.00
Gate Vent System	1	Job	LS	5,000.00
Float Well & Accessories	1	Job	LS	3,000.00
Heating & Vent. System	1	Job	LS	5,000.00
Crane & Hoist	1	Job	LS	7,140.00
Diesel Engine	1	Job	LS	10,000.00
Sump Pumps	1	Job	LS	5,000.00
Electric Systems	1	Job	LS	30,000.00
Grounding System	1	Job	LS	4,000.00
Tile Gage	1	Job	LS	4,000.00
Log Boom	1	Job	LS	10,000.00
Water Quality Control	1	Job	LS	3,300.00
Instrumentation	1	Job	LS	15,000.00
Downstream Measuring Weir	1	Job	LS	10,000.00
TOTAL COST - 1971				286,490.00
ESCALATION to 1972 @ 6%				17,189.40
COST IN 1972				303,679.40

J. F. CAMELLERIE P.E. 23 GREEN STREET HUNTINGTON, N.Y. 11743	DATE JUN 1, 1972 PRICED BY		SHEET NO. ER 4	
	PROJECT: TRUMBULL LAKE DAM			
	ARCHITECT: NEW ENGLAND DIV., CORPS/ENGR.			

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
EQUIPMENT						
TIMBER TRESTLE	480	L.F	73	35,000	37	17,800
YARD CRANE	1x12	MOS	4500	54,300	¹⁵⁰⁰ 1200	32,500
CONVEYOR SYSTEM	-	"		INCLUDED IN CONC PLAC		INCLUDED IN CONC. PLACING
HYDRAULIC BOOM CRANES	2x7	"	1500	21,000	1400	19,600
COMPRESSORS	2x7	"	1100	15,400	1300	18,200
UTILITY TRUCKS	2x15	"	800	24,000	940	28,200
PERSONNEL STAIR TOWERS	3x10	"	80	2,400	-	2,000
DOZER	1x15	"	1200	18,000	1330	20,000
	(SUB TOTAL)			(170,100)		(138,300)
FIELD OVERHEAD						
BRIDGE	1	EA.		1,000		5000
IMPROVE R.R. BED	268,000	#'	1 ⁵⁰	402,000		SUB
ACCESS ROAD VALLEY	72,000	#'	1 ⁰⁰	72,000		SUB
FIELD OFFICES, SHOPS, STORAGE				27,000		3,000
HARDWARE & TOOLS				45,000		-
FUEL & OIL				12,000		-
START-UP & LAYOUT				-		5,000
MIX DESIGNS				1,000		-
CONCRETE TESTING				25,000		SUB
TEMPORARY LIGHTING				3,000		10,000
SANITARY FACILITIES				5,400		SUB
CLEAN-UP				-		20,000
HEATING				20,000		-
PROJECT MANAGER	1 x 117	wks		-	500	58,500
SUPERINTENDANT	1 x 90	"		-	400	36,000
PROJECT ENGINEER	1 x 80	"		-	400	32,000
CLERKS	2 x 80	"		-	200	32,000
SURVEYORS	4 x 80	"		-	250	20,000
UTILITY MECHANICS	6 x 52	"		-	300	93,600
WATCH MEN	3 x 117	"		-	100	35,100
WINTER PROTECTION				2000		5,000
COMMUNICATIONS				5000		5,000
POWER DISTRIBUTION				10,000		10,000
SP 10196A	TOTAL FOR PAGE			800,500		568,500

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE 6.1.72 REV. SKETCH ECR-1

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONNECTICUT

COST ANALYSIS

TOTAL DIRECT COSTS

ITEMS	CONVENTIONAL CONSTRUCTION		RAPID CONSTRUCTION	
	Total Cost	% Direct Cost	Total Cost	% Direct Cost
Cementitious Mat'ls	347,000	9.9	349,300	10.1
Plant & Plant Oper.	1,699,608	48.8	1,607,805	46.6
Cooling	100,600	2.9	100,600	2.9
Conc. Placing & Vib.	134,634	3.8	107,730	3.2
Jnt. Treat., Finish., & Curing	207,364	6.0	159,108	4.6
Forms	535,658	15.4	659,630	19.1
Misc. Inserts	460,418	13.2	464,678	13.5
TOTAL DIRECT COSTS	3,485,282	100.0	3,448,851	100.0
Site Work	1,614,758		1,603,758	
Environment	281,400		222,280	
Field Overhead	690,960		640,128	
TOTAL COST TO CONTRACTOR - 1972	6,072,400		5,915,017	
Escalation thru 1974	302,320		287,400	
Overhead Profit & Contingency	510,000		496,300	
Bid Bond	52,000		50,500	
TOTAL CONTRACT PRICE	6,936,720		6,749,200	

Revised

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE 6.1.72 REV.

SKETCH# ECR-3

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONNECTICUT

COST ANALYSIS

PLANT & PLANT OPERATION				
ITEM	CONVENTIONAL CONSTRUCTION		RAPID CONSTRUCTION	
	Material	Labor	Material	Labor
Borrow Operation	72,000	69,500	72,000	69,500
Aggregate Prod.	128,000	78,500	128,000	78,500
Batch Plant Oper.	437,360	222,300	437,360	209,000
<u>SUB-TOTAL</u>	637,360	370,300	637,360	357,000
Cableway	254,000	77,470	-0-	-0-
Concrete Placing	8,000	-0-	125,000	24,300
Vibration	44,400	-0-	26,100	-0-
Slide Crew	-0-	-0-	-0-	36,500
Field Eng. (Slipform)	-0-	-0-	3,000	-0-
Field Tech. (")	-0-	-0-	4,500	-0-
Conveyors (")	-0-	-0-	12,500	7,000
Mat'ls Towers (")	-0-	-0-	28,800	34,000
Conv. Sup. Brkt	-0-	-0-	1,300	2,300
Conv. Sup. Truss	-0-	-0-	8,500	6,500
Elephant Trunk	-0-	-0-	500	-0-
<u>SUB-TOTAL</u>	306,400	77,470	210,200	110,600
Equipment	172,800	151,900	170,100	138,300
<u>TOTAL</u>	1,116,560	599,670	1,017,660	605,900
Less Cooling	47,000	47,000	47,000	47,000
<u>TOTAL</u>	1,069,560	552,670	970,660	558,900
Payroll tx & Ins (14%)		77,378		78,246
Labor & Mat. Total		1,699,608		1,607,805

R-29-

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE 6.1.72

REV.

SKETCH# ECR-5

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONNECTICUT

COST ANALYSIS

JOINT TREATMENT, FINISHING & CURING

ITEMS	CONVENTIONAL CONSTRUCTION		RAPID CONSTRUCTION	
	Material	Labor	Material	Labor
Horizontal Jnt Treatment	22,000	63,850	11,800	35,400
Finishing	7,300	41,000	3,600	20,200
Curing	4,300	4,300	3,100	3,100
Weekend Over Time	-0-	15,000	-0-	-0-
Slide Crew	-0-	-0-	-0-	30,500
Finishing (Slipform)	-0-	-0-	3,700	-0-
Curing (")	-0-	-0-	700	-0-
Copper Water Stops	14,000	16,000	14,000	18,000
TOTAL	47,600	140,150	36,900	107,200
Payroll tx & Ins (14%)	-0-	19,614	-0-	15,008
LABOR & MATERIAL TOTAL.....		<u>207,364</u>		<u>159,108</u>

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
 PEQUONNOCK RIVER BASIN, CONNECTICUT
 COST ANALYSIS

<u>FORMS.</u>				
	CONVENTIONAL CONSTRUCTION		RAPID CONSTRUCTION	
	Material	Labor	Material	Labor
Foundation	14,640	55,000	14,640	55,000
Lift Starters	5,520	15,000	4,800	6,000
Intermediate	-0-	-0-	1,900	7,800
SUB-TOTAL	20,160	70,000	21,340	68,800
Cantilever	46,200	125,600	31,600	39,000
Transv. Blkhead	22,200	60,400	20,500	25,300
Sliding Forms	-0-	-0-	10,600	16,000
Yokes	-0-	-0-	40,300	26,000
Jack Rods	-0-	-0-	35,000	1,800
Hydraulic Piping	-0-	-0-	-0-	3,200
Platform Decks	-0-	-0-	2,500	6,600
Railing & Ladders	-0-	-0-	7,500	4,100
Strip Forms	-0-	-0-	-0-	26,000
Form Design	-0-	-0-	10,000	-0-
Guide Wheel Brakts	-0-	-0-	15,000	-0-
Precast Inserts	-0-	-0-	44,000	-0-
Slide Crew	-0-	-0-	-0-	34,000
SUB-TOTAL	71,860	200,400	217,000	182,000
		continued on following	page.....	

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONNECTICUT

COST ANALYSIS

FORMS - continued

ITEM	CONVENTIONAL CONSTRUCTION		RAPID CONSTRUCTION	
	Material	Labor	Material	Labor
balance forward...	71,860	200,400	238,340	250,800
Spray Wall	240	1,200	240	1,200
Pump House Slab	1,850	2,470	1,850	2,470
Top Slab	590	1,760	590	1,760
Pump House Walls	5,310	14,160	5,310	14,160
Pump House Shoring	2,150	2,150	2,150	2,150
Top Dam	3,100	18,600	3,100	18,600
Ret. Walls	1,860	7,450	1,860	7,450
Top Curbs	1,650	4,950	1,650	4,950
Gallery & Stairs	11,110	30,500	11,110	30,500
Stair Tower	3,450	8,050	3,450	8,050
SUB-TOTAL	31,310	91,290	31,310	91,290
TOTAL	123,330	361,690	269,640	342,090
Payroll tx & Ins (14%)		50,638		47,890
TOTAL Labor & Material.....		535,658		659,630

Revised

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE 6.1.72

REV.

SKETCH# ECR-7

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONNECTICUT

COST ANALYSIS

MISCELLANEOUS INSERTS				
ITEM	CONVENTIONAL CONSTRUCTION		RAPID CONSTRUCTION	
	Material	Labor	Material	Labor
Hydraulic Package	303,680	-0-	303,680	-0-
Ext. 36" Blow-Off	5,000	2,000	5,000	2,000
3-1/2" Steel Pipe	4,060	6,380	4,060	6,380
2-1/2" Steel Pipe	3,760	7,530	3,760	7,530
3" Drain Holes	20,750	-0-	23,300	-0-
1-1/2" Grout Holes	73,920	-0-	73,920	-0-
6" Drains	4,150	-0-	4,720	-0-
8" Wells	2,140	-0-	2,140	-0-
Plumb Line Shaft	360	3,300	360	300
Reinforcing Steel	15,000	8,000	15,000	9,000
TOTAL	432,820	24,210	435,940	25,210
Payroll tx & ins. (14%)		3,388		3,528
TOTAL Labor & Material.....		460,418		464,678

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE 6.1.72 REV.

SKETCH# ECR-3

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONNECTICUT

COST ANALYSIS

SITE COSTS				
ITEM	CONVENTIONAL CONSTRUCTION		RAPID CONSTRUCTION	
	Material	Labor	Material	Labor
Clearing & Grubbing	18,000	-0-	18,000	-0-
Disposal	7,500	-0-	7,500	-0-
Excavation, Unclass.	72,000	-0-	72,000	-0-
Excavation, Rock	100,000	-0-	100,000	-0-
Excavation, Talus	42,000	-0-	42,000	-0-
Hand Cleaning	52,500	-0-	52,500	-0-
Chain Link Fence	3,000	1,700	3,000	1,700
Foundation Grouting	45,000	-0-	45,000	-0-
Diversion	714,000	-0-	714,000	-0-
Backfill	-0-	24,000	-0-	24,000
Rock Slope Prot.	2,400	8,000	2,400	8,000
Road Gravel	5,400	3,000	5,400	3,000
Bit. Conc. Pave.	6,000	-0-	6,000	-0-
Hand Rail	10,000	3,000	10,000	3,000
Bridge	1,000	5,000	1,000	5,000
Improve R.R. Bed	402,000	-0-	402,000	-0-
Access Road, Top	11,000	-0-	-0-	-0-
Access Road, Valley	72,000	-0-	72,000	-0-
TOTAL	1,563,800	44,700	1,552,800	44,700
Payroll Tx & Ins (14%)		6,258		6,258
LABOR & MATERIAL TOTAL		1,614,758		1,603,758

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE 6.1.72 REV. SKETCH# ECR -9
 TRUMBULL LAKE DAM
 PEQUONNOCK RIVER BASIN, CONNECTICUT
 COST ANALYSIS

<u>ENVIRONMENT</u>				
ITEMS	CONVENTIONAL CONSTRUCTION		RAPID CONSTRUCTION	
	Material	Labor	Material	Labor
Turbidity Control	90,000	-0-	80,000	-0-
Dust Control (Rds)	1,000	-0-	1,000	-0-
Noise Control	100,000	-0-	80,000	-0-
Landscape Renewal	25,000	10,000	5,000	2,000
Railroad Beds	54,000	-0-	54,000	-0-
TOTAL	270,000	10,000	220,000	2,000
Payroll tx & Ins (14%)		1,400		280
TOTAL LABOR & MAT.....		<u>281,400</u>		<u>222,280</u>

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE 6.1.72

REV.

SKETCH# ECR-10

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONNECTICUT

COST ANALYSIS

FIELD OVERHEAD				
ITEM	CONVENTIONAL CONSTRUCTION		RAPID CONSTRUCTION	
	Material	Labor	Material	Labor
From Cost Sheet	820,800	620,900	800,500	568,500
Less Items in Site Work	486,000	5,000	475,000	5,000
TOTAL	334,800	615,900	325,500	563,500
Less Equipment	172,800	151,900	170,100	138,300
TOTAL	162,000	464,000	155,400	425,200
Payroll tx & Ins (14%)		64,960		59,528
TOTAL Labor & Material		690,960		640,128

COST ANALYSIS

ANALYSIS OF CONSTRUCTION COSTS

As the savings in plant, placing, vibration and joint treatment are balanced by the increased cost of the forming system, the savings in direct costs is of a minor nature. The increased cost of the forming is brought about by the fact that in effect two completely different forming systems come into play reducing the reuse factors of both conventional cantilever and slip forms.

The savings in the system resulted from reduction of indirect costs such as Field Overhead, Environmental Control and Escalation costs as a result of reducing the construction time. Using Rapid Construction methods, that is to say, the combination of slip forms and belt conveyors, reduces concrete placing time by about 40 working days or just about two calendar months.

COST IMPACT OF DAM AND SITE CONDITIONS

It is interesting to note that such construction cost items as aggregate production, foundation treatment, foundation, abutment and starter forms, accessory structures, "plumbing", site work, excavation, access and stream diversion are captive to the site and basic design and cannot be influenced by innovations in construction technology. In the case of Trumbull Dam, these items amounted to 50 percent of the cost. When one considers that the two and one-half percent savings in total cost is really 5 percent of the area vulnerable to cost reduction the prospects seem brighter for larger dams where the ratio to "untouchables" is better.

COST OF FORMING SYSTEM

As discussed in "Analysis of Cost" above, the reuse factors are rather low for this dam. Actually, only half of the formed surface lends itself to a repetitive systemized forming system such as slip forming. The reuse factor for this expensive equipment is only 3-1/2 and the height to be slipped is limited, which means high erection and dismantling costs. In order to explore this idea further a study was made to determine the effect on form costs if

the contact area lending itself to this system were twice as large and again three times as large. We checked the effect of vertical increase, which saves in both material and erection cost, and horizontal increase which saves only in material cost. The results were as follows (SEE SKETCH ER-A1 thru ER-A11):

	<u>CONVENTIONAL FORMS</u>	<u>SLIP FORMS</u>
Trumbull Pond Cost	\$ 2.94 / ϕ'	\$ 4.66 / ϕ'
Twice Hor. Increase	2.86	4.00
Thrice Hor. Increase	2.74	3.80
Twice Vert. Increase	2.92	3.26
Thrice Vert. Increase	2.74	2.79

IMPACT OF FORMING SYSTEM ON PLANT AND EQUIPMENT

The cost savings that accrue from the slip form operation do not show up in the forming item but rather in plant and overhead items. Conveyor costs are improved by reducing repositioning of conveyors; batch plant utilization is improved; equipment rentals and field supervision salaries are of shorter duration. Sheets ER-A11 thru ER-A21 study the effects of doubling and tripling the areas lending themselves to slip forming. The results are summarized on sheets 209-SR-18A thru 20 together with forming costs based on cubic yards of concrete formed.

The curves indicate that with increase in height the combined forming-plant-overhead costs favor slip forming at a 60 percent increase in height. With horizontal increase in formed surface, slip forming gains at a very low rate.

IMPACT OF REDUCED CONSTRUCTION TIME

As a result of the additional 2 months required by the conventional methods the concreting operations are very tightly scheduled with work into November during both 1973 and 1974 and over-run time going into cold weather. The Rapid Construction allows concrete operations to be completed by September or October, both years with over-runs running into October. This capability to better schedule concrete operations relative to climatic conditions has a cost advantage which was not numerically evaluated in this report.

If start of construction is delayed until the beginning of 1973, this Rapid Construction may be able to pick up savings over Conventional Construction similarly delayed as follows:

50% of labor in 1973 at 8% escalation	4.0%
50% of labor in 1974 at 14% escalation	7.0%
	<hr/>
TOTAL	11.0%

75% of Purchases in 1973 at 8% escalation.....	6.0%
25% of Purchases in 1974 at 12% escalation.....	3.0%
	<hr/>
TOTAL	9.0%

The equivalent escalation for conventional construction going into 1975 is 13 and 10 percent respectively - (SEE conventional construction report).

This represents a saving of:

2% labor at \$2,000,000	\$40,000
1% material at \$4,000,000	40,000
	<hr/>
	\$80,000

Construction cost will be increased over a 1972 letting by 7% x \$4,000,000 or \$280,000.

COST OF CONVEYOR SYSTEM

The use of conveyors including the material hoist towers and slip form supports costs \$300,800 including payroll taxes and insurance. The cable way operation runs \$350,000 or \$50,000 more than the conveyors. The 24 inch conveyor sizing is based on 6 inch aggregate. If the maximum aggregate size were reduced to four inches, sixteen inch conveyors may be used to furnish the required capacity of 160 yards per hour. This would reduce conveyor cost by 30 percent of equipment cost or \$137,500 x .3 or \$41,000. Including escalation, overhead and profit the savings are \$43,000, using the 24 inch conveyors with an additional \$45,000, if four inch aggregate were used.

The use of four inch aggregate would increase the amount of portland cement required by, say - 5 percent or approximately \$20,000, leaving the savings of going to four inch aggregate at \$25,000. There are additional advantages that accrue from lighter weight equipment which we assigned no monetary value to.

COST OF CEMENTATIOUS MATERIALS

Savings in this area can be effected only by design and mix changes. Generally speaking, a thin layer of very high cement content concrete on the upstream face with the rest of the concrete at extremely low cement content and maximum flyash substitution is a direction for saving.

PLANT AND PLANT OPERATION

The plant cost for aggregate production, batching and placing (nearly half the total direct costs) is captive between the volume of concrete on one hand and the construction schedule on the other. The use of conveyors, compression of construction schedule and improved utilization did effect a savings of \$95,000 in this area but this is only a cost reduction of 5-1/2 percent. In order to make more significant cost reductions in this important area, the volume of concrete placed must be reduced. This militates against gravity dams. The use of prestressed rock anchors may have merits in this area.

CONCRETE PLACING AND VIBRATION

A savings of 20 percent was made in this area due to the better spreading abilities of the conveyor system, especially in the slip form placements. Actually, the savings was greater but some of the man hour savings went into premium time for shift work.

HORIZONTAL JOINT TREATMENT

The use of slip forming has reduced the number of horizontal joints and therefore the cost of joint treatment significantly. With other valley cross-sections this decrease can be much greater. The reduction in difficulties and "agony" connected with this work cannot be assigned a numerical value.

MISCELLANEOUS INSERTS

These ran slightly higher because of premium pay during slip operation.

SUMMARY, RECOMMENDATIONS

AND

DISCUSSION OF ADDITIONAL MODIFICATIONS

SUMMARY

The most effective application of rapid, economical construction methods to the dam at Trumbull lies in the combined use of slip forming and conveyor systems. This results in a time savings of two months and a minimum cost saving of \$185,000. Because of the size of this dam and the configuration of the valley, the application of innovative construction techniques was limited.

Tests at the Water Experiment Station in Vicksburg, Mississippi indicate no serious problems in the use of slip forms with mass concrete.

The equipment and skills required for constructing this dam by the methods recommended are readily available in the industry.

REVISIONS REQUIRED TO SPECIFICATIONS TO ALLOW USE OF THE
SYSTEM DESCRIBED

- 1- In order to meet slip form requirements, exterior mass concrete will be required on both upstream and downstream faces of the dam but not on the monolith interfaces.
- 2- Permit concrete placement of full height of monoliths without horizontal joints.
- 3- Delete maximum height difference requirement between adjacent monoliths. Insulation as specified in Paragraph --16_ "Special Protection", page 73 of guide specification CE-1401.01 may be required in project specifications.
- 4- Permit conveying of 6 inch aggregate by conveyors.

RECOMMENDATIONS

1- It is recommended that the use of 4 inch maximum size aggregate be given careful consideration as the use of six inch aggregate required placements of eighteen inches in depth. Allowing two hours between successive placements obtains a minimum placing rate of nine inches per hour. Considering the low strength gain of the mass concrete maintaining such a rate may be impossible in cold weather using the slip form system. In addition, the small aggregate will reduce problems and possibly sizing in all handling equipment as well as number of sizes stored.

2- The extension and gating of the overflow conduit is recommended to enable inclusion in stream diversion scheme.

3- It is highly desirable to implement a research and development program to develop a set regulated shrinkage retarded cement of medium early strength to be used as exterior mass concrete to allow more rapid construction and at the same time reduce shrinkage and thermal problems.

4- American contractors are traditionally conservative. It is recommended, therefore, that a promotional program be implemented to increase contractor enthusiasm and to allay fear of innovations.

5- The following design modifications are suggested as a means of achieving additional savings:

- a- The gallery layouts be oriented in elevation to the horizontal joints so that the support system can be simplified and systematized.
- b- That all sloped sections of the gallery be at one slope to enable reuse of forms and systematizing in general. Drawing 209-RM-1 shows two such layouts related to the jointing and using 45 degrees for all inclined sections. NOTE the horizontal to inclined transition sections become standardized.
- c- It is suggested that the transition from sloped surfaces to the vertical surfaces at the top of the dam be made at the same elevation on both faces of the dam and related to lift modules.

- d- The five foot vertical section at the bottom of the downstream face is extremely difficult to form. If possible this vertical section should be eliminated.
- e- Minimizing or eliminating the overhang of the roadway at the top of the dam (at the expense of additional concrete if necessary) will reduce cost in this area.
- f- An alternate for precasting the spray wall may be desirable as it will allow the unbroken use of the standard cantilevered forms.

**DISCUSSION OF ADDITIONAL
MODIFICATIONS TO PRESENT
DESIGN TO IMPROVE ECONOMICS**

CONTINUOUS CONSTRUCTION

Continuous construction, that is to say the partial or complete elimination of vertical bulkheads dividing the dam into monoliths has often been suggested by knowledgeable people in this field. The slip form system suggested for use at Trumbull Lake is one of the several arrangements possible and was not intended to rule out any other sequence or monolith combination. If the requirement for subdivision into monoliths is removed, it is possible to slip form large sections of the dam at one time using the slip form - belt conveyor combination. In order to study this possibility we decided to determine the cost of slip forming on a continuous basis a section of the dam comprising monoliths 4 thru 10 (420 lineal feet) starting at elevation 185'-0". In doing this, we neglected stream diversion problems and planned on placing concrete at a rate of 4 inches per hour (half the rate used in the original study). This slow rate keeps the required plant size down to a 160 yard/hour capacity, and is better suited to the slow strength pick-up of the concrete, making the use of less expensive anchors possible.

The cost of this construction is \$6,616,000 as shown on cost sheets EM-S and EM-1 thru 4. This represents a savings of \$134,000 from slip forming by monoliths and \$321,000 from conventional construction. This saving accrues from elimination of bulkhead forming and a four week reduction in construction time. This saving was reduced by the added plant cost of forms and conveyors to do the work in one operation. A variation of this alternate may be doing two or three monoliths at a time resulting in intermediate savings. Naturally, the inclusion of stream diversion by keeping down monolith 5 will reduce the savings very seriously while on higher dams the savings would be enhanced.

IMPACT OF NO-SLUMP CONCRETE

Continuous construction utilizing no-slump concrete is a possibility worthy of consideration. Drawing 209-RM-4 shows such a construction with the exterior mass concrete as normal slump concrete. The normal slump concrete is required at the faces because of the difficulty of compacting the no-slump concrete with hand vibrators.

In tests conducted by the Tennessee Valley Authority under the direction of R. W. Cannon, a mix having a slump of under one-half inch was successfully placed and compacted using trucks and a vibratory roller. The mix consisted of 94 lbs of Portland Cement, 130 lbs of fly ash, 3 inch maximum size crushed limestone and water reducing and air entraining admixtures.

On the Trumbull Site, truck hauling is not feasible, but the conveyor system devised is entirely adequate and spreads very uniformly. Vibratory rollers may be used in the 420 foot long section without problems. The no-slump concrete is placed in convenient stable layers and the areas between the no-slump concrete and the forms is then filled with normal concrete before placing the next layer of no-slump.

The only cost areas effected by this procedure as compared to continuous placing using low slump concrete are cementitious materials and vibration. These savings, as worked out on our cost sheet EM-S-5 is as follows for this particular situation:

Cementitious Material.....	\$48,500
Vibration	<u>9,500</u>
TOTAL	\$ 58,000

The switching back and forth between no-slump and low-slump concrete will create some hardship on the batch plant and conveying operations but it is felt that our plant is capable of absorbing the difficulties without cost increases.

CONTINUOUS MIXER PLANT

The yardage and rate of placing requirements for this particular project do not warrant consideration of a continuous type of mixer plant. The use of two 4 yard mixers is not only adequate, it provides the capability of continuing operations with one mixer if the other mixer temporarily breaks down. An important consideration in using a continuous type mixing plant is the lead time for design and procurement.

PLANT PLACED ON MONOLITH

Placing a plant directly on the monoliths presents some problems and in this particular situation no advantages. Conveying materials to the moving plant presents a problem because of the constantly changing elevation, but this problem is not too serious as dry aggregates can be raised in bucket elevators when conveyor inclines become too steep and dry aerated cement can be pumped vertically. The conveying systems must of course, have flexibility designed into the layout. A hydraulically activated support tower will also have to be incorporated into the plant. On the positive side, the materials hoist towers can be eliminated; raising dry materials is always more desirable and less expensive than raising wet concrete.

The two serious impediments are those which occur at the base and at the top of the dam construction. Initially, a concrete supply is required before sufficient structure is available to support the plant on the monoliths. It is possible to set the plant on a tower supported directly on rock with a pick-up arrangement as the work progresses. This can be done when conditions warrant the expense and possibly delay involved and when the well, left to be filled in later, is not objectionable.

At the top, the dimension of the dam is greatly reduced, in this case to ten feet. The small depth of the dam as well as the constantly changing dimension offer physical problems to the support of the plant as well as to distribution.

It is conceivable that for larger dams of a different design a plant can be mounted on the monoliths. Gravity dams do not present much hope in this direction.

PRECAST, LEAVE-IN-PLACE, CONCRETE FORMS

This type of form has been used in Europe and some success was claimed for this type of forming. Leave-in-place forms offer two major advantages: saving of stripping time and a guaranteed good surface. They are at least as difficult to place as wood or steel cantilever forms and

require high capacity cranes on a continuous basis. In addition, a precast yard must be set up on the site and a handling system must be designed to transport the forms from the casting yard to the crane pickup point. As an alternate, these forms may be obtained from an established precast yard and transported at some cost in trucking and annoyance to nearby communities.

The most important concept that must be kept in mind is that only a relatively small number of steel forms need be brought to the monoliths from their point of fabrication. After their first installation the movements are mostly vertical by hand, davits, jacks or very light duty jacks; there is a minimum of horizontal movement. The form weight is half the weight of the precast panels. On the other hand, each and every precast form panel, that is to say, a very large number of precast panels must be transported from their point of fabrication to the point of installation. This involves expensive horizontal logistics.

In addition, precast panels have the same anchor problems related to hydrostatic pressures from concrete that all other forms have; this pressure militates in favor of heavier sections, heavy reinforcement to take cantilever stresses from anchors in the lift below and reinforcement for handling stresses during transport. Add to this the cost of lifting inserts and adjustment devices and you have a fairly expensive form. Again, you do save stripping.

Light weight concrete is often used to reduce weight and thermal stresses. The handling savings accrued from using lightweight concrete will probably be more than offset by the complications resulting from handling a different family of aggregates than are being batched for the in-situ concrete.

Two systems of precast concrete forms were considered as part of this study; one a checker-board system spanning laterally and vertically and well suited to continuous operations; the other a typical cantilever system. These systems are shown on sheets EM-F1, EM-F2 and EM-S17 thru EM-S22.

The cost of implementing these systems at Trumbull are \$295,000 and \$335,000 respectively. The cost of using standard cantilever forms is \$172,000.

PRECAST GALLERIES

The relative economy of precast concrete galleries versus forming the galleries in place was investigated for this particular dam. Two arrangements were used as shown on Drawings 209-RM-1 & RM-2.

Arrangement A envisions channel sections with pouring ports in the roof which rest on support beams blocked or shimmed on the top of a concrete lift. The trough is formed by separate rectangular beams also resting on the support beams.

Arrangement B is oriented to have the top of the support beam at the top of a concrete lift to act as a screed and be in position to receive the channel section forming the roof and walls of the gallery which will be placed in the next lift. This arrangement requires support to the top of the next lower lift and a full precast trough. As an alternate to using the precast columns, steel trestles may be used to support the support beam to exact elevation.

In both cases standardization of sections and simplicity of forming was given serious consideration. A casting yard was assumed to the northeast of the batch plant with a small crane and a flat bed trailer for handling the sections. Erection was assumed to be handled by the three cranes included in the general equipment item and not picked up here.


The total cost for casting and erecting the galleries in precast sections as shown on cost sheets EM-G, EM-S6 thru S17 is \$59,400 not including pertinent percentages. The cost of forming the galleries is \$41,600.

SUMMARY


The amount of money that may be saved by applying advance construction techniques to the building of a small gravity dam such is the one at Trumbull Lake, is limited by design and site conditions to less than ten percent.

By using slip form construction omitting vertical joints to the extent possible, substituting belt conveyors for a cableway, reducing aggregate size and using no-slump concrete about \$400,000 may be saved. This represents approximately 6 percent of the total cost.

The opportunity for savings would obviously be greater on larger dams and in some instances dams having different configurations. To effect savings beyond ten or fifteen percent, radical design changes must be considered using structural concrete with or without low cement fills.




CONVENTIONAL FORM PLACING SEQUENCE
ALTERNATE PRECAST ARRANGEMENT 'B'




SLIP FORM PLACING SEQUENCE
PRECAST ARRANGEMENT 'A'




J. F. CAMERON, PE CHIEF ENGINEER DATE: 1968		DEPARTMENT OF THE ARMY WASHINGTON, D. C. 20315 DATE: 1968	
WATER RESOURCES DEVELOPMENT PROJECT TRUMBULL LAKE PELLISSAND RIVER BASIN, CONNECTICUT			
PRECAST CONCRETE GALLERIES GENERAL ARRANGEMENT			
OFFICE: SUPERVISOR: DRAWN BY: CHECKED BY: DATE: SHEET: 209-101-1			




GALLERY ARRANGEMENT A




SECTION A-A




DETAIL AT BOTTOM OF GALLERY VERTICAL TRANSITION




GALLERY ARRANGEMENT B



DETAIL AT TOP OF GALLERY VERTICAL TRANSITION



SECTION B-B




STEEL FRAME SUPPORT ALTERNATE




GRAPHIC SCALE

DATE	DESCRIPTION	BY	APP'D
J. F. CAMELLERIE, P.E. CONSULTING ENGINEER 1000 FARMINGTON ROAD FARMINGTON, CT 06030		DEPARTMENT OF THE ARMY WASH DC 20315-5000 CORPS OF ENGINEERS 385 THOMAS ST WASHINGTON, DC 20315	
PROJECT	WATER RESOURCES DEVELOPMENT PROJECT		
LOCATION	TRUMBULL LAKE		
CONTRACT NO.	PEQUONNOCK RIVER BASIN CONNECTICUT		
SECTION	PRECAST CONCRETE GALLERIES		
SECTION NO.	SECTIONS & DETAILS		
DESIGNED BY	APPROVED	DATE	SCALE
SCALE	DATE	SCALE	DATE
209-71-2		SHEET	



DOWNSTREAM ELEVATION




PLAN

NOTE: FOR CONVEYOR SUPPORT DETAILS
SEE DWG RM-4.




GRAPHIC SCALE

DESIGN	DATE	REVISION	BY
J. F. CAMELLERIE, P.E. CONSULTING ENGINEER HUNTINGTON, NEW YORK		DEPARTMENT OF THE ARMY NEW CANAAN DIVISION CORPS OF ENGINEERS HUNTINGTON, NEW YORK	
SCALE	DATE	BY	DATE
J.F.C.	11/22/55	J.F.C.	
WATER RESOURCES DEVELOPMENT PROJECT TRUMBULL LAKE PEQUONNOK RIVER BASIN CONNECTICUT			
CONTINUOUS SLIP FORM OPERATION WITH TRANSVERSE JOINTS ELIMINATED			
APPROVED	DATE	BY	DATE
SCALE NONE	SPEC. NO.	DRAWING NUMBER	
		15-211-3	
SHEET			



SECTION THRU MONOLITH NO. 6



PLAN



ENGINE SCALE

DATE	BY	APPROVED	BY
J. F. CAMELLERIE, PE CONSULTING ENGINEER MANUFACTURING		DEPARTMENT OF THE ARMY WEST ENGINEERING DIVISION CORPS OF ENGINEERS	
WATER RESOURCES DEVELOPMENT PROJECT			
TRUMBULL LAKE			
PEQUONNOK RIVER BASIN CONNECTICUT			
CONTINUOUS SLIP FORM OPERATION UTILIZING NO SLUMP CONCRETE			
DRAWN		CHECKED	
SCALE		DATE	
209-PM-4			

COST AND FEASIBILITY STUDY
ALTERNATE DESIGNS TO PERMIT USE
OF SLIP FORM AND OTHER TECHNIQUES
TO MAXIMIZE ECONOMIES

BOOK RA

RAPID CONSTRUCTION UTILIZING SLIP FORM TECHNIQUE

APPENDIX: ILLUSTRATIONS AND CALCULATIONS

BOOK RA - RAPID CONSTRUCTION UTILIZING SLIP FORM TECHNIQUE

APPENDIX: ILLUSTRATIONS AND CALCULATIONS

Page RA-2 Illustrations

Page RA-26 Calculations

- 1 Schedule 209-SR-1 through SR-20
- 2 Sketches 209-W-4 and W-5
- 3 Sketches 209-CR-1 through CR-14

ILLUSTRATIONS

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11 1972 REV.

SKETCH # SK-1

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

SLIP FORM CONSTRUCTION

CONCRETE DEMAND SCHEDULE				
MONTH -				
WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE $\frac{Yds}{HR}$	REMARKS
1	1	660	110	
2	2	530	90	
3	3	115	20	
4	4	530	90	
5	5	440	75	
6	6	960	160	
7	7	1000	160	
8	8	750	125	
9	9	1090	160	
10 x 2	10	1860	155	
11	11	540	90	
12	12	314	50	
13 x 2	13	1870	155	
14 x 2	14	1120	95	
15 x 2	15	1180	100	
16 x 2	16	1650	135	
17	17	340	60	
18	18	160	15	
19 x 2	19	1710	140	
20 x 2	20	1350	115	
21 x 2	21	1430	120	
22 x 2	22	1650	135	

Revised

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11 1972 REV.

SKETCH # 05-C

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

SLIP FORM CONSTRUCTION

CONCRETE DEMAND SCHEDULE

MONTH-

WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE $\frac{Yds}{HR}$	REMARKS
23	23	315	50	
24	24	695	115	
25 x 2	25	1730	145	
26	26	610	100	
27 x 2	27	1485	125	
28 x 2	28	1550	130	
29	29	320	55	
30 x 2	30	1340	110	
31 x 2	31	1500	125	
32	32	225	40	
33 x 2	33	1330	110	
34	34	65	10	
35	35	425	70	
36	36	225	40	
37 x 2	37	1270	105	
	END OF PHASE "I"			

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11 1972 REV.

SKETCH# S.R

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CON

SLIP FORM CONSTRUCTION

CONCRETE DEMAND SCHEDULE

MONTH -

WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE ^{Yds} / _{HR}	REMARKS
38 x 2	38	1240	105	START PHASE II
39	39	200	35	
40	40	385	65	
41 x 2	I	158/FT MAX	92 @ 7"	
42 x 3		33/FT MIN.	25 @ 9"	
43 x 3		96/FT AVER.	64 @ 8"	
44 x 3		67.5 FT		
45 x 2		6485 TOTAL		
46		41	1020	160
47	42	60	10	
48	43	935	155	
49 x 2	44	1280	105	
50 x 2	45	1200	100	
51 x 2	II	186/FT MAX.	108 @ 7"	
52 x 3		33/FT MIN.	25 @ 9"	
53 x 3		110/FT AVER.	73 @ 8"	
54 x 3		82.5 FT		
55 x 5		9065 TOTAL		
56 x 2		46	1440	120
57	47	1040	160	
58	48	620	105	
59	49	90	15	

Revised

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1 1972 REV.

SKETCH # SR - 4

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

SLIP FORM CONSTRUCTION

CONCRETE DEMAND SCHEDULE

MONTH -

WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE $\frac{Yds}{HR}$	REMARKS
60	50	175	30	
61x2	III	158/FT MAX.	92@7"	
62x3		33/FT MIN.	25@9"	
63x3		96/FT AVER.	64@8"	
64x3		67.5 FT		
65x2		64.85 TOTAL		
66	51	350	60	
67x2	52	1360	115	
68	53	1030	160	
69	54	300	5	
70	55	135	25	
71x2	IV	186/FT MAX.	108@7"	
72x3		33/FT MIN.	25@9"	
73x3		110/FT AVER.	73@8"	
74x3		82.5 FT		
75x5		9.065 TOTAL		
76	56	980	160	
77	57	615	105	
78	58	200	35	
79	59	290	50	
80	60	705	120	

Revised

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
 PEQUONNOCK RIVER BASIN, CONN.
 SLIP FORM CONSTRUCTION

CONCRETE DEMAND SCHEDULE				
MONTH -				
WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE ^{Yds} / _{HR}	REMARKS
81 x 2	VI	186/FT MAX.	108@7"	
82 x 3		33/FT MIN.	25@9"	
83 x 3		110/FT AVER.	73@8"	
84 x 3		82.5 FT		
85 x 5		9,065 TOTAL		
86	61	830	140	
87	62	800	135	
88	63	260	45	
89	64	595	100	
90	65	205	35	
91 x 2	V	172/FT MAX.	100@7"	
92 x 3		33/FT MIN.	25@9"	
93 x 3		103/FT AVER.	67@8"	
94 x 3		75 FT		
95 x 3		7,700 TOTAL		
96	66	800	135	
97	67	720	120	
98	68	490	80	
99	69	135	25	
100	70	325	55	

Revised

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1 1972 REV.

SKETCH

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

SLIP FORM CONSTRUCTION

CONCRETE DEMAND SCHEDULE

MONTH -

WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE ^{Yds} / _{HR}	REMARKS
101 x 2		200/FT MAX.	117@7"	
102 x 3		76/FT MIN.	67@9"	
103 x 3	VII	133/FT AVER.	92@8"	
104 x 3		70.0 FT		
105 x 2		9500 TOTAL		
106 x 2	VIII	20 FT	33@8'	
107 x 2		1,000 TOTAL		
108	71	800	135	
109	72	615	105	
110	73	670	110	
111	74	250	40	
112	75	610	100	
113	76	690	115	
114	77	510	85	
115	78	480	80	
116	79	30	5	
117	80	610	100	
118	81	615	105	
119	82	405	70	
120	83	190	30	
121	84	190	30	
122	85	190	30	

Revised

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1 1972 REV.

SKETCH# 512 7

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

SLIP FORM CONSTRUCTION

CONCRETE DEMAND SCHEDULE

MONTH-

WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE $\frac{Yds}{HR}$	REMARKS
123	86	510	85	
124	87	300	50	
125	88	300	50	
126	89	190	30	
127	90	185	30	
128	91	405	70	
129	92	40	5	
130	93	190	30	
131	94	185	30	
132	95	185	30	
133	96	300	50	
134	97	185	30	
135	98	190	30	
136	99	295	50	
137	100	295	50	
138	101	185	30	
139	102	295	50	
140	103	295	50	
141	104	40	5	
142	105	40	5	
143	106	295	50	
144	107	40	5	

Revised

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.


DATE JUN 1, 1972 REV.

SKETCH # 209-SB-Y


TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN

CANTLIVER SLIP FORM - PRECAST INSERT



FRONT FACE ELEVATION




SECTION B-B

J. F. CAMELLERIE, P.E.
25 GREEN STREET
HARTINGTON, N. Y.

DATE JUN 1, 1912 REV.
TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CONN.
CANT. SLIP FORM-WHEEL BRACKETS

WHEEL-BRACKET



J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUN. 1, 1972 REV.


SKETCH # 209-SR-

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

CANTILEVER SLIP FORM - INSERT SUPPORT

CUT ENDS SQUARE
& GRIND IF NECESSARY



VERTICAL PIPE SUPPORT
FOR PRECAST CONCRETE BLOCK

CONSTRUCTION SCHEDULE - RAPID CONSTRUCTION

MONTH YEAR	JAN.	FEB.	MAR.	APR.	MAY	JUNE	JULY	AUG.	SEPT.	OCT.	NOV.	DEC.
1972										PROCUREMENT		
										STRIPPING		
1973	PROCUREMENT			DIVERSION - STAGE I						DIVERSION - STAGE II		
			STRIPPING					CONC. PHASE I				
				PLANT ERECTION								
1974						CONCRETE - PHASE II						
										C.D. & E. *		

* CLEAN UP, DEMOBILIZATION & ENVIRONMENT

CONTRACTURAL COMPLETION DATE DEC 31, 1974

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN CONN.
CONSTRUCTION SCHED. - RAPID CONSTR

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
 PEQUONNOK RIVER, BASIN, CONN.
 RAPID CONSTRUCTION SCHED. - DELAYED CONST. ST.

RAPID CONSTRUCTION SCHEDULE - DELAYED CONSTRUCTION START

MONTH YEAR	JAN.	FEB.	MAR.	APR.	MAY	JUNE	JULY	AUG.	SEPT.	OCT.	NOV.	DEC.
1973	PROCUREMENT					PLANT ERECTION						
		STRIPPING			DIVERSION - STAGE I				CONC. PHASE I			
					CONCRETE - PHASE II							
1974	DIVERSION - STAGE II								C. D. A. E. *			

* CLEAN UP, DEMOBILIZATION & ENVIRONMENT

CONTRACTURAL COMPLETION DATE DEC. 15, 1974 — 1974

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUN. 1, 1972 REV. APR. 1, 1974 SKETCH # 209-SR-14

TRUMBULL LAKE DAM




PEQUONNOCK RIVER BASIN, CONN.

SLIP FORM SCHEDULES

SLIP FORM CONSTRUCTION SCHEDULE

WORKING DAYS



16 21 26 31 36 41 46 51 56 61 66 71 76 81 86 91 96 101 106 111 116 121



Revised


J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 9, 1928 REV. SKETCH# 209-SR-15
TRUMBULL LAKE DAM
PEQUONNOK RIVER BASIN - CONN.
COPPER WATERSTOP PLACING DET.




J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN - CONJ
DRAIN WELL FORMING.



PLAN - LEAD MONOLITH

PLAN - TRAILING MONOLITH



SECTION A-A

ANCHOR PULL OUT SUMMARY

TEST RESULTS - WATER EXPERIMENTATION STATION

AGGREGATE	DISCHARGE TEMPERATURE	TEMPERATURE IN FORM	AGE IN FORM	COMPRESSION STRESS	TENSILE STRESS	TYPE OF ANCHOR	ANCHOR EMBEDMENT	PULL OUT STRENGTH	REMARKS
"TRUMBULL POND	51°F	59°F	8 hr.	—	1.2 psi	II	2'-6"	2,500#	
"	51°	59°	8	—	2.1	I	2'-6"	5,100#	
"	51°	59°	8	—	1.4	I	2'-6"	6,000#	
CRUSHED LIMESTONE	47°	57°	8	24 psi	3.2	I	5'-0"	12,300#	
CRUSHED LIMESTONE	47°	57°	12	56 psi	9.1	I	5'-0"	*14,300#	

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1, 1972 REV.
 TRUMBULL LAKE DAM
 PEQUONNOK RIVER BASIN, CONN.
 FORM ANCHOR TESTING

SKETCH# 209-SR-1B

1. CEMENT FACTOR 2.61 CWT WITH 35 PERCENT FLY ASH SUBSTITUTION

2. AMBIENT TEMPERATURE = 73°

* CRACKING OF MONOLITH INDICATED THAT PULL OUT STRENGTH WAS NOT FULLY DEVELOPED DUE TO SIZE OF MONOLITH

CONCRETE SET & STRENGTH GAIN SUMMARY

TEST RESULTS - WATER EXPERIMENTATION STATION

AGGREGATE	DISCHARGE TEMPERATURE	TEMPERATURE IN FORM	AGE OUT OF FORM	COMPRESSION STRENGTH	TENSILE STRENGTH	AGE AT 500 PSI PENETRATION	JACKING LOAD LB/FT FORM	REMARKS
3" CRUSHED LIMESTONE	70°F	70°F	2 TO 3 HRS			5 TO 6 HRS	WOOD 100 TO 300	
6" CRUSHED LIMESTONE	70°	70°	5 TO 8 HRS			5 TO 6 HRS	WOOD 200 TO 400	
6" TRUMBULL POND	51°	59°	4 TO 6 HRS		1.2 TO 2.1 PSI @ 8 HRS	7 TO 8 HRS	WOOD 400 TO 600	
6" TRUMBULL POND	51°	59°	3 TO 4 HRS		1.2 TO 2.1 PSI @ 8 HRS	7 TO 8 HRS	WOOD 400 TO 600	
6" CRUSHED LIMESTONE	47°	57°	2 TO 4 HRS	24 PSI @ 8 HRS	3.2 PSI @ 8 HRS	8 TO 9 HRS	STEEL 150 TO 250	
6" CRUSHED LIMESTONE	47°	57°	3 TO 4 HRS	5.6 PSI @ 12 HRS	9.1 PSI @ 12 HRS	8 TO 9 HRS	STEEL 150 TO 250	

1. CEMENT FACTOR 2.61 CWT PER YARD WITH 35% FLY ASH SUBSTITUTION.
2. AMBIENT TEMPERATURE = 73°

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1, 1972 REV.
 TRUMBULL LAKE DAM
 PEQUONNOK RIVER BASIN, CONN.
 CONCRETE STRENGTH GAIN.
 SKETCH# 209-521

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUL. 1, 72 REV. APR. 1, 1974 SKETCH # 209. SR

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

COMPARISON SHEET

AREAS CAPABLE OF BEING SLIPPED

		CONV. COST/YD.	RAPID COST/YD.	DIFF.
AS IS	FORMS	3.72	5.91	+2.19
	PLANT + OPER.	3.52	3.24	-0.28
		<u>7.24</u>	<u>9.15</u>	+1.91
TWICE AS LONG	FORMS	3.62	5.10	+1.48
	PLANT + OPER.	2.74	2.75	+0.01
		<u>6.36</u>	<u>7.85</u>	+1.49
3 X. AS LONG	FORMS	3.45	4.80	+1.35
	PLANT + OPER.	2.42	2.50	+0.08
		<u>5.87</u>	<u>7.30</u>	+1.43
TWICE AS HIGH	FORMS	3.70	4.16	+0.46
	PLANT + OPER.	2.74	1.15	-1.59
		<u>6.44</u>	<u>5.31</u>	-1.13
3 X AS HIGH	FORMS	3.45	3.52	+0.07
	PLANT + OPER.	2.40	0.65	-1.75
		<u>5.85</u>	<u>4.17</u>	-1.68

Revised

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.


DATE JUN 1, '72 REV APR. 1, 1974 SKETCH # 209-SR-19

TRUMBULL LAKE DAM

PEQUONNOC RIVER BASIN, CONN.

COMPARISON

COST
\$/c.y.




FORM & PLANT COST VARIATION BY DAM HEIGHT

Revised

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUN. 1, 1972 REV APR. 1, 1974 SKETCH # 209.5R-20
TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CONN.
COMPARISON



FORM & PLANT COST VARIATION BY DAM LENGTH

Revised

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.


DATE JUN 1, 1972 REV.

SKETCH #209-W-4


TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

SUGGESTED TEST PROCEDURES, BLOCK II



FRONT FACE ELEVATION



SECTION B-B


J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.


TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN

SUGGESTED TEST PROCEDURES, BLOCK II



FRONT FACE ELEVATION



SECTION A-A

CALCULATIONS

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE June-1, 1972 REV.

SKETCH # 204-CK-T

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN Conn.

SLIP FORMING SYSTEM, DOWN STREAM, E.C.

GRAVITY LOADING

MOMENT

<u>ITEM</u>		<u>WT.</u>	<u>M.A.</u>	<u>+</u>	<u>-</u>
YOKE BEAM.	39 x 16.67	654 #	0		
YOKE EXTN.	8 x 7.4	59.2 #	6.25		370
YOKE EXTN. (WITH PLATFORM)	8 x 10	80	8.5		680
MAIN PLATFORM.	36 x 5	180	2		360
<u>FINISH PLATFORM</u>					
(1) PLYWOOD	32 x 2				
[]	= 64				
	16 x 10.5				
	= 168	232	3.6	835	
(2) PLYWOOD	40 x 2				
	= 80				
[]	16 x 10.5				
	= 168	248	5	1240	
RAILING	9.8 x 4.5 x 2				
	= 89				
	2 x 40				
	= 80	169	6.5	1100.	
<u>LADDER</u>					
1)	4.5 x 18	81	3.6	290	
2)	8 x 18	144	1	144	
3)	8 x 18	144	5.8	835	
		<u>1991</u>		<u>3609</u>	<u>2245</u>

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1, '72 REV.

SKETCH# 209-CR-2

TRUMBULL LAKE DAM.

PEQUONNOCK RIVER BASIN, CONN.

SLIP FORMING SYSTEM, DOWN STREAM, F.
 MOMENT.

ITEM.	WT. 1991	M.A.	MOMENT	
			+	-
WOODEN PLATFORM SUPPORT.			3609	2245
	1.75x7.5x2	30		30
PROP -	3.5x7x2	49	0	-
PORTAL FRAME				
	56x11.8	672	2.25	1490
WOODEN WALES				
	3x36 = 108		3.2	337
FORM SHEATHING				
	32x2 = 64 <u>172</u>	172	3.25	557
SPLASH GUARD				
	2x3x7.4 = 45 1.6x8x2 = 25 <u>70</u>	70	6.0	420
JACK ROD WITH JACK				
	40	7		280.
	<u>3024</u>		<u>3609</u>	<u>5359</u>


$$C.G. = \frac{(5359 - 3609)}{3024} = .58' \text{ INBOARD OF TOP ANCHOR AT FACE OF DAM}$$

TRAVEL = 2.0' EACH WAY


J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

JUNE 1, 1972
TRUMBULL LAKE DAM.
PEQUONNOK RIVER BASIN, CONN.
SLIP FORMING SYSTEM, DOWNSTREAM, E.C.

WEIGHT & FORCE STUDY



DRAG = $300 \text{ #/LF} \times 8 = 2400 \text{ #}$
 L.L. = 25 #/ft
 $= 25(8) = 200 \text{ #/FT WIDTH}$
 HYDRO PRES = $225 \text{ #/ft}^2 \times 3 = 675 \text{ #/ft}^2$
 $675 \times 8 = 5400 \text{ #/Yoke}$



$\cos \theta = .6$
 $\sin \theta = .8$
 $\tan \theta = 1.33$

$F_2 = F \cos \theta$
 $F_1 = F \sin \theta$

CASE - 1 CONSIDERING THE WORST CASE, WHEN THE WHEEL IS AT THE LOWER LEVEL, $R_u - R_v$ POSITION.

DL + PART. L.L. JACK LOAD = $4700(.8) = 3280 \text{ #}$

	WT.	M.A.	+	-
L.L. ON FINISHING PL. 1.	(500)	3.0	(1500)	
L.L. ON FINISHING PL. 2.	(400)	1.6	(640)	
LL. ON MAIN PL.	900	4.00		3600
L.L. ON TOP PL.	200	10.5		2100
JACK			↑ -3280	.67 2200
D.L.			3000	2.58 7740

$R_u = \frac{13440 - 2200}{4} = 2.8 \text{ # T}$
 $R_v = (.60)(3280) + (.8)(2800) = 5.3 \text{ # C}$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
 PEQUONNOCK RIVER BASIN, CONN.
 SLIP FORMING SYSTEM, DOWN STREAM, F.


CASE II

D.L. + HYDROSTATIC + PARTIAL L.L. (WHEEL AT LOWEST POS)

JACK LOAD:

400 (.8) (500)
 320 (.8) (400)
 2400 (.8) (3000)
 0 (0) (5400)
 2400 (1.0) (2400)

 5520



	WT.	M.A.	+	-
L.L. ON FINISHING PL. 1.	500	3.0	1500	
L.L. ON FINISHING PL. 2.	400	1.6	640	
L.L. ON TOP PL.	(200)	10.5		(2100)
L.L. ON MAIN PL.	(900)	4.0		(3600)
D.L.	3000	2.58		7740
HYDROSTATIC	(5400)	11.5	62000	
DRAG	2400	0		
JACK	5520	.67	3,680	
	1840		67,820	7740

$$R_L = \frac{(67,820 - 7,740)}{4} = 15.0 C$$

$$R_u = .6(5520) + .6(2400) - (.8)(5400) - .8(15,000) = 17,760$$


$$R_u = 14.450/A = 18.1^k T$$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 11, 1964
 TRUMBULL LAKE DAM,
 PEQUONNOCK RIVER BASIN, CONN.
 SLIP FORMING SYSTEM, DOWN STREAM, E.C.

CASE - III

ALL LOADING INCLUDED
 WHEEL @ HIGHEST POSITION



	WT	M.A.	+	-
L.L. ON FINISHING PL. 1 -	500	7.0	3500	
L.L. ON FINISHING PL. 2 -	400	5.6	2240	
L.L. ON MAIN PL.	900	0.0		
L.L. ON TOP PL.	200	6.5		1300
D. L.	3000	1.42	4260	
	5000		10,000	1,300
DRAG (2400) (.8)	1920		-	-
	6920		10,000	1,300
JACK	6400	.67	4,300	
			14,300	1,300
HYDIZO STATIC	5400	7.5	40,500	
	1440		54,800	1,300


$R_L = 13.4^k C$

$R_U = \frac{(5.4 + 13.4)(.8) + (2.4 - 6.4)(.6)}{0} = 15.7^k T$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

REV. 11-10
 SHEET 204-012-0
 TRUMBULL LAKE DAM
 PEQUONNOK RIVER BASIN, CONN
 SLIP FORMING SYSTEM, DOWNSTREAM FC.

JACK LOAD.



$$\begin{aligned} \text{JACK LOAD} &= 24000\# \text{ DL + L.L. (5000) (18)} \\ &\quad 2400\# \text{ DRAG (2400)} \\ &= 6400\# \text{ AXIAL} \end{aligned}$$

USE 3 TON JACK

LOADING SUMMARY

JACK	6.4 ^k	
Rupper	18.1 ^k TENSION (PULL OUT)	
	5.3 ^k COMPRESSION	
R LOWER	15.0 ^k COMPRESSION	
	2.8 ^k TENSION (PULL OUT)	

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUN 17 1972 REV.

SKETCH# 209-CV-1

TRUMBULL LAKE DAM

DEQUONNOK RIVER BASIN, CONN.

SLIP FORM SYSTEM, VERT. FORMS

UPSTREAM SLIPFORM

WEIGHT OF MEMBERS & C.G.

MOMENTS

	WEIGHT	DIST.		+		-	
		1:12	VERT	1:12	VERT	1:12	VERT
YOKE BEAM 20x22"	440"	0'-5"	0-0	185	0		
JACK ROD PLATF. 8x2x5"	80"	2'-6"	1-3+	200	100		
2,5x6"	21"	2-0+	1-0+	42	21		
JACK ROD+JACK 10x2,5"	25"	2-9+	1-9+	69	44		
WITH BRACKET	25"	2-6+	1-9+	63	44		
7x10"	70"	1-3+	0-6+	88	35		
FORM BRACKETS 3x7"	21"	1-0+	0-3+	21	5		
3x7"	21"	0-9+	0-3+	16	6		
PLACING PLATF. 3x7	21"	0-6+	0-3-	11			5
2,5x8x5"	100"	0-6+	0-3-	50			25
24x3"	72"	0-9-	1-6-			54	110
8x12"	96"	1-0-	1-6-			96	144
FORM WALES 16x12"	192"	1-3+	0-8+	240	127		
FINISHERS PLATFORM	100"	1-6-	1-6-			150	150
8x10"x2	160"	1-6-	1-6-			240	240
	20"	1-6-	1-6-			30	30
	72"	2-9-	2-8-			200	190
8x8"	64"	3-0-	2-10-			192	180
TRAILING PLATF.	80"	2-3-	2-0-			180	160
4x2,5x5	50"	1-9-	1-6-			88	75
YOKE L 16x5	80"	1-0-	0-9-			80	60
FILLERS	40"	0-9-	0-9-			30	30
TOTAL	1850"	1:12	985	1340	382	1399	
		VERT.					

$$\frac{1399}{382} \quad \frac{1340}{985}$$

$$1017/1850 = 0,55 \approx 6\frac{1}{2}'' \quad 355/1850 = 0,19' \approx 2\frac{1}{4}'' -$$

TOTAL HEIGHT 1850" / 8 FT SECTION
C.G. 1:12 2'4" { OUTBOARD OF TOP WHEEL


J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1/72 REV.

SKETCH# 209-cc-23

TRUMBULL LAKE DAM

PERUGANNOCK RIVER BASIN, CONN
 SLIP FORMING SYSTEM, VILT FORMS



JACK LOAD

1,9
 0,4 K
 0,5
 2,4
 0,5
 0,2
5,9 K

$+M_x$	$-M_x$
	$5,9 \times 0,75 = 4,40$
$0,4 \times 0,25 = 0,1$	$5,4 \times 7,5 = 40,50$
	$0,5 \times 2,25 = 1,12$
	$0,5 \times 2,25 = 1,13$
	$0,2 \times 2,0 = 0,40$
	$1,9 \times 1,55 = 2,94$
+ 0,1	- 50,49

$50,49$
 $+ 0,10$
 $\Delta M_x = 50,39$

$R_B = \frac{50,39}{4} = 12,6 \text{ COMP}$

$R_T = 18,0 \text{ K PULL-OUT}$

← FACE OF CONC. & MOMENT
 REFERENCE LINE

← BASE MEMBER OF YOKE ASSEMBLY

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE: JUN 11 1964 REV. _____
TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CONN.
SLIP FORM SYSTEM, ANCHOR DESIGN

AGE OF CONCRETE

RATE OF SPEED = 9"/HR MAX

DISTANCE BELOW FORM 6" TO 24"

MAKE TOP WHEEL OPERATIVE AT 24"

TOTAL AGE OF CONCRETE = $72"/9" = 8$ HOURS

CONCRETE STRENGTH

TESTS AT WEBS USING CONCRETE AT 70°

INDICATE STRENGTHS ABOVE 1000 PSI @ 8 HRS

& STRENGTHS ABOVE 100 PSI @ 5 HOURS

A STRENGTH OF 100 PSI WILL BE USED AS
SLIPPING WILL NOT PROCEED AT STRENGTHS
LOWER THAN THIS

ALLOWABLE STRESSES:

TENSION = 50 PSI

COMPRESSION = 100 PSI

LOADING: 18 KIPS PULLOUT
6 KIPS BEARING

BEARING AREA REQUIRED

$$6,000/100 = 60''$$

12 X 10 PRECAST BLOCKS
ARE ADEQUATE

BEARING AREA FOR PULL-OUT

$$18000/100 = 180''$$

USE 10 X 18" PLATE

$$M = \frac{1}{2}(100)(5)^2 = 1250''\#$$

5" THK

$$S_{req} = \frac{1250}{24,000} = .052/\text{INCH}$$

$$Em. 5\frac{1}{2}'' \# \quad S = \frac{1}{8}(5)^2 = .065/\text{INCH}$$

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JAN 1, 1972 REV.

SKETCH# 209-CR-10

TRUMBULL LAKE DAM

DEQUONNOK RIVER BASIN, CONN.


SLIP FORM SYSTEM, ANCHOR DESIGN

DESIGN OF RODS

LOAD PER ROD = 9K

USE 5/8" ϕ H.S. RODS (= A325)

DESIGN OF CONCRETE.



PULL ON CONCRETE

$$18'' \times 1.41 = 25,300 \#$$

AREA OF CONCRETE

$$A = [(35 \times 35) - 25] 1.41$$


$$AREA = 1200 \text{ in}^2 (1.41) = 1690 \text{ in}^2$$

$$STRESS = \frac{25,300}{1690} = 15 \text{ psi} < 50$$

OK.

23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
DEQUONNOK RIVER BASIN, CONN
SLIP FORM STUDY - CONVEYORS



WEIGHT OF CONV. 25#/LF
W. OF CONC. 100 #
TOTAL 125#/LF

$$\frac{1240 \times 49.5}{2 \times 34} = -900''$$

$$\frac{850}{2} = +425''$$

$$25 \times \frac{(19.5 + 19.5^2)}{68} = +625''$$

$$+150''$$

$$\frac{2575}{150} + 2425'' / 2 = 1212'' / \text{BRACKET}$$

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUN 1, 1972 REV.

SKETCH# 209

TRUMBULL LAKE DAM

PERQUONNOCK RIVER BASIN, CONN

SLIP FORM STUDY - CONVEYOR

UNSUPPORTED L OF (A) = 13'-0"

$K=1$

TRY DOUBLE L $3 \times 2 \times 5/16$ $A = 2,93 \text{ D}''$ $10''/\text{LF}$

$KL/r = \frac{1 \times 13 \times 12}{0,9} = 173$

$F_a = 5000 \#$

All. P = $2,93 \times 5^k = 14,6 \text{ K} > 2,5 \times 1,5$

TOTAL MATERIAL REQ.

$23' \times 2 = 46$

$26' \times 2 = 52$

$14' \times 2 = 28$

$8' \times 2 = 16$

$142' \times 10'' = 1420''$


BRACING (L 3x3)

$12 \times 6 \times 2 = 144$

$3 \times 3 \times 2 = 48$

$192' \times 5'' = 960''$

TOTAL: SAY 1,3 TONS




J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
PEGUONMOCK RIVER BASIN, CONN.
SLIPFORM STUDY - CONVEYOR TRUSS

LOADS: EMPTY CONV. = 25 #/LF
 FULL CONV. = 200 #/LF
 + L.L.
 DL. STEEL = 100 #/6 FT

$$\begin{array}{r} 6 \times 200 = 1200 \\ \hline 100 \\ \hline 1300 \end{array}$$



ESTIMATED WEIGHT OF TRUSS $\approx 40 \# / LF$

USE DOUBLE TRUSS ON BOTH SIDES TO FORM A "BOX".

TOTAL WEIGHT PER DOUBLE TRUSS (2 REQ.)
 $200' \times 40 \# = 8000 \#$
 MISC. STEEL $\approx 500 \#$
 TOTAL = 8500 #

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CONN.
SLIP FORM STUDY - TRESTLE

TRESTLE ON UPSTREAM SIDE OF DAM

ASSUMED TRESTLE WIDTH = 20 FT - 2 LANES
CRANE LOAD 160 TONS

USE 8 POSTS

UNSUPPORTED LENGTH = 20 FT

SPAN = 15 FT.

GROSS WEIGHT OF VEHICLE = 300,000[#] FOR AN
APPROX. LENGTH OF 22 FT

$$\frac{300,000 \times 15}{22} = 200,000 \text{ PER 15 FT SPAN}$$

TRY WOOD STRINGERS (20")

$$\frac{200,000}{2800 \times 8} = 9 \text{ REQ.}$$

STEEL STRINGERS

$$\frac{200,000}{28,000} = 7 \text{ REQ.} \quad (15" \text{ DEPTH})$$

$$\frac{200,000}{42,000} = 5 \text{ REQ.} \quad (18" \text{ DEPTH})$$

2 TONS/LANE/BAY

TRESTLE BENTS, POSTS

TOTAL L.L. = 100 TONS

IMPACT = 50

DL. = 5 "

155 TONS

USE 10x10 POSTS - ALL LOAD = 25 TONS

$$\frac{155}{25} = \underline{\underline{6 \text{ EA. / 10 FT WIDTH.}}}$$

10x10, 20 FT LONG, 6 EA

167 x 6 = 1002 BOARD FEET/BENT

23 GREEN STREET
HUNTINGTON, N. Y.


TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN
SLIPFORM STUDY - TRESTLE

TIMBER FLOORING.

CLEAR DISTANCE BETWEEN 18 I-BEAMS = 18"
1.5 x 1.5 = 2.25 SAY 3" DEEP

3 x 12 x 20' LG. = 45 BOARD FEET

FOR ONE LANE 10' x 45 = 450 B.F./LANE/BAY



MATERIAL FOR LANE
15' LONG, 10' WIDE

18 I STRING.	2 TONS
POSTS	1000 BF
GIRDERS	230 "
DECK	500 "
RAILING	150 "
BRACING	100 "
MISC.	100 "

TOTAL LUMBER: 2,080 BF
+ 10' ADD'L DK: 920 BF
3,000 BF

COST AND FEASIBILITY STUDY
ALTERNATE DESIGNS TO PERMIT USE
OF SLIP FORM AND OTHER TECHNIQUES
TO MAXIMIZE ECONOMIES

BOOK RC
RAPID CONSTRUCTION UTILIZING SLIP FORM TECHNIQUES
APPENDIX: COST STUDY SHEETS

BOOK RC - RAPID CONSTRUCTION UTILIZING SLIP FORM TECHNIQUE

APPENDIX: COST STUDY SHEETS

Page RC-2 Cost Study Sheets, Slip Forming
Page RC-46 Cost Study Sheets, Modified Design

- 1 Sheets ER-A1 through -A21
- 2 Sketches ER-S1 through -S22
- 3 Sheets EM-S, EM-1 through EM-4
- 4 Sheets EM-G, -F₁, -F₂
- 5 Sketches EM-S-1 through -S-22

COST STUDY SHEETS

SLIP FORMING

J. F. CAMELLERIE P.E. 23 GREEN STREET HUNTINGTON, N.Y. 11743	DATE	PRICED BY	SHEET NO. ER-A1
	Jun 1, '72		
	PROJECT: TRUMULL LAKE DAM		
	ARCHITECT: NEW ENGLAND DIV. -CORPS./ENGR.		

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
COST OF FORMING OF THOSE AREAS CAPABLE OF BEING SHIPPED:						
AREAS AS USED IN COST STUDY: (CONVENTIONAL FORMS)						
CANTILEVER	74,000	CA	.43	31,800	1.17	86,600
TRANSV. BULKHEADS	30,000	CA	.43	12,900	1.17	35,200
				44,700		121,800
ESCALATION THRU 1974			2%	890	11%	13,400
				45,590		135,200
PAYROLL, TAXES & INSURANCE					14%	18,900
						154,100
						45,600
TOTAL COST TO CONTR.						199,700
O'HD, PROFIT & CONTINGENCY					8%	16,000
						215,700
BID BOND					3/4%	1,600
TOTAL CONTRACT PRICE						217,300
TOTAL YDS. - 58,400 C.Y.						
TOTAL CONTACT AREA - 74,000						
COST/C.Y. - 217,300/58,400 = \$3.72/C.Y.						
COST/S.F. 217,300/74,000 = \$2.94						

J. F. CAMELLERIE P.E.
 23 GREEN STREET
 HUNTINGTON, N.Y. 11743

DATE JUN 1, '72 PRICED BY

SHEET NO. ER-A2

PROJECT: TRUMBULL LAKE DAME

ARCHITECT: NEW ENGLAND DIV. - CORPS/ENG'R.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
COST OF FORMING OF THOSE AREAS CAPABLE OF BEING SLIPPED:						
AREAS AS USED IN COST STUDY: (RAPID CONSTR.)						
SLIDING FORMS	1,520	LF	7.00	10,600	10.50	16,000
YOKES	192	EA.	210.	40,300	135.	26,000
JACK RODS (6T)	14,000	LF	2.50	35,000	.13	1,800
HYDRAULIC PIPING	4,000	LF	-	INCL.	.80	3,200
PLATFORM DECKS	1,650	LF	1.50	2,500	4.00	6,600
RAILING & LADDERS	1,650	LF	4.50	7,500	2.50	4,100
STRIP FORMS	-	-	-	-	-	26,000
FORM DESIGN	-	-	-	10,000	-	-
GUIDE WHEEL BRACKETS	230	EA.	65.	15,000	-	INCL.
PRECAST INSERTS	3,500	EA.	12.50	44,000	-	INCL.
SLIDE CREW	-	-	-	-	-	34,000
				164,900		117,700
ESCALATION THRU 1974			2%	3,300	11%	12,900
				168,200		130,600
PAYROLL TAXES & INSURANCE					14%	18,300
						148,900
						168,200
TOTAL COST TO CONTRACTOR						317,100
O'HD, PROFIT & CONTINGENCY					8%	25,400
						342,500
BID BOND					3/4%	2,600
TOTAL CONTRACT PRICE						345,100
COST/C.Y. - 345,100/58,400						\$5.91/C.Y.
COST/S.F. - 345,100/74,000						\$4.66

Basin

	J.F. CAMELLERIE P.E. 23 GREEN STREET HUNTINGTON, N.Y. 11743	DATE JUN 1, '72 PRICED BY	SHEET NO. ER-A3
		PROJECT: TRUMBULL LAKE DAM	
		ARCHITECT: NEW ENGLAND DIV. - CORPS/ENG'R.	

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
<u>ALTERNATE COST MONOLITHS TWICE AS HIGH: (CONVENTIONAL)</u>						
CANTILEVER FORMS	148,000	CA	.38	56,200	1.17	173,000
TRANSV. BULKHEADS	60,000	CA	.38	22,800	1.17	70,000
				79,000		243,000
ESCALATION THRU 1974			2%	1,580	11%	34,000
				80,580		277,000
PAYROLL, TAXES & INSURANCE					14%	38,800
						315,800
						80,580
TOTAL COST TO CONTR.						396,380
O'HD, PROFIT & CONTINGENCY					8%	31,700
						428,080
BID BOND					3/4%	3,200
TOTAL CONTRACT PRICE						431,280
TOTAL YDS - 116,800 YDS.						
TOTAL CONTACT AREA - 148,000 S.F.						
COST/S.F. 431,280/148,000 - \$2.92/S.F.						
COST/C.Y. 431,280/116,800 - \$3.70/C.Y.						

J. F. CAMELLERIE P.E.
 23 GREEN STREET
 HUNTINGTON, N.Y. 11743

DATE JUN 1, '72 PRICED BY

SHEET NO. ER-A6

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGLAND DIV. - CORPS/ENG'R

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
ALTERNATE COST, TWICE AS MANY MONOLITHS; (R/PID)						
SLIDING FORMS:	1,520	L.F.	7.00	10,600	21.	32,000
YOKES	192	EA.	210.	40,300	270.	52,000
JACK RODS	28,000	L.F.	2.50	70,000	.13	3,600
HYDRAULIC PIPING	8,000	L.F.	-	INCL.	.80	6,400
PLATFORM DECKS	1,650	L.F.	1.50	2,500	8.00	13,200
RAILINGS & LADDERS	1,650	L.F.	4.50	7,500	5.00	8,200
STRIP FORMS	-	-	-	-	-	52,000
FORM DESIGN	-	-	-	10,000	-	-
GUIDE WHEEL B'KT	230	EA.	65.	15,000	-	INCL.
PRECAST INSERTS	7,000	EA.	2.50	88,000	-	INCL.
SLIDE CREW	-	-	-	-	-	68,000
				243,900		235,400
ESCALATION THRU 1974			2%	4,900	11%	25,900
				248,800		261,300
PAYROLL, TAXES & INSURANCE					14%	36,600
						297,900
						248,800
TOTAL COST TO CONTRACTOR						546,700
O'HD, PROFIT & CONTINGENCY					8%	43,800
						590,500
BID BOND					3/4%	4,450
TOTAL CONTRACT PRICE						594,950
COST/S.F. - 594,950/148,000 - \$4.00/S.F.						
COST/C.Y. - 594,950/116,800 - \$5.10/C.Y.						

J. F. CAMELLERIE P.E.
 23 GREEN STREET
 HUNTINGTON, N.Y. 11743

DATE June 1, '72 PRICED BY SHEET NO. ER-A8
 PROJECT: TRUMBULL LAKE DAM
 ARCHITECT: NEW ENGLAND DIV. - CON'S/ENG'R.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
COST OF FORMING OF THOSE AREAS CAPABLE OF BEING SLIPPED:						
ALTERNATE COST - MONOLITHS EX AS HIGH (RAPID)						
SLIDING FORMS	1,520	LF	7.00	10,600	10.50	16,000
YOKES	192	EA.	210.	40,300	135.	26,000
JACK RODS	42,000	LF	2.50	105,000	.13	5,400
HYDRAULIC PIPING	4,000	LF	-	INCL.	.80	3,200
PLATFORM DECKS	1,650	LF	1.50	2,500	4.00	6,600
RAILINGS & LADDERS	1,650	LF	4.50	7,500	2.50	4,100
STRIP FORMS	-	-	-	-	-	26,000
FORM DESIGN	-	-	-	10,000	-	-
GUIDE WHEEL BKT.	230	EA	65.	15,000	-	INCL.
PRECAST INSERTS	10,500	EA	12.50	132,000	-	INCL.
SLIDE CREW	-	-	-	-	-	102,000
				322,900		189,300
ESCALATION THRU 1974			2%	6,450	11%	20,800
				329,350		210,100
PAYROLL, TAXES & INSURANCE					14%	29,400
						239,500
						329,350
TOTAL COST TO CONTR.						568,850
O'HD, PROFIT & CONT.					8%	45,500
						614,350
BID BOND					3/4%	4,600
						618,950
COST/C.Y. 618,950/176,000 - \$3.52/C.Y.						
COST/S.F. 618,950/222,000 - \$2.79/S.F.						

J. F. CAMELLERIE P.E.
 23 GREEN STREET
 HUNTINGTON, N.Y. 11743

DATE Jun 1, 1972 PRICED BY _____ SHEET NO. ER-A9

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGLAND DIV. - CORPS/ENG'R.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
COST OF FORMING THOSE AREAS CAPABLE OF BEING SLIPPED:						
ALTERNATE COST, 3X AS MANY MONOLITHS: (CONV.)						
CANTILEVER FORMS	222,000	CA	.30	66,700	1.17	260,000
TRANSV. BULKHEADS	90,000	CA	.30	27,000	1.17	105,000
				93,700		365,000
ESCALATION THRU 1974			2%	1,850	11%	40,200
				95,550		405,200
PAYROLL, TAXES & INSURANCE					14%	56,700
						461,900
						95,550
TOTAL COST TO CONTR.						557,450
O'HD, PROFIT & CONT.					3%	44,600
						602,050
BID BOND					3/4%	4,500
TOTAL CONTRACT PRICE						606,550
COST/S.F. - 606,550/222,000 - \$2.74/S.F.						
COST/C.Y. - 606,550/176,000 - \$3.45/C.Y.						

J. F. CAMELLERIE P.E.
 23 GREEN STREET
 HUNTINGTON, N.Y. 11743

DATE: Jun 1, '72 PRICED BY: SHEET NO. ER-A10
 PROJECT: TRUMBULL LAKE DAM
 ARCHITECT: NEW ENGLAND DIV. - CORPS/ENG'R.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
COST OF FORMING THOSE AREAS CAPABLE OF BEING SLIPPED						
ALTERNATE COST - 3X AS MANY MONOLITHS: (RAPID)						
SLIDING FORMS	1,520	LF	7.00	10,600	31.50	48,000
YOKES	192	EA	210.	40,300	405.	78,000
JACK RODS (6T)	42,000	LF	2.50	105,000	.13	5,400
HYDRAULIC PIPING	12,000	LF	-	INCL.	.80	9,600
PLATFORM DECKS	1,650	LF	1.50	2,500	12.00	19,800
RAILINGS & LADDERS	1,650	LF	4.50	7,500	7.50	12,400
STRIP FORMS	-	-	-	-	-	78,000
FORM DESIGN	-	-	-	10,000	-	-
GUIDE WHEEL BRKT.	230	EA	65.	15,000	-	INCL.
PRECAST INSERTS	10,500	EA	12.50	132,000	-	INCL.
SLIDE CREW	-	-	-	-	-	102,000
				322,900		353,200
ESCALATION THRU 1974			2%	6,450	11%	38,800
				329,350		392,000
PAYROLL, TAXES & INSURANCE					14%	55,000
						447,000
						329,350
TOTAL COST TO CONTR.						776,350
O'HD, PROFIT & CONT.					8%	62,100
						838,450
BID BOND					3/4%	6,300
TOTAL CONTRACT PRICE						844,750
COST/S.F. - 844,750/222,000 - \$3.80/S.F.						
COST/C.Y. - 844,750/176,000 - \$4.80/C.Y.						

J. F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

DATE JUN. 1, '72 PRICED BY

SHEET NO. ER-A12

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGLAND DIV. - CORPS. / ENGR

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
<u>CONCRETE HANDLING PLANT (RAPID)</u>						
CONCRETE PLACING	—	—	—	73,000	—	—
VIBRATION	58,365	C.Y.	.35	20,400	—	—
SLIDE CREW	—	—	—	—	—	36,500
FIELD ASSIST. ENG.	15	DAYS	200	3,000	—	—
FIELD TECHNICIAN	30	DAYS	150	4,500	—	SUB
CONVEYORS	58,400	C.Y.	.21	12,500	.12	7,000
MATERIAL TOWERS	4x6	Mos.	1200	28,800	—	34,000
CONV. SUPP. BRKT.	7	EA.	—	1,300	—	2,300
CONV. SUPP. TRUSS	6	EA.	—	8500	—	6,500
ELEPHANT TRUNKS	—	—	—	500	—	—
	(SUB-TOTAL)			162,500		86,300
EQUIP. SAVINGS (ON JOB 3 MONTHS LESS) (CONVENTIONAL LESS RAPID)						
YARD. CRANES	1 x 3	Mos.	4500	13,500	—	8,200
HYDRAULIC BOOM CRANES	2 x 3	"	1500	9,000	1400	8,400
COMPRESSORS	2 x 3	"	1100	6,600	1300	7,800
UTILITY TRUCKS	2 x 3	"	800	4,800	740	5,700
PERSONNEL STAIR	3 x 3	"	80	720	—	—
DOZER	1 x 3	"	1200	3600	1330	4000
	(SUB-TOTAL)			38,220		34,100
FIELD OVERHEAD (ON JOB 3 MONTHS LESS)						
PROJECT MANAGER	12	WKS	—	—	500	6000
SUPERINTENDENT	12	"	—	—	400	4800
PROJECT ENGR	12	"	—	—	400	4800
CLERKS	2 x 12	"	—	—	200	4800
SURVEYORS	4 x 12	"	—	—	250	12,000
UTILITY MECHANICS	6 x 12	"	—	—	300	21,600
WATCHMEN	3 x 12	"	—	—	100	3,600
	(SUB-TOTAL)					57,600
EQUIP. + FIELD O'HD SAVINGS						
				38,220		91,700
TIMBER TRESTLE (ADD'L)	480	LF	73	35,000	37	17,800
TEMPORARY LIGHTING (ADD'L)			—	1,000	—	4,000
				36,000		21,800

J. F. CAMELLERIE P.E.
 23 GREEN STREET
 HUNTINGTON, N.Y. 11743

PROJECT: TRUMBULL LAKE DAM
 ARCHITECT: NEW ENGLAND DIV. - CORPS. / ENGR.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
COST OF PLANT + OPERATION - CONCRETE				HANDLING PLANT		
ALTERNATE COST - MONOLITHS TWICE AS HIGH: (RAPID)						
CONCRETE PLACING	116,730	CY	-	73,000	-	-
VIBRATION	116,730	C.Y.	.35	40,800	-	-
SLIDE CREW	-	-	-	-	-	73,000
FIELD ASS'T ENGR	15	DAYS	200	3,000	-	-
FIELD TECHNICIAN	30	DAYS	150	4,500	-	SUB.
CONVEYORS	116,730	C.Y.	.21	12,300	.12	14,000
MATERIAL TOWERS	-	-	-	35,200	-	51,000
CONV. Supp. BRKT.	7	EA.	-	1,300	-	2,300
CONV. Supp. TRUSS	6	EA.	-	8500	-	6500
ELEPHANT TRUNKS	-	-	-	500	-	-
	(SUB-TOTAL)			179,100		146,800
LESS Equip. + Field OHD SAVINGS				-74,500		183,400
				103,600		-36,600
PLUS TIMBER TRESTLE +	480	LF	73	35,000	37	17,800
TEMP. LIGHT ADD'L.				1,000		4,000
				139,600		-14,800
ESCALATION THRU 1974			2%	2,300	11%	-1,600
				+142,400		-16,400
PAYROLL TAXES + INSURANCE					14%	-2,300
						-18,700
						+142,400
TOTAL COST TO CONTRACTOR						+123,700
OHD, PROFIT + CONTINGENCY					8%	9,900
						133,600
BID BOND					3/4%	1,000
TOTAL CONTRACT PRICE						134,600

COST/c.y. = 134,600 / 116,730 = \$ 1.15/c.y.

J. F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

PROJECT: TRUMBULL LAKE DAM
ARCHITECT: NEW ENGLAND DIV. - CORDS/ ENGR

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
COST OF PLANT + OPERATION - CONCRETE HANDLING PLANT						
ALTERNATE COST - TWICE AS MANY MONTHS (RAPID)						
CONCRETE PLACING	116,730	C.Y.		138,000	-	-
VIBRATION	116,730	C.Y.	.35	40,800	-	-
SLIDE CREW	-	-	-	-	-	73,000
FIELD ASS'T ENGR	15	DAYS	200	3000	-	-
FIELD TECHNICIAN	30	DAYS	150	4500	-	SUB.
CONVEYORS	116,730	C.Y.	.21	17,000	.12	14,000
MATERIAL TOWERS	4 x 8	MOO.	1200	38,400	-	68,000
CONVEYOR SUPP. BRKT	7	EA.	-	1,300	-	4,600
CONV. SUPP. TRUSS	6	EA.	-	8,600	-	13,000
ELEPHANT TRUNKS	-	-	-	500	-	-
	(SUB-TOTAL)			252,100		172,600
LESS EQUIP + FIELD O'HD SAVINGS				-74,500		-183,400
				+ 177,600		-10,800
PLUS TIMBER TRESTLE	960	L.F.	73	+70,000	37	+35,600
				247,600		+24,800
PLUS ADD'L TEMP. LIGHTING				1,000		8,000
				248,600		+37,800
ESCALATION THRU 1974			2%	5,000	11%	3,600
				253,600		36,400
PAYROLL TAXES + INSURANCE					14%	5,100
						41,500
						253,600
TOTAL COST TO CONTRACTOR						295,100
O'HD, PROFIT + CONTINGENCY					8%	23,600
						318,700
BID BOND					3/4%	2,400
TOTAL CONTRACT PRICE						321,100
COST/C.Y. = 321,100 / 116,730 = \$ 2.75/c.y.						

J. F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

DATE JUN. 1, '72 PRICED BY

SHEET NO. ER-A 19

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGLAND DIV. - CORP./ENGR.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
COST OF PLANT & OPERATION FOR THOSE AREAS CAPABLE OF SLIDGING:						
COIX. HANDLING PLANT: 3x AS HIGH: (RAV. ID)						
CONCRETE PLACING	—	—	—	73,000	—	—
VIBRATION	176,000	C.Y.	.35	61,600	—	—
SLIDE CREW	—	—	—	—	—	109,500
FIELD ASSIST. ENGR	15	DAYS	200	3,000	—	—
FIELD TECH.	30	DAYS	150	4,500	—	SUB
CONVEYORS	175,200	C.Y.	.21	37,500	.12	21,000
MATERIAL TOWERS	—	—	—	48,000	—	68,000
CONV. SUPP. BRKT.	7	EA.	—	1,300	—	2,300
CONV. SUPP. TRUSS	6	EA.	—	8,500	—	6,500
ELEPHANT TRUNKS	—	—	—	500	—	—
	(SUB-TOTAL)			227,900		207,300
LESS EQUIP. + FIELD OHD SAVINGS				-114,600		-275,100
				+123,300		-67,800
PLUS TIMBER TRESTLE	480	L.F.	73	+35,000	37	+17,800
				158,300		-50,000
PLUS ADD'L TEMP. LIGHTING				+1,000		+4,000
				159,300		-44,000
ESCALATION THRU 1974			2%	3,200	11%	-5,100
				162,500		-51,100
PAYROLL TAXES + INSURANCE					14%	-7,100
						-58,200
						+162,500
TOTAL COST TO CONTR.						104,300
OHD, PROFIT + CONT.					8%	8,300
						112,600
BID BOND					3/4%	900
TOTAL CONTRACT PRICE						113,500
COST/C.Y. 113,500 / 176,000 = \$.65/C.Y.						

J. F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

DATE JUN. 1, '72 PRICED BY

SHEET NO. ER-A21

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGLAND DIV. - CORPS / ENGR.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
COST OF PLANT & OPERATIONS - CONCRETE				HANDLING F	ANT	
ALTERNATE COST - 3X AS MANY MONTHS				(RAPID)		
CONCRETE PLACING	176,000	C.Y.	—	204,000	—	—
VIBRATION	176,000	C.Y.	.35	61,600	—	—
SLIDE CREW	—	—	—	—	—	109,500
FIELD ASST ENGR	15	DAYS	200	3,000	—	—
FIELD TECH.	30	DAYS	150	4,500	—	—
CONVEYORS	176,000	C.Y.	.07	12,500	.12	21,000
MATERIAL TOWERS	4x10	Mos.	1200	48,000	—	102,000
CONV. SUPP. BRKT	7	EA.	—	1,300	—	6,900
CONV. SUPP. TRUSS	6	EA.	—	3,600	—	19,500
ELEPHANT TRUNKS	—	—	—	500	—	—
	(SUB-TOTAL)			344,000		253,400
LESS EQUIP. + FIELD OHD SAVINGS				-114,600		-275,100
				+229,400		-16,700
PLUS TIMBER TRESTLE	1440	LF	73	105,000	37	+53,400
				334,000		+37,200
PLUS MOD. TEMP. LIGHTING				+1,000		+12,000
				335,000		49,200
ESCALATION THRU 1974			2%	6,700	11%	5,400
				341,700		54,600
PAYROLL TAXES + INSURANCE					14%	7,600
						67,200
						341,700
TOTAL COST TO CONTR.						403,900
OHD, PROFIT + COST.					8%	32,300
						436,200
BID BOND					3/4%	3,300
TOTAL CONTRACT PRICE						439,500
COST/C.Y. = 439,500 / 176,000 = 2.50/c.y.						

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1/72 REV.

SKETCH # 110-31

TRUMBULL LAKE DAM

DEQUONNOCK RIVER BASIN, CONN.

CONCRETE ESTIMATE

	CY	CEMENT	FLYASH
INT. CONC.	88.700	$\times 1.40 = 124,200 \text{ CWT}$ $/376 = 33.000 \text{ bbl}$	$\times 1.10 = 97,500 \text{ CWT}$ $/286 = 34.000 \text{ bbl}$
EXT. CONC.	30.300	$\times 1.83 = 55,000 \text{ CWT}$ $/376 = 14,600 \text{ bbl}$	$\times 0.78 = 23,600 \text{ CWT}$ $/286 = 8.250 \text{ bbl}$
3000 PSI 4000 PSI	8.000	$\times 4.7 = 37,600 \text{ CWT}$ $\times 1.25 \text{ bbl} = 10.000 \text{ bbl}$	
		57,600 bbl	42,250 bbl
		216,800 CWT	121,100 CWT

TOTAL bbl
 CEMENT 57,600
 FLYASH 42,250
99,850 bbl

CEMENT $216,800/20 = 10,840 \text{ TONS}$

FLYASH $121,100/20 = 6,055 \text{ "}$

J. F. CAMELLERIE, P.E.

23 GREEN STREET

HUNTINGTON, N. Y.

DATE JUN. 1, 1972 REV. APR. 1, 1974 SKETCH# ER-52

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN

BATCH PLANT OPERATION

COST PER SHIFT

\$ 461.10 LAB + \$190.00

SEE CONVENTIONAL CONSTR. REPORT
SHEET N° EC-54

NO OF DAYS OPERATION (SEE CONC DEMAND
SCHEDULE 209-SR1 THRU SR8

NO OF WORKING DAYS (146-37) 109 days

ADD'L SHIFTS 21 x 1.125 24 days

WEEK DAY SHIFT DAYS
96 x 1.125 = 108 days

SAT. MORNING SHIFT (II, IV, VI) (V)
4 x 2 8 days

STRAIGHT TIME SHIFTS (I, III, V, VII, VIII)
5 x 1 5 days

PAY 254 days

TOTAL LABOR COST = 254 (461) = \$ 117,000

" SUPPLIES " = 235 (190) = 44,500

" LABOR (COOLING) = 254 (117) = 29,500

" SUPPLIES (") = 235 (85) = 20,000

\$ 211,000

UNIT COST = $\frac{211,000}{127,000} = 1.66$

PLUS ADMIX

$\frac{.02}{1.68/yd}$

SAY \$ 1.65

Revised

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE SUB. 1, 1972 REV. APR 1974 SKETCH# ER-53
TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CONN.
CONCRETE PLACING

NON SLIP FORMED CONCRETE

SLIP FORMED CONC

SLIP I	=	6485	CY.
" II	=	9065	CY
" III	=	6485	CY
" IV	=	9065	CY
" V	=	7700	CY
" VI	=	9065	CY
" VII	=	9500	CY
" VIII	=	1000	CY

58365 CY TOTAL

127,000 Less 58,400 = 68,600 CY NON SLIP

CREW

SPREADING
FOREMAN

3 MEN
1 MAN

4 MEN @ \$ 5.60 = 22.40

+ .50 FOREMAN = 1.50

COST PER DAY = $\$ 22.90 \times 8 = \$ 183.20 / \text{day}$

TOTAL SHIFTS WORKED 133

TOTAL LABOR COST = 133 (183) = 24,000

COST PER YD = $\frac{\$ 24,000}{68,600} = .35\text{\$}$ (PLUS CONV. OPERATORS)

VIBRATION

4 MEN @ 5.60 = 22.40

COMP. OPER. = 7.40

$\$ 29.80 \times 8 = 238 / \text{DAY}$

EQUIPMENT — — — — — \$ 200 / DAY

TOTAL COST = 133 (238) = \$ 31,600

COST PER YD = .46 LAB

133 (200) = \$ 26,600

COST PER YD = .38 MTL

Revised

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUN 1, 1972 REV. APR 1, 1974 SKETCH# ER-54

TRUMBULL LAKE DAM

PERQUONNOCK RIVER BASIN, CONN

CONVEYOR OPERATION

DURING CANTILEVER FORM OPERATION

OPERATORS

FEEVER CONV. (STATIONARY) PLANT TO TRESTLE	1
SIDE DISCHARGE CONVEYOR ON TRESTLE	1
RADIAL OR SIDE DISC. CONV ON MONOLITH	1
	<u>3</u>

CREW 3 OPERATORS @ 7.75 = 23.25
 3 LABORERS (MOVING) @ 5.60 = 16.80
 CRANE OPER & OILER ELSEWHERE \$ 40.05/hr
 COST PER DAY = 8 x 40.05 = 320.40
 COST PER YD = $\frac{320.40 \times 133 \text{ days}}{68,600 \text{ yd}}$ = \$.62

COMBINE WITH PLACING CREW

3 OPERATORS @ 7.75 = 23.25
 3 LABORERS (MOVE & SPREAD) 16.80
 1 FOREMAN 6.10
 \$ 46.15/hr
 COST PER DAY = 8 x 46.15 = 369.20/day
 COST PER YD = $\frac{369.20 \times 133}{68,600}$ = \$0.71/yd.

CONVEYOR REQUIREMENTS

BATCH PLANT TO TRESTLE	50 L.F
DISTRIBUTOR CONVEYORS	430 L.F
ABUTMENT CONVEYOR	200 L.F
PLACING CONVEYORS	150 L.F
RADIAL CONVEYOR	30 L.F
	<u>860 L.F</u>

860 L.F @ 150 = \$ 129,000
 RAIL & ACCESS @ 10% 13,000
 SIDE DISCHARGE 1,000
 RADIAL CONV. 2,000
 \$ 145,000
 SAY 70,000 SALVAGE
 \$ 75,000

Revised

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUN 1, 1972 REV. 3
TRUMBULL LAKE DAM
PEQUONNOK RIVER BASIN, CONN.
CONVEYOR OPERATION

CONVEYOR EQUIPMENT COST

TOTAL USE 160 days.

$$\text{COST PER DAY} = \frac{\$75,000}{160} = \$470.00/\text{day}$$

CHECK ON RENTAL BASIS

$$860 \text{ LF @ } 1.25 = \$1075/\text{day}$$

USE \$750/day

COST PER YARD:

$$\frac{750 \times 160}{68,600} = \$1.75$$

CONVEYOR ERECTION (INITIAL)

$$5 \text{ MEN @ } 8.00 = \$40/\text{hr}$$

$$\times 2 \text{ WKS} = \$3200/\text{WK ERECT}$$

$$\times 1 \text{ WK} \quad \underline{1600/\text{WK DISMANTLE}}$$

\$4800 TOTAL

$$\text{COST PER YD} = \frac{\$4,800}{68,600} = .07$$

SAY .07/YD.

TOTAL EQUIPMENT COST PER YARD

RENTAL 1.75

ERECT. .07

\$ 1.82

DURING SLIPFORM OPERATION

OPERATORS

- FEEDER CONY (STATIONARY) TO TRESTLE 1
(TAKES CARE OF SIDE DISCHARGE
& CONVEYOR TO MATERIALS HOIST
TOWER. ALL INTERCONNECTED)
- FEEDER CONVEYOR @ TOP (HOIST TOWER TO 1
SIDE DISCHARGE CONVEYOR AND SID
DISCHARGE CONVEYOR, INTERCONN)
- SPREADER CONVEYOR 1
3

CREW 3 OPERATORS @ \$7.75 = \$23.75/hr.
INCLUDE IN SLIDE CREW

CONVEYOR REQUIREMENTS

ADD'L TO GENERAL SYSTEM

MATERIAL TOWER TO FEEDER	40 LF
DISTRIBUTOR CONVEYOR	90 LF
SPREADING CONVEYOR	60 LF
	<u>190 LF</u>

\$
190 LF @ 150 = 28,500
 BAIL & ACC 3,000
 SIDE DISCH 1,500
 \$33,000
 SBY 16,000 SALVAGE
 \$17,000

CONVEYOR EQUIPMENT COST

TOTAL USE 41 days

COST PER DAY = 17,000/41 = \$415

RENTAL PER DAY = 190 @ .25 = \$47.50

COST PER YD = $\frac{300 \times 41}{58,400} = .21$

USE \$300

CONVEYOR ERECTION 5 MEN @ \$8.00 x 2 days x 7 hrs.
 = \$4,480 \$
 + DISMANTLE = 2240 \$
 6,720 TOTAL

COST PER YD = $\frac{6,720}{58,400} = .12$

TOTAL = .21 + .12 = .33

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUN 1, 1972 REV. A11 SKETCH# ER-57
TRUMBULL LAKE DAM
PEQUANNOCK RIVER BASIN, CONN.
CONCRETE PLACING

FINISHING

TOTAL AREA = 146,000 ϕ'

SLIP FORMED AREAS

SLIP I	67.5'
II	82.5'
III	67.5'
IV	82.5'
V	75.0'
VI	82.5'
VII	70.0'
VIII	20.0'

$547.5' \times 60' \times 2.25 = 74,000 \phi'$

NON-SLIP-FORMED AREA = 72,000 ϕ'

HORIZONTAL JOINTS

ELIMINATED BY SLIP FORMING

EL. 177'-6"	1 x	83.75	=	83.75
	4 x	77.50	=	310.00
	5 x	71.25	=	356.25
	7 x	65.00	=	455.00
	7 x	58.75	=	411.25
	7 x	52.50	=	367.50
	7 x	46.25	=	323.75
	7 x	40.00	=	280.00
	7 x	33.75	=	236.25
	7 x	27.50	=	192.50
	7 x	21.25	=	148.75

$3,165.00 \times 60 = 190,000$

TOTAL AREA = 425,650

JOINTS ELIM. = 190,000

JOINTS REMAINING = 235,650 ϕ'

LIFT STARTER FORMS

REPLACED BY INTERMEDIATE FORMS:

$$\left. \begin{array}{l} \text{SLIDE I} \\ \text{III} \\ \text{IV} \\ \text{V} \end{array} \right\} 4 \times 60' \times 2.25 = 540 \phi'$$

$$\begin{array}{r} \text{SIDE = I} \quad 2 \times 77.5 = \quad 155 \phi' \\ \text{III} \quad \quad \quad \quad \quad \quad \quad 155 \phi' \\ \text{IV} \quad 2 \times 90.0 \quad \quad \quad \quad 180 \phi' \\ \hline \quad \quad \quad \quad \quad \quad \quad \quad 1030 \phi' \end{array}$$

$$\begin{array}{r} \text{TOTAL AREA REPLACED} = 7.5(1030) = 7750 \phi' \\ \text{TOTAL " CONVENTIONAL} \quad \quad \quad \underline{12,850 \phi'} \end{array}$$

$$\text{AREA REMAINING} \quad \quad \quad 5,100 \phi'$$

CANTILEVER FORMS

$$\begin{array}{l} \text{AREA REPLACED BY SLIP FORMS} = 74,000 \phi' \\ \text{TOTAL CANTILEVER FORM} = 107,300 \phi' \\ \text{REMAINING CANTILEVER FORM} = 33,300 \phi' \end{array}$$

TRANSVERSE BULKHEADS

ELIMINATED BY SLIP FORM

$$\begin{array}{r} \text{EL. 170'-0" to 177'-6"} \quad 1 \times 86.88 = \quad 86.88 \\ \quad \quad \quad \quad \quad \quad 4 \times 80.63 = \quad 322.52 \\ \quad \quad \quad \quad \quad \quad 5 \times 74.38 = \quad 371.90 \\ \quad \quad \quad \quad \quad \quad 7 \times 68.13 = \quad 476.91 \\ \quad \quad \quad \quad \quad \quad 7 \times 61.88 = \quad 433.16 \\ \quad \quad \quad \quad \quad \quad 7 \times 55.63 = \quad 389.41 \\ \quad \quad \quad \quad \quad \quad 7 \times 49.38 = \quad 345.66 \\ \quad \quad \quad \quad \quad \quad 7 \times 43.13 = \quad 301.91 \\ \quad \quad \quad \quad \quad \quad 7 \times 36.88 = \quad 257.16 \\ \quad \quad \quad \quad \quad \quad 7 \times 30.65 = \quad 214.41 \\ \quad \quad \quad \quad \quad \quad 7 \times 24.38 = \quad 170.66 \\ \quad \quad \quad \quad \quad \quad 7 \times 18.13 = \quad 126.91 \\ \hline \quad \quad \quad \quad \quad \quad \quad \quad \quad \quad \quad \quad 3,497.99 \end{array}$$

$$\begin{array}{l} \text{AREA ELIMINATED} = (3497)(7.5) \frac{8}{7} = 30,000 \phi' \\ \text{TOTAL} = 51,600 \\ \text{LESS} \quad \underline{30,000} \quad \quad \quad \underline{21,600 \phi'} \end{array}$$

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUN. 1, 1972 REV. APR. 1, 1974 SKETCH # ER - 59
TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONN.

FORM COSTING

COST FOR CANTILEVERED FORM

FORMS USED FOR

LIFT STARTERS	5,100 SF
FACE FORMS	33,300 SF
TRANSV BLKHD	21,600 SF
	<hr/>
	60,000 SF

COST OF FORMS = 9,600 ϕ ' \times 7.20 = \$69,000

LESS SALVAGE = 24,000

\$45,000

PLUS ANCHORS = 12,000

\$57,000

COST PER ϕ ' = $\frac{57,000}{60,000} = .95 \phi$

Revised

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMULL LACE DAM ER-510
 PLEASANT RIVER PARK, CONN.
 SLIP FORM OPERATION

SLIDING FORMS

2 SETS REQUIRED (SEE SCHEDULE 209-SR-11)

2 SETS CONSISTS OF

- 120 LF DOWNSTREAM FACE FORMS
- 120 LF UPSTREAM FACE FORMS
- 340 LF TRANSV. BULKHEAD FORMS (LEAD HEAD)

TOTAL LINEAL FOOT OF SLIP FORM REQD.

- 420 LF DOWNSTREAM FACE FORMS
- 420 " UPSTREAM " "
- 680 " TRANSV BULKHEAD FORMS (8x35FT)

- 1520 LF

DOWNSTREAM & UPSTREAM FORMS MAY BE
 MADE IN 2 SETS USING STEEL & WALS

COST PER 8'-0" x 4'-0" PANEL

STEEL PLATE	32' x 8" = 250 #
LS	16' x 3.2 = 51.2 #
WALS	16' x 3.5 = 56 #
LIFT POINT	4' x 3.5 = 14 #
	<hr/>
	471.2 #
	+ 10 %
	<hr/>
	518.3 #

Cost Per 1/2' = $\frac{518.3 \times 1.30}{22} = 31.00$

REUSE = $\frac{7}{2} = 3.5$

Cost Per 1/2' = $\frac{5.0 \times 1.25}{3.5} = 1.43/lf$

Cost Per LF = $1.43 \times 5 = 7.15/lf$



23 GREEN STREET
HUNTINGTON, N. Y.

PEQUONNOK RIVER BASIN, CONN.
SLIP FORM OPERATION

SLIDING FORMS

USING WOOD FORMS W/ NO REUSE (4' x 8' PANEL)

1x4 T $\frac{1}{2}$ G BOARDS
32 bd' x 1.25 x .30 = \$12.00

12x10 WALES
10 bd' x 8' x 1.2 x .17 = 16.30

2x6 TRUSSING
1 bd' x 14' x .17 = 1.40

HARDWARE 2.00

\$31.70

COST PER SQ FT \$1.00 MATERIAL

MAKE-UP $40 \left(\frac{51 \text{ bd' ft}}{32} \right) = .64$

\$1.64 / ft'

\$6.60 / LF

AVERAGE COST PER L.F.

(ASSUME WOOD BULKHEAD FORMS, STEEL FACE FORMS)

840 F.F x \$7.20 = 6,050

680 B.F x 6.60 = 4,500

1520

10,550

AV COST = \$7.00

J. F. CAVALLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUCKBUILT, L.A. 1950
 PENNSYLVANIA POWER & LIGHT CO., INC.
 SHIP FROM L.A. 1/27/51

SHIP FORM YOKES

REQUIREMENTS PER SET, 2 SETS REQ'D

8 DOWNSTREAM YOKES
 8 UPSTREAM " } SIMILAR
 20 TRANSVERSE "

TOTAL REQUIREMENTS TO MAKE

16 DOWNSTREAM YOKES
 56 UPSTREAM YOKES

TOTAL REQUIREMENTS TO ERRECT

8x7 = 56 DOWNSTREAM YOKES
 8x7 = 56 UPSTREAM " "
 10x2 = 20 TRANSVERSE " "
 192 TOTAL

DOWNSTREAM YOKES

SEE COMP SHEET 207-01-100

YOKES BEAM	654 [#]
YOKES EXTENSION	59 [#]
JACK ROD PLAT HORN	20 [#]
FIN RAY SUPPORTS	336 [#]
MAIN " "	79 [#]
PORTAL FRAME	612 [#]
SPLASH GUARD	70 [#]
	<u>1890[#]</u>

COST PER YOKE = 2000[#] x 1890 = 3,780,000

UPSTREAM YOKES (COMP SHEET 207-01-100)

YOKES BEAM	740 [#]
JACK ROD PLAT HORN	70 [#]
JACK ROD BRKT	70 [#]
PLATFORM SUPPORTS	289 [#]
FIN PLAT	64 [#]
TRAILING PLAT	80 [#]
MISC	170 [#]
PORTAL FR	612 [#]
	<u>1926[#]</u>

23 GREEN STREET
HUNTINGTON, N. Y.

PEQUONNOK RIVER BASIN, CONN.

SLIP FORM OPERATION

SLIP FORM YOKE'S (CONT)

TOTAL COST

16 DOWNSTREAM x \$600 = \$ 9,600
56 UPSTREAM x \$550 = 30,800
\$40,400

COST PER UNIT = $\frac{\$40,400}{192} = \210

FORM ERECTION

YARD CRANE AVAILABLE (SEE EQUIPMENT SHEET ERA.)
4 PER DAY

CREW 5 IRON WORKERS @ 10.20 = \$51.00/hr
FOREMAN 10.70/hr
\$61.70/HR
\$493.60/DAY
SHORES & RIGGING 45.00

ERECTION PER YOKE = $\frac{\$538.60}{4} = \135

JACK RODS

SLIDE NO	I	8 x 2.25 x 67.5 =	1210	
		8 x 2.0 x 67.5 x .6 =	650	1860
	II	8 x 2.25 x 82.5 =	1490	
		11 x 2.0 x 82.5 x .6 =	1080	2570
	III			1860
	IV			2570
	V	8 x 2.25 x 75 =	1350	
		10 x 2.0 x 75 x .6 =	900	1350
	VI			1490
	VII & VIII	8 x 2.25 x 90 =	1620	
		12 x 2.0 x 90 x .6 =	1300	1620
			TOT =	13,320

SAY, 14,000 LF

23 GREEN STREET
HUNTINGTON, N. Y.

PEQUONNOK RIVER DAM
PEQUONNOK RIVER BASIN, CONN.
SLIP FORM OPERATION

PLATFORM DECKS

S 14

DOWNSTREAM FORMS

$$\text{LUMBER} = 5' \times \frac{10}{9.5} \times 2 = 10.5 \text{ bd ft/ft}$$

$$3 \times 10 \text{ stringer } 2.5 \times 1.1 = 2.8 \text{ " "}$$

$$\text{TOP PLANK } 2 - 2 \times 10 \times 1.1 = 2.7 \text{ " "}$$

$$2 \times 10 \text{ STRINGER } 1.33 \times 1.1 = 1.5 \text{ " "}$$

$$\underline{17.5 \text{ bd ft/ft}}$$

$$\text{PLYWOOD } 4.5 \times \frac{5}{4.5} = 5 \text{ } \phi \text{ / FT}$$

$$\text{COST PER FT} = 17.5 \times .175 = \$3.05$$

$$5.0 \times .265 = \$1.32$$

$$\text{HARDWARE } .10$$

$$\underline{\$4.47/\text{FT}}$$

$$\text{REUSE} = \frac{4.47}{3.5} \times 1.25 = 1.60$$

$$\text{PLACING } .020(9)(22.5) = 4.05/\text{FT}$$

$$\text{LGT OF DECKING} = 7 \times 60 = 420 \text{ L.F}$$

UPSTREAM & BULKHEAD FORMS

MAIN DECK, LUMBER

$$4 \times 1 \times 2 = 8.0 \text{ BD.FT.}$$

$$\text{STRINGERS} = 4.3 \text{ " "}$$

$$\text{TOP PLANK } 2.7 \text{ " "}$$

$$\underline{15.0} \times .175 = 2.60$$

$$\text{PLYWOOD } 1.32$$

$$\text{HARDWARE } .10$$

$$\underline{\$4.02}$$

$$\text{USE } \frac{\$4.02}{3.5} \times 1.25 = 1.44/\text{LF}$$

$$\text{USE } \underline{\$1.50}$$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
 PERQUIMMUCK RIVER BASIN, CONN.
 SLIP FORM OPERATION

RAILING & LADDERS

DOWNSTREAM FACE
 WOOD

PLACING PLATFORM RAILING

POSTS 8' x 16bf x 18 = 1.00 bdf / L.F

TOP RAIL 1 x 16bf x 9/8 = .75 "

SIDE RAILS 3 x 16bf x 9/8 = 1.75 "

3.50 bf/LF.

COST = 3.50 x 175 = 0.61¢/LF

W/REUSE = $\frac{.61 \times 1.25}{3.5} = .25¢/LF$

ERECTION = .020(9)(3.5) = .65¢/LF

STEEL RAILING

MATERIAL (3.5 USES) = \$3.00/LF

PLACING 150/LF

LADDERS \$40 EA RENTAL

TOTAL COST PER FT

WOOD RAILING

STEEL "

LADDERS $\frac{2 \times 3 \times 40}{60} \times \frac{1}{7} = .57$

MTL.

.25

3.00

.57
 \$3.82

LAB

.65

1.50

\$2.15/LF

UPSTREAM FACE

PLACING PLATFORM RAILING

POST 5' x 16bf x 18 = .63 bf/LF

RAILS

2.50

3.13 bf/LF

COST MTL = .20¢

INSTALL = .55¢/LF

TOTAL COST PER FT

WOOD RAILING

STEEL RAILING

LADDERS

MTL.

.20

4.50

.38

\$5.08

LAB

.55

2.00

-

\$2.55

USE AVERAGE COSTS:

MTL: \$4.50

INSTALL: 2.50

J. F. CAMELLEKIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
PEQUONNOK RIVER BASIN, CONN.
SLIP FORM OPERATION

PRECAST INSERTS

S16

PRECAST BLOCK		\$.50
COUPLER	2 @ .75	1.50
RODS	2 @ 3.00	6.00
BEARING PLATE		2.00
PIPE SUPPORT 4 x .40		1.60
WASHER		1.00
		<u>\$ 12.60 EA.</u>

SAY 12.50

NO. OF INSERTS REQ'D:
L.F. JACK ROD = 14,000 LF
INSERT SPACING = 4'

$$\text{No. REQ'D} = \frac{14,000}{4} = 3,500 \text{ EA.}$$

GUIDE WHEEL BRACKETS

WEIGHT EACH	$12 \times 10 \times 3/4$	= 25.5#
2 EA	$10 \times 3 \times 3/8$	= 6.4#
2 EA		37.4#
WHEELS		<u>43.6#</u>
		112.9#
	+ 10% =	<u>11.3</u>
		124.2# (FOR PRICING ONLY)

$$\text{COST} = 125 \# \times .50 \# = \$62.5 / \text{ASSEMBLY}$$

SAY \$65.00

NO REQ'D (2 SETS OF FORMS)

$$72 \text{ LOCATIONS} \times 3 = 216 \text{ SAY } 230$$

FORM DESIGN

$$\text{APPROX. FORM COST} = \$200,000$$
$$\text{DESIGN} = 10\% = \$20,000 / 2 = \$10,000$$

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUN 1, 1972 REV.

SKETCH# EK-311

TIZUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONN

SLIP FORM OPERATION

STRIP SLIP FORMS

SAY 50% ERECTION

ERECT FORMS	16,000
" YOKES	26,000
" DECKS	6,600
" RAILINGS	4,100

$\$52,700 (.50) = \$26,000$

HYDRAULIC PIPING

L.F. FORMS	1520 LF
192 Jacks x 10'	1920 LF
7 x 85' ACROSS	585 LF
	<u>4025 LF</u>

SAY 4000 LF.

CONVEYOR SUPPORT BRACKETS

(SEE COMP SHEETS 209-CR-11 & 12)

EST. WEIGHT PER BRACKET = 1.3 TONS

2 REQ'D AT 1.3 = 2.6 TONS FAB

@ \$500/TON = \$1,300

7 REQ'D TO ERECT = 9.1 TONS.

@ \$250/TON = \$2,300

CONVEYOR SUPPORT TRUSSES

(SEE COMP SHEET 209-CR-13)

ESTIM WEIGHT PER TRUSS = 4.25 TONS

4 REQ'D @ 4.25 = 17 TONS FAB

@ \$500/TON = \$8,500

6 REQ'D TO ERECT = 25.5 TONS

@ \$250/TON = \$6,500

J. T. CARROLL, INC.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
 PEGGONASNOCK RIVER BASIN, CONN.
 SLIDE CREW 5/4

CLASSIFICATION		HOURLY RATE INCL. FRINGE BENEFITS	COST PER SHIFT		
			NORMAL RATE 8 HR. WORK 8 HR. PAY	WEEKDAY SHIFT RATE 8 HR. WORK 9 HR. PAY	WEEKEND RATE 8 HR. WORK 16 HR. PAY
CONVEYOR OPER	3	7.75	\$ 186	\$ 209	\$ 372
HOIST ENGINEER	1	8.60	69	78	138
JACK OPERATOR	1	8.00	64	72	128
CARPENTERS	3*	9.00	216	243	432
ELECTRICIANS	2/3**	8.28	44	50	88
FINISHER FOREMAN	1	9.37	75	84	150
FINISHER	1	8.87	71	80	142
FINISHER HELPER	1	7.15	57	64	114
LABORERS					
FORCHMAN	1	6.10	49	55	98
PLACING	3				
VIBRATION	3				
CURING	1				
	<u>7</u>	5.60	314	353	628
TOTAL PER SHIFT 19 2/3			\$1,145	\$1,288	\$2,290

* 4 ON LEAD MONOLITHS 2 ON TRAIL MONOLITHS

** 1 Shift in Field OVERHEAD

DIVISION BY ITEMS :

PLANT	26.1%
FORMS	24.4%
PLACE & VIB	27.8%
FIN & CURE	21.7%

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
 PEQUODINOCK RIVER BASIN, CONN
 SLIDE CREW

SLIDE NO	NORMAL SHIFT	DOUBLE TIME SHIFT	STRAIGHT TIME SHIFT	TOTAL SHIFTS
I	12		1	13
II	15	1		16
III	12		1	13
IV	15	1		16
V	12	1	1	14
VI	15	1		16
VII	12		1	13
VIII	3		1	4
TOTAL	96	4	5	105

TOTAL COST

96 Shifts @ \$1,288 ----- \$123,700
 4 " @ 2,290 ----- 9,200
 5 " @ 1,145 ----- 5,700

TOTAL \$138,600

SAY \$140,000

DIVISION BY WORK:

PLANT ----- \$36,500
 FORMS ----- 24,000
 PLACE & VIB ----- 39,000

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUN 1, 1972 REV.

SKETCH# ER-521

TRUMBULL DAM

PEQUONNOK RIVER BASIN, COMM

ENVIRONMENT CONTROL

ENVIRONMENT PROTECTION

a) WATER TURBIDITY

METERING DEVICES, FLOCCULATION $\$ 35,000$
 MONTHLY OPERATION:

15 Mos @ $\$ 3,000$ $\underline{45,000}$
 $\$ 80,000$

b) NOISE Abatement

CLEARING & GRUBBING	\$ 9,000
EXCAV	135,000
DRAQLINE & TRUCKS	162,000
AGGREGATE PLANT	490,000
MIXING PLANT	432,000
DIVERSION	80,000
AIR TOOLS	80,000
GEN'L EQUIP	<u>215,000</u>

1,603,000

5% Equip $\$ 80,000$

c) LANDSCAPE RENEWAL

200 Plants @ 25^{00} = 5000
 PLANTING @ 40% = 2000

$\$ 7,000$

TRESTLE (SEE COMP SHEETS 209-CR14 & 15)

LUMBER PER FOOT $\frac{3000 \text{ lbm}}{15} = 200 \text{ lb/ft}$

STRUCT STL PER FOOT $\frac{2 \text{ TON}}{15'}$.13 T/FT

COST PER FT

200 lb/ft x .20
 .13 TON x (250)

MATERIAL

\$ 40.00

33.00

$\underline{\$ 73.00}$

LABOR

(.12) \$24.00

(100) 13.00

$\underline{\$ 37.00}$

J. F. CAMPELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM

1023-2

PEQUONNOK RIVER BASIN, CONN.

ALTERIATE COSTS

CANTILEVER FORMS (REUSE PRICE FOR 2X HT. MONOLITHS)

REUSE INCREASES

146,000 \$'
 + 74,000 \$'

220,000 \$' ≈ 33% INCREASE

COST OF MAT'L

45,000 FORMS LESS SALVAGE
 28,860 ANCHORS
 9,620 33% ADD'L ANCHORS

\$83,480
 / 220,000 \$' = .38 \$' / \$'

CONVEYOR EQUIP.

BATCH PLANT TO TRESTLE
 DIST. CONV.

SOL.F.
430 LF
 480 LF.

480 LF @ 150 / = 72000
 RAILS & ACCES. = 7000
 SIDE DISCHARGE = 1000

TOTAL COST
 RESECTION

125,000 + 5,000 = 130,000 × 480 / 860 = 73,000

\$80,000 - SALVAGE + ERECTIO

CABLEWAY REUSE:

127,000
58,365
 185,365

283,000 / = 1.35
185,365

MATERIAL TOWERS

160' HT. X 5 / FT = 800

4 Towers X 2 MOS. X 800 = 6,400
 4 " X 6 " = 28,800
 35,200

CONV. EQUIP: (TWICE AS LONG)

50
 430
 430
910

(3X AS LG)

910
 430
 130,000 × 1340 / 860

125,000 + 5,000 = 130,000 × 910 / 860 = 138,000

= 204,000

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUN. 1, 1972 REV.

SKETCH# ER-52

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONN.

ALTERNATE COSTS

CANTILEVER FORMS (REUSE FOR 3X HT)

146,000 \$
+ 74,000
+ 74,000

294,000 \approx 50% INC.

COST OF MAT'L

45,000 FORMS LESS SALVAGE
28,860 ANCHORS
14,430 ADD'L (50%) ANCHORS

88,290

294,000 = .30 \$/ft.

CABLEWAY REUSE

127,000
58,365

185,365
243,730

258,000 / 243,730 = #1.04

MAT'L TOWERS

240' HT x 5% = 1200
4 TOWERS x 4 MOS x 1200 = 19,200
4 " x 6 " = 28,800

48,000

COST STUDY SHEETS

MODIFIED DESIGN

RC-46

J. F. CAMELLERIE P.E.
 23 GREEN STREET
 HUNTINGTON, N.Y. 11743

DATE JUN 1, '72

SHEET NO. EM-S

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGLAND DIV. -CORPS/ENG'R

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
SUMMARY						
SHEET EM-1				2,314,890		659,240
" EM-2				284,100		246,940
" EM-3				685,900		78,100
" EM-4				787,500		538,200
				4,072,390		1,522,340
ESCALATION THRU 1974			2%	81,450	11%	167,460
				4,153,840		1,689,800
PAYROLL, TAXES & INSURANCE					14%	236,570
						1,926,370
						4,153,840
TOTAL COST TO CONTRACTOR						6,080,210
O'HD, PROFIT & CONT.					8%	486,420
						6,566,630
B'D BOND					3/4%	49,370
TOTAL CONTRACT PRICE						6,616,000

	J. F. CAMELLERIE P.E. 23 GREEN STREET HUNTINGTON, N.Y. 11743	DATE JUN 1, '72	PRICED BY	SHEET NO. EM-1	
		PROJECT: TRUMBULL LAKE DAM			
		ARCHITECT: NEW ENGLAND DIV. -CORPS./ENG'R.			

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
DAM-SLIP ALL MONOLITHS SIMULTANEOUSLY						
CLEARING & GRUBBING	360,000	S.F.	.05	18,000	-	SUB
DISPOSAL	250,000	S.F.	.03	7,500	-	SUB
EXCAV. UNCLASS.	36,000	C.Y.	2.00	72,000	-	SUB
EXCAV. ROCK	10,000	C.Y.	10.00	100,000	-	SUB
EXCAV. TALUS	14,000	C.Y.	3.00	42,000	-	SUB
HAND CLEANING	70,000	S.F.	.75	52,500	-	SUB
CULVERT PIPE	-	L.F.	4.50	-	1.50	-
CHAIN LINK FENCE	850	L.F.	3.50	3,000	2.00	1,700
FOUNDATION GROUTING	50,000	S.F.	.90	45,000	-	-
DIVERSION	-	L.S.		714,000	-	SUB
CEMENT	10,840	TONS	27.20	294,800	-	-
FLY ASH	6,055	TONS	9.00	54,500	-	-
BORROW OPER.	240,000	TONS	.30	72,000	.29	69,500
AGGREGATE PROD.	231,000	TONS	.53	128,000	.34	78,500
BATCH PLANT OPER.	127,000	C.Y.	3.44	437,360	1.30	166,000
CONC. PLACING (SLIP FORM) <small>EXCEPT</small>	72,700	C.Y.	1.82	132,000	.71	51,600
VIBRATION (")	72,700	C.Y.	.38	27,600	.46	33,400
HORIZ. JT. TREATMENT	250,650	S.F.	.05	12,600	.15	37,600
FINISHING (SLIP FORM) <small>EXCEPT</small>	75,000	S.F.	.05	3,750	.28	21,000
CURING (")	308,800	S.F.	.01	3,100	.01	3,100
FIX FORMS: FDN	18,300	SF CA	.80	14,640	3.00	55,000
LIFT STARTERS	5,100	SF CA	.95	4,800	1.17	6,000
CANTILEVER	34,300	SF CA	.95	32,600	1.17	40,000
TRANSV. BULKHEAD	21,600	SF CA	.95	20,500	1.17	25,300
STAIR TOWER	2,300	SF CA	1.50	3,450	3.50	8,050
INTERMEDIATE	9,750	SF CA	.25	2,440	1.00	9,750
SPRAY WALL	800	"	.30	240	1.50	1,200
SLAB (PUMP HOUSE)	2,470	"	.75	1,850	1.00	2,470
SLAB (TOP)	2,350	"	.25	590	.75	1,760
PUMP HSE WALLS	7,080	"	.75	5,310	2.00	14,160
PUMP HSE SHORING	35,800	CU.FT.	.06	2,150	.06	2,150
VERT. SURF. TOP DAM	12,400	SF CA	.25	3,100	1.50	18,600
RETAINING WALLS	7,450	SF CA	.25	1,860	1.00	7,450
TOP CURBS	3,300	"	.50	1,650	1.50	4,950
SHEET TOTAL						
				2,314,890		659,...

J. F. CAMELLERIE P.E.
 23 GREEN STREET
 HUNTINGTON, N.Y. 11743

DATE July 1, '72 PRICED BY

SHEET NO. EM-2

PROJECT: TRUMBULL LAKE DAM
 ARCHITECT: NEW ENGLAND DIV. - CORDS/ENGR.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
<u>SLIP FORM OPERATION</u>						
SLIDING FORMS	1000	L.F.	7"	7,000	10 ⁵⁰	10,500
YOKES	122	EA.	210"	25,600	135"	16,500
JACK RODS (GT)	10,000	L.F.	2 ⁵⁰	25,000	.13	1,300
PLATFORM DECKS	1,000	L.F.	1 ⁵⁰	1,500	4"	4,000
RAILINGS + LADDERS	1,000	L.F.	4 ⁵⁰	4,500	2 ⁵⁰	2,500
FORM DESIGN	—	—	—	10,000	—	—
SLIDE CREW				—		108,000
FINISHING	71,000	#'	.05	3,600		SLIDE CREW
CURING	71,000	#'	.01	700		SLIDE CREW
FIELD ASSIST. ENGR	15	DAYS	200	3,000	—	—
FIELD TECHNICIANS	30	DAYS	150	4,500	—	SUB
STRIP FORMS	—	—	—	—	—	16,500
HYDRAULIC PIPING	2400	L.F.	—	—	.80	1,900
CONVEYORS	54,300	S.Y.	1 ⁵⁰	82,000	.12	6,500
MATERIAL TOWERS	4 x 4 1/2	MOB.	1200	21,700	—	34,000
CONV. SUPP. BKT	14	EA.	650"	9,100	325"	4,700
PRECAST INSERTS	2500	EA.	12 ⁵⁰	31,300	—	IN CREW
CONV. SUPP. TRUSS	9	EA.	2150"	19,400	1105"	9,900
ELEPHANT TRUSSES				—		—
GUIDE WHEEL BKT.	370	EA.	65"	24,100	—	IN CREW
<u>GALLERIES (FORMED)</u>						
FORMWORK	16,500	sq ft	.65	10,725	12"	28,875
STAIRS	1,300	sq ft	.30	390	12"	1,625
SHEET TOTAL				281,100		246,800

J. F. CAMELLERIE P.E.
 23 GREEN STREET
 HUNTINGTON, N.Y. 11743

DATE JULY 1, '72 PRICED BY

SHEET NO. EM-3

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGLAND DIV. - CORPS / ENGR

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
<u>GENERAL ITEMS</u>						
HYDRAULIC PACKAGE	1	L.S.	-	303,680	-	-
EXTENSION 36" BLOW-OFF	1	L.S.	-	5,000	-	2,000
3 1/2" Ø STL PIPE	1,160	LF	3 ⁵⁰	4,060	5 ⁵⁰	6,380
2 1/2" Ø " "	2,150	LF	1 ⁷⁵	3,760	3 ⁵⁰	7,530
3" DRAINAGE HOLES	2,880	LF	8 ¹⁰	23,300	-	SUB
1 1/2" GROUT HOLES	9,240	LF	8 ⁻	73,920	-	SUB
6" DRAINS	2,770	LF	1 ⁷⁰	4,720	-	SUB
8" WELLS	1,600	LF	2 ²⁵	1,350	-	SUB
PLUMBLINE SHAFT	120	LF	3 ⁻	360	2 ⁵⁰	300
REINF. STEEL	100,000	LBS.	.15	15,000	.09	9,000
BACKFILL	12,000	C.Y.	-	-	2 ⁻	24,000
ROCK SLOPE PROT.	800	C.Y.	3 ⁻	2,400	10 ⁻	8,000
ROCK GRAVEL	12,000	C.Y.	4 ⁵⁰	5,400	2 ⁵⁰	3,000
BIT. CONC. PAVING	12,000	S.Y.	5 ⁻	6,000	-	SUB
ALUM. HAND RAIL	1,000	LF	10 ⁻	10,000	3 ⁻	3,000
COPPER WATERSTOP	2,874	LF	3 ⁵⁰	19,000	4 ⁵⁰	12,900
<u>ENVIRONMENTAL WORK</u>						
TURBIDITY CONTROL			-	77,000	-	SUB
DUST CONTROL			-	1,000	-	-
NOISE CONTROL (EQUIP)			-	80,000	-	-
LANDSCAPE RENEWAL			-	5,000	-	2,000
R.R. BED	279,000	sq'	.20	54,000	-	SUB
<u>SHEET TOTALS</u>						
				685,900		78,100

J. F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

DATE JULY 1, '72 PRICED BY

SHEET NO. EM-4

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGLAND DIV. - CORPS/ENGR.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
EQUIPMENT						
TIMBER TRESTLE	480	L.F.	73'	35,000	37'	17,800
YARD CRANE	1 X 11	Mos.	4500'	49,500	-	29,800
CONVEYOR SYSTEM	-	-	-	CONC. IN PLACING	-	CONC. IN PLACING
HYDRAULIC BOOM CRANES	2 X 6	Mos.	1500	18,000	1400	16,800
COMPRESSORS	2 X 6	"	1100	13,200	1500	15,600
UTILITY TRUCKS	2 X 14	"	850	22,400	940	26,300
PERSONNEL STAIR TOWER	3 X 9	"	80	2,200	-	2,000
DOZER	1 X 14	"	1200	16,800	1330	18,700
(SUB-TOTAL)				157,100		127,000
FIELD OVERHEAD						
BRIDGE	1	EA.		1,000		5,000
IMPROVE R.R. BED	268,000	FT.	1 ^{1/2}	402,000		SUB
ACCESS ROAD, VALLEY	72,000	FT.	1'	72,000		SUB
FIELD OFFICE, SHOPS, STORAGE				27,000		3,000
HARDWARE + TOOLS				45,000		-
FUEL & OIL				12,000		-
START-UP + LAYOUT				-		5,000
MIX DESIGN				1,000		-
CONCRETE TESTING				25,000		SUB
TEMPORARY LIGHTING				3,000		10,000
SANITARY FACILITIES				5,400		SUB
CLEAN-UP				-		20,000
HEATING				20,000		-
PROJECT MANAGER	1 X 113	WKS		-	500	56,500
SUPERINTENDENT	1 X 86	WKS		-	400	34,400
PROJECT ENGINEER	1 X 76	WKS		-	400	30,400
CLERKS	2 X 76	"		-	200	30,400
SURVEYORS	4 X 76	"		-	250	76,000
UTILITY MECHANICS	6 X 48	"		-	300	86,500
WATCHMEN	3 X 113	"		-	100	34,000
WINTER PROTECTION				2000		5,000
COMMUNICATIONS				5000		5000
POWER DISTRIBUTION				10,000		10,000
(SHEET TOTAL)				787,500		538,200

J. F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

DATE: JUNE 1/72 PRICED BY TR

SHEET NO. EM-6

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGL. DIV. - CORPS / ENGR

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
<u>PRECAST GALLERIES</u>						
<u>CASTING PLANT</u>						
EXCAV.	40	CY	3 ⁰⁰	120		SUB
CASTING BEDS, CONC.	18	CY	18 ⁰⁰	324	7 ⁰⁰	126
" " REINF.	1000	SF	.10	100	.05	50
" " FORMS	150	SF	.25	40	.75	110
GRAVEL BASE	500	SF	1 ⁰⁰	500	-	SUB
MISC. INSERTS	-	-	-	50	-	-
<u>FORMS</u>						
1 CHANNEL STEEL FORM	756	SF	8 ⁷⁵	6600	-	SUB
1 TROUGH " "	100	SF	4 ⁰⁰	400	-	"
1 STAIR " "	150	SF	4 ⁰⁰	600	-	"
2 LEV. BEAMS + MISC. RAILS	100	SF	4 ⁰⁰	400	-	"
<u>LABOR FOR 172 UNITS</u> 60 PRODUCTION DAYS						
FOREMAN	1 x 60	DAYS	-	-	31 ⁰⁰	4,900
LABORERS	3 x 60	"	-	-	44 ⁰⁰	8,060
MASONS	1 x 60	"	-	-	71 ⁰⁰	4,270
LATHERS	2 x 60	"	-	-	21 ⁰⁰	9,800
CONV. OPERATOR	1 x 60	"	-	-	62 ⁰⁰	3,720
<u>MATERIALS</u>						
CONC. BY SITE PLANT	-	-	-	-	-	-
REINF.	20	TONS	200 ⁰⁰	4,000	-	-
MISC.	-	-	-	200	-	-
<u>ERECTION CREW</u>						
FOREMAN	1 x 40	DAYS			76 ⁰⁰	3,040
LABORERS	2 x 40	"			44 ⁰⁰	3,590
CRANE OPER	1 x 40	"			68 ⁰⁰	2,750
TRUCK DRIVER	1 x 40	"			42 ⁰⁰	1,720
CRANE	2	Mos	1000	2,000		
FLAT BED	2	"	1000	2,000		
TOTAL				17,300		42,100

J. F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

DATE JUNE 1/72 PRICED BY KK

SHEET NO. EM-F1

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGL. DIV. - CORDS / ENGR

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
<u>PRECAST FACE FORM SECTIONS</u>				<u>SCHEME "1"</u>		
<u>CASTING PLANT</u>						
EXCAV. & GRAVEL BASE	-	-	-	-	-	-
CHARGED TO GENERAL EQUIPMENT COST						
<u>FORMS</u>						
20 STEEL FORMS	1720	SF	5 ⁵⁰	9200	-	SUB
LABOR FOR 1250 UNITS	65	PRODUCTION DAYS				
FOREMAN	1 x 65	DAYS	-	-	87 ⁵⁰	5,300
LABORERS	12 x 65	"	-	-	448 ⁰⁰	35,000
MASONS	2 x 65	"	-	-	71 ²⁰	9,250
LATHERS	8 x 65	"	-	-	21 ⁵⁰	42,450
CONCRETE OPERATOR	1 x 65	"	-	-	42 ⁸⁰	2,780
YARD CRANE OP.	1 x 65	"	-	-	55 ⁵⁰	4,470
<u>MATERIAL</u>						
CONC. BY SITE PLANT	-	-	-	-	-	-
REINF.	156	TONS	200 ⁰⁰	31,200	-	-
MISC. IN CRDS, ETC.	-	-	-	4,500	-	-
<u>EQUIPMENT</u>						
1 YARD CRANE	3	MOS	100 ⁰⁰	3,000	-	-
1 CONC. TRUCK	3	MOS	800 ⁰⁰	2,400		
ERECTION	10	ERECTION DAYS (21H ³⁵)				
<u>LABOR</u>						
FOREMAN	1 x 10	DAYS	-	-	275 ⁰⁰	2,750
LATHERS (2 CRANE)	4 x 10	DAYS	-	-	275 ⁰⁰	11,000
ERECTION CRANE OP.	3 x 10	DAYS	-	-	232 ⁰⁰	6,960
TRANSPORTATION TO ERECTION SITE BY						
9000 CRANE & CABLEWAY						
<u>MATERIAL</u>						
ANCHORS	2500	EA.	9 ⁵⁰	24,000	4 ⁰⁰	10,000
				74,900		129,960
						74,900
						204,860
$\$204,860 \times 107,000 / 74,000 = \$295,000$						
SP 10196A (STEEL FORMS = \$171,800)						

J. F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

DATE JUNE 1/72 PRICED BY KR

SHEET NO. EM-F₂

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGL. DIV. - CEDRS / ENG.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
<u>PRECAST FACE FORMS</u> SCHEM # 2						
<u>CASTING PLANT</u>						
<u>EXCAV. & GRAVEL BASE</u>						
<u>CHARGED TO GENERAL</u>						
<u>EQUIPMENT COST</u>						
<u>FORMS</u>						
20 STEEL FORMS	3800	SF	6 ⁵⁰	24,700	—	SUB
<u>LABOR FOR 1430 UNITS</u>			227	<u>PRODUCTION</u>	<u>DAYS</u>	
FOREMAN	1x88	DAYS	—	—	31 ⁵⁰	7,190
LABORERS	16x88	"	—	—	44 ⁸⁰	63,000
MASONS	2x88	"	—	—	71 ²⁰	12,520
LATHERS	8x88	"	—	—	81 ⁵⁰	57,400
CRANE OPER. (YARD)	2x88	"	—	—	68 ⁵⁰	12,100
CONC. TRUCK OP.	2x88	"	—	—	42 ⁸⁰	7,550
<u>MATERIAL</u>						
CONC. BY SITE PLANT	—	—	—	—	—	—
REINF.	286	TONS	200 ⁰⁰	57,200	—	—
MISC. INSERTS	11600	EA	1 ⁵⁰	11,600	—	—
<u>EQUIPMENT</u>						
2 YARD CRANES	4	MOS	1000 ⁰⁰	4,000	—	—
2 CONC. TRUCKS	4	MOS	800 ⁰⁰	3,200	—	—
<u>ERECTOR</u>						
FOREMAN	1x200	DAYS	—	—	31 ⁵⁰	16,320
LATHERS	1x200	"	—	—	81 ⁵⁰	16,320
LABORERS	2x200	"	—	—	44 ²⁰	17,920
CRANE OPERATORS	1x200	"	—	—	68 ⁵⁰	13,760
<u>MATERIAL</u>						
CONC. ANCHORS	5800	EA.	1 ⁶⁰	9,400	—	—
<u>TRANSPORTATION TO PERMANENT SITE</u>				110,100		224,080
<u>BY 900LN CRANE & CABLEWAY</u>						110,100
						334,180
SP 10196A (STEEL FORMS = 171,800)						

J. F. CAMPELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

IRUNBULL LAKE DAM. EM-S-1
 PEQUONNOK RIVER BASIN, CONN.
 DAM - SLIP ALL MONOLITHS SIMUL.

BATCH PLANT OPERATION:

NO. OF DAYS OPERATION (209-SR1 THRU SR8) _____ 160 DAYS
 LESS SLIP DAYS FOR 1 MONOLITH @ A TIME _____ -37

SPEED = 4"/HR. AVERAGE 75' HIGH SLIP _____ 123 DAYS

$$\frac{75'}{.33'/HR} = 228 \text{ HRS. SLIPPING.}$$

$$3 \text{ SHIFTS/DAY} = 24 \times 5 = 120 \text{ HRS/WK}$$

$$9 \text{ DAYS} \times 3 \text{ SHIFTS/DAY} = 27 \text{ SHIFTS} \times \frac{9}{8} = 30.5$$

$$2 \text{ SHIFT} \times \frac{9}{8} = 2.25$$

$$\underline{29 \text{ SHIFTS}} \quad \underline{32.75} \quad \text{_____} \quad \underline{33 \text{ DAY}}$$

X8

232 HRS

PAY 156 DAY

LABOR COST	156 (461)	=	72,000	} SH. ER.
SUPPLIES	"	=	44,500	
LABOR (COOLING)	"	=	28,600	
SUPPLIES	"	=	20,000	

$$\frac{\$165,100}{127,000} = \$1.30/40$$

CONC. PLACING (EXCEPT SLIP FORM) 68,600 C.Y.

MONO. I	-1240	
II		+1340
III	-1240	
IV		+1340
V		
IV		+1340
III & III		+1340
		+1240

72,720 C.Y.

SAY 72,700 C.Y.

RC-55

J. F. CAMIELLEKIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM EM S-2
 PEQUONNOK RIVER BASIN, CONN.
 DAM - SLIP ALL MONOLITHS SINGLE.

<u>HORIZ. JT. TREATMENT</u>			235,650 ϕ'
MONOLITH	I	-4,300	—
	II	—	+4,650
	III	-4,300	—
	IV	—	+4,650
	V	—	—
	VI	—	+4,650
	VII	—	+9,650 ← 4650 + 5000
			<u>250,650 ϕ'</u>

<u>FINISHING (EXCEPT SLIP FORM)</u>			72,000 ϕ'
MONOLITH	I	-7.5	
	II	+7.5	
	III	-7.5	
	IV	+7.5	
	V	0	
	VI	+7.5	
	VII	+15	
			<u>22.5 x 60 x 2.25 = 3040 ϕ'</u>
			<u>75,000 ϕ'</u>

<u>CURING (EXCEPT SLIP FORM)</u>	308,000 ϕ'	TRANSV. =	560 x 4
+ UP & DOWN STREAM FACE = +3,040 ϕ'			2,240
			<u>-2,240 ←</u>
	<u>308,800</u>		

<u>CAST. FORM</u>	
+1	33,300 ϕ' CA
	+ <u>1,000</u>
	<u>34,300</u>

<u>INT. FORM</u>	
+2	7,750 ϕ' G.A.
	+ <u>2,000</u>
	<u>9,750</u>

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

IRUMBULL LAKE DAM EM-53
PEQUONNOC RIVER BASIN, CONN.
DAM - SLIP ALL MONOLITHS SIMUL.

SLIDING FORMS: 60 x 7 = 420 L.F. DOWNSTREAM
420 L.F. UPSTREAM
80 > TRANSV.
80
1000 L.F.

YOKES 420'
- 4'
416 / 8 = 52 SPA. SAY 53 YOKES DOWNSTREAM
53 UP
8 > ENDS
8
122

<u>SLIDE CREW</u>		HR. RATE	COST / SHIFT
<u>CLASSIFICATION</u>		INCL. FRINGE BENIFITS	WEEKDAY SHIFT RATE 8 HR. WORK / 9 HR. PAY
CONV. OPERATOR	6	7.75	\$ 418
HOIST ENGR	4	8.60	310
JACK OPER.	2	8.00	144
CARPENTERS	10	9.00	810
ELECTRICIAN	3/2	8.28	50
FINISH FOREMAN	1	9.37	84
FINISHER	7	8.87	560
FINISH HELPER	2	7.15	129
LABORERS:			
FOREMAN	1	6.10	55
PLACING	10	5.60	} 1160
VIBRATION	10	5.60	
CURING	3	5.60	
			\$ 3,720

29 SHIFTS @ \$ 3720 = \$ 108,000

FINISHING: 75' x 420' x 2.25 = 71,000 ft³

STRIP FORMS: 50% ERECTION : FORMS 10,500
YOKES 16,500
DECKS 4,000
RAILS 2,500 / 33,500 x 50% = 16,750

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM EM 5.2
PEQUINNOCK RIVER BASIN, CONNS.
DAM - SLIP ALL MONOLITHS SIMUL.

CONVEYORS: (ADD'L)

MAT'L TOWER TO FEEDER 40' x 4 = 160'
DIST. CONV. 90' x 4 = 360'
SPREADING CONV. 60' x 6 = 360'
30' x 2 = 60'
940'

940' x 150% = 141,000
RAIL + ACC. 14,000
SIDE DISCH. 8,000

163,000 LESS 50% SALVAGE = \$82,000

COST/DAY = $\frac{82,000}{14 \text{ DAYS}}$ = \$5,850/DAY

COST/YD = $\frac{82,000}{53,500}$ = \$1.58

LABOR: ERECTION 35 MEN C'S x 2 DAYS = \$4480
DISMANTLE 2240
\$6720

COST/YD = $\frac{6720}{54,300}$ = .12

PRECAST INSERTS: L.F. JACKROD = 10,000' SPA = 4'
 $\frac{10,000'}{4} = 2500 \text{ EA.}$

GUIDE WHEEL BKT: 122 LOCATIONS x 3 = 366
SAY 370

COPPER WATERSTOPS (SH. EC-535)

147 2690
150 -800
1890
148 + 484
133 500
106
800
2874 L.F.

J. F. CAVILLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM ER-5-5
PEQUONNOK RIVER BASIN, CONN.
- No-SLUMP CONCRETE

CEMENT REQUIREMENT

INT. MASS CONCRETE

$$\begin{aligned} \text{CEMENT } 94 \text{ lb} \times 93,000 &= 8750000 \text{ lb} \\ &= 4400 \text{ TONS} \\ \text{FLY ASH } 130 \text{ lbs} \times 93,000 &= 12100000 \text{ lb} \\ &= 6050 \text{ TONS} \end{aligned}$$

DECREASE IN PORTLAND CEMENT:

$$6500 \text{ LESS } 4400 = 2100 \text{ TONS}$$

INCREASE IN FLY ASH:

$$6050 \text{ LESS } 5100 = 950 \text{ TONS}$$

COST DIFFERENTIAL

$$\begin{aligned} 2100 (\$27.20) &= \$57,120 \\ - 950 (\$9.00) &= \underline{8,550} \\ &= \$48,570 \end{aligned}$$

VIBRATION

CA-25 DYNAPAC COMPACTOR

$$\begin{aligned} \$30,000 \\ \underline{1,000} \quad (200 \times \$4 \text{ shipping}) \end{aligned}$$

$$\begin{aligned} \$31,000 \\ \underline{15,000} \text{ SALVAGE} \end{aligned}$$

$$\begin{aligned} \$16,000 \times 2 \text{ ROLLERS} &= \$32,000 \end{aligned}$$

SAVINGS IN AIR COMPRESSOR & VIBRATORS

$$= \$26,000$$

ADD'L COST

$$= \underline{\$6,000}$$

$$\text{CREW } 2 \text{ MEN @ } \$5.60 = \$11.20$$

$$\text{VIB. OPER @ } \$7.80 = \underline{7.80}$$

$$= \underline{\$19.00} \times 8 = 152.00$$

$$\text{TOTAL COST} = \$152 (103 \text{ days}) = \$15,700$$

$$\text{SAVINGS} = 31,200 \text{ LESS } 15,700 = \underline{\$15,500}$$

$$\begin{aligned} \text{TOTAL SAVINGS IN VIBRATION} &= \$15,500 - 6,000 \\ &= \underline{\$9,500} \end{aligned}$$

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

LATE JUNE 1/72 REV.



SKETCH # EM-5-6

TRUMBULL LAKE DAM

PERUGANNOCK RIVER BASIN, CONN.

PRECAST INSPECTION GALLERY

TENTATIVE LAYOUT




J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1 / 72 REV. SKETCH# EM-S-7
TRUMBULL LAKE DAM
POUGHKEEPSIE RIVER BASIN, CONY.
PRECAST INSPECTION GALLERY

PRECAST SECTIONS

		<u>SF/UNIT</u>
1) STRAIGHT UNITS	33 EA.	350
2) SLOPE UNITS	23 EA.	250
3) TOP FILLERS	5 EA.	170
4) BOTT. FILLERS	2 x 6 EA.	90
5) LEVELLING BEAMS	38 EA.	-
6) DRAIN TROUGHS	33 EA.	-
7) STAIR SLABS	28 EA.	-

STRAIGHT UNITS



SEC. B-B

CONC. VOLUME

$$(2 \times 8' + 6.7 + 1.33) \times 0.33' \times 15' = 8.0 \times 15 = 120 \text{ CF} = 4.5 \text{ CY EA.}$$

REINFORCING

$$= 500 \text{ \# EA.}$$

FORM CONTACT AREA

$$(2 \times 8.33 + 2 \times 7.33 + 2 + 4.67) \times 15 + 48 \times 0.33 = 586 \text{ SF}$$

570

16

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1 / 72 REV.


SKETCH # EM-S-5

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

PRECAST INSPECTION GALLERY

SLOPE UNITS



CONC. VOLUME

$$(2 \times 8.0 + 6.7 + 1.33) \times 0.33 \times 10.6 = 8 \times 10.6 = 85 \text{ CF} = \underline{3.2 \text{ CY}}$$

EA.

REINF.

= 350 # EA.

CONTACT AREA : $38 \times 11 + 20 = \underline{440 \text{ SF}}$


TOP FILLERS

CONC. VOLUME

$$\left(\frac{8.48^2}{72} + 12 \times \frac{8.0}{96} \right) \times 0.33 = 55 \text{ CF} = \underline{2 \text{ CY}}$$

REINF.

= 220 #



J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1/72 REV.

SKETCH # E M-S-29


TRUMBULL LAKE DAM
POQUONNOK RIVER BASIN, CONN.
PRECAST INSPECTION GALLERY

BOTT. FILLERS

CONC. VOL.

$90 \times 0,33 = 30 \text{ CF} = 1,1 \text{ CY}$

REINF. = 100"



FORM - SF + CONC. VOL.

	NO	CY	SF-CONTACT AREA	
1/ STR. UNITS	33 EA	$\times 4,5 = 149$	586	- USE 24'x10'x1 CONC. BED FOR BASE ~ 9 CY
2/ SLOPE UNITS	23 EA	$\times 3,2 = 74$	440	
3/ TOP FILLERS	5 EA	$\times 2 = 10$	225	
4/ BOTT. FILLERS	12 EA	$\times 1,1 = 14$	13 (RAILS)	
TOTAL	73	247 CY		

USE ONE STEEL FORM (INTERIOR COLLAPSIABLE) TO
 POUR NO 1, 2) & 3)

REQ. CONTACT AREA = $38 \times 19,5 + 20 = 756 \text{ SF}$

BULKHEAD UNITS TO BE FIELD ADJUSTED FOR ASKEW &
 VERTICAL USE.

5/ LEVELLING BEAMS	38 EA	$\times 1 = 38$	40 (RAILS)	- 24'x10'x1 CONC. BED FOR BASE
6/ DRAIN UNITS	33 EA	$\times 75 = 25$	100	
7/ STAIR SLABS	28 EA	$\times 1,1 = 31$	150	
TOTAL	99	94 CY		

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.


DATE JUNE 1, 1972 REV.

SKETCH # EM-S-11

TRUMBULL LAKE DAM
 DEQUONNOCK RIVER BASIN, CONN.
 PRECAST INSPECTION GALLERY

STAIR SLAB FOR SLOPE UNITS

28 REQ.



CONC. VOL.

$$10,66 \times (6 \times 0,33 + 0,66 \times 0,5 + 5 \times 0,27) \approx 40 \text{ CF} = \underline{1,5 \text{ CY}}$$

$$\text{RE} = \underline{180^2 \text{ ft}} \quad \begin{matrix} 0,33 & 1,35 \end{matrix}$$

CONTACT AREA

$$75 + 11 + 50 + 15 = \underline{151 \text{ SF}}$$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 11/72 REV.

SKETCH# EM-5-11


TRUMBULL LAKE DAM

DEQUONNOCK RIVER BASIN, CON II.

PRECAST INSPECTION GALLERY

LEVELLING BEAMS FOR STRAIGHT UNITS.

38 EA. REQ.



CONC. VOL. $7,5 \times 2,17 + 4,83 \times 2 - 1,67^2 = 24 \text{ CF} \sim 1 \text{ CY}$

RE. = 120" 16,3 9,7 2,5


DRAIN TROUGHS

33 REQ.

CONC. VOL.

$3,66 \times 0,33 \times 15 = 18 \text{ CF}$
 $\sim 0,75 \text{ CY}$

RE. = 100"



28 Strips

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

LATE JUNE 1/72 REV.

SKETCH# EM-S-12

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONN.

PRECAST INSPECTION GALLERY

PRECAST OPERATION

A) FORMS

PRICE/SF
DELIVERED

1) STEEL FORM FOR U SECTIONS	756 SF	8 ⁷⁵	6 600.00
2) 1 FORM FOR TROUGHS	100 SF	4 ⁰⁰	400.00
3) 1 FORM FOR STAIR SLABS	150 SF	4 ⁰⁰	600.00
4) MISC. RAILS FOR BOT. FILLERS & LEVELLING BEAMS	100 SF	4 ⁰⁰	400.00
<u>TOTAL</u>			<u>\$ 8,000.00</u>

CONC. BEDS

1) CONC. COST	(MAT. 18 ⁰⁰ , LABOR 7 ⁰⁰)	
2 x 24 x 10 x 1 = 480 CF = 18 CY x 25 ⁰⁰		450.00
2) RE. MESH 960 SF (LAB+MAT.)		150.00
3) EXCAV. OR GRADE (3 ⁰⁰ /CY) 40 CY x 3 ⁰⁰		120.00
4) GRAVEL BASE, COMPACTED (1 ⁰⁰ /SF)		500.00
500 SF		<u>1220.00</u>
5) MISC. FORMS (LAB+MAT.)		150.00
<u>TOTAL COST FOR FORMS</u>		
	8000.00	
	1220.00	
	150.00	
	<u>\$ 9370.00</u>	

PRECAST PRODUCTION STUDY

I	II	III
33 STR. UNITS	2 x 19 LEV. B.	12 BOT. FILL.
23 + 5 SLOPE + TOPF.	28 STAIRS	33 DRAINS
56 DAYS	47 DAYS	45 DAYS

ITEM				ST	PRODUCTION CYCLE	
I	+ 2-LEVEL BEAMS	+ 1 BOT. FILLER		1 ST		
"	I + 2-	"	+ 1 DRAIN	2 ND	"	"
"	I + 1- STAIR		+ 1 DRAIN	3 RD	"	"

CY	4,5	+	2		+	1,1	=	7,6 CY
"	4,5	+	1,1		+	0,75	=	6,4 CY
"	5,2	+	1,1		+	0,75	=	7,1 CY

SEC ¹⁵	1 EA	+	2		+	1	=	4
"	1	+	1		+	1	=	3
"	2	+	1		+	1	=	4

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
POLLANOCK RIVER BASIN CO.
PRECAST INSPECTION GALLERY

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM

REQUONNOCK RIVER BASIN, CONN.

PRECAST INSPECTION GALLERY

B) LABOR

MAX. NO OF POURS = 4

" CY OF CONC. = 7,6

CHANNEL SECTIONS

OPERATION	MEN	HRS	TOTAL
SET	4	$\frac{1}{2}$	4
POUR	4	$\frac{1}{2}$	6
FINISH	1	2	2
STRIP & CLEAN	4	$\frac{1}{2}$	6
REINF.	2	4	8

PRODUCTION TIME = 4 HR'S | 26 MH'S EA.

CONVEYOR FOR CONC. DISTRIBUTION REQUIRES ONE FULLTIME OPERATOR

SCHEDULED LEVELLING BEAMS, FILLERS, DRAINS & STAIRS WILL REQUIRE AN APPROX. PRODUCTION TIME OF 4 HR'S

TOTAL CREW FOR PRECAST OPERATION

1 FOREMAN	10.20	10.20
3 LABORERS	5.60	16.80
1 MASON	8.90	8.90
2 LATHERS	10.20	20.40
1 CONV. OPER.	7.75	7.75

$64.05/HR \times 8 = 512.40 / \text{SHIFT}$

ASSUME 60 WORKING DAYS

$60 \times 512.40 = \underline{\underline{30,744.00}}$

CRANE & CRANE OPERATOR FOR YARD: SEE SUMMARY SHEET "EM-G"

9

J. F. CAMELLERIE, P.E.

23 GREEN STREET

HUNTINGTON, N. Y.

DATE JUNE 1/72 REV.

SKETCH# EM

TRUMBULL LAKE DAM

PERQUONNOK RIVER BASIN, CO.

PRECAST INSPECTION GALLERY

C) REINFORCING SUMMARY

1/ $33 \times 500^{\#} = 16,500^{\#}$

2/ $23 \times 350^{\#} = 8,050$

3/ $5 \times 220^{\#} = 1,100$

4/ $12 \times 100^{\#} = 1,200$

5/ $38 \times 120^{\#} = 4,560$

6/ $33 \times 100^{\#} = 3,300$

7/ $28 \times 180^{\#} = 5,040$

39,750[#] ≈ 20 TONS

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11 1972 REV.

SKETCH# EM-5

TRUMBULL LAKE DAM

PEQUONNOK FIVER BASIN, CONN.

PRECAST INSPECTION GALLERY


TOTAL PRECAST COST.

1) SITE PREPARATION & CONC. BEDS	1,420
2) FORMS	8,000
3) LABOR	30,750
4) REINF + MISC.	4,200
<u>TOTAL</u>	<u>\$ 44,370</u>

FOR ERECTION COST SEE SUMMARY SHEET "EM-6"

J. F. CAMELLENKIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRIMBULL LAKE DAM
PULLMAN & BRYER BASIN, CONN.
PRECAST DAM FORMS, SECTION



EL. OF PRECAST FORMS (VIEW FROM INSIDE DAM)
CONC. LIFTS NOT SHOWN

"CANTILIVER" FORMS FOR CONT. POURING OPERATION.

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
PERQUIMANKETIVER BASIN, CONN.
PRECAST FACE FORM SECTIONS
 SCHEME #1

MISC.

CONC. VOLUME FOR ONE PRECAST SECTION

SLAB = $10' \times 6' \times 0,33' = 20,0 \text{ CF}$
 RIBS = $(2 \times 10' + 3 \times 6') \times 0,66 \times 0,5 = 12,5 \text{ CF}$
 $32,5 \text{ CF} = 1,2 \text{ CY EA.}$

REINFORCING ~ 200 # / UNIT

FORM CONTACT AREA

$60' + 44' \times 0,66' = 89 \text{ SF} \times 20 \text{ REQ} = 1780 \text{ SF}$

NO OF SECTIONS REQUIRED = 1250 EA.

ASSUMED PRODUCTION RATE PER DAY = 20 EA.
 $1250 / 20 = 63 \text{ WORKING DAYS, APPROX. 3 MONTH.}$

REQ. CONC. VOL. PER DAY = $20 \times 1,2 = 36 \text{ CY}$

PRECAST OPERATION

<u>A) LABOR</u>	<u>MEN</u>	<u>HR'S</u>	<u>TOTAL</u>
SET	2	$\frac{1}{2}$	1
POUR	3	$\frac{1}{2}$	$\frac{1}{2}$
FINISH	1	34	34
STRIP &	2	$\frac{1}{2}$	1
CLEAN			
REINF.	2	$\frac{1}{2}$	3.
<u>PRODUCTION TIME</u>		$\frac{1}{2}$	

$5 \times \frac{1}{2} = 7 \frac{1}{2}$ EACH CREW POURS 5 SLABS PER DAY

MANPOWER REQ. FOR 20 UNITS PER DAY

FOREMAN	1	10.20	10.20
LABOR	12	5.60	67.20
MASON	2	8.90	17.80
LATHERS	8	10.20	81.60
CRANE OP.	1	8.60	8.60
TRUCK OP.	1	5.35	5.35
			PER SHIFT
<u>TOTAL PER HR</u>			$131.75 \times 8 = 1054.00$

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1/72 REV.

SKETCH # ZEM-S 19

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONN.

PRECAST FACE FORM SECTIONS

SCHEME # 1

B/ FORMS

COST PER SF. DELIVERED = 5.50

TOTAL SF. REQ. = $1780^{SF} \times 5.50 = \underline{9,800.00}$


CONC. BEDS

GRAVEL BASE

$155' \times 40' \times 1' = 6200 \text{ SF}$

+ 1000 "

7200 SF OR CF



GRADING & EXCAVATING

APPROX 3000 CY

FOR COST SEE "GENERAL EQUIPMENT"

C/ REINFORCING.

$1250 \text{ UNITS} \times 250^{\#} = 312^K = 156 \text{ TONS}$


J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1 / 72 REV.

SKETCH # EM-S 2.0

TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CONN.
PRECAST FACE FORMS, SCHEME "P"

ELEV. OF PRECAST
FORMS (VIEW FROM
INSIDE DAM)
CONC. LIFTS NOT
SHOWN



J. F. CAMELLEKIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM E111-S-21
POQUONNOC RIVER BASIN, CONN.
PRECAST FACE FORMS - SCHEME "2"

MISC.

CONC. VOL. FOR ONE TYP. PRECAST SECTION

$$10 \times 7.5' \times 0.33 + 11.25' \times 0.33' \times 0.66' \times 4 + 3.75' \times 0.33' \times 0.66' \times 2$$

25 13 25

$$= 41CF = 1.50$$

REINFORCING

~ 400# / UNIT

FORM CONTACT AREA

190 SF / UNIT

NO OF SECTIONS REQUIRED

$$\frac{107,270 SF}{75 SF} = 1430 EA.$$

PROJECTED PRODUCTION RATE PER DAY.

20 UNITS PER DAY REQ. $\frac{1430}{20} = 72$ PRODUCTION DAYS
ASSUME 88 DAYS OR 4 MONTHS

PRECAST OPERATION

A) LABOR

	MEN	HR'S	TOTAL
SET	2	1	2
POUR	3	34	24
FINISH	1	34	34
STRIP &	2	1	2
CLEAN			
REINF.	2	2	4

PRODUCTION TIME 234

1 CREW POURS 3 UNITS PER DAY

7 CREWS / 20 UNITS

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 1977 REV.

SKETCH # E-19-S 2

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN.

PRECAST FACE FORMS - SCHEME

MANPOWER REQ. TO POUR 20 SECTIONS PER DAY

FOREMAN	1	10.20 / HR	81 <u>60</u> / DAY
LABOR	16	5.60	44 <u>80</u>
MASON	2	8.90	71 <u>20</u>
LATHERS	8	10.20	81 <u>60</u>
CRANE OP.	2	8.60	68 <u>80</u>
TRUCK OP.	2	5.35	42 <u>80</u>

B) FORMS

TOTAL SF. REQ. = $20 \times 190 \text{ SF} = 3800 \text{ SF}$

$$3800 \times 6.50 = \underline{24,700.00}$$

POURING BEDS

CHARGED TO "GENERAL EQUIPMENT"

C) REINFORCING

$$1430 \text{ UNITS} \times 400'' = 572^{\text{K}} = 286 \text{ TONS}$$

D) ANCHORS

SPECIAL PERMANENT ANCHORS MAY BE REQUIRED TO MAKE THE PRECAST PANELS RESIST POSSIBLE HYDROSTATIC OR ICE PRESSURE IN THE JOINT BETWEEN PRECAST SECTIONS & POURED-IN-PLACE CONCRETE.

THIS COST STUDY INCLUDES CONVENTIONAL CANTILEVER FORM ANCHORS.

COST AND FEASIBILITY STUDY
ALTERNATE DESIGNS TO PERMIT USE
OF SLIP FORM AND OTHER TECHNIQUES
TO MAXIMIZE ECONOMIES

BOOK A
STUDY OUTLINE
ALTERNATE DAM DESIGN TO
PERMIT USE OF SLIP FORM AND OTHER
TECHNIQUES TO MAXIMIZE ECONOMICS

BOOK A - STUDY OUTLINE - ALTERNATE DAM DESIGN TO PERMIT
USE OF SLIP FORM AND OTHER TECHNIQUES TO MAXIMIZE ECONOMY

Page A-1	Purpose and Limits of Study
Page A-4	Cost and Feasibility Study, Composite Dam
Page A-18	Costs and Feasibility Study, Massive Head Buttress Dam
Page A-57	Costs and Feasibility Study, Cellular Dam
Page A-70	Comments and Conclusions

Drawings and Sheets

1	Drawings 209-AD-1, AD-1A, AD-2, AD-3, AD-3A, and AD-4
2	Sheets AD-1S, AD-11 through AD-16
3	Sheets AD-2A, AD-2B1, and AD-2B2
4	Sheets AD-2S, AD-21 through AD-25
5	Sheets AD-2C, AD-S1 through 7 (Book AC-2)
6	Sheets AD-2CS, AD-2C-1 through C-5
7	Sheets AD-3S, -31 through -35
8	Sheets AD-4A, AD-4S
9	Sheets AD-11 through AD-16
10	Sheets AD-41 through AD-46
11	Sheets AD-S-108 through -113 (Book AC-1)
12	Sheets AD-S-201 through -227 (Book AC-2)
13	Sheets AD-S-401 through -414 (Book AC-4)
14	Sheet AD-EC-S
15	Sheets AD-EC-S1 through -S3 (Book AC-2)
16	Sheets AD-EC-1 through -3
17	Sheets AR-401 through -411 (Book AC-4)
18	Sheets AR-200 through -217 (Book AC-2)

PURPOSE AND LIMITS OF STUDY

The purpose of this study is to explore the possibility of applying slip form and other construction techniques to alternate designs for the dam at Trumbull Lake that are substantially different from the gravity dam as presently designed. Although time requirements will not justify redesign of this dam, the information gained will be useful for other dam sites yet to be designed. Topography, geology, dam size and many other factors will reduce the quantitative value of the comparative cost figures obtained. Nevertheless, the overall cost trends will be valuable in indicating potentially fruitful design and construction methods to be investigated for future dams.

Four different dam designs are considered for the purpose of this study:

1. A composite dam utilizing slip formed structural concrete, no-slump fill concrete and precast concrete blocks.
2. A slip formed Massive Head Buttress Dam.
3. An Ambursen Dam with slip formed buttresses.
4. A cellular type dam.

Actual alternate designs of the dam are obviously beyond the scope of this report. By rational extension of the basic design, some educated assumptions and a minimal amount of stability and soil pressure calculations, proportions and quantities were obtained which are probably correct within the limitation to accuracy that results from physical characteristic variations of different dam sites.

Although possibly the most promising alternate design to be investigated, arch dams have not been studied in this report due to their sensitivity to design and site conditions as well as the range of possible configurations. The results obtained in the studies on massive head and cellular dams do have some application to arch dams and these results are discussed relative to arch dams under Conclusions and Comments.

The discussion relative to the use of slip form techniques to implement the basic design applies here to diversion, construction sequence, environmental impact, access, escalation, and labor considerations.

Cost figures are developed for each of these alternate designs for comparison with the basic design and with each other. Some variations in design and construction procedures as well as increase in size are also analyzed.

COST AND FEASIBILITY STUDY
COMPOSITE DAM

GENERAL DESCRIPTION

This alternate (shown on drawing 209-AD-1) is essentially identical in concept and design with the Trumbull Lake Dam as designed, but differs in materials and construction process used. This combination of structural, precast and mass concrete fill was proposed and successfully implemented in the construction of two small dams by V.M. Wallingford of Hydro-Quebec.

The basic concept of this design is the provision of an impermeable structural concrete wall upstream, a serviceable precast surface downstream and an economical low cement fill in between. The savings accrue from elimination of downstream and transverse forming, elimination of horizontal joints, immunity to temperature cracking and overall low cement requirement.


This study includes two modifications from Mr. Wallingford's proposal. One is the substitution of a cellular upstream face in lieu of a heavy monolithic wall. This has the advantage of completely eliminating dangers of thermal stresses that may exist in the more massive wall, reduces the amount of concrete to be handled during the slip and provides a good platform at the top for carrying construction equipment such as cranes. The second modification is in the configuration of the precast blocks. In order to facilitate placing of the fill concrete, these are designed without overhang on the concrete side. A flush rather than stepped downstream face is also achieved by this block configuration.

The no-slump concrete used is described under the heading "Impact of No-Slump Concrete" in the "Discussion of Additional Modifications" section of the preceding report on utilization of slip form techniques.


The cells on the upstream face may be filled with low cement concrete or a granular fill. Although lighter in weight, the granular fill would have certain drainage advantages.

CONSTRUCTION METHODS


Using structural concrete, slip forming may proceed at rates upward of twelve inches per hour thereby obtaining very good economy. The cost of forming out the cells is minimal in view of the advantages obtained. Drawing



SECTION A-A



PLAN




SECTION B-B




GRAPHIC SCALE


DESIGNER	J. F. CAMELLERIE, P.E.	DEPARTMENT OF THE ARMY
CHECKED	W. H. BROWN	ENGINEER
DATE	APR 1953	
WATER RESOURCES DEVELOPMENT PROJECT		
TRUMBULL LAKE		
PEQUONNOC RIVER BASIN, CONNECTICUT		
COMPOSITE DESIGN FOR GRAVITY DAM		
209-AD-1		



SLIP FORM SYSTEM



SECTION THROUGH SPILLWAY



CONCRETE DISTRIBUTION SYSTEM



GRAPHIC SCALE

DATE	SITE	DISTRICT	BY
J. F. CAMELLERIE, P.E. CONSULTING ENGINEER		DEPARTMENT OF THE ARMY WATER RESOURCES DIVISION CORPS OF ENGINEERS	
PROJECT NO. 474188-07E		WATER RESOURCES DEVELOPMENT PROJECT TRUMBULL LAKE PEQUONNOK RIVER BASIN CONNECTICUT	
DRAWN BY: []		COMPOSITE DESIGN FOR GRAVITY DAM	
CHECKED BY: []		DATE: []	
APPROVED BY: []		SCALE: []	
DRAWING NO. 209-AD-1A		SHEET	

A

209-AD-1A shows the slip form system which is the "common garden variety" in general use on silo construction. Concrete is brought up to the placing deck by means of a cable guided skip hoist supported on the slip form system and automatically emptying into a deck hopper. Concrete may be distributed laterally by buggy, conveyor, monorail, or a combination. Pumping directly into the forms is difficult but pumping vertically (in lieu of hoist) and laterally to distribution points is entirely feasible. The slip is made in three sections of 160 feet each.

In the area of the spillway, the longitudinal walls are stopped below the level of transverse walls as shown on section thru spillway. Fix formed panels are required to place the fill above this point and to continue the concrete surface to meet the highest pre-cast block. The slip form deck which is continued to the top may be used to cast the roadway deck and as a working platform for forming the curb and overhang.

Temporary steel beams are provided over the spillway to allow use of a crane for placing the precast blocks.

The keyed concrete blocks resist the hydrostatic pressure from the fill concrete by gravity and need no cantilever system for support. Their height is 2'-6" coordinated with the fill lifts of 5'-0" and their length 10'-0" to keep the weight down below 10 tons. These blocks may be cast on the site or purchased from a nearby casting yard. Rate of production used is 21 blocks per day; setting varies from 16 per day at bottom to 32 per day at the top to keep pace with placement of fill.

The no-slump concrete fill is placed by a conveyor system suspended from the previously slipped upstream cells. The trusses supporting the distributing conveyors run on a rail system and are hydraulically supported and raised by hydraulic jacks as the work progresses. This system allows headroom for the placing crew and the vibratory compactor. At elevation 222'-6" insufficient room remains for using the vibratory compactor; low slump concrete capable of being vibrated by hand tools must be used above this point.

The areas below elevations 162'-6" and 185'-0" between monoliths 3 and 12, all of monoliths 1, 2 and 3 and

all of monoliths 12 through 16 are constructed by conventional methods in 7'-6" lifts.

The cells are filled directly by a conveyor at the top of the cells.

CONSTRUCTION SCHEDULE

As shown on concrete demand schedule, sheets AD-S108 through 113, placing of the monoliths takes 166 working days, substantially the same time as required for slip forming the dam as designed. Three months of construction time are saved as compared to placing by conventional methods.

CONSTRUCTION COST

Cost Summary Sheet AD-15 and Cost Sheets AD-11 thru 16 shows the total cost for constructing the dam by this method to be \$7,204,000 as compared to \$6,937,000 using conventional methods.

J.F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

DATE JUL 15, '72 PRICED BY

SHEET NO. AD-11

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGLAND DIV. - CORPS/ENG'R.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
ITEM 04 DAM						
CLEARING & GRUBBING	360,000	S.F.	.05	18,000	-	SUB
DISPOSAL	250,000	S.F.	.03	7,500	-	SUB
EXCAV., UNCLASS.	36,000	CY	2.00	72,000	-	SUB
EXCAV., ROCK	11,000	CY	10.00	110,000	-	SUB
EXCAV., TALUS	14,000	CY	3.00	42,000	-	SUB
HAND CLEANING	70,000	S.F.	.75	52,500	-	SUB
CULVERT PIPE	-	LF	4.50	-	1.50	-
CHAIN LINK FENCE	850	LF	3.50	3,000	2.00	1,700
FOUNDATION GROUTING	50,000	S.F.	.90	45,000	-	-
DIVERSION	-	L.S.		714,000	-	SUB
PRECAST SPRAY WALL	17.5	C.Y.	150.	2,700	200.	3,500
CEMENT	11,660	TONS	27.20	320,000	-	-
FLYASH	5,840	TONS	9.00	52,500	-	-
BORROW OPERATION	240,000	TONS	.30	72,000	.29	69,500
AGGREGATE PRODUCTION	231,000	TONS	.52	128,000	.34	78,500
BATCH PLANT OPER.	127,000	C.Y.	3.44	437,360	1.65	209,000
CONC. PLACING (CONV.)	35,280	C.Y.	-	-	.81	28,600
CONC. PLACING (FILL CHLLS FILL INT. MASS)	71,600	C.Y.	-	-	.46	33,000
VIBRATION (CONV.)	35,280	C.Y.	.44	15,500	.52	18,300
VIBRATION (FILL)	71,600	C.Y.	.21	15,000	.18	12,900
FINISHING	28,000	S.F.	.05	1,400	.28	7,900
CURING	279,000	S.F.	.01	2,800	.01	2,800
HORIZ. JT. TREATMENT	146,000	S.F.	.05	7,300	.15	21,900
FORMS: FOUNDATION	16,000	S.F.	.80	12,800	3.00	48,000
CANTILEVER	13,000	S.F.	.80	10,400	1.17	15,200
TRANSV. BLK'HD	16,000	S.F.	.80	12,800	1.17	18,700
LONG 'L BLK'HD	8,000	S.F.	.80	6,400	1.17	9,400
LIFT STARTERS	4,000	S.F.	.80	3,200	1.17	4,700
SLAB (P.H.)	2,470	S.F.	.75	1,850	1.00	2,470
SLAB (ROAD)	2,350	S.F.	.25	590	.75	1,760
WALLS (P.H.)	7,080	S.F.	.75	5,310	2.00	14,160
RET. WALLS	7,450	S.F.	.25	1,860	1.00	7,450
CURBS (TOP)	3,300	S.F.	.50	1,650	1.50	4,950
PUMP HSE. SHORING	35,800	CU.FT.	.06	2,150	.06	2,150
STAIR TOWER	2,300	S.F.	1.50	3,450	3.50	8,050
SP 10196A			-//-	2,181,020		624,590

J. F. CAMELLEKIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGLAND DIV., CORPS/ENG'R.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
SLIP FORM OPERATION						
SLIDING FORMS	1,350	L.F.	14.	18,900	21.	28,300
YOKES (3T)	200	EA.	-	INCL.	50.	10,000
JACK ROD (3T)	20,900	L.F.	1.65	34,400	.05	1,000
DECKS (INT.)	5,600	S.F.	.50	2,800	1.00	5,600
DECKS (EXT.)	1,920	S.F.	.50	960	1.00	1,920
INSIDE SCAFFOLDS	2,800	S.F.	1.50	4,200	2.00	5,600
HYDRAULIC PIPING	3,350	L.F.	-	INCL.	.80	2,700
FIELD ASSIST. ENG'R.	14	DAYS	200.	2,800	-	-
FIELD TECH.	24	DAYS	150.	3,600	-	SUB
OUTSIDE SCAFFOLDS	1,920	S.F.	1.50	2,900	2.00	3,840
TOPPING OUT RODS	200	EA.	2.00	400		INCL.
CONCRETE (SLIP FORMED)	13,430	C.Y.	-	INCL.	-	INCL.
STEEL REINF. (IN SLIP)	520	TONS	230.	119,600	150.	78,000
FINISH	51,000	S.F.	.05	2,600	-	SLIDE CREW ^{IN}
CURING	102,000	S.F.	.01	1,000	-	SLIDE CREW ^{IN}
SLIDE CREW	-	-	-	-	-	98,200
RAILINGS & LADDERS	1,000	L.F.	4.50	4,500	2.50	2,500
FORM DESIGN	-	-	-	10,000	-	-
STRIP FORMS				-	-	42,500
GALLERY BULKHEADS	2,240	S.F.	.50	1,100	2.00	4,500
HORIZ. KEYS	480	L.F.	.15	75	1.00	480
REBAR PLACING & LISTING	520	TONS	20.00	10,400	-	-
WELD #2 (CRANE)	34	EA.	55.00	2,200	36.	1,200
WELD #2 (CRANE)	192	EA.	13.50	2,600	21.	4,100
JAY POST	1,275	LF.	1.50	1,920	1.00	1,275
SPILLWAY BULKHEADS	3,280	S.F.	.50	1,640	1.00	3,280
BEAM BLOCKOUTS	320	S.F.	.35	100	.85	300
WELD #2 (CONV.)	18	TONS	500.	9,000	-	INCL.
SPILLWAY TOP						
SHORING				1,000		-
FORMS ABOVE SLIP	3,600	SF CA	.30	1,100	1.20	4,300
FORMS BELOW SLIP	5,300	"	.30	1,600	1.20	6,400
PRECAST GALLERY						
				15,580		39,400
SP 10196A		-/2-		256,975		345,395

	J. F. CAMELLERIE P.E. 23 GREEN STREET HUNTINGTON, N.Y. 11743	DATE JUL 15, '72 PRICED BY				SHEET NO. AD-13	
		PROJECT: TRUMBULL LAKE DAM					
		ARCHITECT: NEW ENGLAND DIV. - CORPS/ENG'R.					
	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR	
PRECAST CONC. BLOCKS							
CASTING PLANT, STORAGE YARD, ROAD							
EXCAV. & GRADING CHARGES TO "SITE EQUIPMENT"							
GRAVEL BASE	42,500	S.F.	1.00	42,500	-	SUB	
ACCESS ROAD, GRAVEL	4,000	S.F.	1.00	4,000	-	SUB	
FORMS							
STEEL FORMS	2,940	S.F.	6.50	19,100	-	SUB	
LABOR FOR 1548 UNITS - 80 PRODUCTION DAYS							
FOREMAN	1 x 80	DAYS	-	-	81.60	6,530	
LABORERS	15 x 80	"	-	-	44.80	53,800	
MASONS	2 x 80	"	-	-	71.20	11,400	
CONV. OPER.	2 x 80	"	-	-	62.00	9,900	
YARD CRANE OPER.	2 x 80	"	-	-	68.80	11,000	
MATERIALS							
CONC. BY SITE PLANT	-	-	-	-	-	-	
INSERTS (LIFTING)	6,200	EA.	1.50	9,300	-	-	
MISC.	-	-	-	1,000	-	-	
EQUIPMENT (80 DAYS)							
YARD CRANES (2 EA.)	2 x 4	MOS.	1000	8,000	-	-	
CONVEYORS	700	L.F.	1.50	84,000	-	-	
A-FRAMES	-	-	-	4,000	-	SUB	
CONC. HOPPER	-	-	-	3,500	-	SUB	
MISC.	-	-	-	1,500	-	-	
ERECTION (75 DAYS)							
FOREMAN	1 x 75	DAYS	-	-	76.00	5,700	
LABORERS	3 x 75	"	-	-	44.80	10,100	
CRANE OPER.	1 x 75	"	-	-	68.80	5,160	
2 MASONS (20,000 ^{L.F.} OF JTS.)	2 x 70	"	-	1,000	71.20	10,900	
1 LABORER	1 x 70	"	-	-	44.80	3,140	
EQUIPMENT	-	-	-	2,000	-	-	
SP 10196A		-/3-		179,900		126,730	

COST ANALYSIS

In spite of earlier completion by 3 months this design shows a cost \$267,000 higher than is obtained using conventional methods. The inherent problem is the division of construction into 4 different operations, cantilever forming, slip forming, precasting and dry placing. Each operation must be completely implemented and reuse of plant, formwork and equipment is considerably reduced.

A rectangular valley cross-section would of course improve economy greatly by eliminating or greatly reducing the conventional costing required.

As always, an increase in dam size would result in better utilization of plant and equipment and a more favorable economic position for this design alternate.

COST AND FEASIBILITY STUDY
MASSIVE HEAD BUTTRESS DAM

GENERAL DESCRIPTION

This type of dam has been slip formed in Europe with good success. It is so designed that each buttress section is monolithic and self-sufficient. The foundations are cut into the rock sufficiently to provide safety against sliding and are stepped as required. The low sections at the abutments are shown and costed as also slip formed but these can be fixed formed more economically using structural concrete methods. The design and construction methods for the Massive Head Buttress Dam are shown on Drawings 209-AD-2 and 3A.



As shown on Section B-B, the driveway sits directly on the head and stem avoiding any intermediate sections which would increase construction operations. The spillway section is shown on Section C-C, and consists of a concrete slab placed on precast concrete sections spanning buttress to buttress and acting as leave-in-place forms. The pumping station may be placed in the enclosed area under the spillway, nestled between the buttresses or placed in a specially designed double buttress section.

This type of dam allows use of prestressed rock anchors to reduce the overall size and weight (concrete content) of the dam. As an alternate to the cast-in-place concrete spillway slab, a fully precast spillway slab may be used. Both of these possibilities were studied and are discussed in this report. A flat spillway slab at the top with a lip and sheer drop to the base is also a possibility.

DESIGN


Cursory stability and heel pressure calculations were made for the Massive Head Dam on calculation sheets AR-200 through AR-217. A base length of 135 feet (Scheme #2) was selected with the dimensions shown for a height of 140' above footings. This results in heel pressures of 730 pounds per square foot.

An alternate design was made with a 120 foot base resulting in an uplift pressure of 3270 pounds per square foot at the heel or a total uplift of 448 kips per monolith. Prestressed anchor bolts were provided to reduce this stress to positive pressures. These prestress anchors were allowed to run to the top of the dam thereby resulting in a compressed condition of the upstream face with superior impermeability.




DESIGNED BY J. F. CAMELLERIE, P.E. CORPS OF ENGINEERS		DEPARTMENT OF THE ARMY WATER RESOURCES DEVELOPMENT PROJECT TRUMBULL LAKE PEQUONNOK RIVER BASIN CONNECTICUT	
DRAWN BY [Blank]		CHECKED BY [Blank]	
SCALE AS SHOWN		DATE [Blank]	
PROJECT NO. 209-AD-2		SHEET NO. 20	


NOTE: FOR SECTIONS SEE DWG NO 209-AD-3A




SECTION C-C




SECTION F-F AMBURSEN DAM



SECTION B-B



SECTION D-D



SECTION E-E



GRAPHIC SCALE

DATE	BY	CHECKED	APPROVED
J. F. CAMELIERE, P.E. CONSULTING ENGINEER HARTFORD, CT 06108		DEPARTMENT OF THE ARMY WATER RESOURCES DIVISION CORPS OF ENGINEERS 600 3RD ST. WASH. D.C. 20315	
WATER RESOURCES DEVELOPMENT PROJECT TRUMBULL LAKE PESQUONNOC RIVER BASIN CONNECTICUT			
BUTTRESS DAM SECTIONS			
DRAWN BY: []			
CHECKED BY: []			
DATE: []			
SCALE: []			
209-AD-3A SHEET			

Refined calculations will probably result in a more economical design.

CONSTRUCTION METHODS

In this study, conventional cantilever forming has been entirely eliminated thereby obtaining a one system forming, that being a slip form system. The head and stem sections of each buttress monolith are slip formed as a unit in a continuous 24 hour operation in groups of one to three monoliths joined or separated as site conditions and economy dictate. The head and stem areas under the driveway slide the full height of the dam and may be constructed of steel for reuse on all monoliths. The sloped section of the stem is constructed of wood as it must be continually cut as the slip proceeds. Concrete is handled by a cable guided skip bucket and a side discharge conveyor riding on and with the form as shown on Sections B-B and D-D. The slip form system for forming the sloped surfaces is identical with the system described for slipping the gravity dam.

The casting of the spillway slab presents some problems because of the weight of concrete, span and the fact that the form will end up on the underside of the slab where cranes cannot reach for stripping. For this reason precast leave-in-place forms were selected to support the concrete slab as shown on Section C-C and E-E. The concrete is placed by a slip form riding on the buttress walls and a conveyor resting on this form. The form is weighted by use of water ballast tanks to overcome the uplift due to concrete hydrostatic forces. The concrete is brought up by the skip buckets and brought down the face of the spillway by conveyors running diagonally along the face. Pumping of the concrete seems to have definite advantages in this operation.

This system for casting the spillway slabs results in two distinct operations in addition to the basic buttress slide and is therefore subject to reduction of economy. As an alternate, the face of the spillway may be entirely precast with no concrete facing. Watertight joints are required but the elimination of the spillway slab slide will result in overall economy.

If the spillway slab is eliminated altogether, and the water is allowed to fall free from flat slab at the top of the buttresses on to rock protection at base, another construction operation is eliminated and additional economy is gained.

Prestressing of the upstream face may be accomplished using four 1½" diam. high strength rods per buttress. Average embedment into the rock is assumed at twenty feet. These rods are readily placed in the same manner as reinforcing steel and are partially or finally prestressed through boxes left in the concrete or at the top of the slide. Wrapping prevents bond to the concrete.

CONSTRUCTION SCHEDULE

The construction schedule for the massive head buttress dam is shown on Sheet AD-S-218. This compares favorably with conventional construction for the base gravity dam design reducing the construction time by at least 2 months, and matches the construction time for constructing the base gravity dam utilizing slip form techniques. An additional two months may be saved if the spillway slab is eliminated.

CONSTRUCTION COST

The cost for constructing the massive head buttress dam is \$7,256,000 as shown on cost sheets AD-2S and AD-21 through AD-25. (See also Cost Study Sheets AD-S201 through AD-S220.) This cost is \$283,000 higher than conventional construction of the base gravity dam.

If the spillway face is constructed using precast sections, the cost is reduced by \$200,000 as shown on cost sheet AD-2A (Study sheet AD-S-221).

The use of prestressed rock anchors and reduction of dam width to suit will result in a savings of \$64,000 as shown on Cost Sheets AD-2B1 and AD-2B2 (Study Sheets AD-S222 thru S225).

Assuming the precast and rock bolt alternates are used the total cost is reduced to approximately \$6,992,000.

Elimination of the spillway slab entirely (free fall to rock protected base) will result in a significant saving in the area of \$500,000.

J. F. CAMELLERIE P.E.
 23 GREEN STREET
 HUNTINGTON, N.Y. 11743

DATE 10, 74 PRICE BY SHEET NO. 20
 MASSIVE HEAD BUTTRESS DAM
 PROJECT: TRUMBULL LAKE DAM
 ARCHITECT: NEW ENGLAND DIV. C/E

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
SUMMARY - MASSIVE HEAD BUTTRESS DAM						
SHEET AD-21				1,953,600		66,800
22				1,539,355		885,995
23				249,095		403,350
24				282,720		273,750
25				96,000		319,000
TOTAL				4,120,770		1,948,895
ESCALATION THRU 1974			2%	82,416	11%	215,000
				4,203,186		2,163,895
PAYROLL, TAXES & INS.					14%	303,000
						2,466,895
						4,203,186
TOTAL COST TO CONTRACTOR						6,670,081
OVERHEAD, PROFIT & CONT.					8%	532,000
						7,202,081
BID BOND					3/4%	54,000
TOTAL CONTRACT PRICE						7,256,081

J. F. CAMELLERIE P.E. 23 GREEN STREET HUNTINGTON, N.Y. 11743	DATE: JUL 15, '72 PRICED BY MASSIVE HEAD BUTTRESS DAM		SHEET NO. AD-21	
	PROJECT: TRUMBULL LAKE			
	ARCHITECT: NEW ENGLAND DIV., CORPS/ENGRS			

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
SITE WORK						
CLEARING & GRUBBING	360,000	S.F.	.05	18,000	-	SUB
DISPOSAL	250,000	S.F.	.03	7,500	-	SUB
EXCAVATION (UNCLASS.)	36,000	CY	2.00	72,000	-	SUB
" (ROCK)	2,860	CY	10.00	28,600	-	SUB
" (TALUS)	14,000	CY	3.00	42,000	-	SUB
HAND CLEANING	27,500	S.F.	.75	20,600	-	SUB
CULVERT PIPE	-			-		-
CHAIN LINK FENCE	850	LF	3.50	3,000	2.00	1,700
FOUNDATION GROUTING	27,500	S.F.	.90	25,000	-	-
DIVERSION		L.S.		714,000	-	SUB
BACK FILL	12,000	CY	-	-	2.00	24,000
ROCK SLOPE PROT.	800	CY	3.00	2,400	10.00	8,000
ROAD GRAVEL	1,200	CY	4.50	5,400	2.50	3,000
BIT. CONC PAVING	1,200	CY	5.00	6,000	-	SUB
ALUM. HAND RAIL	1,000	LF	10.00	10,000	3.00	3,000
TIMBER TRESTLE	480	LF	73.00	35,000	37.00	17,800
BRIDGE	1	EA		1,000		5,000
IMPROVE R.R. BED	268,000	S.F.	1.50	402,000		SUB
VALLEY ACCESS ROAD	72,000	S.F.	1.00	72,000		SUB
MECHANICAL ITEMS						
HYDRAULIC PACKAGE	1	L.S.		303,700		-
EXTENSION 36" BLOW-OFF	1	L.S.		5,000		2,000
PLUMBLINE SHAFT	120	LF	3.00	400	2.50	300
ENVIRONMENTAL WORK						
TURBIDITY CONTROL				80,000		SUB
DUST CONTROL				1,000		-
NOISE ABATEMENT				40,000		-
LANDSCAPE RENEWAL				5,000		2,000
R.R. BED "	270,000	S.F.	.20	54,000	-	SUB
SP 10196A			-2-	1,953,600		66,800

J. F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

DATE JUL 15, '72 PRICED BY

SHEET NO. AD-23

MASSIVE HEAD BUTTRESS DAM

PROJECT: TRUMBULL LAKE

ARCHITECT: NEW ENGLAND DIV. CORPS/ENGR

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
FOUNDATIONS						
FORMWORK	22,400	S.F.	.20	4,500	.80	18,000
CONCRETE	6,000	CY	-	-	7.00	42,000
REINF. STL.	96	TONS	230	22,000	400	38,500
CURING	30,000	S.F.	.01	300	.02	600
KEYWAYS	3,000	LF	1.00	3,000	1.00	3,000
WATERSTOPS	2,000	LF	3.50	7,000	4.00	8,000
SPILLWAY						
SLIDING FORMS	288	LF	13-	3,800	20.50	6,000
FORM RAILS	1,260	LF	3-	3,800	3.00	3,800
JACK ROD ANCHORS	24	EA	25-	600	50.00	1,200
JACK ROD 22T	4,776	LF	2.50	12,000	.20	1,000
PLATFORM DECKS	288	LF	1.00	300	1.00	300
FORM DESIGN				5,000		-
SLIDE CREW				-		108,000
FIELD ENGR.	14	DAYS	200-	2,800		-
FIELD TECHNICIAN	30	DAYS	150-	4,500		-
HYDRAULIC PIPING	300	LF		INCL	1.00	300
CONCRETE	1,620	YDS	-	-	-	-
REINF. STEEL	122	TONS	230	28,000	135-	16,500
FINISHING	54,500	S.F.	.05	2,725		SLIDE CREW
CURING	54,500	S.F.	.01	550		SLIDE CREW
STRIP FORMS				-		6,000
PRECAST FORMS	54,500	S.F.	2.25	122,620	2.50	136,250
FILL AT TOP	570	CY	-	-	8.00	4,600
FINISHING TOP	10,800	S.F.	.05	500	.15	1,600
CURING TOP	10,800	S.F.	.01	100	.02	200
STARTER FOOTINGS	500	CY	50-	25,000	15.00	7,500
SP 10196A			-27-	249,095		403,350

J.F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

DATE JUL 15, '72 PRICED BY
MASSIVE HEAD BUTTRESS DAM

SHEET NO. AD-25

PROJECT: TRUMBULL LAKE

ARCHITECT: NEW ENGLAND DIV., CORPS/ENGR.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
FIELD OVERHEAD						
FIELD OFFICES, SHOPS, STORAGE				15,000		2,000
HARDWARE & TOOLS				20,000		-
FUEL & OIL				10,000		-
START-UP & LAYOUT				-		5,000
MIX DESIGNS				1,000		-
CONCRETE TESTING				15,000		SUB
TEMPORARY LIGHTING				6,000		20,000
SANITARY FACILITIES				4,000		SUB
CLEAN-UP				-		10,000
HEATING				10,000		-
PROJECT MANAGER	1 x 117	WKS		-	500	58,500
SUPERINTENDENT	1 x 60	"		-	400	24,000
PROJECT ENGR.	1 x 52	"		-	400	20,800
CLERKS	2 x 52	"		-	200	20,800
SURVEYORS	4 x 52	"		-	250	52,000
UTILITY MECH.	6 x 36	"		-	300	64,800
WATCHMEN	3 x 87	"		-	100	26,100
WINTER PROTECTION	NONE			-		-
COMMUNICATIONS				5,000		5,000
POWER DISTRIB.				10,000		10,000
SP 10196A			-29-	96,000		319,000

J. F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

DATE JUL 13, '74 PRICED BY

SHEET NO. AD-2A

MASSIVE HEAD BUTTRESS DAM

PROJECT: TRUMBULL LAKE

ARCHITECT: NEW ENGLAND DIV. - CORPS/ENGR.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
PRECAST SPILLWAY ALTERNATE						
SPILLWAY FROM SH. AD-23				212,295		293,250
PRECAST SPILLWAY						
PRECAST SLABS	33,200	S.F.	8.00	265,600	-	-
PLACING CREW	33,200	S.F.	-	-	.50	16,600
PLACING CRANE	1	MO		INCL. IN EQUIPMENT		INCL. IN EQUIPMENT
JOINT TREATMENT	13,500	LF	5.00	67,500		INCL. IN PLACING CREW
FILL AT TOP	570	CY	-	-	8.00	4,600
FINISHING TOP	11,000	S.F.	.05	550	.15	1,650
CURING TOP	11,000	S.F.		110		220
STARTER FOOTINGS	500	CY	50-	25,000	15-	7,500
				358,760		30,570
DIFFERENCE			(-)	146,465		262,680
ESCALATION THRU 1974			2%	2,930	11%	28,895
			(-)	149,395		291,575
PAYROLL, TAXES & INS.					14%	40,820
						332,395
						149,395
						183,000
OVERHEAD, PROFIT & CONT.					8%	14,640
						197,640
BID BOND					3/4%	1,483
CREDIT IF SPILLWAY ALT. IS USED						199,123

J. F. CAMELLERIE P.E.
 23 GREEN STREET
 HUNTINGTON, N.Y. 11743

DATE JUL 15, '72 PRICED BY
 MASSIVE HEAD BUTTRESS DAM SHEET NO. AD-2B1

PROJECT: TRUMBULL LAKE
 ARCHITECT: NEW ENGLAND DIV. C/E

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
PRESTRESSING ALTERNATE						
FOUNDATIONS (REDUCTION)						
FORMWORK	2,700	S.F.	.20	540	.80	2,160
CONCRETE	600	CY	-		7.00	4,200
REINF. STEEL	-					
CURING	4,050	S.F.	.01	40	.02	81
KEYWAYS	-					
WATERSTOPS	-					
BUTTRESS SLIDE (REDUCTION)						
SLIDING FORMS	900	LF	6.65	5,985	10.50	9,450
YOKES	60	EA	-	INCL.	75.-	4,500
JACK RODS (3T)	3,450	LF	1.65	5,693	.05	173
DECKS	2,250	SF	.25	563	1.00	2,250
SCAFFOLDS	1,800	SF	.50	900	1.50	2,700
RAILINGS & LADDERS	900	LF	1.50	1,350	1.50	1,350
HYDRAULIC PIPING	2,100	LF	-	INCL.	.80	1,680
CONCRETE	5,400	CY	-	INCL.	-	-
FINISH	3,600	SF	.05	180	-	SLIDE CREW
CURING	3,600	SF	.01	36	-	SLIDE CREW
CEMENT	1,700	TONS	27.20	46,240	-	-
BORROW OPERATION	6,300	TONS	-	3,600	.29	1,827
AGGREGATE PROD.	9,600	TONS	-	-	.34	3,264
BATCH PLANT OPERATION	6,000	CY	-	-	1.75	10,500
SITE WORK (REDUCTION)						
EXCAVATION (ROCK)	150	CY	10.00	1,500	-	SUB
HAND CLEANING	4,050	SF	.75	3,038	-	SUB
FDN. GROUTING	4,050	SF	.90	3,645	-	SUB
SP 10196A			- 21 -	73,310		44,135

COST ANALYSIS

The cost figures for this and the other two design alternates are based on site work, excavation, diversion, access and mechanical items remaining unchanged. Rock excavation, hand cleaning and foundation grouting were varied however to suit the different conditions. The driveway at the top of the dam was not changed in length or profile but the configuration of the dam immediately below was altered slightly. The cost of the pumping station, retaining walls and stair tower was arrived at using the original quantity estimates prepared by the Corps of Engineers for these items and applying a reasonable cost figure for concrete of this type in place less the cost of concrete which is included elsewhere. On first consideration the slip formed massive head dam seems not to offer any economy in construction cost and the construction time differential is not impressive. Construction of the spillway surfaces is more expensive than for the gravity design even when precast concrete is used for this purpose. Actually the spillway for this type of dam must be handled in another manner.

The savings in cost that accrues from the use of prestressed rock anchors is modest but so is the amount of prestressing used. It can be reasonably deduced from this study that the use of such anchor bolts holds promise for better economy and that their use should be considered in future designs.

The use of pumping in lieu of conveyor equipment was studied on cost study sheets AD-S226 and S227. Pumping saves over \$120,000 in this particular situation, most of the savings (\$70,000) resulting from the elimination of the material hoists required for raising the concrete vertically to the conveyors. The pumps do have the advantage of vertical rise capabilities.

As a matter of interest some cost figures were run for a dam twice as high and twice as wide with the savings not as great as for the smaller dam. If the hoists are deducted, the savings drop to less than \$10,000 (less than the cost of the special slip form cantilevered brackets required because of the sloped buttresses).

In general it may be said that pumping has an edge in equipment and installation cost while conveyors have an edge in labor cost involved in using the equipment.

If vertical lifting equipment is not required for raising concrete to the conveyors, the two methods are quite competitive with the pumping possibly more economical on smaller dams and the conveyors more economical on larger dams.

The possibility is obvious that a cost comparison based on a dam the size of the one at Trumbull Lake may not give sufficient construction volume to truly arrive at cost differentials between various designs. This is especially true when one considers that most of the cost and construction time is expended on site work, diversion, mechanical, etc., which are not in this instance related to the design of the structure itself. In order to explore this possibility, a study was made of a dam twice the height and twice the width of the one at Trumbull. Many simplifying assumptions had to be made; proportions of the dam would remain the same, volume of concrete would be quadrupled, diversion clearing and site work would remain substantially the same. The results of this cost study for both the conventional gravity dam and the slip formed massive head dam are shown on Cost Sheets AD-EC-S and AD-2CS, respectively. Backup cost sheets are included here; calculation sheets (see Sheets AD-EC-S1 thru S-3 and AD-2C-S1 thru S7) and cost study sheets and construction schedules are in the appendix.

J. F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

CONVENTIONAL DAM (INCR. SIZE)

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGLAND DIV. C/E

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
CLEARING & GRUBBING	430,000	SF	.05	21,500	-	SUB
DISPOSAL	320,000	SF	.03	9,600	-	SUB
EXCAV., UNCLASS.	72,000	CY	2.00	144,000	-	SUB
EXCAV., ROCK	20,000	CY	10-	200,000	-	SUB
EXCAV., TALUS	28,000	CY	3.00	84,000	-	SUB
HAND CLEANING	140,000	SF	.75	105,000	-	SUB
CHAIN LINK FENCE	850	L.F.	3.50	3,000	2.00	1,700
FOUNDATION GROUTING	100,000	SF	.90	90,000	-	-
DIVERSION STAGE I	-	-	L.S.	547,000	-	SUB
DIVERSION STAGE II	-	-	L.S.	167,000	-	SUB
CEMENT	43,100	TON	27.20	1,175,000	-	-
FLY ASH	24,500	TON	9.00	220,500	-	-
BORROW OPERATION	933,000	TON	.20	178,000	.29	271,000
AGGREGATE PRODUCTION	924,000	TON	.46	426,000	.34	314,000
BATCH PLANT OPER.	508,000	C.Y.	2.04	1,036,720	1.75	888,000
CABLEWAY OPER.	508,000	C.Y.	1.28	646,000	.61	310,000
CONCRETE PLACING	508,000	C.Y.	.03	15,200	.52	264,000
VIBRATION	508,000	C.Y.	.35	178,000	.41	208,000
HOR. JOINT TREATMENT	851,300	SF	.05	42,600	.15	128,000
FINISHING	292,000	SF	.05	14,600	.28	81,500
CURING	861,600	SF	.01	8,616	.01	8,616
FORMS: FDN	18,300	CA	.80	14,640	3.00	55,000
LIFT STARTERS	12,830	CA	.43	5,520	1.17	15,000
CANTILEVER	227,400	CA	.43	98,000	1.17	266,000
BULKHEAD	206,400	CA	.43	88,500	1.17	241,000
LONG 'L BLKH'D	11,520	CA	.30	3,460	1.25	14,400
SPRAY WALL	1,600	CA	.30	500	1.50	2,400
SLAB (P.H.)	2,470	CA	.75	1,850	1.00	2,470
SLAB (TOP)	2,350	CA	.25	590	.75	1,760
WALLS (P.H.)	7,080	CA	.75	5,310	2.00	14,160
DAM (TOP)	12,400	CA	.25	3,100	1.50	18,600
RET. WALLS	7,450	CA	.25	1,860	1.00	7,450
CURBS	3,300	CA	.50	1,650	1.50	4,950
GALLERY	16,500	CA	.65	10,720	1.75	28,875
STAIRS	1,300	CA	.30	390	1.25	1,625
HYDRAULIC PACKAGE	1	L.S.	-	303,680	-	-
			-34-	5,852,103		3,148,506

J. F. CAMPELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

CONVENTIONAL DAM (INCR. SIZE)

PROJECT: TRUMBULL LAKE DAM
ARCHITECT: NEW ENGLAND DIV. C/E

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
EQUIPMENT						
YARD CRANE	1 x 24	MOS	4500	108,000	2700	64,800
HYDRAULIC BOOM CRANE	2 x 20	"	1500	60,000	1400	56,000
COMPRESSORS	2 x 20	"	1100	44,000	1300	52,000
UTILITY TRUCKS	2 x 27	"	800	43,200	940	51,000
PERSONNEL STAIR TOWER	3 x 24	"	80	5,800	-	-
DOZER	1 x 27	"	1200	32,400	1330	36,000
FIELD OVERHEAD						
ACCESS ROAD TOP	7,350	SF	1.50	11,000	-	SUB
BRIDGE	1	EA	-	1,000	-	5,000
IMPROVE R.R. BED	268,000	SF	1.50	402,000	-	SUB
ACCESS ROAD VALLEY	72,000	SF	1.00	72,000	-	SUB
FIELD OFF., SHOPS & STOR.	-	-	-	90,000	-	4,000
HARDWARE & TOOLS	-	-	-	135,000	-	-
FUEL & OIL	-	-	-	48,000	-	-
STARTUP & LAYOUT				-	-	5,000
MIX DESIGNS				1,000	-	SUB
CONC. TESTING				75,000	-	SUB
TEMPORARY LIGHTING				3,000	-	6,000
SANITARY FACILITIES				24,000	-	SUB
CLEAN-UP				-	-	30,000
HEATING				48,000	-	-
PROJECT MANAGER	1 x 175	WKS		-	500	87,500
SUPERINTENDENT	1 x 140	"		-	400	56,000
PROJECT ENGR.	1 x 140	"		-	400	56,000
CLERKS	2 x 140	"		-	200	56,000
SURVEYORS	4 x 120	"		-	250	120,000
UTILITY MECHANICS	6 x 90	"		-	300	162,000
WATCHMEN	3 x 170	"		-	100	51,000
WINTER PROTECTION				6,000		15,000
COMMUNICATIONS				10,000		6,000
POWER DISTRIBUTION				15,000		15,000
SP 10196A		-32-		1,234,400		934,300

J. F. CAMELLERIE P.E. 23 GREEN STREET HUNTINGTON, N.Y. 11743	DATE JUL 15, '72 PRICED BY		SHEET NO. AD-2C-1	
	MASSIVE HEAD BUTTRESS DAM			
	PROJECT: TRUMBULL LAKE		ARCHITECT: NEW ENGLAND DIV. C/E	

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
SITE WORK						
CLEARING & GRUBBING	387,500	S.F.	.05	19,300	-	SUB
DISPOSAL	277,500	S.F.	.03	8,300	-	SUB
EXCAVATION (UNCLASS)	72,000	CY	2.00	144,000	-	SUB
" (ROCK)	5,720	CY	10-	57,200	-	SUB
" (ALUS)	28,000	CY	3.00	84,000	-	SUB
HAND CLEANING	55,000	S.F.	.75	41,200	-	SUB
CHAIN LINK FENCE	850	LF	3.50	3,000	2.00	1,700
FOUNDATION GROUTING	55,000	S.F.	.90	50,000	-	-
DIVERSION		LS		714,000	-	SUB
BACKFILL	12,000	CY	-	-	2.00	24,000
ROCK SLOPE PROT.	800	CY	3.00	2,400	10-	8,000
ROAD GRAVEL	1,200	CY	4.50	5,400	2.50	3,000
BIT. CONC. PAVING	1,200	CY	5.00	6,000	-	SUB
ALUM. HAND RAIL	1,000	LF	10-	10,000	3.00	3,000
TIMBER TRESTLE	480	LF	73-	35,000	37-	17,800
BRIDGE	1	EA.		1,000		5,000
IMPROVE R.R. BED	268,000	S.F.	1.50	402,000	-	SUB
VALLEY ACCESS RD.	72,000	S.F.	1.00	72,000	-	SUB
MECHANICAL ITEMS						
HYDRAULIC PACKAGE	1	L.S.		303,700		-
EXTENSION 36" BLOW-OFF	1	L.S.		5,000		2,000
PLUMBLINE SHAFT	120	L.F.	3.00	400	2.50	300
ENVIRONMENTAL WORK						
TURBIDITY CONTROL				80,000	-	SUB
DUST CONTROL				2,000		-
NOISE ABATEMENT				80,000		-
LANDSCAPE RENEWAL				5,000		2,000
R.R. BED "	270,000	S.F.	.20	54,000	-	SUB
				2,184,900		
SP 10196A				-40-		

J. F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

DATE: JUL 15, '72 PRICED BY

SHEET NO. AD-2C-2

MASSIVE HEAD BUTTRESS DAM

PROJECT: TRUMBULL LAKE

ARCHITECT: NEW ENGLAND DIV., C/E

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
BUTTRESS SLIDE						
SLIDING FORMS	12,650	L.F.	6.65	84,200	10.50	133,000
YOKES	750	EA.	-	INCL.	75.00	56,200
JACK RODS (3T)	276,410	L.F.	1.65	456,000	.05	13,800
DECKS	33,000	S.F.	.25	8,250	1.00	33,000
SCAFFOLDS	28,000	S.F.	.50	14,000	1.50	42,000
RAILINGS & LADDERS	14,000	L.F.	1.50	21,000	1.50	21,000
HYDRAULIC PIPING	20,750	L.F.	-	INCL.	.80	16,600
TOPPING OUT RODS	360	EA.	2.00	720	-	INCL.
FORM DESIGN				10,000		-
FIELD ENG'R	20	DAYS	200-	4,000	-	-
FIELD TECH.	40	DAYS	150-	6,000		SUB
CONCRETE	224,000	CY	-	INCL.	-	-
REINF. STEEL	1,000	TONS	230-	230,000	-	SLIDE CREW
SLIDE CREW				-		1,100,000
FINISH	1,485,000	S.F.	.05	74,200	-	SLIDE CREW
CURING	1,485,000	S.F.	.01	14,850	-	" "
STRIP FORMS				-		37,000
VERTICAL KEYS	9,600	L.F.	1.00	9,600	.50	4,800
WATERSTOPS	9,600	L.F.	3.50	33,600	4.00	38,400
REBAR PLACING & LISTING	1,400	TONS	15-	21,000	-	-
END BULKHEAD FORMS	240	L.F.	3.60	900	10.50	2,500
YOKES	60	EA.	180-	10,800	135-	8,100
JACK RODS (6T)	13,000	L.F.	2.50	32,600	.13	1,700
PRECAST INSERTS	3,260	EA.	9.00	29,300	-	SLIDE CREW
GUIDE WHEEL BRACKETS	18	EA.	65-	1,200	-	" "
SPILLWAY SLAB SEAT	5,500	L.F.	6-	33,000	9.00	49,500
PRECAST SEAT	5,500	L.F.		INCL.		INCL.
HORIZ. PRECAST SEAT	576	L.F.	3-	1,800	6.00	3,600
CEMENT	73,000	TONS	27.20	1,990,000	-	-
BORROW OPERATION	440,000	TONS	.23	102,000	.29	128,000
AGGREGATE PROD.	416,000	TONS	.63	263,000	.34	142,000
BATCH PLANT OPER.	260,000	YDS.	2.12	552,000	1.75	455,000
SP 10196A			-4/-	4,004,020		2,286,200

J. F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

DATE JUL 15, '72 PRICED BY
MASSIVE HEAD BUTTRESS DAM

SHEET NO. AD-2C-3

PROJECT: TRUMBULL LAKE

ARCHITECT: NEW ENGLAND DIV. C/E

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
FOUNDATIONS						
FORMWORK	43,400	S.F.	.20	8,700	.80	34,700
CONCRETE	11,500	CY	-	-	7.00	81,000
REINF. STEEL	192	TONS	230-	44,200	100-	77,000
CURING	60,000	S.F.	.01	600	.02	1,200
KEYWAYS	6,000	L.F.	1.00	6,000	1.00	6,000
WATERSTOPS	4,000	L.F.	3.50	14,000	4.00	16,000
SPILLWAY						
SLIDING FORMS	288	L.F.	13-	3,800	20.50	6,000
FORM RAILS	2,520	L.F.	3-	7,600	3.00	7,600
JACK ROD ANCHORS	24	EA.	25-	600	50.00	1,200
JACK RODS (22T)	9,550	L.F.	2.50	24,000	.20	2,000
PLATFORM DECKS	288	L.F.	1.00	300	1.00	300
FORM DESIGN				5,000		-
SLIDE CREW				-		216,400
FIELD ENG'R	14	DAYS	200-	2,800		-
FIELD TECH	30	DAYS	150-	4,500		-
HYDRAULIC PIPING	300	L.F.		INCL.	1.00	300
CONCRETE	3,240	CY		-		-
REINF. STEEL	244	TONS	230-	56,000	135-	33,000
FINISHING	109,000	S.F.	.05	5,450		SLIDE CREW
CURING	109,000	S.F.	.01	1,100		SLIDE CREW
STRIP FORMS				-		6,000
PRECAST FORMS	109,000	S.F.	2.25	245,000	2.50	272,500
FILL @ TOP	570	CY	-	-	8.00	4,600
FINISHING TOP	10,800	S.F.	.05	500	.15	1,600
CURING TOP	10,800	S.F.	.01	100	.02	200
STARTER FOOTINGS	1,000	CY	50-	50,000	15-	15,000
SP 10196A			-42-	480,250		782,600

J. F. CAMELLERIE P.E. 23 GREEN STREET HUNTINGTON, N.Y. 11743	DATE JUL 15, '72 PRICED BY	SHEET NO. AD-2C-11
	MASSIVE HEAD BUTTRESS DAM	
	PROJECT: TRUMBULL LAKE	
ARCHITECT: NEW ENGLAND DIV. C/E		

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
<u>DRIVEWAY TOP OF DAM</u>						
PRECAST DECK	7,800	S.F.	2.50	19,500	2.50	19,500
CONCRETE FILL	8,000	S.F.	.25	2,000	.50	4,000
CURBING	800	L.F.	2.50	2,000	2.50	2,000
ADD'L CONC. @ FDN.	30	CY	30-	900	50-	1,500
PUMPING STATION	750	CY	30-	22,500	95-	71,250
RETAINING WALLS	350	CY	30-	10,500	45-	15,800
STAIR TOWER	60	CY	55-	3,300	125-	7,500
<u>EQUIPMENT</u>						
CRANE	1 x 12	MOS.	4500	54,000	1500 1200	32,400
DOZER	1 x 14	MOS.	1200	16,800	1330	18,600
UTILITY TRUCKS	2 x 14	MOS.	800	22,400	940	26,300
PERSONNEL TOWER	3 x 16	"	80	3,800	-	2,000
HEEDE HOIST	6 x 5	"	2000	60,000	1500	9,000
LOWER CONV. SYS.	30	WKS.	3000	90,000	-	5,000
SPILLWAY CONV. SYS.	16	WKS.	875	14,000	-	19,000
SLIPFORM CONV.	30	WKS.	875	26,200	-	48,000
CONV. SUPP. BKT.	30	EA.	200	6,000	300	9,000
SP 10196A		- 1/3 -		353,900		290,850

Use of the massive head design for a larger dam results in a cost saving of 3/4 million dollars and nearly two years of construction time (see Construction Schedules Sheets AD-EC-S2 and AD-2C-S7). The savings accrue almost entirely from reduction in cost escalation. Savings in finance cost, field inspection and accounting will be in addition to the 3/4 million dollars.

COST AND FEASIBILITY STUDY

AMBURSEN DAM

GENERAL DESCRIPTION


This type of dam takes advantage of the water pressure for stability. Such a dam was very successfully slip formed at West Chazy, N.Y. in 1967. This was a very small dam with 34 foot wide bays sloped at 43 degrees and a height of approximately 35 feet. The dam for Trumbull Lake is shown on drawings 209-AD-3 and Section F-F of drawing 209-AD-3A having 30 foot bays but much higher. Prestressed precast face sections 4'-0" deep by 3'-0" wide by 22'-0" long are shown on Section F-F. A concrete deck similar to section C-C may also be used.

DESIGN


Calculations for this dam using a 20 foot span are given on computation sheets AR-301 through AR-312. Although it was decided to increase the span to 30 feet between buttresses, it is felt that this change will not invalidate the stability calculations beyond the accuracy of the study. The precast sections were designed by C.W. Blakeslee and Sons who also submitted a preliminary quotation for furnishing the sections on a turnkey basis. The sections for the face are designed for a maximum of 8000 pounds per square foot at the base to 650 pounds per square foot at the top. The most heavily loaded sections are 48 inches deep with twelve $\frac{1}{2}$ " diameter strands per foot of width bottom steel, No. 11 @ 9" top bars and No. 4 @ 12 inch stirrups. Strands and rebars are decreased to suit pressure change. Lightening holes and depth changes are used to decrease concrete.

CONSTRUCTION METHODS

The buttresses may be constructed by either the slip form method as shown on sections B-B and D-D or by conventional forming. The face of the dam may be slip formed against fixed forms or precast leave-in-place forms as shown on Section C-C and E-E or constructed of precast sections as shown on Section F-F. The precast sections may be cast on the site or trucked in from a commercial precasting yard. A trestle provided upstream will furnish access and working areas for the trucks and cranes. The slip form systems are similar to those described for the massive head dams.




DOWNSTREAM ELEVATION



DOWNSTREAM ELEVATION (CONT'D)

PLAN



PLAN (CONT'D)



GRAPHIC SCALE

DESIGNED BY	REVIEWED BY
J.F. CAMELLERIE, PE	
Checked by	
Approved by	
DATE	1968
WATER RESOURCES DEVELOPMENT PROJECT	
TRUMBULL LAKE	
REGUONNOCK RIVER BASIN CONNECTICUT	
AMBURSEN DAM	
SCALE	AS SHOWN
209-AD-3	

CONSTRUCTION SCHEDULE

Construction time for this dam will approximate the schedule required for the massive head dam.

CONSTRUCTION COST

The cost for constructing the dam using this design alternate is approximately \$7,480,000 as shown on Cost Sheets AD-3S and AD-31 through AD-35. Cost Study Sheets AD-S301 through S311 are to be found in the appendix.

J. F. CAMELLERIE P.E.
 23 GREEN STREET
 HUNTINGTON, N.Y. 11743

DATE: 000 10, 74 PRICE BY
 AMBURSEM DAM

SHEET NO. AD-31

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGLAND DIV. C/E

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
<u>SITE WORK</u>						
CLEARING & GRUBBING	360,000	S.F.	.05	18,000	-	SUB
DISPOSAL	250,000	S.F.	.03	7,500	-	SUB
EXCAVATION (UNCLASS.)	360,000	C.Y.	2.00	72,000	-	SUB
" (ROCK)	3,000	C.Y.	10-	30,000	-	SUB
" (TALUS)	14,000	C.Y.	3-	42,000	-	SUB
HAND CLEANING	29,100	S.F.	.75	22,000	-	SUB
CHAIN LINK FENCE	850	L.F.	3.50	3,000	2-	1,700
FOUNDATION GROUTING	37,100	S.F.	.90	33,500	-	-
DIVERSION		L.S.		714,000	-	SUB
BACKFILL	12,000	CY	-	-	2-	24,000
ROCK SLOPE PROTECT.	800	CY	3.00	2,400	10-	8,000
ROAD GRAVEL	1,200	CY	4.50	5,400	2.50	3,000
BIT. CONC. PAVING	1,200	CY	5-	6,000	-	SUB
ALUMINUM HANDRAIL	1,000	L.F.	10-	10,000	3.00	3,000
TIMBER TRESTLE	480	L.F.	73-	35,000	37-	17,800
BRIDGE	1	EA.	-	1,000	-	5,000
IMPROVE R.R. BED	268,000	S.F.	1.50	402,000	-	SUB
VALLEY ACCESS ROAD	72,000	S.F.	1.00	72,000	-	SUB
<u>MECHANICAL ITEMS</u>						
HYDRAULIC PACKAGE	1	L.S.		303,700		-
EXTENSION 36" BLOW-OFF	1	L.S.		5,000		2,000
PLUMBLINE SHAFT	120	L.F.		400		300
<u>ENVIRONMENTAL WORK</u>						
TURBIDITY CONTROL				80,000	-	SUB
DUST CONTROL				1,000		-
NOISE ABATEMENT				40,000		-
LANDSCAPE RENEWAL				5,000		2,000
R.R. BED RENEWAL	270,000	S.F.	.20	54,000	-	SUB
SP 10196A				1,973,900		66,800

J. F. CAMELLERIE P.E. 23 GREEN STREET HUNTINGTON, N.Y. 11743	DATE: JUL 15, '72 PRICED BY	SHEET NO. AD-32
	AMBURSEN DAM	
	PROJECT: TRUMBULL LAKE DAM	
ARCHITECT: NEW ENGLAND DIV. C/E		

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
BUTTRESS SLIDE						
SLIDING FORMS	7,100	L.F.	6.65	47,300	10.50	74,600
YOKES	323	EA.	-	INCL.	75.00	24,200
JACK RODS (3T)	50,000	L.F.	1.65	82,500		2,500
DECKS	25,500	SF	.25	6,375	1.00	25,500
SCAFFOLDS	11,100	SF	.50	5,600	1.50	16,800
RAILINGS & LADDERS	6,600	L.F.	1.50	9,900	1.50	9,900
HYDRAULIC PIPING	11,600	L.F.	-	INCL.	.80	9,300
TOPPING OUT RODS	360	EA.	2.00	720	-	INCL.
FORM DESIGN	-	-	-	7,500	-	-
FIELD ENGINEER	20	DAYS	200-	4,000	-	-
FIELD TECH.	40	DAYS	150-	6,000	-	SUB
CONCRETE	40,370	CY	22.50	910,000	-	-
REINF STL	-	-	-	-	-	-
SLIDE CREW	-	-	-	-	-	296,000
FINISH	355,000	SF	.05	17,750	-	SLIDE CREW
CURING	355,000	SF	.01	3,550	-	SLIDE CREW
STRIP FORMS	-			-		37,000
REBAR PLACING & LIST'G	-	-	-	-	-	-
PRECAST SEAT	6,100	LF	4.00	24,400	5.00	30,500
END BULKHEAD FORMS	240	LF	3.60	900	10.50	2,500
YOKES	60	EA	180-	10,800	135-	8,100
JACK RODS 6T	6,200	LF	2.50	15,500	.13	800
PRECAST INSERTS	1,550	EA	9.00	13,950	-	SLIDE CREW
GUIDE WHEEL BRKTS.	18	EA	65-	1,200	-	" "
SP 10196A		- 57 -		1,157,945		537,700

J. F. CAMELLERIE P.E.
 23 GREEN STREET
 HUNTINGTON, N.Y. 11743

DATE JUL 15, '72 PRICED BY
 AMBURSEN DAM

SHEET NO. AD-34

PROJECT: TRUMBULL LAKE DAM
 ARCHITECT: NEW ENGLAND DIV. C/E

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
FIELD OVERHEAD						
FIELD OFFICES, SHOPS, & STORAGE				15,000		2,000
HARDWARE & TOOLS				20,000		-
FUEL & OIL				10,000		-
START-UP & LAYOUT				-		5,000
MIX DESIGNS				1,000		-
CONCRETE TESTING				15,000		SUB
TEMPORARY LIGHTING				6,000		20,000
SANITARY FACILITIES				4,000		SUB
CLEAN-UP				-		10,000
HEATING				10,000		-
PROJECT MANAGER	1 x 117	WKS		-	500	58,500
SUPERINTENDENT	1 x 60	"		-	400	24,000
PROJECT ENGR.	1 x 58	"		-	400	23,200
CLERKS	2 x 58	"		-	200	23,200
SURVEYORS	4 x 58	"		-	250	58,000
UTILITY MECH.	6 x 36	"		-	300	64,800
WATCHMEN	3 x 93	"		-	100	27,900
WINTER PROTECTION	NONE			-	-	-
COMMUNICATIONS				5,000		5,000
POWER DISTRIBUTION				10,000		10,000
SP 10195A			-34-	96,000		331,600

COST ANALYSIS

This design alternate comes out to be the least economical of all the systems studied, including the basic conventionally built gravity dam. In addition, its relative economy will not be improved materially as larger dams are considered. On the contrary, it has maximum possibilities in the construction of low dams in wide flat valley configurations. Under these conditions the use of ready-mix concrete, gang forms for the buttresses and cranes seems to be the most promising construction combination. The decks may be constructed either by slip forming or precast sections made watertight at the joints.

This type of dam also lends itself to complete precasting including the buttresses. Tilt-up construction is also promising in this area. If time is a major consideration, the Ambursen type dam may be the answer within height limitations.

COST AND FEASIBILITY STUDY

CELLULAR DAM

GENERAL DESCRIPTION

This design alternate is shown on Drawing No. 209-AD-4 and is probably the least orthodox of the group studied. It combines features from both the composite design and the massive head design, substituting a beehive structure for the massive head and the buttresses for the no-slump fill. Because the buttresses (stems) go up the full height and are not sloped, this design is quite prismatic and therefore lends itself completely to the most economical use of slip forming and concrete handling equipment.

The area under the slip formed cells is mass concrete of minimum dimensions while the abutments are constructed as monoliths in the conventional manner.


The stems have been allowed to run the full height in the spillway area, but this is not in any way necessary. Piers are however provided for running a roadway completely across the spillway area. Section A-A shows the two lane driveway which encloses the cellular area. The spillway slab is also shown here indicating a vertical drop for the spill water. If necessary, the areas between the buttresses may be filled with low cement mass concrete to produce a sloped fall but this will not be as economical. Spilling through or around the cellular area is of course also possible.

The power station, stair towers and such other structures as may be required may easily be integrated into the cellular enclosure. The precast galleries are carried on the cross walks as shown and the cells are filled with gravel for drained ballast.


The downstream end of the buttresses can be easily enclosed by means of a continuous wall and the entire dam roofed to yield a park and/or overlook area.

DESIGN


Preliminary design of this dam is accomplished on calculation sheets AR-401 through 411. An infinite combination of cell and wall configurations is possible. The configuration selected is reasonable but probably not optimum. This type of construction offers infinite choice as to variation in plan; walls may be of variable thickness, haunched, curved or irregular. Weight masses may be placed where statics indicate the best economy



DOWNSTREAM ELEVATION



PLAN



SECTION A-A



J. F. CANELLERIE, P.E. ENGINEER-IN-CHARGE		DEPARTMENT OF THE ARMY NEW ENGLAND DISTRICT CORPS OF ENGINEERS NEW YORK, NEW YORK	
PROJECT: WATER RESOURCES DEVELOPMENT PROJECT TRUMBULL LAKE		PEQUONNOK RIVER BASIN CONNECTICUT	
CELLULAR DAM		DAM	
209-AD-4		DRAFT	

to be. The requirement is, however, to maintain the plan dimensions the full height of the structure so as to maintain the extruded prism concept; departure from this will chip away from the economy.

CONSTRUCTION METHODS

The walls and cells are constructed monolithically in three sections as shown utilizing slip forms, cable guided hoists and conveyors as shown on Section A-A. The concrete is placed in buttress walls and in the longitudinal walls directly from side discharge conveyors; cross walls are served by means of concrete buggies. All the concrete in this part of the construction is structural concrete, allowing the slip operation to proceed of speeds of 24 feet per 24 hour day and more. The concrete demand remains constant improving the overall plant utilization.

The abutment monoliths are handled in the conventional manner as in the slip form construction for the basic gravity dam.

CONSTRUCTION SCHEDULE

The construction schedule for this dam is shown on Sheet AD-S413. On Sheet AD-S414 is shown an accelerated schedule which pushes somewhat deeply into winter weather to obtain substantial completion within one year.

CONSTRUCTION COST

Construction Summary Sheet AD-4S and Cost Sheets AD-41 through 46 indicate the cost for constructing this dam. See also Cost Study Sheets AD-S401 through AD-S412. The total cost of \$6,753,000 is the lowest cost obtained from any alternate studied in this report.

J. F. CAMELLERIE P.E.
 23 GREEN STREET
 HUNTINGTON, N.Y. 11743

DATE JULY 15/72 PRICED BY
 CELLULAR DAM

SHEET NO. AD-46

PROJECT: TRUMBULL LAKE DAM

ARCHITECT: NEW ENGLAND DIV.-CORPS/ENG'R.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
EQUIPMENT						
TRUCK CRANE	1 x 15	MOS.	4500	67,500	2700	40,500
DOZER	1 x 12	"	1200	14,400	1330	16,000
UTILITY TRUCKS	2 x 10	"	800	16,000	940	18,800
PERSONNEL TOWERS	3 x 8	"	80	1,900		2,000
HEEDE HOISTS	3 x 6	"	2000	36,000	1500	4,500
LOWER CONVEYOR SYS.	860	L.F.		50,000		5,000
UPPER CONVEYOR SYS.	3 x 920	L.F.		120,000		19,000
FIELD OVERHEAD						
FIELD OFF, SHOP, STORAGE	-	-	-	27,000	-	3,000
HARDWARE & TOOLS	-	-	-	45,000	-	-
FUEL & OIL	-	-	-	12,000	-	-
STARTUP & LAYOUT	-	-	-	-	-	5,000
MIX DESIGN	-	-	-	1,000	-	-
CONCRETE TEST.	-	-	-	25,000	-	SUB
TEMP. LIGHTING	-	-	-	3,000	-	10,000
SANITARY FAC.	-	-	-	5,400	-	SUB
CLEAN UP	-	-	-	-	-	20,000
HEATING	-	-	-	20,000	-	-
PROJECT MANAGER	1 x 104	WKS.	-	-	500	52,000
SUPERINTENDANT	1 x 65	"	-	-	400	26,000
PROJ. ENG'R.	1 x 65	"	-	-	400	26,000
CLERKS	2 x 65	"	-	-	200	26,000
SURVEYORS	4 x 65	"	-	-	250	65,000
UTILITY MECH.	6 x 42	"	-	-	300	75,600
WATCHMEN	3 x 104	"	-	-	100	31,200
WINTER PROTECTION	-	-	-	2,000	-	5,000
COMMUNICATIONS	-	-	-	5,000	-	5,000
POWER DISTRIBUTION	-	-	-	10,000	-	10,000
SP 10196A			-67-	461,200		439,600

J. F. CAMELLERIE P.E.
23 GREEN STREET
HUNTINGTON, N.Y. 11743

CELLULAR DAM
PROJECT: TRUMBULL LAKE DAM
ARCHITECT: NEW ENGLAND DIV.-CORPS/ENG'R.

	QUANTITY	UNIT	UNIT	MATERIAL	UNIT	LABOR
PERSONNEL OVERHEAD						
NORMAL SCHEDULE						
PROJECT MANAGER	1 x 104	WKS.			500	52,000
SUPERINTENDENT	1 x 65	"			400	26,000
PROJECT ENGINEER	1 x 65	"			400	26,000
CLERKS	2 x 65	"			200	26,000
SURVEYORS	4 x 65	"			250	65,000
UTILITY MECHANICS	6 x 42	"			300	75,600
WATCHMEN	3 x 104	"			100	31,200
						301,800
ACCELERATED SCHEDULE						
PROJECT MANAGER	1 x 80	WKS.			500	40,000
SUPERINTENDENT	1 x 40	"			400	16,000
PROJECT ENGINEER	1 x 40	"			400	16,000
CLERKS	2 x 40	"			200	16,000
SURVEYORS	4 x 35	"			250	35,000
UTILITY MECHANICS	6 x 26	"			300	46,800
WATCHMEN	3 x 65	"			100	19,500
						189,300
DIFFERENCE - NORM. & ACC. SCHED.						
						112,500
ESCALATION THRU 1974						
					11%	12,375
						124,875
PAYROLL, TAXES & INS.						
					14%	17,463
						142,358
OVERHEAD, PROFIT & CONT.						
					8%	11,389
						153,747
BID BOND						
					3/4%	1,154
TOTAL DIFF. - NORM. & ACC. SCHED.						
						154,901

COST ANALYSIS

The cost for constructing the cellular type dam seems to be the most economical of all method/design alternatives studied. In addition, its economy will increase as the size of the dam increases in much the same manner as the massive head dam. Because of the vertical stems, the equipment and form utilization for this construction will show more economy than the massive head dam with increase in size.

COMMENTS AND CONCLUSIONS

The preceding studies give strong indication that alternate dam designs using slip forming and other advanced construction techniques will result in more rapid and therefore more economical construction. Maximum promise lies in the area of dams designed to use smaller volumes of structural strength concrete assisted in some instances by rock anchors and pre-stressing techniques. The economic advantage of such dams lies in the smaller plants required; more uniform plant utilization, decreased rock preparation, less formwork, less joints and most important of all, rapid construction.

Spillways, pumping stations and other accessory structures must be designed in the same vein.

The massive head buttress dam and the cellular dam are both designed in accordance with the above precepts and both result in halving the construction time and reducing the cost by 5 to 10 percent for large dams (twice the height of the dam at Trumbull Lake). The cellular dam is the more economical of the two designs as it permits more uniform plant utilization, more formwork reuse and less joints.

The design concepts illustrated and costed in the study of the massive head and cellular dam designs apply directly to arch dam design, particularly in valley cross-sections that are deep and rectangular in configuration. Slip forming gives great latitude to the designer whether single or multiple arch designs are considered. In lieu of the vertical curves and beautiful (but expensive) profiles now being designed, cellular vertical sections are suggested having some width and vertical outside faces. These cells may be filled with concrete, gravel or nothing at all as desired to meet design requirements for weight distribution. Aesthetic values and utility of the top deck can be incorporated into the design.

Smaller construction plants and shorter construction schedules will reduce the environmental impact of dams so constructed.

Considering the preceding investigations and discussions, cost and feasibility studies to determine the applicability of advanced construction techniques to dams yet to be designed seems entirely justified and may very well yield savings in time and money far in excess of the cost of such studies.

COST AND FEASIBILITY STUDY
ALTERNATE DESIGNS TO PERMIT USE
OF SLIP FORM AND OTHER TECHNIQUES
TO MAXIMIZE ECONOMIES

BOOK AC1

APPENDIX: COMPOSITE DAM

COST STUDY SHEETS

BOOK AC-1 - APPENDIX: COMPOSITE DAM


Sketches AD-S101 through S129

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15 1964 REV. SKETCH AD-310
TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CONN.
COMPOSITE DESIGN - GRAVITY DAM

SLIDING FORMS



DOWNSTREAM FACE 3(160) = 480'

UPSTREAM " 3(160) = 480'

CELLULAR CORES 2x12.5' = 25'

2x14 = 28

53' x 32 = 1700'

END BULKHEADS (1ST POUR) 19

5
24'

24'

END BULKHEADS (2ND POUR)

5'

" " (3RD POUR)

19'

2708 L.F. / 2 = 1354 LF.

YOKES
(3T)

6/CELL x 32 CELLS =

192

+ 2 STARTING, END

194

+ 6 HOIST + EQUIP.

200

JACK ROD (3T)

2 RODS x 116.5 =

234'

6 RODS x 116.5' = 700' x 21 CELLS

14,600'

UP 21 x 94 =

1980

DN 21 x 94 =

1980

CROSS 22 x 94 =


2070

20,864

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
 PEQUONNOK RIVER BASIN, CONN.
 COMPOSITE DESIGN - GRAVITY DAM

DECKS (INT.)



$$14 \times 12.5 = 175 \text{ ft}^2 / \text{CELL}$$

$$\times 32 \text{ CELLS}$$

$$\underline{5600 \text{ ft}^3}$$

DECKS (EXT.)

$$480'$$

$$\times 2 \text{ SIDES}$$

$$\underline{960' \times 2 = 1920 \text{ ft}^3}$$

CONCRETE: SLIP #1

160 x 2.5 =	400
160 x 2.5 =	400
11 x 14' x 2.5 =	386
	<u>1186 ft³ x 116.5' = 138,000 cuft</u>

$$138,000 / 27 = \frac{5150 \text{ c.y.}}{116.5} = 44 \text{ c.y. / HR.}$$

SLIP #2

up 80 x 2.5 x 116.5 =	23,400
80 x 2.5 x 102 =	20,400
DN 80 x 2.5 x 116.5 =	23,400
80 x 2.5 x 80 =	16,000
CROSS 11 x 14 x 2.5 x 116.5 =	45,200
	<u>128,400 / 27 = 4750 c.y.</u>

SLIP #3

up 160 x 2.5 x 80 =	32,000
DN 160 x 2.5 x 68 =	27,200
CROSS 11 x 14 x 2.5 x 94 =	36,000
	<u>95,200 / 27 = 3530 c.y.</u>

TOTAL

5150
4750
3530
<u>13,430 c.y.</u>

MAX. 44 yd / HR. = 9 BUGGIES \approx SAY 10

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15, '72 REV. SKETCH # AD-1103
 TRUMBULL LAKE DAM
 PEQUONNOK RIVER BASIN, CONN.
 COMPOSITE DESIGN - SLIDE CREW

SPEED = 12"/HR AVE. SLIP #1 $116 \frac{6}{1}$ = 116.5 HRS
 SLIP #2 $116 \frac{6}{1}$ = 116.5
 SLIP #3 $94 \frac{1}{1}$ = 94

WORK 3 SHIFTS/DAY = 24 x 5 = 120 HR/WK.

SLIP #1 — WEEK 1, 5 DAYS

SLIP #2 — WEEK 2, 5 DAYS

SLIP #3 24 x 4 = 96 HRS OR 4 DAYS

14 DAYS x 3 SHIFTS/DAY = 42 SHIFTS

CLASSIFICATION	#	HR. RATE INCL. FRINGE BENEFITS	COST/SHIFT.		
			WEEKDAY 8 HR. WORK	SHIFT RATE / 9 HR. PAY	
HOIST ENGR	1	8.60	#	77	
JACK OPER.	2	8.00		144	
CARPENTERS	2	9.00		162	
ELECTRICIAN	$\frac{2}{3}$	8.28		50	
FINISH FOR.	1	9.37		84	
FINISHERS	1	8.87		80	
FINISH HELPER	1	7.15		64	
LABORERS:					
FOREMAN	1	6.10		55	* PLACING HAS 1 TOP MAN, 10 BUGGIES, 10 SHOVEL, 1 UTILITY MAN
PLACING *	22	5.60	}	1460	
VIBRATING	5	5.60			
CURING	2	5.60			
CRAVE OPER.	$\frac{2}{3}$	8.60		52	
OILER	$\frac{2}{3}$	6.85		41	
CONV. OPER	1	7.75		70	

2339

42 SHIFTS x \$ 2339 = \$ 98,200

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 19, 1972 REV. SKETCH# AD-3102
 TRUMBULL LAKE DAM
 PEQUONNOK RIVER BASIN, CONN.
 COMPOSITE DESIGN - CAVITY DAM

<u>FINISH</u>	SLIP #1	116.5 x 160 x 2 =	37,500
	SLIP #2	116.5 x 80 x 2 =	18,800
		102 x 80 x 1 =	8,200
		90 x 80 x 1 =	7,200
	SLIP #3	102 x 160 x 1 =	16,300
		90 x 160 x 1 =	14,400
			102,400 $\phi' / 2 = 51,000$

CURING

<u>CROSS</u>	2 x 14 = 28 x 116.5 x 43 WALLS =	141,000
	28 x 94 x 21 WALLS =	55,000

<u>EXT.</u>		102,000 ← REQ'D
<u>INT.</u>	2 x 12.5 = 25 x 2 = 50 x 116.5 x 16 CELLS =	93,000
	50 x 94 x 16 =	75,000
		NOT REQ'D
		<u>466,000 ϕ'</u>

RAILINGS + LADDERS

480'
 480'
 960 ≈ SAY 1000

STRIP FORMS

50% ERECTION x FORMS 65,000
 YOKES 10,000
 DELKS < 5600
 1920
 RAILS 2,500
 55,000 x 1/2 = 42,500

REINF. ST'L

77 #/40 x 13,430 c.y. = 1,040,000 $\frac{1}{2000}$ = 520 TONS

GALLERY BULKHEADS

33 CROSS WALLS

7 + 10 + 10 = 27 LF x 2.5' = 67.5 ϕ' / WALL x 33 WALLS = 2240 ϕ' = 9036
 2.5

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUL 15 1964
TRUMBULL LAKE DAM
PEQUONNOK, RIVER BASIN, CONN.
COMPOSITE DESIGN GRAVITY DAM

CRANE SUPPORT


WHEEL LOADING = 123K'
 $M = \frac{1}{8}(123K')(12.5)^2 = 2,400'K$

$S_{req} = \frac{2,400 \times 12}{24 \times 1.33} = 900$

USE WF 36 x 260#

TOTAL WEIGHT =
 $\frac{2 \times 260 \times 24.0' \times 1.05}{2000} = 65 \text{ TONS}$

BEAM BLOCKOUTS

17 EA.  7.5 LF/BOX

LUMBER PER BOX = 7.5 x 2.5 x 17 x 260 lb/ft
= 640 lb/ft
320 # @ (2 x 17)
SAY 35¢

MAKE UP 35¢
PLACE \$9.00 / 18.75 # = .50

TOTAL PLACING COST 85¢

WELD PLATES FOR CRANE

ANCHOR BOLTS
2 x 5.3# x 4' = 42#

PL 1.33 x 1.33 x 61# x 2 = 216#

SAY 250# EA @ 15'
@ .25 = 65 EA. MTL.
@ 4 x # 9 = #36 EA. MTL.

AT 30" SPACING (OVER WALL)


ANCHOR BOLTS	\$3.00	\$21.00
PLATE @ 1.33 (40)	\$13.30	
	13.30	\$21.00

NO REQ'D = $\frac{240 \times 2}{2} = 192$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 13, 1957. ORIGINAL SIZE
 TRUMBULL LAKE DAM
 PESQUONNOCK RIVER BASIN, CONN.
 COMPOSITE DESIGN-GRAVITY DAM

CONVEYOR SUPPORT TRUSS
 LOADING. EACH OF DOUBLE TRUSSES



$$\downarrow \frac{75' \times 50''}{2} = 1900 \#$$

$$M = 100 \times 60 \times 30 + 1,900 \times 60$$

$$= 180 + 114 = 294 \text{ K} \text{ SAY } 300 \text{ K}$$

BOT CHORD:

$$B = \frac{300 \text{ K}}{16'} = 18.75 \text{ K}$$

$$T = 18.75 \times \frac{62}{60} = 19.6 \text{ K}$$

$$\text{MIN } R = \frac{720}{200} = 3.6$$

BOT CHORD

2 L 8 x 4 x 7/16 (35 #/ft)

$$\text{Top Chord} = \frac{744}{240} = 3.1$$

TOP CHORD

2 L 5 7/8 x 4 x 3/8

(27 #/ft)

DIAGONALS:

$$V = 6 + 19 = 7.9 \text{ K} \text{ SAY } 8 \text{ K}$$

$$\text{LOAD} = 8 \times 1.5 = 12 \text{ K}$$

$$\text{MIN } Y = \frac{300}{300} = 1.0$$

USE 8 x 6 x 7/16 L

TOTAL WEIGHT OF TRUSS:

$$92 \# \times 1.10 \times 60' = 6000 = 3 \text{ TONS}$$

$$3 \text{ TONS} \times 10 = 30 \text{ TONS}$$

(20 #/ft) x 1.5

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15, '72 REV.


SKETCH # AD-510

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONNS.

COMPOSITE DESIGN - GRAVITY DAM

CONV. SUPPORT TRUSS CONT



TRY W6 x 25

$$M = \frac{pl}{8} = \frac{20 \times l}{8} = 2.5l$$

$$M = S_s = \frac{13.4 \times 24}{12} = 26.8$$

$$2.5l = 26.8$$

$$l = 10.75'$$

SAY 10'-0"

CONVEYOR RAIL

$$20^{\#} \times 7 \times 116 = 16,200^{\#}$$

$$20^{\#} \times 3 \times 94 = \frac{5,700^{\#}}{}$$

$$22,000^{\#} = 11 \text{ TONS}$$

WELD RES

$$10 \times 12 \times \frac{1}{2}'' = 15^{\#}$$

$$\text{Ancors } 1.5^{\#} \times 12' = \frac{18^{\#}}{}$$

$$33^{\#}$$

NO OF RES = 1100

$$\text{TOTAL WEIGHT} = 33^{\#} \times 1100 = 36,000^{\#}$$

18 TONS

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11 1972 REV.

SKETCH # AD

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, COI

SLIP FORM CONSTRUCTION

CONCRETE DEMAND SCHEDULE

MONTH -

WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE ^{Yds} / _{HR}	REMARKS
1	1	115	15	
2	2	530	67	
3	3	830	104	
4	3	830	104	
5	4	570	72	
6	4	565	72	
7	5	960	120	
8	6	545	69	
9	6	545	69	
10	7	935	117	
11	7	935	117	
12	8	930	117	
13	8	930	117	
14	9	840	105	
15	9	840	105	
16	10	590	74	
17	10	585	74	
18	11	855	107	
19	11	855	107	
20	12	830	104	
21	12	830	104	
22	13	900	113	

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11 1972 REV.

SKETCH # A

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, C.

SLIP FORM CONSTRUCTION

CONCRETE DEMAND SCHEDULE

MONTH-

5 DAYS
SLIDE,
DAY 29
TO 33

WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE ^{Yds} / _{HR}	REMARKS
23	14	715	90	
24	14	715	90	
25	15	875	110	
26	15	875	110	
27	16	825	104	
28	16	825	104	
IN SLIDE	17	560	70	
↑	17	560	70	
	18	745	94	
	18	740	93	
	19	750	94	
	19	750	94	
	20	775	97	
	20	775	97	
	21	680	85	
	21	680	85	
	22	665	84	
	22	665	84	
	23	640	80	
↓	23	640	80	
IN SLIDE	24	620	78	
IN SLIDE	24	620	78	

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11 1972 REV.

SKETCH # AD-5110

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONN.

SLIP FORM CONSTRUCTION

CONCRETE DEMAND SCHEDULE				
MONTH -				
WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (YD)	PLACING RATE $\frac{YD}{HR}$	REMARKS
IN SLIDE	25	607	76	
IN SLIDE	26	935	117	
34	27	544	68	START FILLING CAVITIES
35	28	316	40	WHERE CONCRETE CAPACITY AND TIME IS AVAILABLE
36	29	194	25	
37	30	510	64	
38	30	510	64	
IN SLIDE	31	609	77	
IN SLIDE	31	608	76	
IN SLIDE	32	519	65	
IN SLIDE	32	513	65	
IN SLIDE	33	765	96	
IN SLIDE	33	760	95	
39	34	225	29	
39 $\frac{1}{3}$ SEE DEMAND	35	560	70	$\frac{1}{3}$ DAY ALLOWED FOR PART NOT IN SLIP
IN SLIDE	35	560	70	
IN SLIDE	36	690	87	
IN SLIDE	36	690	87	
40 $\frac{1}{3}$	37	312	39	
41 $\frac{1}{3}$	38	424	53	
42 $\frac{1}{3}$	39	350	44	

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11, 1912 REV.

SKETCH # AD-SIII

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONN.

SLIP FORM CONSTRUCTION

CONCRETE DEMAND SCHEDULE

MONTH -

WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (YD)	PLACING RATE $\frac{YD}{HR}$	REMARKS
42 $\frac{2}{3}$	40	557	70	$\frac{1}{3}$ DAY ALLOW
IN SLIDE	40	557	70	FOR PART NOT IN SLIDE
43 $\frac{2}{3}$	41	491	62	
44 $\frac{2}{3}$	42	612	77	
45 $\frac{2}{3}$	43	670	84	ONLY PARTIALLY
IN SLIDE	43	670	84	IN SLIDE
55	44	516	65	$\frac{1}{3}$ DAY ALLOW
IN SLIDE	44	516	65	FOR PART NOT IN SLIDE
56	45	900	113	
57	46	63	8	
58	47	225	29	
59	48	535	74	
60	49	335	49	
61	50	900	113	
IN SLIDE	51	718	90	
62	52	610	77	
63	53	794	100	
64	54	617	78	
IN SLIDE	55	615	77	
65	56	610	77	
66	57	139	24	SPILLWAY
67	58	691	87	

9. DAYS

SLIDE
DAY 46
THRU 54

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11 1972 REV.

SKETCH # AD-511

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CONN

SLIP FORM CONSTRUCTION

CONCRETE DEMAND SCHEDULE				
MONTH -				
WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (YDS)	PLACING RATE ^{YDS} / _{HR}	REMARKS
68	59	764	96	
IN SLIDE	60	512	64	
69	61	189	24	
70	62	189	24	SPILLWAY
71	63	615	77	
72	64	768	96	
IN SLIDE	65	406	51	
IN SLIDE	66	186	24	
IN SLIDE	67	186	24	
73	68	512	64	
74	69	784	98	
IN SLIDE	70	302	38	
IN SLIDE	71	186	24	
IN SLIDE	72	186	24	
75	73	406	51	
76	74	667	84	
IN SLIDE	75	189	24	
77	76	189	24	SPILLWAY
78	77	302	38	
79	78	481	61	
IN SLIDE	79	296	37	
IN SLIDE	80	296	37	

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUNE 11 1972 REV.

SKETCH #A

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, C

SLIP FORM CONSTRUCTION


CONCRETE DEMAND SCHEDULE

MONTH -

WORKING DAY	PLACEMENT DESIGNATION	CONCRETE DEMAND (Yds)	PLACING RATE Yds ³ /HR.	REMARKS
IN SLIDE	81	296	37	
80	82	186	24	
81	83	186	24	
IN SLIDE	84	296	37	
ROAD 82	85	38	5	
ROAD 83	86	38	5	
84	87	296	37	
85	88	296	37	
86	89	247	31	
ROAD 87	90	38	5	
ROAD 88	91	31	4	
ROAD 89	92	38	5	
ROAD 90	93	38	5	
ROAD 91	94	38	5	
91 DAYS FOR	CONV. + SLIPFORM			
75 DAYS FOR	PRECAST + FILL			
166	TOTAL			

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15/72 REV. SKETCH# AD-5114-
 TRUMBULL LAKE DAM
 TROUGHBROOK RIVER BASIN, CONN.
 COMPOSITE DESIGN - GRAVITY DAM.



VOLUME SUMMARY

	SEC. I	SEC. II	SEC. III	TOTAL CY
1) SLIP WALLS	5,100	4,870	3,640	13,610
2) CORE FILL	8,000	7,530	5,480	21,010
3) LOW SLUMP	2,770	2,770	2,020	7,560
4) PRECAST	2,400	2,400	1,700	6,500
5) NO SLUMP	18,330	18,330	6,380	43,040
				<u>91,720 CY</u>

TOTAL CONC. IN DAM = 127,000 C.Y.
 - 91,720

 35,280 C.Y. CONVENTIONAL

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15 '72 REV.

SKETCH# AD-5115

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONN.

COMPOSITE DESIGN - GRAVITY DAM

TYPE OF CONCRETE	C. Y.	CEMENT	FLYASH	REMARKS
SLIP FORMED	13,610	$x 470 = 6,400,000$ $= 6.4 \times 10^6$	—	
CELL FILL (NO SLUMP)	21,010	$x 94 = 1,980,000$ $= 1.98 \times 10^6$	$x 130 = 2,740,000$ $= 2.74 \times 10^6$	
LOW SLUMP (EXT. MASS)	7,560	$x 183 = 1,380,000$ $= 1.38 \times 10^6$	$x 78 = 590,000$ $= .59 \times 10^6$	
PRECAST BLOCKS	6,500	$x 470 = 3,060,000$ $= 3.06 \times 10^6$	—	
NO SLUMP CONCRETE	43,040	$x 94 = 4,050,000$ $= 4.05 \times 10^6$	$x 130 = 5,600,000$ $= 5.6 \times 10^6$	
EXT. MASS CONC. (CONV. FORM)	35,280	$x 183 = 6,450,000$ $= 6.45 \times 10^6$	$x 78 = 2,750,000$ $= 2.75 \times 10^6$	
TOTALS		$23.32 \times 10^6 \#$	$11.68 \times 10^6 \#$	

$$23,320,000 / 2000 = 11,660 \text{ TONS OF CEMENT}$$

$$11,680,000 / 2000 = 5,840 \text{ TONS OF FLYASH}$$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15/72 REV.


SKETCH# AD-S116

TRUMBULL LAKE DAM

REGUONNOCK RIVER BASIN, COA

COMPOSITE DESIGN - GRAVITY DAM

B) TRIANGULAR GRAVITY SECTION



1/ $V_{1,2} = \frac{68 \times 90.5}{2} \times 160 = 492,000$ CF

$V_3 = \frac{48.5 \times 68}{2} \times 160 = 264,000$ CF

2) PRECAST CONC. FACE

$V_{P,1,2} = 101 \times 160 \times 4 = 64,700$ CF

$V_{P,3} = 72 \times 160 \times 4 = 46,100$ CF

3) LOW SLUMP CONCRETE

a) INT. FACE.

$V_{IN,1,2} = 85 \times 2.5 \times 160 = 34,000$ CF

$V_{IN,3} = 62 \times 2.5 \times 160 = 24,800$ CF

b) EXT. FACE

$V_{EX,1,2} = 102 \times 2.5 \times 160 = 40,800$ CF

$V_{EX,3} = 74 \times 2.5 \times 160 = 29,600$ CF

34,000
 40,800
 74,800 CF = 2,770 CY

24,800
 29,600
 54,400 CF = 2,020 CY

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH # AD-S117

TRUMBULL LAKE DAM

REGULATED FLOW BASIN

COMPOSITE DESIGN-GRAVITY DAM

A/ CONCRETE VOLUMES

1) SLIP FORM SECTION

SECTION # 1 (NO SPILLWAY)

NO	L	W	H	VOL. CF	FILL CF	TOT. VOL.
1	160	19	116,5	354,000		
10	12,5	14	116,5		204,000	} FILL
1	7,5	14	116,5		12,230	
				WALL VOL. = 354,000 - 216,230	= 137,770 CF	say <u>137,800 CF</u>

SECTION # 2 (77,5 FT SPILLWAY)

WALL VOL. $(77,5 - 5 \times 2,5) \times (15 + 26) \times 2,5 = 137,800 \text{ CF}$
 $= - 6,660 \text{ "}$
131,140 CF

FILL $216,200 - 65 \times \left(12 \times 14 + \frac{9 \times 7}{2}\right) = \underline{\underline{203,200 \text{ CF}}}$

SECTION # 3 (160 FT SPILLWAY)

WALL VOL. $160 \times (79 + 68) \times 2,5 = 59,000 \text{ CF}$
 $11 \times 14 \times 94 \times 2,5 = 36,100 \text{ "}$
95,100 CF

FILL $132,5 \times (94 \times 14 - 200) = \underline{\underline{148,000 \text{ CF}}}$


J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUNE 1/72 REV.

SKETCH # AD-5118

TRUMBULL LAKE DAM

REGUENNOCK RIVER BASIN, CONN.



$$14 \times 12,5 = 175 \text{ SF}$$

A 1 FT LAYER REQ. 6,5 CY OF CONC.

RATE OF PLACEMENT: 160 CY/HR / 6.5 = 25 FT/HR

MAX. LATERAL PRESSURE OF 3000 P.S.F.
 GOVERNS.

$$\text{MAX. NEG. M} = \frac{p \times l^2}{12} = \frac{3 \times 13,25^2}{12} = \underline{43,8'K}$$

$$-A_s = \frac{43,8}{1,76 \times 26,5} = 0,94 \text{ D}''$$

say #7 @ 8" (3")

$$+A_s = 0,47 \text{ D}''$$

say #7 @ 16 (1,6")

TEMP. STEEL

$$0,0015 \times 30'' \times 12'' = 0,54 \text{ D}''$$

say #5 @ 15" E.F.

(2 x 0,9")

RE: TOTAL WEIGHT PER LIN. FT

EXT. WALLS

$$3'' + 1,6'' + 1,8'' = 6,4''$$

$$\frac{27}{25} = 10,8 \times 6,4 = \underline{69''/CY}$$

CROSS WALLS

$$10,8 \times 7,8 = \underline{84''/CY}$$

$$\underline{\underline{AVERAGE = 76''/CY}}$$

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15 1972 REV.
TRUMFULL LAKE DAM
PEQUONNOK RIVER BASIN, CONN.
COMPOSITE DESIGN - LIBERTY DAM

CONC. PLACING (CONV.)

CONV. OPERATORS 3 @ 7.75 = 23.25
CREW 3 MEN @ 5.60 > = 22.90
1 FORMAN @ 6.10 > = 46.15

COST/DAY = \$46.15 x 8 = \$370/DAY

\$370/DAY x 77 DAYS = \$28,600

COST / C.Y. = \$28,600 / 35,280 C.Y. = .81 \$/YD.

CONC. PLACING (FILL INT. MASS & CELLS)

3 CONV. OPER @ 7.75 = 23.25
1 HOIST OPER @ 8.60 = 8.60
CREW 3 MEN > = 22.90
1 FORMAN > = 54.75

COST/DAY \$54.75 x 8 = \$440/DAY

\$440/DAY x 75 DAYS = \$33,000

COST / C.Y. = \$33,000 / 71,600 C.Y. = .46 \$/CY.

VIBRATION

PLACING INT. MASS CONC.
FILL. & FILL CELLS.

1 HAND VIB. = 5.60
1 COMPACTOR OPER = 7.80
1 COMPRESSOR " = 7.40
20.80
x 8
\$167/DAY

EQUIP (NOT INCL. COMPACTOR) = 200/DAY

167 x 75 = 12,500 / 71,600 = .18 \$/YD.

200 x 75 = 15,000 / 71,600 = .21 \$/YD.

PLACING CONV. CONC. ON SIDES
AND FOR PHASE I @ BOTTOM.

4 MEN @ \$5.60 = 22.40
COMPRESSOR OPER. 7.40
\$29.80 x 8 = \$239/DAY

EQUIP. --- --- --- \$200/DAY

\$239/DAY x 77 DAYS = \$18,400 = .52 \$/YD.
35,280 YD

\$200/DAY x 77 = 15,400 / 35,280 = .44 \$/YD.

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CONN.
COMPOSITE DESIGN - GRAVITY DAM

FINISHING

TOTAL AREA = 146,000 ϕ'
 SLIP AREA
 $116.5 \times 160 \times 2 \times 2.25 = 84,000$
 $94 \times 160 \times 1 \times 2.25 = 34,000$
118,000

146,000
 - 118,000
28,000 ϕ'

CURING:

308,000 ϕ'
 - 29,000
279,000 ϕ'

12 x 40 x 60' = 29,000 ϕ'
 ↑ LAYERS ↑ AVE. WIDTH

HORIZONTAL JT. TREATMENT

TOTAL = 425,650 ϕ'

ELIMINATED BY SLIPFORM = 190,000 ϕ' (ER-57)

ADD'L ELIMINATION
 $83.75 \times 12 = 1000$ → 1000.00
 77.50
 71.25
 65.00
 58.75
 52.50
 46.25
 40.00
 33.75
 27.50
 21.25

1493.55 x 60 = 89,600

425,650
 - 279,600
146,050 ϕ' REMAINING

190,000
279,600

JAY POST

31 JACKRODS x 15' = 465 LF
 31 " x 26' = 810
1275 LF

SPILLWAY FIXED BULKHEADS 16 CROSS WALLS

16 WALLS x 2 x 2.5' x 15' = 1200 ϕ'

16 " x 2 x 2.5 x 26' = 2080

TOT'L = 3280 ϕ'

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE July 15, '72 REV. SKETCH# AD-5121
 TRUMBULL LAKE DAM
 PEQUONNOCK RIVER BASIN, CONN.
 COMPOSITE DESIGN - GRAVITY DAM

CONVEYOR SYSTEM

	LF.
BATCH PLANT TO TRESTLE =	50
MAIN DISTRIBUTION CONV. ON TRESTLE =	430
3 DISTRIBUTION CONV. ⊥ TO TRESTLE (3x50) =	150
1 CONV. (MAT'L TOWER TO CELL FILLER CONV.) =	15
CELL FILLER DISTRIBUTION CONV. =	465
3 CONV. (CELL FILLER CONV. TO ELEPHANT TRUNKS (3x10) =	30
2 CONV. (DIST. CONV. ON DBL. TRUSS) (2x60) = (1 RE-USE)	120
2 CONV. (SPREADERS) (2x80) = (2 RE-USE)	160
1 CONV. (SPREADERS) (1x90) = (1 RE-USE)	90
	<u>1510</u>

ADD'L CONVEYORS:

ABUTMENT CONV.	200
PLACING CONV. (FOR CONVENTIONAL)	150
RADIAL CONV.	30
	<u>380</u>

TOTAL 1510

$$\frac{380}{1890} \text{ LF} \times \# 150/\text{LF} = \# 284,000$$

RAIL + ACCESS @ 10% 29,000

SIDE DISCHARGE 7,000

320,000

SAY - 160,000 SALVAGE

160,000

160,000 BASED ON 24" CONV.

WE'LL USE 16" CONV. ∴ 67% x 160,000
 = \$107,000 FOR 166 DAYS

107,000 / 166 DAYS = \$650/DAY

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15, '77. REV.

SKETCH# AD-5122

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN COND.

COMPOSITE DESIGN - GRAVITY DAM

CONV. SYSTEM CONT:

INITIAL ERECTION

5 MEN @ 8.00 = \$40/HR = \$1600/WK

X 5 WKS = 8000 ERECT

X 3 WKS = 4800 DISMANTLE

\$ 12,800 TOTAL

COST/YD = $\frac{12,800}{127,000} = .10\text{\$/YD.}$


J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15/78 REV.

SKETCH# 102-512

TRUMBULL LIME DAM
PEQUONNOK RIVER BASIN, C. VAL.
COMPOSITE DESIGN - PRECAST TILES

PRECAST BLOCKS



MISC.

1/ CONG. VOL. FOR ONE UNIT.

$$5 \times 2.5 \times 10 = 125 \text{ CF} = 4.7 \text{ CY}$$

$$\text{WEIGHT} = 12750 \text{ lb} \approx 9.5 \text{ TONS}$$

1548 UNITS

SEC. THRU PRECAST UNIT

$$L = 10 \text{ FT}$$

ASSUME DAILY PRODUCTION OF 21 EA.

STORAGE \approx 7 DAY SUPPLY

2) FORMS 21 EA. REQ

CONTACT AREA

$$5 \times 10 + 7 \times 10 + 2 \times 10 = 140 \text{ SF}$$

3) INSERTS

4 EA. PER UNIT (USE PRESTRESSING STRANDS)

$$1,548 \times 4 = 6,192 \text{ SAY } 6,200 \text{ EA. @ } 1.50 \text{ EA.}$$

$$6,200 \times 1.5 = 9,300.00$$

4) REINF. - NONE

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH # AD-5124


TRUMBULL LAKE DAM

REGUONNOCK RIVER BASIN CON. CO.

COMPOSITE DESIGN - PRECAST PILES

CRANE CYCLE & SETTING TIME

- 1/ PICKUP POINT UPSTREAM EL. 170' ±
- 2/ LANDING POINT DOWNSTREAM - LOW POINT 162' ±
 HIGH PT. 250' ±



CENTER OF UNLOADING
 AREA ~ 110 FT FROM
 PICKUP HORIZONTALLY.
VERT. TRAVEL TO CTR.
OF UNLOADING AREA ~ 230 FT

1/ HOOK PRECAST SEC.	120	SEC.	
2/ ACCELERATE & RAISE	60	"	
3/ SWING	60	"	
4/ LOWER & DECELERATE	60	"	
5/ SPOT & PLACE SEC.	360	"	
UNHOOK	60	"	720 SEC
6/ RAISE, SWING &	90	"	90 "
LOWER HOOK			810 SEC/CYCLE
			= 13.5 MIN/CYCLE

ASSUME 7 1/2 PRODUCTION HR'S PER 8 HR DAY

SAY 14 MIN/CYCLE.

$$\frac{7.5 \times 60}{14} = \underline{\underline{32 \text{ SECTIONS/DAY}}}$$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15/72 REV. SKETCH# AD-5125
TRUMBULL LAKE DAM
DEQUANNOCK RIVER BASIN, CONNY
COMPOSITE DESIGN-PRECAST PILES

PRODUCTION SCHEDULE & STORAGE

DAY	Nº PRODUCED	Nº SET			
1	21	0	POUR 21/DAY	1 ST PHASE	
7	147 = STOCK	0			
8	168	16	POUR 21/DAY	1 ST PHASE	
25	525	288			SET 16/DAY
32	672	516			SET 32/DAY
	- 516				
	156 = STOCK				
33	693	532	POUR 21/DAY	2 ND PHASE 3 RD SIM.	
50	1050	804			SET 16/DAY
57	1197	1028			SET 32/DAY
	- 1028				
	169 = STOCK				
74	1548 EA				

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15 / 77 REV.

SKETCH# AD-5120

TRUMBULL LAKE DAM

TRUMBULL LAKE DAM

COMPOSITE DESIGN - PRECAST FACE

PRECAST OPERATION FOR 1548 BLOCKS

A/ FORMS, 21 REQ.

$21 \times 140^{SF} = 2940 SF \times 6.50 = \underline{19,100}$

PRICE/SF DEL. 6⁵⁰


CASTING BEDS

GRAVEL BASE

$130 \times 50 \times 1' = 6500^{SF} CF$

COMPACTED 6500^{CF}

@ 1⁰⁰/SF



EXCAVATION & GRADING CHARGED TO "GEN. EQUIPMENT"

B/ LABOR

NO OF POURS/DAY = 21

CONCRETE /DAY = $21 \times 4.7 CY = 100 CY/DAY$

LABOR FOR FACE BLOCKS (GANG MOLDS)

OPERATION	MEY	HRS	TOTAL
SET	3	<u>14</u>	34
POUR	3	<u>34</u>	2 1/4
FINISH	1	<u>34</u>	34
STRIP & CLEAN	3	<u>1</u>	3

PRODUCTION TIME 2 HRS 6³⁴ HRS

ONE CREW PRODUCES 4 UNITS / 8 HR DAY

5 CREWS WILL BE REQ. FOR 21 UNITS/DAY

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH# AD-512

TRUMANVILLE LAKE DAMREGUONNICKOFTIVEPTASIN, COMM.COMPOSITE DESIGN - PRECAST FACECREW FOR PRECAST OPERATION

1 FOREMAN	10.20	10.20
15 LABORERS	5.60	84.00
2 MASONS	8.90	17.80
2 CONV. OPER.	7.75	<u>15.50</u>
		127.50 / HR x 8 = 1020 ⁰⁰ / SHIFT

ASSUME 80 PRODUCTION DAYS

$$80 \times 896 = \underline{71,680}^{00}$$

2 YARD CRANE OPERATORS 8.60 17.20 x 8 = 137⁶⁰ / SHIFT

C) CONCRETE PRODUCTION & PLACING.

1) CONC. PRODUCTION CHARGED TO MIXING PLANT

2) TRANSPORTATION & PLACING.

a) 1 - 400 FT CONVEYOR @ 1⁵⁰ / LF / DAY x 80 = 48,000⁰⁰

A-FRAMES TO SUPPORT ABOVE CONV. = 2000⁰⁰
INCL. INSTALLATION.

b) 2 - 150 FT CONVEYORS @ 1⁵⁰ / LF / DAY x 80 = 36,000⁰⁰

A-FRAMES FOR ABOVE = 2000⁰⁰

c) 1 - CONC. HOPPER = 3500⁰⁰

D) STORAGE YARD - EXCAV., GRADING & ACCESS - ROAD

1 FT GRAVEL BED COMPACTED - 300' x 120' = 36,000 SF

@ 1⁰⁰ / SF = 36,000⁰⁰

EXCAV. & GRADING CHARGED TO "GEN. EQUIPMENT"

4000 SF OF ACCESS ROAD @ 1⁰⁰ / SF = 4000⁰⁰

E) EQUIPMENT

2 YARD CRANES 1000⁰⁰ / MONTH

6
J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH# AD-512

TRUMPELL LAKE DAM

DEQUONHOCK TOWER BASIN, CONN.

COMPOSITE DESIGN-PRECAST FACE

F / ERECTION

20,000 LF OF JT.

ASSUME 3 SQ. INCH AREA \approx 15 CY OF MORTAR

REQ. CREW = 2 MASONS
1 LABORER

PROJECTED WORKING TIME

60 DAYS AT 335 LF/DAY
SAY 70 DAYS

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15/77 REV.


SKETCH # AD-5121

TRUMBULL LAKE DAM

DECUONNICK RIVER BASIN, COM.

COMPOSITE CONSTRUCTION, PRECAST

PROPOSED PRECAST PLANT LAYOUT



**COST AND FEASIBILITY STUDY
ALTERNATE DESIGNS TO PERMIT USE
OF SLIP FORM AND OTHER TECHNIQUES
TO MAXIMIZE ECONOMIES**

BOOK AC2

**APPENDIX: MASSIVE HEAD BUTTRESS DAM
CALCULATIONS AND COST STUDY SHEETS**

BOOK AC-2 - APPENDIX: MASSIVE HEAD BUTTRESS DAM,
CALCULATIONS AND COST STUDY SHEETS

- 1 Sketches AR-200 through -217
- 2 Sketches AD-S201 through -227
- 3 Sketches AD-EC-S1 through -S3
- 4 Sketches AD-2C-S1 through -S6

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH# AR-200

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONN.

BUTRESS DAM STUDY

THIS PRELIMINARY INVESTIGATION ENCOMPASSES HEAD BUTRESS DAMS OF 4 DIFFERENT SIZES AND ONE FLAT SLAB BUTRESS DAM.



- 1) THE HEAD BUTRESS DAMS WERE INVESTIGATED FOR VARYING STEM SIZES WITH CONSTANT HEAD DIMENSIONS.

SCHEME #	STEM LENGTH	STEM WIDTH
1	135'	10'
2	135'	8'
3	100'	8'
4	120'	8'

- 2) SCHEME #2 SATISFIES THE CONDITION OF 0-STRESSES AT THE HEEL IN THE MOST SATISFACTORY WAY.
- 3) SCHEME #1 INCLUDES A SPILLWAY LAYOUT WHICH IS APPLICABLE TO THE OTHER SIZES.
- 4) SCHEME #4 WAS DESIGNED FOR MODERATE UPLIFT (~ 450 K) AND USE OF ROCK BOLTS (1/2" ROCK ANCHORS)
- 5) THE FIRST TRY FOR THE AMBURSEN DAM RESULTED IN NEGATIVE STRESSES AT THE HEEL (-5.2 K/SF)
IT IS SUGGESTED TO USE A 125 FT BASE-LENGTH INSTEAD OF 118 FT.

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15/78 REV. SKETCH# AR-201
 TRUMBULL LAKE DAM
 PEGUONNOCK RIVER BASIN, CONN.
 BUTTRESS DAM STUDY, SCHEME #1



MAX. WATER PRESSURE = $130' \times 60 = 7,8^k$

$M_{MAX} = \frac{7,8 \times 10^2}{2} = 390^k$

$A_s = \frac{390}{1,76 \times 92,5} = 2,4 \text{ in}^2$

FOR $H = 65' - M = 195^k$

$A_s = 1,2 \text{ in}^2$


FOR $H = 32,5' - M = 97,5^k$

$A_s = 0,6 \text{ in}^2$

TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CONN.
BUTTRESS DAM STUDY, SCHEME #1

I) CENTER OF GRAVITY OF CONC. SECTION

A) HEAD



$$\text{II, C.G.} = \frac{4,5 \times 10 \times 60}{40} = 2,62'$$

$$4,5 - 2,62 = 1,88'$$

C.G. OF I+II

$$\frac{3,5 \times 30 \times 17,5}{184} + \frac{4,5 \times 20 \times 5,38}{484} = X_1 = 3,43'$$

TOT. VOL. OF BUTTRESS HEAD


$$V_I = (105 + 90) \times 140 = 27,300 \text{ CF} = \underline{\underline{1010 \text{ CY}}}$$

TOT. WEIGHT OF BUTTRESS HEAD

$$1010 \times 4,000^{\#} = \underline{\underline{4,040 \text{ K}}}$$

B) STEM

$$\text{C.G. OF STEM} = x_2 = \frac{2 \times 127}{3} - \frac{12^2}{3(12+127)} = 84,2'$$



TOT. VOL. OF STEM

$$V_{II} = 69,5 \times 140 \times 10' = 97,300 \text{ CF} = \underline{\underline{3,600 \text{ CY}}}$$

TOT. WEIGHT OF STEM

$$3600 \times 4000^{\#} = \underline{\underline{14,400 \text{ K}}}$$

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15/72. REV.

SKETCH # AR 2

TRUMBULL LAKE DAM

REGUONNOCK RIVER BASIN, CO

BUTTRESS DAM STUDY, SCHEM

C) C.G. OF HEAD + STEM

$$\frac{4,040 \times 131.57 + 14,400 \times 84.2}{18,440} = Z = 94.5'$$

$$\begin{array}{r} 14400 \\ \underline{4040} \\ 18,440^k \end{array}$$

2) WATER PRESSURE (HORIZ.)

RESULTANT WATER PRESSURE = $P_w = \frac{W \times H^2}{2} \times b$

$H = 135'$

$b = 30'$

$P_w = \frac{62.5 \times 135^2 \times 30'}{2} = \underline{17,100^k / BUTTRESS}$


J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH # AR 204

TRUMBULL LAKE DAM
 DEQUONNOCK RIVER BASIN, COM. N.Y.
 BUTTRESS DAM STUDY, SCHEME #1

30



FORCE	MOMENT ARM-FT	MOMENT 'A'
$W_c = 18,440^k$	94.5	$+1,741,000^k$
$P_w = 17,100^k$	45.0	$-769,000^k$
	RIGHTING M =	$+972,000^k$

$M_c = 2.26$
 M_w

- 1) UPLIFT MAY BE DISREGARDED WITH PROPER DRAINAGE.
- 2) $2.26 > 1.5$ O.K. BECAUSE EARTHQUAKE & ICE NOT CONSIDERED IN CALCULATION.

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH # AR-

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CO


BUTTBRESS DAM STUDY, SCHE

CENTER OF GRAVITY OF BASE

$$\begin{array}{r} 135.0 \\ \underline{3.43} \\ 131.57 \end{array}$$

$$\begin{array}{r} 195 \\ \underline{1270} \\ 1465 \end{array}$$

TAKING M : $\frac{195 \times 131.57 + 1270 \times 63.5}{1465} = Y = 72.5'$ FRONT
ROUND 'A'



J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 17 72 REV.

SKETCH # AH-206

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN, CON

BUTTRESS DAM STUDY, SCHEME

STRESS ANALYSIS

$$S = \frac{W}{A} \pm \frac{M \times Y}{I}$$

$$\frac{(P/W)}{(W/C)} = \frac{+769,000}{-406,000} = 22 \times 18440^K$$
$$363,000^K$$

$$W = 18,440^K$$

$$A = 195 + 1270 = 1465 \text{ SF}$$

$$M_{CG} = +363,000^K$$


$$Y_{1,2} = 72.5', 62.5'$$

$$I = \frac{30 \times 62.5^3 + 10 \times 72.5^3 - 2 \times 10 \times 56.75^3}{3}$$

$$= \frac{30 \times 244,140 + 10 \times 381,100 - 20 \times 182,300}{3}$$

7,330,000 3,811,000 3,646,000

$$I = 2,498,300 \text{ FT}^4$$



$$S_{TOE} = 12.6 + \frac{363,000 \times 72.5}{2,498,300} = 23.1 \text{ KSF}$$
$$= 160 \text{ PSI}$$

$$\frac{0.074}{5.4}$$

$$S_{HEEL} = 12.6 - 9 = 3.6 \text{ KSF}$$
$$= 25 \text{ PSI}$$

$$\frac{363,000 \times 62.5}{2,498,300} = 9$$

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

TRUMBULL LAKE DAM

PERUONNOCK RIVER BASIN, CON.

BUTTRESS DAM STUDY, SCHEME

10 FT STEP

SPILLWAY SLAB

CLEAR SPAN = 20'-0"

ASSUME SLAB THICKNESS OF 12" - d = 9"

DL = 150 "/SF

LL = 620 * /SF (10 FT SURCHARGE)

770 "/SF

M = $\frac{wL^2}{10} = 0,77 \times 40 = \underline{30,8} \text{ 'K} > 23,9 \text{ 'K}$

TRY 18" SLAB - d = 15"

DL = 216 "/SF

LL = 620 "/SF

836 "/SF

M = $0,836 \times 40 = 33,4 \text{ 'K} < 66 \text{ 'K} \left(\frac{Kd^2}{1000} \right)$

$A_s = \frac{33,4}{1,76 \times 15} = 1,26 \text{ "}$

SAY #8@8"

(#8@7" FOR 22 FT SPAN)


J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH# AR-208


TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CO.
BUTRESS DAM STUDY, SCHEME #1

30



J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 11, 1966 REV. _____
TRUMBULL LAKE DAM
REGULATING RIVER BASIN, CONN.
BUTTES DAM STUDY, SCHEME # 2



STEM VOLUME
 $69.5 \times 140 \times 8 = 77,800 \text{ CF}$
2,880 CY

STEM WEIGHT
 $2880 \times 4 = 11,520 \text{ K}$

	CY	FORCE ^K	MOMENTARY	MOMENT	TOTAL
HEAD	1,010	4,040	131.57	+532.000	
STEM	2,880	11,520	84.20	+971.000	+1,503,000
WATER	-	17,100	45.00	-769.000	-769,000

RIGHTING M = +734,000

$$\frac{M_c}{M_w} = \frac{1,503,000}{769,000} = 1.96$$

C.G. OF BASE
TAKING M AROUND TOE.
 $\frac{195 \times 131.57 + 1016 \times 63.5}{1211} = Y = 74.4'$

195
1016
1211

25600
64,500
90,100

$W_c = 4,040 \text{ K}$
 $\frac{11,520}{15,560 \text{ K}}$

C.G. OF HEAD + STEM FORCES
 $\frac{4,040 \times 131.57 + 11,520 \times 24.2}{15,560} = 97' \text{ FROM TOE}$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH# AR-210

TRUMBULL LAKE DAM

DEQUANNOCK FIVER BASIN, CONN.

BUTTRESS DAM STUDY, SCHEME #2

STRESS ANALYSIS

$$S = \frac{W}{A} \pm \frac{M \times Y}{I}$$

$$W = 15,560 \text{ K}$$

$$A = 1211 \text{ SF}$$

$$M_{CG} = +419,000 \text{ 'K}$$

$$Y_{1/2} = 74,4', 60,6'$$

$$I = \frac{30 \times 60,6^3 + 8 \times 74,4^3 - 2 \times 11 \times 54,85^3}{3}$$


$$\frac{30 \times 222,545 + 8 \times 411,830 - 22 \times 165,000}{3}$$

$$6,676,400 \quad 3284,640 \quad 3,630,000$$

$$I = \underline{2,110,350 \text{ FT}^4}$$

$$\begin{aligned} \frac{S_{TOE}}{12.83} &= \frac{15,560}{1,211} + \frac{419,000 \times 74,4}{2,110,350} \\ &= 12,83 + 14,8 = +27,63 \text{ KSF} \\ &= +192 \text{ PSI} \end{aligned}$$

$$\begin{aligned} \frac{S_{HEEL}}{12.83} &= 12,83 - 12,1 = +0,73 \text{ KSF} \\ &= +5 \text{ PSI} \end{aligned}$$




$$\begin{aligned} (P_w) &+769,000 \\ (W_c) &-350,000 \quad 15,560 \times 22,5 \\ &+419,000 \text{ 'K} \end{aligned}$$

$$Y_2 = \frac{54,85 + 5,175}{60,60'}$$

$$\frac{M \times Y_2}{I} = \frac{419,000 \times 60,6}{2,110,350} = 12,1$$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
DEQUONNOK RIVER BASIN
BUTRESS DAM STUDY, SCHEME #3



8 FOOT STEM
BASE LENGTH = 100 FT

1) C.G. OF CONC. SECTION

A) BUTRESS HEAD: 1010CY - 4040^K


B) STEM

VOL. = 52' x 140' x 8' = 58,200 CF = 2160CY

WEIGHT = 2160 x 4^K = 8640^K

C.G. OF STEM

$$\frac{2 \times 92}{3} - \frac{12^2}{3 \times (12 + 92)} = \frac{60.8'}{6.13 \quad 0.46}$$



$$\frac{100.00'}{3.43} = 96.57'$$

$$\frac{4040}{8640} = 12,680$$

C) C.G. OF HEAD + STEM

$$\frac{4040 \times 96.6 + 8640 \times 61}{12,680} = Z = 66'$$

2) WATER PRESSURE

P_w = 17,100^K/BUTRESS

3) C.G. OF BASE (M AROUND TOE)

$$\frac{195^{SF} \times 96.6' + 736^{SF} \times 46'}{931} = Y = 56.5'$$

$$\frac{195}{736} = 931$$

J. F. CAMELLERIE, P.E.


23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH # AR-212

TRUMBULL LAKE DAM
DEQUONNOCK RIVER BASIN COM.
BUTTRISS DAM STUDY, SCHEME # 3

30



FORCE	MOMENT ARM, FT	MOMENT 'A'	$\frac{M_c}{M_w} = 1.1$
$W_c = 12,680^k$	66	+ 836,000 ^{IK}	
$P_w = 17,100^k$	45	- 769,000 ^{IK}	
		RIGHTING MOMENT = + 67,000 ^{IK}	

$$769,000 \times 2 = 1,538,000^{\text{IK}} \quad (\text{ASSUMING SAFETY FACTOR } 2)$$

$$- 836,000^{\text{IK}}$$

$$702,000^{\text{IK}} = \text{ADDITIONAL "M" REQ.}$$


ASSUME LEVER ARM OF 97 FT

$$\frac{702,000^{\text{IK}}}{97} = 7,250^k \quad - \text{ TOO HIGH, TRY 120 FT BASE}$$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 10/12 REV. SKETCH # AR-213
TRUMBULL LAKE DAM
DEQUONNOCK RIVER BASIN, CONN.
BUTRESS DAM STUDY, SCHEME # 4

30



8 FT STEM
BASE LENGTH = 120 FT

1) CG. OF CONC. SECTION
A) BUTRESS HEAD: 1010 CY - 4,040^k

B) STEM
VOL. = 62 x 140 x 8 = 69,500 CF
= 2,580 CY
WEIGHT = 2580 x 4^k = 10,300^k

C.G. STEM
 $\frac{2 \times 112}{3} - \frac{12^2}{3 \times (12 + 112)} = \frac{74.3'}{0.39}$

4,040
 10,300
 14,340 = Wc
 112 x 8 = 896
 195
 896
 1091 SF

C) C.G. OF HEAD + STEM
 $\frac{4,040 \times 116.6 + 10,300 \times 74.3}{14,340} = z = 86'$

2) WATER PRESSURE
 $P_w = 17,100^k$

3) C.G. OF BASE (M AROUND TOE)
 $\frac{195^{SF} \times 116.6 + 896^{SF} \times 56}{1091} = y = 67'$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH # AH-214

TRUMPULL LAKE DAM
PEQUONNOCK RIVER BASIN, CONN.
BUTTRESS DAM STUDY, SCHEME #3

FORCE	MOMENT ARM, FT	MOMENT "A"	
$W_c = 14,340$	86	+1,235,000	$\frac{M_c}{M_w} = 1.61$
$P_w = 17,100$	45	-769,000	
RIGHTING MOMENT =		+466,000	

STRESS ANALYSIS

$$S = \frac{W}{A} + \frac{M \times Y}{I}$$

$$W = 14,340 \text{ K}$$

$$A = 1,091 \text{ SF}$$

$$M_{CG} = 769,000 - 19' \times 14,340 = 469,500 \text{ 'K}$$

$$Y_{1/2} = 67', 53'$$

$$I = \frac{30 \times 53^3 + 8 \times 67^3 - 2 \times 11 \times 47.25^3}{3}$$

$$\frac{30 \times 148,877 + 8 \times 300,763 - 22 \times 105,642}{3}$$

$$I = 1,513,000 \text{ FT}^4$$

$$S_{TOE} = \frac{14,340}{1,091} + \frac{469,500 \times 67}{1,513,000}$$

$$13,13 + 20,75 = +33,88 \text{ KSF}$$

$$= +235 \text{ PSI}$$

$$S_{HEEL} = 13,13 - 16,4 = -3,27 \text{ KSF}$$

$$= -23 \text{ PSI}$$

86
 67
 19'



53
 575
 47,25

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15 1972 REV.

SKETCH# AR-215

TRUMBULL LAKE DAM
PEQUONNOK RIVER BASIN
BUTTRESS DAM STUDY SCHEME



J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH# AR-216

TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, COA. N.Y.
BUTTRESS DAM STUDY, SCHEME #4

A) POINT OF ZERO STRESS

$$13,13 = \frac{469,500 \times Y}{1313,000}$$


$$Y = 42.1'$$

B) TOTAL UPLIFT

$$1) \frac{1.55 \times 5.25 \times 8}{2} = 33^k$$

$$2) \frac{3.27 + 1.55}{2} \times 5.75 \times 30' = 415^k$$

$$\text{TOTAL} = 415 + 33 = 448^k$$




USING HIGH STRENGTH ROCK ANCHORS - 4 EA REQ. @ 112' EA
TO BE SPACED EQUALLY ALONG C.G. LINE OF HEAD

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 19/72 REV. SKETCH # AN-411
TRUMPELL LAKE DAM
PEQUONNOCK RIVER BASIN, CONY.
BUTTRESS DAM STUDY, SCHEME #1

30



COST STUDY SHEETS
MASSIVE HEAD BUTTRESS DAM


J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15, 72 REV.
 TRUMBULL LAKE DAM

SKETCH# A05201

PEQUONNOK RIVER BASIN CONN.
 BUTTRESS DAM ESTIMATE

BUTTRESS STEM VOLUME



$e = 3.5(30) = 105$

$f = 4.5(11) = 49.5$

$g = 17.5(8) = 140$

294.5 S.F (2385) / 27 = 26,000 CY
 TOTAL H OF ALL HEADS

1/2 B	H	AREA	1/2 B	H	AREA	1/2 B	H	AREA
14	36	504	51	126	6420	14	35	490
22	54	1190	48	108	5190	8	19	162
27	68	1840	45	101	4550	7	15	105
29	72	2080	43	95	4080	5	12	60
32	81	2590	41	91	3730	3	8	24
39	98	3830	40	89	3560			
48	120	5760	39	88	3440			
51	129	6580	36	85	3060			
54	137	7400	34	72	2450			
56	143	8020	15	31	465			
54	143	7730	14	26	374			
53	140	7420	14	26	374			
52	132	6880						

100,308 S.F.

$h = [100,308(8)] / 27 = 30,000$

TOTAL STEM
 QUANT. = 56,000 CY

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15, 1952 REV.


DRAWING NO. 5202

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONN.

BUTTRESS DAM ESTIMATE

AREA OF ROCK EXCAVATION



$$a = 4.5(30)(30) = 4050 \text{ S.F.}$$

$$b = \frac{1}{2}(10.5)(4.5)(2)(30) = 1420 \text{ S.F.}$$

$$c = 9(765) = 6885 \text{ SF}$$

$$d = 9(1688) = 15192 \text{ SF}$$

$$\frac{27,547 \text{ SF.}}$$

VOLUME OF ROCK EXCAVATION

$$\left[\frac{(27,547 - 15,192) 5 (\text{AVER.}) + 15,192 (1)}{27} \right] = 2,860 \text{ CY.}$$

VOLUME OF FOUNDATION CONC.

$$\left[\frac{(27,547 - 15,192) (8) + 15,192 (4)}{27} \right] = 6000 \text{ CY}$$

AREA PRECAST PLANK AT SPILLWAY

$$24(20)(12) = 5,750$$

$$(\sqrt{(83)^2 + (97)^2}) 6(24) = 18,300$$

$$(\sqrt{(67)^2 + (25)^2}) 2(24) = 5,380$$

$$(\sqrt{(30)^2 + (30)^2}) 2(24) = 2,030$$

$$(\sqrt{(25)^2 + (25)^2}) 2(24) = 1,750$$

$$A_T = 33,210 \text{ S.F.}$$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15, 72 REV.
 TRUMBULL LAKE DAM

SKETCH# AD-5203

PEQUONNOCK RIVER BASIN, CONN.

BUTTRESS DAM ESTIMATE

SPILLWAY SLAB VOLUME

$$1.5 \left[26(360) + 121(240) + 68(30) + 39(30) + 34(60) \right] \frac{1}{127}$$

$$= 1620 \text{ CY.}$$

CONCRETE SUMMARY

FOUNDATION	= 6000	CY
BUTTRESS STEM	= 56000	CY
SPILLWAY SLAB	= 1620	CY
	<u>63620</u>	CY

KEYWAYS - 7,850 LF


WATERSTOPS - 6820 LF

FOUNDATION FORMS

$$3 \left[\begin{array}{l} 30(30) + 24(30) + 2576(2) \\ 30(9) \end{array} \right] = 21,125$$

$$\text{SIDE } a = 4.5(285) = \underline{1,285}$$

TOTAL AREA = 22,410 SF.



H. OF FORM EXC. FOR
 SIDE a = 3' AVER.

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15, 72 REV.


SKETCH # AD5204

TRUMBULL LAKE DAM


PERUONNOCK RIVER BASIN, CONN.

BUTTRESS DAM ESTIMATE

REINFORCEMENT




$$\begin{aligned}
 2 \times 2386 \#7 \times 18' &= 175,000\# \\
 2 \times 2386 \#9 \times 8' &= 140,000\# \\
 2386 \#11 \times 29.5' &= 375,000\# \\
 60 \#7 \times 2385' &= 292,000\# \\
 \hline
 &= 982,000
 \end{aligned}$$



$$\begin{aligned}
 63(30) + 2576(2) &= \\
 7042 \text{ LF} & \\
 7100 \#9 \times 8' &= 192,000 \#
 \end{aligned}$$

FOOTING



$$\begin{aligned}
 \#7 @ 12 &= 2.04 \\
 \#10 @ 12 &= 4.3 \\
 \hline
 6.34 / 1.5 &= 4.2\# / \text{C.F.} \\
 4.2(27) &= 113\# / \text{CY.} \\
 + 35\# / \text{CY} & \\
 \hline
 147\# / \text{CY} & \\
 \text{SAY } 150\# / \text{CY} &
 \end{aligned}$$

SPILL WAY = 1620 CY \therefore 1620 (150) = 243,000#

SPILL WAY

TOTAL WT = 1,417,000#

1,417,000 / 2000 = 709 T

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 17, 1911 REV.

SKETCH AD-3 205


TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONNS.

MASSIVE HEAD BUTTRESS DAM

BUTTRESS SLIDE

SLIDING FORMS



a	30' x 30 =	900'
b	2 x 3.5 x 30 =	210
c	2 x 12 x 30 =	720
d	2576 x 2 =	5152
e	(SEE END BLKH. FORMS)	6,982'
	8 x 30 = 240	<u>SAY, 7000'</u>

YOKES

HEAD: 4 YOKES / POUR x 30 POURS = 120 YOKES

STEM:	①	30	⑥	24	⑪	16
	②	30	⑦	20	⑫	14
	③	30	⑧	20	⑬	11
	④	27	⑨	19	⑭	9
	⑤	26	⑩	18	⑮	5
					⑯	1

TOTAL IN STEM: 300

END FORM IN STEM: 2 x 30 = 60

TOTAL = 120

300
420

JACK RODS

HEAD:	8 RODS x 2380'	=	19,040 LF
①	2 x 2380	=	4760
②	2 x 2380	=	4760
③	2 x 2200	=	4400
④	2 x 1913	=	3826
⑤	2 x 1650	=	3300
⑥	2 x 1401	=	2802
⑦	2 x 1180	=	2360
⑧	2 x 998	=	1996
⑨	2 x 701	=	1402

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.


DATE JULY 17 1971
 TRUMBULL LAKE DAM
 PEQUONNOCK RIVER BASIN, CONNS.
 MASSIVE HEAD BUTTRESS DAM

- ⑩ 2 x 610 = 1220
- ⑪ 2 x 521 = 1042
- ⑫ 2 x 297 = 594
- ⑬ 2 x 208 = 416
- ⑭ 2 x 134 = 268
- ⑮ 2 x 54 = 108
- ⑯ 2 x 11 = 22

52,506 LF

END BULKHEAD JACKRODS

#	B	H	B ²	H ²	L ²	L	2L
1	28	36	784	1296	2080	46	92
2	44	54	1936	2916	4852	70	140
3	54	68	2916	4624	7540	87	174
4	58	72	3364	5184	8548	93	186
5	64	81	4096	6561	10,657	103	206
6	78	98	6084	9604	15688	126	252
7	96	120	9216	14400	23616	154	308
8	102	129	10404	16641	27045	165	330
9	108	137	11664	18769	30433	175	350
10	112	143	12544	20449	32993	181	362
11	112	143	12544	20449	32993	181	362
12	106	140	11236	19600	30836	176	352
13	104	132	10816	17424	28240	168	336
14	102	126	10404	15876	26280	162	326
15	96	108	9216	11664	20830	144	288
16	90	101	8100	10201	18301	135	270
17	86	95	7396	9025	16421	124	248
18	82	91	6724	8281	15005	122	244
19	80	89	6400	7921	14321	119	238
20	78	88	6084	7744	13628	117	234
21	72	85	5184	7225	12409	111	222
22	68	72	4624	5184	9308	99	198



J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15, '72 REV.

SKETCH# AD. 5207

TRUMBULL LAKE DAM


PEQUONNOCK RIVER BASIN, CONN.

MASSIVE HEAD BUTTRESS DAM

LF	B	H	B ²	H ²	L ²	L	2L
33	30	31	900	961	1861	43	86
34	28	26	784	676	1460	38	76
35	28	26	784	676	1460	38	76
26	28	35	784	1225	2009	45	90
27	16	19	256	361	617	25	50
28	14	15	196	225	421	21	42
29	10	12	100	144	244	16	32
30	6	8	36	64	100	10	20

TOTAL = 6190 LF

DECKS HEADS



30
 3.5
 3.5
 12
 12
 12
 12
 4

77 LF x 2' = 154 ϕ '

154 ϕ ' x 30 = 4620 ϕ '

STEMS: 2576 LF

30 x 7 = 210

2786 LF x 5' WIDE = 13,930 ϕ '

TOTAL = 18,550 ϕ '

SCAFFOLDS

6982 LF x 2' WIDE = 13,964 ϕ '

RAILING + LADDERS

MAIN DECK: 6982 LF

SAY 7000 LF

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15 '72 REV.

SKETCH# AD-S208

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONNS.

MASSIVE HEAD BUTTRESS DAM

HYDRAULIC PIPING

$$\begin{aligned} \text{LGT. FORM} &= 7000 \text{ LF} \\ 10' \times (425+60) &= 4850 \text{ LF} \\ \hline &= 11,850 \text{ LF} \end{aligned}$$

TOPPING-OUT RODS

$$12'/\text{HEAD} \times 30 = 360 \text{ EA}$$

SLIDE CREW

9 SETS OF HD FORMS
 (2 WKS TO DISMANTLE + RE-ASSEMBLE)
 30 SETS OF STEM FORMS (NO REUSE)

SLIDE @ 12"/HR.

SLIDE	9/8	14/8
1,2,3	15	3
4,5,6	15	1.5
7,8,9	15	1
10,11,12	15	-
13,14,15	15	-
16,17,18	15	-
19,20	12	-
	102	6

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
 PEQUODNOCK RIVER BASIN, CONN.
 MASSIVE HEAD BUTTRESS DAM

CLASSIFICATION	#	HR. RATE INCL. FR. BENEFITS	COST/SHIFT 9/8	COST/SHIFT 16/8
CONV. OPER.	1	7.75	70	124
HOIST OPER.	3	8.60	234	415
JACK OPER.	3	8.00	217	385
CARPENTER	6	9.00	488	868
ELECTRICIAN	1	8.28	75	132
FIN. FORMAN	1	9.37	85	150
FINISHERS	6	8.87	480	854
FIN. HELPERS	3	7.15	192	343
LABORERS:				
FORMAN	1	6.10	55	98
PLACING	15	5.60	755	1340
VIBRATION	6	5.60	303	538
CURING	6	5.60	303	538
IRONWORKERS	6	10.20	553	980
CRANE OPER.	2/3	8.60	51	92
OILER	2/3	6.85	41	74
IRONWORKER FORM.	1	10.70	97	171
			3999	7102

102 SHIFTS X 3999 = 408,000
 6 " X 7102 = 42,700
450,700

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15 '72 REV.


SKETCH# AD-S 210

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONNS.

MASSIVE HEAD BUTTRESS DAM

FINISH + CURING



AREA "a"	=	30' W X HT.	30 X 2380 =	71,400 ϕ'
b	=	3.5 W X 2 X HT	7 X 2380 =	16,660
c	=	12' W X 2 X HT	24 X 2380 =	57,120
d	=	12' W X 2 X HT		57,120
e	=	100300 (2)		200,600
f	=	3100 (6)		18,600
				<hr/>
				421,500
				<hr/>
				SAY 425,000 SF

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.


TRUMBULL LAKE DAM
 PEQUONNOK RIVER BASIN, CONN.
 MASSIVE HEAD BUTTRESS DAM

VERTICAL KEYS + WATERSTOPS

$2380 \times 2 = \underline{4760 \text{ LF}}$

SPILLWAY HORIZ. PRECAST SEAT

$48' \times 12 = \underline{576 \text{ LF}}$



SPILLWAY SLAB SEAT
 + PRECAST SEAT

#	LF	#	LF
14	163	23	86
15	288	24	76
16	270	25	76
17	248	26	90
18	244	27	50
19	238	28	42
20	234	29	32
21	222	30	20
22	198		

2577 LF

SPILLWAY

SLIDING FORMS

$12 \text{ BAYS} \times 24' \text{ W} = \underline{288 \text{ LF}}$

FORM RAILS

BAY 14	162'	21	111
15	144	22	99
16	135	23	86
17	124	24	76
18	122	25	76
19	119	26	90
20	117		

TOTAL = 1261 LF

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15, 72 REV.

SKETCH # AD-5212

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONN.

MASSIVE HEAD BUTTRESS DAM

JACKROD ANCHORS

2 ANCHORS / POUR x 12 POURS = 24

JACK ROD (22T)

#	LF
1 - 14	326
1 - 15	288
2 - 15	288
2 - 16	270
3 - 16	270
3 - 17	248
4 - 17	248
4 - 18	244
5 - 18	244
5 - 19	238
6 - 19	238
6 - 20	234
7 - 20	234
7 - 21	222
8 - 21	222
8 - 22	198
9 - 22	198
9 - 23	86
10 - 23	86
10 - 24	76
11 - 24	76
11 - 25	76
12 - 25	76
12 - 26	90

4776 LF

SPILLWAY SLIDE CREW

2 SETS OF FORMS
 18"/HR. SLIDE SPEED

POUR	HT	HRS	9/8	
1	144	96	12 SHIFTS	SAY
12	38	26	3.3	1 WK
2	135'	90	11.2	1 WK
11	38	25	3.1	
3	124	83	10.4	1 WK
10	43	29	3.6	
4	122	81	10.1	2 WK
9	99	65	8	
8	111	74	9.3	
5	119	79	10	1 WK
6	117	79	10	1 WK
7	111	74	10	1 WK
				8 WKS

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15 '76 REV.

SKETCH # AD-5 419

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONN.

MASSIVE HEAD BUTTRESS DAM

SPILLWAY SLIDE CREW CONT'

$$\text{BWKS} \times \frac{5 \text{ DAYS}}{\text{WK}} = 40 \text{ DAYS} \times \frac{3 \text{ SHIFTS} (\frac{9}{8})}{\text{DAY}} = 120 \text{ SHIFTS}$$

CLASSIFICATION	#	HR. RATE INCL. FRINGE BENEFIT	COST/SHIFT 9/8
LOWER CONV. OPER	1	7.75	70
TOP CONV. OPER	1	7.75	70
HOIST OPER	1	8.60	78
JACK OPER	1	8.00	72
CARPENTER	1	9.00	81
ELECTRICIAN	1	8.28	75
FIN. FORMAN	1	9.37	85
FIN. HELPER	1	7.15	64
LABORERS.			
FORMAN	1	6.10	55
PLACING	3	5.60	} 252
VIBRATION	1	5.60	
CURING	1	5.60	


902

$$120 \text{ SHIFTS} @ \frac{\$902}{\text{SHIFT}} = \underline{\$108,204}$$

HYDRAULIC PIPING 288 LF FORM
 SAY 300 LF

FINISHING + CURING 2270 LF X 24 FT. WIDE = 54,500 ϕ '

FILL @ TOP



$$\frac{2}{3} bh = \frac{2}{3} (26)(2.5) = 43 \phi'$$

$$43 \phi' \times 360' = 15,200 \text{ CF}$$

FIN: 30 LF X 360' = 10,800 ϕ '

$$15,200 \text{ CF} / 27 = \underline{570 \text{ CY}}$$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUL 15 '72 REV.

SKETCH # AD-3-214

MASSIVE HEAD BUTTRESS DAM

TRUMBULL LAKE

NEW ENGLAND DIV., CORPS/ENGR.

SLIDING FORMS 2550 LF ST'L FORMS (30 HEADS)

USE 9 SETS (3.33 USES / SET) - 1 = 2.33 REUSES

$\times 5\%$
 $.116$

ST'L FORMS = \$5.00/ft w/ REUSE $\frac{5.00 \times 1.116}{3.33} = \$1.67/ft$

COST/LF = \$1.67 x 4 = \$6.70

4450 LF WOOD FORM (NO REUSE). COST/LF = \$6.60

AVERAGE COST =

2550 LF @ 6.70 = 17,100


4450 LF @ 6.60 = 29,400

$\frac{46,500}{7000} = \$6.65$ AV. COST.

SPILLWAY YOKES

$\frac{\$600 \text{ EA}}{3.33} = \180

SPILLWAY SLAB SEAT



FORM HT = 8'

DEPTH = 4'

LUMBER = 32 x 36 ft x .20 = \$20.00

HANGERS = $\frac{3}{8}$ x 2 x 6 x .25 = 2.00

HARDWARE = 2.00

\$24

LABOR = 4 x 9 =

36

\$60

OR \$15 / LF

\$6 MAT'L

\$9 LAB.

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUL 15 '72 REV.


SKETCH# AD-S-215

MASSIVE HEAD BUTTRESS DAM

TRUMBULL LAKE

NEW ENGLAND DIV. CORPS/ENGRS.

SPILLWAY FORM



FORM 6 LF
 3' TANK 9 LF
 2' TANK 6 LF
 DIAPHRAGMS 5 LF

$$\frac{26 \text{ LF} @ 5^{\#} = 130^{\#} / \text{LF}}{+ 20\% \quad \quad \quad 26^{\#}}$$

$$156^{\#} / \text{LF} @ .40 = 62.4 \quad \quad \quad \$ 156^{\#} / \text{LF}$$

SAY \$60.00/LF.

12 SLIDES TO BE MADE
 2 SETS OF FORMS REQ'D
 6 REUSES

$$\text{COST PER LF} = \frac{\$ 60.00 \times 1.3}{6} = \$ 13.00$$

PLACING

5 IRON WORKERS @ 10.20 = 51.00 / hr.
 FOREMAN 10.70
 CRANE & OILER IN EQUIP 61.70 / hr.

$$\$ 493.60 / \text{DAY}$$

$$\text{COST / L.F.} = \frac{493}{24} = \$ 20.50 / \text{LF. INCL DISMANTLING}$$

FORM RAILS

$$30 \text{ lb} \times .144 \times 4 = 18000 \text{ lb FAB (600 LF)}$$

$$@ 20^{\#} = \$ 3600$$

$$\text{PLACING} = 30^{\#} \times 10^{\#} = \$ 3.00 / \text{LF}$$

SAY 3^{\#} / LF

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

MASSIVE HEAD BUTTRESS DAM
 TRUMBULL LAKE
 NEW ENGLAND DIV. CORPS/ENGRS.

CONVEYOR REQUIREMENTS

TRESTLE CONVEYOR 450 LF
 ABUTMENT " 200 LF
 # 650 LF

650 L.F. @ \$110 = 72,000
 RAIL & ACC @ 10% = 7,000
 SIDE DISCHARGE 1,500

80,500

SAY 40,000 SALVAGE
 40,500

TOTAL USE = 100 DAYS

COST / DAY = \$400

CHECK RENTAL BASIS = 650 LF @ 1.25 = \$800/day
 USE \$600/day
 = 3000/wk

ERECTION = \$5,000

DISTRIBUTING CONVEYORS FOR SLIP FORM

2 @ 90' = 180 L.F.

180 LF @ \$110 = \$20,000

RAIL & ACC 2,000

SIDE DISCH 1,500

\$ 23,500

11,500 SALVAGE

\$ 12,000

\$12,000/100 days = \$120/day

CHECK RENTAL BASIS = 180 x 1.25 = \$225/day

USE 175⁰⁰/day

875/wk

ERECTION = \$1600 x 30 = 48,000

SPILLWAY CONVEYOR

4 x 30 = 120 LF @ \$110 = 13,200

1,300

1,500

Rental = 120 LF x \$1.25 = \$150/day

16,000

\$8000/40 days = \$200/day

8,000

USE \$175/day

\$8,000

ERECTION = \$1600 x 12 = \$19,200

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUL 15 '72 REV.


SKETCH# AD-5-21

MASSIVE HEAD BUTTRESS DAM

TRUMBULL LAKE

NEW ENGLAND DIV, CORPS/ENG'GS

FLAT SLAB STARTER FOOTINGS



WIDTH = 22'

AVER. AREA = $(4 + \frac{b}{2})(3 + \frac{a}{2})$

VOL = AA (22) / 27 = CY

a	b	AREA	Vol.
6	7.5	7.8 (6) = 46.8	38.5
5.5	7	7.5 (5.8) = 43.5	35.5
5	6	7 (5.5) = 38.5	31.5
4	5	6.5 (5) = 32.5	26.5
1.5	2	5 (3.8) = 19	15.5
1.5	2	5 (3.8) = 19	15.5
1.5	2	5 (3.8) = 19	15.5
5	6	7 (5.5) = 38.5	31.5
27	33	20.5 (16.5) = 338	275.0
5	5.5	6.8 (5.5) = 37.5	30.5
0	0	4 (3) = 12	10.
0	0	4 (3) = 12	10.
			536. CY

CONSTRUCTION SCHEDULE - MASSIVE HEAD BUTTRESSES												
MONTH YEAR	JAN.	FEB.	MAR.	APR.	MAY	JUNE	JULY	AUG.	SEPT.	OCT.	NOV.	DEC.
1972										STRIPPING		
										PROCUREMENT		
1973	PROCUREMENT			DIVERSION - STAGE I						DIVERSION - STAGE II		
			STRIPPING	PLANT ERECTION				FOUNDATIONS				
1974				BUTTRESSES			SPILLWAY					
				MISC. CONC. & TOP DRIVE						C.D. & E.		

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

UNIT NO. 1 (P. 11) 12-1974
TRUMBULL LAKE
PEQUONNOK RIVER BASIN CONN.
MASSIVE HEAD BUTTRESS DAM

* CLEAN-UP, DEMOBILIZATION & ENVIRONMENT
CONTRACTURAL COMPLETION DATE DEC. 1974

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH # AD-5-219

TRUMBULL LAKE DAM

REGUONNICK RIVER BASIN, CONN.

BUTTRESS DAM; COST STUDY

ON SITE PLANT

MASSIVE HEAD BUTTRESS DAM

SUBSTITUTE SITE PLANT FOR READY MIXED CONC.

CONVENTIONAL CONSTRUCTION

	MAT	LAB	TOTAL
BORROW OPERATION	.30/TON	.29/TON	.59/TON
AGGREGATE PROD.	.53/TON	.34/TON	.87/TON
BATCH PLANT	3.44/CY	1.75/CY	5.19/CY

HEAD BUTTRESS

TOTAL CONC. REQ.

BUTTRESS	56,000 CY
FOUND.	6,000 CY
SPILLWAY	1,620 CY
MISC.	1,200 CY
<u>TOTAL</u>	<u>64,820 CY</u> × 22.50

PLANT EQUIPMENT

BORROW OPER.	72,000
AGGR. PROD.	128,000
BATCH PLANT	437,000
	<u>\$ 637,000</u>

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH # AD-S 220

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN, CONN.

BUTTFESS DAM, COST STUDY

ON SITE PLANT

ASSUME 6 BAGS OF CEMENT / CY

AGGREGATE ~ 3200" / CY

1) CEMENT REQ.

$$64,820 \text{ CY} \times 6 \times 94" = 36,600^k = \frac{18,300 \text{ TONS}}{\times 27.20 = \$497,000}$$

2) AGGREGATE REQ.

$$64,820 \times 1.6 \text{ TONS} = \underline{104,000 \text{ TONS}}$$

3)

		MAINT.	LAB.	TOTAL
BORROW OP.	110,000 TONS	.65	.29	\$.94
AGGR. PROD.	104,000 TONS	1.23	.34	\$1.57
CONC. BATCH	64,820 CY	6.75	1.75	\$8.50

$$110,000 \times .94 = 103,300$$

$$104,000 \times 1.57 = 163,000$$

$$64,820 \times 8.50 = \underline{550,000}$$

$$\$ 816,300$$

$$\text{CEMENT} \quad \$ \underline{497,000} \quad (27.20 / \text{TON})$$

$$1,313,300$$

$$\text{READY MIX} = 1,460,000$$

$$\text{SITE PLANT} = \underline{1,313,000}$$

$$\text{SAVINGS} = \$ \underline{147,000}$$

FOR 7 BAG MIX

$$\text{DEDUCT} \quad \$ \underline{-78,000}$$

$$\text{SAVINGS} = \$ \underline{69,000}$$

$$\begin{array}{r} 3200 \\ - 3060 \\ \hline = 140" / \text{CY} \times \\ 64,820 \times 0.14 = 9100 \\ \times 0.94 = 4,550 \\ \hline - 83000 \\ + 4300 \\ \hline 78,700 \end{array}$$

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUL 15, 72 REV.

SKETCH# AD-5-221

TRUMBULL LAKE DAM

PEQUONNOCOK RIVER BASIN, CONN.

MASSIVE HEAD BUTTRESS DAM

ALTERNATE PRECAST SPILLWAY DESIGN

COST OF PRECAST (QUOTATION)

#8.00/SQ. FT

WEIGHT = $1.33' \times 3.0' \times 24' \times 150^{\#} = 14,400^{\#}$

SAY 7 TONS

PLACING RATE:

$3 \times 24 \times 3/hv \times 8 hv. = 1730 \#'$

LENGTH OF OPERATION:

$33200 \# / 1730 \# = 19.2 \text{ days}$

SAY 20 DAYS

PLACING CREW:

1 FOREMAN	10.70
6 ERECTORS	61.20
2 FINISHERS	17.80
1 HELPER	5.60

$\$95.30/hv (8)(20) = 15,250$

COST PER SQ. FT = $\frac{15250}{33200} = .46$

SAY 50¢/sq'

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15 '72 REV.

SKETCH# AD-S 222

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN CONN.

MASSIVE HEAD BUTTRESS DAM - SCHEME

ALTERNATE

CONCRETE VOLUME REDUCTION:

$$\text{STEM: } \frac{15}{12} (2385) (8) / 27$$

$$= 5,400 \text{ CY}$$

$$\text{FTG: } 15 (30) (9) (4) / 27$$

$$= \underline{600 \text{ CY}}$$

$$\text{TOTAL} = 6,000 \text{ CY}$$

SURFACE AREA REDUCTION (BUTTRESS)

$$\frac{15}{12} (2385) (2) = 36,000 \text{ SF}$$

ROCK EXCAVATION REDUCTION

$$9 (15) (30) (1) / 27 = 150 \text{ CY}$$

HAND CLEANING REDUCTION

$$15 (9) (30) = 4050 \text{ SF}$$

FOUNDATION GROUTING REDUCTION

$$15 (9) (30) = 4050 \text{ SF}$$

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15, 72 REV.

SKETCH# AD-5223

TRUMBULL LAKE DAM

PEQUONNOCK RIVER BASIN CONN.

MASSIVE HEAD BUTTRESS DAM - SCHEME 4

ALTERNATE

CEMENT REDUCTION

$$6000 \text{ CY} \times 6 \times 94\% = 3400 \text{ K} = 1700 \text{ TONS}$$

AGGREGATE REDUCTION

$$6000 \text{ CY} \times 1.6 \text{ TONS} = 9,600 \text{ T}$$

BORROW OPERATION REDUCTION

$$6000 + 5\% = 6300 \text{ TONS}$$

RENTAL OF EQUIPM'T 10 MO. FOR 110,000 TONS

$$(6300/110,000)(10) = .57 \text{ SAY } \frac{1}{2} \text{ MO.}$$

$$5(7200) = 3,600 \text{ REDUCTION}$$

JACK ROD REDUCTION

3	1	x	29	x	2	=	58
4	2.5		26		2	=	130
5	4		26		2	=	208
6	5.5		22		2	=	242
7	7		21		2	=	294
8	8.5		20		2	=	340
9	10.		19		2	=	380
10	11.5		18		2	=	414
11	13.0		15		2	=	390
12	14.5		12		2	=	348
13	16		10		2	=	320
14	17.5		6		2	=	210
15	23		2		2	=	92
16	11		1		2	=	22

3448 LF

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15, 72 REV.

TRUMBULL LAKE DAM

SKETCH# AD-521

PEQUONNOK RIVER BASIN CONN.

MASSIVE HEAD BUTTRESS DAM - SCHEM

ALTERNATIVE

YOKE REDUCTION

$$2 \text{ YOKES PER BUTTRESS} = 60 \text{ YOKES}$$

SLIDING FORM REDUCTION

$$15(2)(30) = 900 \text{ LF}$$

DECK REDUCTION

$$15(5)(30) = 2250 \text{ SF}$$

SCAFFOLD REDUCTION

$$15(2)(2)(30) = 1800 \text{ SF}$$

RAILING & LADDER REDUCTION

$$15(2)(30) = 900 \text{ LF}$$

HYDRAULIC PIPING REDUCTION

$$15(2)(30) + 10(4)(30) = 2100 \text{ LF}$$

FINISH / CURING REDUCTION (STEM)

$$3600 \text{ SF}$$

REINF. REDUCTION (FTG)

$$2 \times 16 \#9 \times 8'-0 = 256(2.044) = 520 \#$$

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15, 1977 REV.

TRUMBULL LAKE

SKETCH# AD-5225

PEQUONNICK RIVER BASIN CONN.

MASSIVE HEAD BUTTRESS DAM - SCHEFF

ALTERNATE

FOUNDATION :

FORMWORK REDUCTION:

$$15(2)(3)(30) = 2700 \text{ SF}$$

CURING REDUCT. (FTG)

$$9(15)(30) = 4050 \text{ SF}$$

KEYWAY REDUCTION

NONE

WATERSTOP REDUCTION

NONE

PRESTRESS ITEMS (ADDED)

4 - 1 1/4 H.S. RODS PER BUTTRESS :

$$4(30) = 120 \text{ RODS @ } 128 \text{ (AVER.)}$$
$$= 15,360 \text{ LF.}$$

$$\text{LABOR : } 15,360 \text{ @ } \$1.00/\text{LF} = \$15,360$$

$$\text{ROCK DRILLING : } 120(20) = 2400 \text{ LF.}$$

$$\text{@ } \$2.00/\text{LF} = \$4,800$$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JUL 15 '72 REV.

SKETCH# AD-522

MASSIVE HEAD BUTTRESS DAM

TRUMBULL LAKE

NEW ENGLAND DIV. CORPS / ENGR

PUMPING ALTERNATE

LOWER CONVEYORS	650 L.F.
VERTICAL RUN	110 L.F.
DISTRIB. RUNS	180 L.F.
	<u>940 L.F.</u>

COST OF EQUIPMENT:

PUMP	\$ 4000
LINE @ #6 ⁱⁿ	\$ 6000 INCL GATES
LINE SUPPORT	\$ 2000
	<u>\$12,000</u>
	4,000 33% SAVINGS
	<u>\$ 8,000 EQUIP COST</u>

SAVINGS IN EQUIP COST:

CONVEYORS	: 52,500
PUMPING	: 8,000
	<u>\$ 44,500</u>

ERECTION SAME COST

HEEDE HOISTS ARE NOT REQUIRED

SAVINGS: 60,000 RENTAL
 9,000 ERECTION

CONVEYOR SUPPORT BRACKETS
 6,000 EQUIP
 9,000 ERECTION

PLACING CREWS

CONVEYOR:	3 CONVEY. OPER @ 7.75 = 23.25
	1 HOIST OPER @ 8.60 = 8.60
	<u>\$ 31.85</u>

PUMPING

	1 PUMP OPER @ 7.75 = 7.75
	3 GUNMAN @ 6.85 = 20.55
	4 LABORERS @ 5.60 = 22.40
	<u>\$ 50.70</u>

DIFF/HR PLACING: PUMPING \$3.35 MORE

TOTAL COST DIFF. FOR SLIP: $\frac{11885 \times 8}{2551.00} (450,700) = 19,000$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

MASSIVE HEAD BUTTRESS DAM
 TRUMBULL LAKE
 NEW ENGLAND, DIV. CORPS/ENGES.

SPILLWAY OPERATION

AD-5227

240 L.F. @ #6⁰⁰ support $\frac{\$1440}{\$1000}$
 $\frac{\$2500}{500}$ SALVAGE
 $\$2000$ Equip Cost
 ERECTION SAME COST

SAVINGS IN EQUIPMENT $\$8,000$
 LESS $\frac{2,000}{\$6,000}$

PLACING CREW: CONVEYOR $\$31.85/hr.$
 PUMPING:
 1 PUMP OPERATOR @ 7.75 = $\$7.75$
 1 GUNMAN 6.85 6.85
 2 LABORERS 5.60 11.20
 $\$25.80$

DIFF/HR Pumping $\$6.05$ LESS
 TOTAL COST DIFF = $\$6(8)(40) = \2000

SUMMARY	BUTTRESSES		SPILLWAY	
	CONV.	PUMP.	CONV.	PUMP
EQUIPMENT	52,500	$\$6,000$	8,000	2,000
PLACING LABOR		$\$19,000$	2,000	
HOISTS	69,000			
SUPPORT	15,000			
TOTAL	136,500	$\$25,000$	$\$10,000$	$\$2,000$

TOTAL SAVING PUMP $\$119,150$

SUMMARY DAM TWICE AS HIGH & WIDE (SAME L&T)

	BUTTRESSES		SPILLWAY	
	CONV	PUMP	CONV.	PUMP
EQUIPMENT	52,500	6,000	8,000	2,000
PLACING LABOR		76,000	8,000	
HOISTS	99,000			
SUPPORT	24,000			
TOTAL	175,500	$\$82,000$	16,000	2,000

TOTAL SAVING PUMP $\$107,500$

23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBUCC LINE

PEQUONNOC RIVER BASIN CONN.
CONV. DAM (INCREASED SIZE)

BATCH PLANT OPER: 127,000 (4) = 508,000 CY.

BORROW OPERATION : 231,000 (4) + 9000 = 933,000 T

AGGREGATE PROD : 924,000 T

PLANT EQUIP.

a) BORROW OPERATION	EQUIP.	SALVAGE	NET
1- 2 1/2 CY DRAGLINE	100,000	50,000	50,000
4- 6CY REAR DUMP TRUCKS	52,000	13,000	39,000
			<u>\$ 89,000</u>

b) AGGREGATE PROD.

INSTALLATION			10,000
CRUSHER UNIT	490,000	295,000	195,000
WATER DISTRIB			8,000
			<u>\$ 213,000</u>

c) MIXING PLANT:

MIX. EQUIP	432,000	50,000	358,000
INSTALLATION			110,000
CEMENT VEYOR	60,360	10,000	50,360
			<u>\$ 518,360</u>

d) CABLEWAY

6 CY CABLEWAY	395,000	130,000	265,000
INSTALLATION & MAINT.			58,000
			<u>\$ 323,000</u>

CEMENT REQ.

10,755 (4) = 43,020 T

		MAT'L	LABOR
BORROW OPER	933,000 T	.10	.29
AGG. PROD.	924,000 T	.23	.34
CONC. BATCH.	508,000 CY	1.02	1.75
CABLEWAY	508,000 CY	.64	.61

NOTE: MATERIAL PRICES BASED ON 160 YD CAPACITY.
PLANT USE 320 YD PLANT (DOUBLE MAT'L COST)

CONSTRUCTION SCHEDULE

HUNTINGTON, N. Y.

RECONSTRUCTION NIGRA DRAINAGE CONN. DAM (HIGHER SIZE) CONSTRUCTION SCHED.

MONTH YEAR	JAN.	FEB.	MAR.	APR.	MAY	JUNE	JULY	AUG.	SEPT.	OCT.	NOV.	DEC.
1972										PROCUREMENT		
										STRIPPING		
1973	PROCUREMENT			DIVERSION - STAGE I								
			STRIPPING					CONC. - PHASE I				
				PLANT ERECTION								
1974					CONC. I		CONC. - PHASE II					
			DIVERSION - STAGE I									
1975					CONCRETE - PHASE II							
1976					CONC. - II							
							C. P. & E. *					

* CLEAN-UP, DEMOBILIZATION & ENVIRONMENT.

- 64 -

23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL WARE

PEQUONNOCK RIVER BASIN, CONN.
CONVENTIONAL DAM (INCR. SIZE)

ESCALATION IMPACT

ASSUMED ESCALATION:	LABOR	MATERIAL
1973	8%	8%
1974	6%	4%
1975	4%	4%
1976	4%	4%

LABOR ESCALATION

1973	30% OF WORK @ 8%	--- 2.4%
1974	30% OF WORK @ 8+6%	--- 4.2%
1975	30% OF WORK @ 14+4%	--- 5.4%
1976	10% OF WORK @ 18+4%	--- 2.2%
		<u>14.2%</u>

MATERIAL ESCALATION

1973	50% OF WORK @ 8%	----- 4.0%
1974	20% OF WORK @ 8+4%	---- 2.4%
1975	20% OF WORK @ 12+4%	---- 3.2%
1976	10% OF WORK @ 16+4%	---- 2.0%
		<u>11.6%</u>

USE 14% LABOR ESCALATION
12% MATERIAL "

HUNTINGTON, N. Y.

TRUMBULL RIVER BASIN, CONN.


MASSIVE HEAD BUTTRESS DAM

HEIGHT + WIDTH, LENGTH SAME AS TRUMBULL

FORMS SLIDE

SLIDING FORMS

$$\begin{aligned} \text{LENGTH} &= 6982' \quad (\text{AD-S205}) \\ d' &= 2576 \times 2 = 5152' \\ 8' \times 2 &= 16 \times 30 = 480' \\ \hline &12,614' \text{ LF} \end{aligned}$$




END BULKHEAD FORMS = 240 LF

YOKES

HEAD	-----	120 yokes	(AD-S205)
STEM	-----	600	
		30	
		<u>750</u>	
END FORM	-----	60	

JACK RODS



23 GREEN STREET
HUNTINGTON, N. Y.

IRUMBULL LAKE DAM
PEQUONNOC RIVER BASIN, CONN.
MASSIVE HEAD BUTTRESS DAM

(AD-5205)

HEAD 19,040 x 2 = 38,080 LF

ROD	X STEM	L/STEM	L	X 2
1	30	295	8870	17,740
2	30	295	8870	17,740
3	30	295	8870	17,740
4	30	290	8700	17,400
5	30	280	8400	16,800
6	27	270	7300	14,600
7	27	260	7000	14,000
8	26	250	6500	13,000
9	26	240	6250	12,500
10	24	230	5500	11,000
11	24	220	5300	10,600
12	20	210	4200	8,400
13	20	200	4000	8,000
14	20	190	3800	7,600
15	20	180	3600	7,200
16	19	170	3250	6,500
17	19	160	3050	6,100
18	18	150	2700	5,400
19	18	140	2520	5,040
20	16	130	2075	4,150
21	16	120	1920	3,840
22	14	110	1540	3,080
23	14	100	1400	2,800
24	11	90	990	1,980
25	11	80	880	1,760
26	9	70	630	1,260
27	9	60	540	1,080
28	5	50	250	500
29	5	40	200	400
30	1	30	30	60
31	1	20	20	40
32	1	10	10	20

238,330

→ 238,330

276,410 LF

23 GREEN STREET
HUNTINGTON, N. Y.

PEQUONNOK RIVER BASIN, CONN.
MASSIVE HEAD BUTTRESS DAM

END BULKHEAD JACKRODS $6200 \times 2 = 12400 \text{ LF (AD-S207)}$

DECKS (AD-S207)
4620 ϕ' HEAD
13,930 ϕ' STEM
14,500 STEM
33,050 ϕ'

SCAFFOLDS $6982 \text{ LF} \times 2 = 13,964$
 $\times 2' \text{ WIDE}$
27,928
SAY 28,000 ϕ'

HYDRAULIC PIPING L.F. FORM $12,650'$
 $10' (750+60) = 8,100'$
20,750 LF

CONCRETE $56,000 \text{ CY} \times 4 = 224,000 \text{ CY}$

REINF. ST'L
982,000 # HEAD $\times 2 = 1,960,000 = 982^T$
192,000 DWLS $\times 2 = 384,000 = 192^T$
243,000 SPILLWAY $\times 2 = 486,000 = 244^T$

SLIDE CREW 9 SETS OF HD. FORMS.
SLIDE $6'12''/\text{HR.}$ 2 WKS TO DISMANTLE + RE-ASSEMBLE)
SLIP 3 BUTTRESSES 30 SETS OF STEM FORMS (NO RE-USE)
AT A TIME.

AVERAGE FOR FIRST $\frac{1}{2}$ OF SLIDE = $9''/\text{HR.} = 6'/\text{SHIFT}$
AVERAGE FOR 2ND HALF = $12''/\text{HR} = 8'/\text{SHIFT}$

AVERAGE HT. OF SLIP = $165' = 24 - \frac{9}{8}$ SHIFTS.

10 SLIPS $\times 21 \text{ SHIFTS/SLIP} = 210 \text{ SHIFTS } (\frac{9}{8})$

HUNTINGTON, N. Y.


MASSIVE HEAD BUTTRESS DAM

CLASSIFICATION	#	HR. RATE INCL. FR. BENIFITS	COST/SHIFT 9/8
CONV. OPER.	1	7.75	70
HOIST OPER.	3	8.60	234
JACK OPER.	3	8.00	217
CARPENTERS	6	9.00	488
ELECTRICIAN	1	8.28	75
FIN. FOR.	1	9.37	85
FINISHERS	9	8.87	720
FIN. HELP.	4	7.15	258
LABORERS:			
FORMAN	1	6.10	55
PLACING	25	5.60	} → 2320
VIB.	12	5.60	
CURING	9	5.60	
IRONWORKERS	6	10.20	553
CRANE OPER.	2/3	8.60	51
OILER	2/3	6.85	41
IRONWORKER FOR.	1	10.70	97
			5,264

210 SHIFTS x \$5,264 = \$1,100,000

FINISH + CURING (AD-S210)

a	71,400 x 2 =	142,800
b	16,600 x 2 =	33,200
c	57,120 x 2 =	114,240
d	57,120 x 2 =	114,240
		404,480



RATIO $\frac{\text{AREA B}}{\text{AREA A}} = \frac{270,410}{52,506} = 5.4$

e $200,600 \times 5.4 = 1,080,000$

$\frac{404,480}{1,484,480}$

SAY 1,485,000

23 GREEN STREET
HUNTINGTON, N. Y.

PEQUONNOK RIVER BASIN, CONN.
MASSIVE HEAD BUTTRESS DAM

PLANT EQUIP.	EQU.	SALV.	NET
a) BORROW OPERATION			
1-2 1/2 CY DRAGLINE	100,000	40,000	60,000
4-6 CY REAR DUMP TRUCKS	52,000	10,000	42,000
			102,000
b) AGGREGATE PRODUCTION			
INSTALLATION			10,000
CRUSHER UNIT	490,000	245,000	245,000
WATER DISTRIBUTION			8,000
			263,000
c) MIXING PLANT			
MIK. EQUIP.	432,000	50,000	382,000
INSTALLATION			110,000
CEMENTVEYOR	60,360	10,000	50,360
INSTATION			10,000
			552,360

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
PEQUONNOCK RIVER BASIN, CONN.
MASSIVE HEAD BUTTRESS DAM

LABOR ESCALATION

1973	40% OF WORK @ 8%	-----	3.2%
1974	60% OF WORK @ 8+6%	----	8.4%
			<u>11.6%</u>

MATERIAL ESCALATION

1972	60% OF WORK @ 0%	-----	0.0%
1973	20% OF WORK @ 8%	---	1.6%
1974	20% OF WORK @ 8+4%	---	2.4%
			<u>4.0%</u>

USE 11½% Labor Escalation
4% Material "

CONSTRUCTION SCHEDULE - MASSIVE HEAD BUTTRESSES (INCR. SIZE)												
MONTH YEAR	JAN.	FEB.	MAR.	APR.	MAY	JUNE	JULY	AUG.	SEPT.	OCT.	NOV.	DEC.
1972										STRIPPING		
										PROCUREMENT		
1973	PROCUREMENT			DIVERSION - STAGE I						DIVERSION - STAGE II		
			STRIPPING	PLANT ERECTION				FOUNDATIONS				
1974			BUTTRESSES									
						SPILLWAY						
				MISC. CONC. & TOP DRIVE					C.D. & E *			

23 GREEN STREET
HUNTINGTON, N. Y.

PERQUOICK RIVER BASIN CONUL.
MASSIVE HEAD BUTTRESS DAM (INCR. SIZE)

* CLEAN-UP, DEMOBILIZATION & ENVIRONMENT
CONTRACTORAL COMPLETION DATE DEC. 1974

**COST AND FEASIBILITY STUDY
ALTERNATE DESIGNS TO PERMIT USE
OF SLIP FORM AND OTHER TECHNIQUES
TO MAXIMIZE ECONOMIES**

BOOK AC3

**APPENDIX: AMBURSEN DAM
CALCULATIONS AND COST STUDIES**

BOOK AC-3 - APPENDIX: AMBURSEN DAM,
CALCULATIONS AND COST STUDIES

1. Sketches AR-301 through -312
2. Sketches AD-S-301 through -311

J. F. CARWELL, INC.
23 GREEN STREET
HUNTSVILLE, N. Y.

TRUMPOLI LAKE DAM
PLANE RESTRAINED BASIN DAM
AMBURSEN DAM

CONSIDER 1 FT STEP AT $h = 130$ FT

$$F = 130 \times 62.5 = 8,12^k$$

$$M = \frac{8,12 \times 20^2}{10} = 325^k$$

$$K = \frac{24000 \times 8.0}{1200} = 295$$

$$\frac{325}{295} = 1.1 = F = 12 \times 33 \quad \text{USE } 33 + 3 = 36''$$

$$A_s = \frac{325}{1,76 \times 33} = 5,6 \text{ } \square''$$

$$2,37 - d = \frac{78}{3} = 26$$

6-9

$$2,37 \times 1,76 \times 33 = 137,5''$$

$$\frac{\sqrt{137,5 \times 10}}{2,12} = L = 13' \text{ (CLEAR SPAN)}$$

FOR 8 FT WIDE STEMS, SPACING CAN BE 21' O.C.

USE STEMS 20' O.C.

3'-0" SLAB, PARTIALLY RESTRAINED.

$$\text{MAX. } A_s = 2,37 \square'' = \#11 @ 8''$$

TRY ALTERNATE: SLAB CONTINUOUS OVER
6 SPANS = 120 FT

J. F. CAMELLERIE, P.E.
 93 GREEN STREET
 HUNTINGTON, N. Y.

DATE: 12/15/70 REV.


SKETCH # AR-301

TEMPERALL LAKE DAM

PELOUCHING RIVER BASIN, CONN.

AMBURSEN DAM

ASSUME SLAB CONTINUOUS OVER 3 - 20 FT SPANS.



1) FORCE ON ONE FT. STRIP AT H=130 FT

$$p = 130 \times 62.5 = 8,12 \text{ K/5F}$$

2) $-M_{MAX} = -0.1 \times 8,12 \times 12^2 = \underline{\underline{117 \text{ K}}}$

ASSUME SLAB THICKNESS TO BE 36"

$$-A_s = \frac{117}{1.16 \times 32} = \underline{\underline{2.08 \text{ sq}}}$$

say #9 @ 6" (MAX. RE)


3) $+M_{MAX} = +0.07 \times 8,12 \times 12^2 = \underline{\underline{82 \text{ K}}}$

$$+A_s = \frac{82}{1.16 \times 32} = \underline{\underline{1.45 \text{ sq}}}$$

say #9 @ 8"

23 GREEN STREET
HUNTINGTON, N. Y.

TRASH BASKET AND FLOOD BASIN
AMBURSEN DAM



USE 125 FT BASE, VARY ANGLE
ACCORDINGLY


61.5	85
42.6	61.5
18.9	23.5

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRIMMILL LAKE DAM
DEERFIELD FIVER BASIN, N.Y.
AMBLERSEN DAM

1) C.G. OF CONC. SECTION
A) FLAT SLAB

VOL. = $171' \times 20' \times 3' = 10,260 \text{ CF} = 380 \text{ CY}$
 WEIGHT = $380 \times 4^k = 1520^k$



B) STEM

VOL. = $65.5' \times 140' \times 8' = 73,300 \text{ CF} = 2720 \text{ CY}$
 WEIGHT = $2720 \times 4^k = 10,900^k$

C.G. STEM

$$\frac{16.5^2 + 16.5 \times 114.5 + 114.5^2}{3 \times (16.5 + 114.5)} = 39'$$

272
 1896
 13160
 15262
 393

C) C.G. OF SLAB + STEM

$$\frac{1520 \times 69' + 10900 \times 39'}{12420} = Z = 42.6'$$

1520^k
 10900
 12420^k
 105000
 425820
 530000

2) WATER PRESSURE

$b = 20'$

A) HORIZ.

$P_w = 11,400^k$

B) VERT.

$$W_w = \frac{62.5 \times 94.5 \times 135 \times 20'}{2} = 7,960^k$$

FORCE	MOMENT ARM	MOMENT "A"	
$W_c = 12,420$	$42.6'$	$+ 530,000^k$	
$W_w = 7,960$	$25.0'$	$+ 676,000^k$	$+ 1,206,000^k$
$P_w = 11,400$	$45.0'$	$- 513,000^k$	$- 513,000^k$
		RIGHTING M =	+ 693,000^k

$$\frac{M_w}{M_p} = 2.35$$

3) C.G. BASE (M AROUND TOE)

$$\frac{70 \times 116.25}{915} = 57.25 = Y = 61.5'$$

60540
 985.

STRESS ANALYSIS

$$S = \frac{W}{A} + \frac{M \times Y}{I}$$

$$W = 12420 \times 7,960 = 20,380^K$$

$$A_{BASE} = 3,5 \times 20 + 114,5 \times 8 = 990 SF$$

$$M_{CG} = \frac{11,400^K \times 45'}{513,000} + \frac{12,420^K \times 18,9'}{235,000} - \frac{7,960^K \times 23,5'}{187,000} = 561,000$$

$$Y_{1,2} = 61,5', 56,5'$$

$$I = \frac{20 \times 56,5^3 + 8 \times 61,5^3 - 2 \times 6 \times 53^3}{3}$$

$$\frac{20 \times 180,362 + 8 \times 232,608 - 12 \times 142,830}{3,610,000 \quad 1,861,000 \quad 1,785,000}$$

$$I = 1,228,500 FT^4$$

$$S_{TOE} = \frac{20,380}{990} + \frac{561,000 \times 61,5}{1,228,500}$$

$$20,6 + 28,1 = +48,7 KSF$$

$$= +333 PSI < 1000 PSI ALL$$

$$S_{HEEL} = 20,6 - \frac{561,000 \times 56,5}{1,228,500} = -5,2 KSF$$

$$25,8$$

$$= -36 PSI < 102 PSI$$

ALL

$$\frac{H}{V} = \frac{11,400}{20,380} = 0,56$$

USE 125 FT BASE INSTEAD OF 118 FT

d = 44"

48" SLAB

1) $\underline{V_d} = 89 - 8,12 \times 3,83 = 58^k$

$\underline{V_d} = \frac{58000}{12 \times 44} = \frac{58000}{528} = 110 \text{ PSI} > 70 \text{ PSI}$

2) $\underline{V_d} = 89 - 8,12 \times 1,92 = 73,4^k$

$\underline{V_d} = \frac{73400}{12 \times 44} = \frac{73400}{528} = 139 \text{ PSI} > 126 \text{ PSI}$

3) $\underline{A_s} = \frac{490}{1,16 \times 44} = 6,3 \text{ " } - 4^{\#} 11 / \text{LIN FT}$

$100 \text{ CF} / 27 = 3,7 \text{ CY} / \text{LF HEIGHT}$

$4 \times 5,3^{\#} = 21,2 \times 25 = 530^{\#} / 3,7 = 143^{\#} / \text{CY}$


TEMP. STEEL " 8 @ 9"

$4^{\#} / \text{SF} \times 25 = 100^{\#} / 3,7 = 27^{\#} / \text{CY}$

170^{\#} / \text{CY}

27
 J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TELEPHONE COVE DAM
 PECHERDING TUNNEL BASIN, CONN.
 AMBURSEN DAM



$$p = 130 \times 62.5 = 8,12^k$$

$$V_s = 11' \times 8,12^k = 89^k$$

$$\frac{M_{MAX}}{K} = \frac{8,12 \times 22^2}{8} = 490^k$$

$$F = \frac{M}{K} = \frac{490}{293} = 1,66 \quad d \approx 41''$$

SAY 48" SLAB - $d = 44''$

$$V_{ol} = 89 - 4,5 \times 8,12 = 52,5^k$$

$$V = \frac{52,5}{12 \times 30} = 87 \text{ PSI}$$

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.


DATE 04/11/77 REV.

SKETCH BY

TIMBERLAKE DAM

ROCKY MOUNTAIN RIVER BASIN, COLORADO


AMBURSEN DAM



73.4
53.5
17.9

STRESS ANALYSIS

CONSTRUCTION LOAD ON PRECAST SECTION.



J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
ROUSHOROCK FINEE BASIN DAM
AMBURSEN DAM

1) C.G. OF CONCRETE SECTION

A) SLAB + PRECAST $L = 25'-0"$

AVERAGE SLAB THICKNESS = 4.30 FT

" PRECAST " = 1.00 "

$5.30 \text{ FT} \times 25' = 133 \text{ CF}$

a) CONC. VOLUME

$$178' \times 133' = 23674 \text{ CF} = \underline{876 \text{ CY / UNIT}}$$

b) C.G. = 72.5' FROM TOE (x₁)

c) WEIGHT = 876 × 4^k = 3500^k

B) STEM

a) CONC. VOLUME

$$\frac{130' + 20'}{2} \times 140' \times 8' - 178 \times 3 \times 7.5 = 80,000 \text{ CF}$$

84000

4000

$$= \underline{3000 \text{ CY}}$$

b) WEIGHT = 12,000^k

c) C.G. OF STEM

$$x_2 = \frac{20^2 + 20 \times 130 + 130^2}{3 \times 150} = 44'$$

c) C.G. OF SLAB + STEM

$$\frac{3500 \times 72.5 + 12,000 \times 44'}{15,500} = z = 55'$$

254000
522000
782000

2) WATER PRESSURE

A) $T_H = \frac{62.5 \times 135^2 \times 30}{2} = 17100 \text{ k / STEM}$

B) VERT. WATER PRESSURE

$$W_w = \frac{62.5 \times 106' \times 135' \times 30'}{2} = 13,400 \text{ k}$$

3/ MOMENTS AROUND TOE.

FORCE	MOMENT ARM	MOMENT "A"	
$W_C = 15,500$	55'	+852,000 ^{IK}	
$W_W = 13,400$	93,4'	+1,250,000 ^{IK}	+ 2,102,000 ^{IK}
$P_W = 17,100$	45'	-769,000 ^{IK}	- 769,000 ^{IK}
			1,833,000 ^{IK}

$$\frac{M_W}{M_P} = 2,73$$

4/ C.G. BASE (M-A")

$$\frac{130 \times 8 \times 65 + 22 \times 10 \times 125}{1260} = Y = 75,5'$$

1040
+ 220
1260
67500
+ 27500
95000

STRESS ANALYSIS

$$S = \frac{W}{A} + \frac{M \times Y}{I}$$

$$W = 15,500 + 13,400 = 28,900^K$$

$$A_{BASE} = 1260 SF$$

$$M_{CG} = 17,100 \times 45' + 15,500 \times 20,5' - 13,400 \times 17,9' = 342,000^K$$

770,000 318,000 240,000

$$Y_{1,2} = 75,5' , 54,5'$$

$$I = \frac{30 \times 54,5^3 + 8 \times 75,5^3 - 22 \times 44,5^3}{3}$$

$$= \frac{30 \times 161879 + 2 \times 430369 - 22 \times 22121}{3}$$

$$= 2,120,000 FT^3$$

4,255,500
+ 3,445,000
8,700,500
- 4,850,000
3,850,500

$$S_{TOE} = \frac{28,900}{1260} + \frac{342,000 \times 75,5}{2,120,000}$$

0,4 \times 75,5 = 30,2

$$= 23 + 30,2 = 53,2 KSF = 370 PSI$$

$$S_{HEEL} = 23 - 0,4 \times 54,5 = 1,2 KSF = 8,3 PSI$$

J. F. CASSELLERIE, P.E.
23 CALLEN STREET
HUNTINGTON, N. Y.

DATE: JUNE 1, 1964 REV.


SKETCH: 4/18/64

TERRACE LAKE DAM

PREPARED BY: J. F. CASSELLERIE, P.E.

AMBROSEN DAM

10



CONC. VOL. OF SLAB

$$32' \times 350' \times 2.5' = 28,000 \text{ CF} = 1040 \text{ CY}$$

$$\text{REINF. } 30''/\text{CY} \times 710 = 15.6 \text{ TONS}$$

USING PRECAST FORMS, THE AVERAGE SLAB THICKNESS WILL BE 1 1/2 FT.

$$\text{CONC. VOL.} = 32 \times 350 \times 1.5 = 16,800 \text{ CF} = \underline{625 \text{ CY}}$$

COST STUDY SHEETS

AMBURSEN DAM


J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15, 72 REC.
 TRUMBULL LAKE

SKETCH AD-3-

HEQUONNOCK RIVER DAM CONCR.
 AMBURSEN DAM ESTIMATE


CONCRETE!
BUTTRESS FOOTINGS



$$a = 30(30)(8)(9)/27 = 2400 \text{ CY}$$

$$b = 1627(4)(9)/27 = 2170 \text{ CY}$$

FLAT SLAB STARTER FTGS -



$$\sin 52^\circ = \frac{4.2}{X}$$

.61979
<u>9.89653</u>
.72326

$$X = 5.3$$

VOLUME = 2350 CY
 (SEE TABULATION ON NEXT SHEET)

BUTTRESS STEM

= 40,370 CY

(SEE TABULATION ON NEXT SHEET)

STARTER FTGS TABULATION

BUTTRESS STAIR TAB.

6'-3" x d/2	4' x c/2	VOLUME	
		①	②
13.3	13.5	100	148
11.8	11	130	106
8.3	6	50	41
9.8	9	28	72
12.8	12.5	160	130
15.3	15.5	230	194
9.8	8.5	80	68
9.3	8.5	79	65
8.3	7	52	48
6.8	5	34	28
6.8	5.5	37	30
9.3	8	74	61
6.8	7.5	60	54
9.3	8	74	60
9.3	7.5	70	57
8.3	7	58	48
8.8	6.5	50	47
6.8	5	34	28
6.8	4.5	31	26
7.3	5.5	40	33
11.3	11.0	105	102
22.3	24.5	540	456
8.3	6.5	50	44
6.3	4	25	21
6.3	4	25	21
13.3	13	170	141
7.8	6	40	39
7.3	6	40	36
8.3	6	50	41
4	4		14

8 (4) (31) / 27 = 37

292 LF 247 LF

2296 CY
 + 54 CY
 + 675 CY
 3025 CY

* STARTER FTG SITTING ON BUTTRESS FTG ** ALTH. 2' EXCAL.


- 16 -

1/2 B	H	A	Vol. (ft³)
23.5	59	1385	
30.5	77	2350	
36	92	3310	
38	95	3610	
41.5	105	4360	
48	122	5820	
56.5	144	8150	
60	152	9100	
63	161	10150	
65	166	10900	
65	167	10850	
64	164	10500	
61.5	157	10250	
59	150	8850	
56	142	7940	
53	135	7150	
51	130	6630	
49	125	6120	
48.5	123	5970	
48	122	5870	
47	120	5630	
42	106	4450	
26.5	65	1740	
24	60	1440	
24	60	1440	
24	60	1440	
16.5	43	710	
15.5	40	620	
14.5	36	522	
12.5	22	270	

157,493 (8/27) = 46,700 CY

① [24(20)(8/27)] 19 = 2710 V = 26,700

② [37(30)(8/27)] 11 = 3620



- 6330

V_T 21,370

J. F. CABELLERIE, P.E.
 23 GREEN STREET
 HUNTERTON, N. Y.

TRUMBULL DAM

REQUINNECK RIVER DAM CON.

AMBURSEN DAM ESTIMATE

PRECAST SLAB PANELS

B	H	$\sqrt{B^2 + H^2} = L$
28	35	44.5
28	35	44.5
42	53	67.5
52	68	88
57	71	91
64	81	102
76	98	120
94	120	153
101	128	163
106	137	173
110	142	180
108	140	177
103	133	168
98	126	160
92	113	149
86	111	140
82	106	133
78	101	127
77	99	126
77	98	125
75	96	122
64	82	102
32	41	52
28	36	46
28	36	46
28	36	46
14	19	23.5
11	16	18
9	12	15
5	8	9.5
2352		3013 LF.

$$A = 3013(23.5) = 73,800 \text{ SF}$$


J. F. CABELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE
PERIODIC RIVER BASIN, CONN.
AMBURSEN DAM ESTIMATE

JOINT TREATMENT (AT PRECAST UNITS)

$$\frac{3013}{3} = 1005 (23.5) + 3013 (2) + 30 (23.5) =$$
$$= 30,400 \text{ LF}$$

SPILLWAY (CELLULAR DAM BY PROPORTIONS)



1. CANTILEVER FORMS = 1100 SF

2. CONCRETE = $860 (.84) = 725 \text{ CY}$

3. REINF STL = $15 (.84) = 12.6^T$ SAY 13^T


4. FINISHING = $9600 (.84) = 8100 \text{ SF}$

5. CURING = 8100 SF

J. F. CARROLL, INC., INC.
23 GREEN STREET
HUNTINGTON, N. Y.

MAUNDULL DAM
FEARHUNCK RIVER BASIN CONNL.
AMERSON DAM ESTIMATE

ROCK EXCAVATION



$$30 \times 30 (9) (5) / 27 = 1500 \text{ CY}$$

$$1627 (9) (1) / 27 = 550 \text{ CY}$$

STARTER FTGS

$$9.4 (22) (29) (4) / 27 = 900 \text{ CY}$$

$$\underline{2950 \text{ CY}}$$

FOUNDATION FORMS

$$[900(2) + 1627(2) + 30(9)(2)] 3 = 17,400 \text{ SF}$$

$$247(22)(2) - 22(2)(1)(27) = 8,660 \text{ SF}$$

$$\text{SLOPING FORM ADD } 30\% \text{ OF } 8660 = 2,400 \text{ SF}$$

$$\underline{28,660 \text{ SF}}$$

HAND CLEANING:

$$(1627 + 900)(9) + 9.4(22)(30) = 29,00 \text{ SF}$$

REINF STL (DWLS)

$$\#9 \text{ @ } 2' \times 8'-0" (2527) = 90,700 \# = 40^T$$

3.4

CONCRETE SUMMARY

BUTTRESS STEMS	40370 CY
" FTGS	4570 CY
STARTER FTGS	2350 CY
	<u>47,290 CY</u>

PLANT EQUIPMENT

BORROW OPERATION	\$ 72,000
AGGREGATE PROD.	128,000
BATCH PLANT	437,000

ASSUME: 6 BAGS OF CEMENT / CY
AGGREGATE - 3200 # / CY

CEMENT REQUIREMENT

$$47,290 (6)(94) = 25,800,000 \# = \underline{12,900 T.}$$

AGGREGATE REQUIREMENT

$$47,290 (1.6 T) = \underline{75,700 T.}$$

		MAT.	LABOR	TOTAL
1. BORROW OPER.	80,000 T	.90	.29	1.19
2. AGG. PROD.	76,000 T	1.69	.34	2.03
3. CONC. BATCH	47,300 CY	9.30	1.75	11.05

- 1. 80,000 (1.19) = 95,200
- 2. 76,000 (2.03) = 154,000
- 3. 46,000 (11.05) = 510,000
- 4. CEMENT 12,900 (27.20) = 351,000


$\$ 1110,200$
 READY MIX 46,000 (22.50) = $\$ 1,035,000$
 $\$ 75,200$

SAVING IF
READY MIX
IS USED

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUSS
REQU...
AMERICAN DATA ESTIMATE

SLIDING FORMS



$a = 30 = 240 \text{ SF}$

$b = [2527 + 30(30)] \cdot 2 = 6854 \text{ SF}$

$c = \text{SEE END BULKH'D} = 7094 \text{ SF}$

FORM - MASSIVE HEAD
BUTTRESS. EST.

SAY 7100 SF

YOKES - STEM (SIDES a & b)


1 - 30	7 - 22	12 - 16
2 - 30	8 - 21	13 - 11
3 - 30	9 - 20	14 - 9
4 - 30	10 - 19	15 - 7
5 - 30	11 - 18	16 - 4
6 - 26		

TOTAL = 323

(SIDE C) $2 \times 30 = 60$

JACK RODS = 50,000 LF.

DECKS & SCAFFOLDS



$$\text{MAIN DECK} - 5[(2527)] + [22(29)]20 = 25,395 \text{ S.F.}$$

$$\text{SCAFFOLDS} - [2(2527) + 8(2)(30)] 2' \text{ WIDE} = 11,100 \text{ S.F.}$$

RAILINGS & LADDERS

$$\text{RAILINGS} - (2527)2 + 22(29)(2) = 6340 \text{ LF}$$

$$\text{LADDERS} - 260 \text{ LF}$$

$$\text{TOTAL} = 6600 \text{ LF}$$

HYDRAULIC PIPING

$$2527(2) + 323(2)(10) = 11,600$$

TOPPING OUT RODS

$$3(2)(60) = 360$$


J. F. CARROLLING, Inc.
23 GREEN STREET
HUNTINGTON, N. Y.

TRUMBULL LAKE

REDUNDANT WATER MAIN, CONJ

AMBUSEMENT ESTIMATE

FINISH & CURING



$$a = 8 (2360) = 18,880$$

$$b = 8 (3020) = 24,160$$

$$c = 156,000 (2) = 312,000$$

354,040

SAY = 355,000 SF

PRECAST SLAB SEAT

$$3013 (2) = 6026 LF$$

SAY 6100 LF

PRECAST CURB AND GUTTER

COST OF PRECAST (VARIES)

\$ 24.00 / ϕ' @ BOTTOM
 TO 8.00 / ϕ' @ TOP
 $\$ 32.00 / \phi' / 2 = 16.00 / \phi'$ AVERAGE

MAXIMUM WEIGHT

$\frac{4 \times 3 \times 26 \times 4^2}{27} = 46^k = 2.3 \text{ TONS MAX}$

(WEIGHT DECREASES AS REACH INCREASES)

PLACING RATE

$3 \times 26'' \times 3 / \text{hr} \times 8 \text{ hr} = 1,880 \phi' / \text{DAY}$

LQT OF OPERATION:

$\frac{73,800 \phi'}{1,880} = 39 \text{ DAYS}$

SAY 8 WEEKS

PLACING CREW

1 FOREMAN	10.70
6 ERECTORS	61.20
4 FINISHERS	35.60
2 HELPERS	11.20
1 CRANE OPER	8.60
1 OILER	6.85

$\$ 134.15 / \text{hr}$

TOTAL COST = $\$ 134.15 \times 8 \times 40 = 43,000$

COST PER SQ. FT :

$\frac{\$ 43,000}{73,800} = .58 \phi' / \phi'$

SAY 60 ϕ' / ϕ'

J. E. CAMPBELL, P.E.
 25 CLEON STREET
 BIRMINGHAM, N. Y.

TRUMBULL LAKE DAM
 REDDONNOCK RIVER BASIN CONN.
 AMBULEN DAM

CLASSIFICATION	#	HR RATE INC. FR. BENEFITS	COST/SHIFT 5/8	COST/SHIFT 16/8
CONV. OPER.	1	7.75	70	124
HOIST OPER.	3	3.60	234	415
JACK OPER.	2	8.00	144	256
CARPENTER	6	9.00	488	868
ELECTRICIAN	1	8.28	75	132
FIN. FOREMAN	1	9.37	85	150
FINISHERS	4	8.87	319	568
FIN. HELPERS	2	7.15	129	228
LABORERS:				
FOREMAN	1	6.10	55	98
PLACING	11	5.60	554	985
VIBRATION	3	5.60	151	269
CURING	4	5.60	202	358
IRONWORKERS	6	10.20	—	—
CRANE OPER.	2/3	8.60	52	92
OILER	2/3	6.85	73	41
IRONWORKER FOREMAN	1	10.70	—	—

2631

4584

102 SHIFTS x 2631 = 268,400

6 SHIFTS x 4584 = 27,500

\$ 295,900

COST AND FEASIBILITY STUDY
ALTERNATE DESIGNS TO PERMIT USE
OF SLIP FORM AND OTHER TECHNIQUES
TO MAXIMIZE ECONOMIES

BOOK AC4

APPENDIX: CELLULAR DAM
CALCULATIONS AND COST STUDIES

BOOK AC-4 - APPENDIX: CELLULAR DAM, CALCULATIONS AND COST STUDIES

- 1 Sketches AR-401 through -411
- 2 Sketches AD-S401 through -S414

J. F. CAMELLERIE, P.E.

23 GREEN STREET
HUNTINGTON, N. Y.


DATE: JULY 15/72 REV.

SKETCH # AR

TRUMBULL LAKE DAM

REGUCCANOCK RIVER BASIN, CONN

GILL DAM STUDY




J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH# AR-400

TRUMBULL LAKE DAM
REGUONNOCK FIVER BASIN, CONN
CELL DAM STUDY



BASE LENGTH = 80'-0"
 STEM = 2'-6"

1/ C.G. OF CONC + CELL FILL

A/ HEAD SECTION

$$\left(\frac{35.5 \times 15 \times 150}{80} - \frac{12.5 \times 28 \times 50}{17.5} \right) \times 135' = \underline{8450^k}$$

B/ STEM (INCL. BASE)

$$2.5 \times 44.5 \times 150' \times 137.5 = \underline{2290^k}$$

C/ HEAD FOUNDATION

$$35.5 \times 15' \times 5' \times .15^k = \underline{400^k}$$

D/ C.G. OF A,B,C

$$\frac{(8,450 + 400) \times 62.25' + 2,290 \times 22.25'}{11,40} = \underline{z = 54'}$$

8850
 2290
 11140

2/ WATER PRESSURE

$$H = 135' \quad b = 15'$$

$$P_w = \frac{62.5 \times 135^2 \times 15}{2} = \underline{8550^k}$$

3/ C.G. OF BASE

$$\frac{533 \times 62.25 + 111 \times 22.5}{644} = \underline{y = 55.5}$$

33200
 2500
 35700

J. F. CAMPBELL, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE: 10/15/77 REV. SKETCH# AR-403
TREMBULL LAKE DAM
DEQUONNOCOK RIVER BASIN, CONN.
CELL DAM STUDY

E) RESISTANCE AGAINST OVERTURNING

FORCE	MOMENT ARM	MOMENT "TOE"	$\frac{M_{CB}}{M_W} = 1,56$
$W_{CB} = 11,140^K$	54'	+ 602.000	
$P_W = 8,550^K$	45'	- 385.000	
RIGHTING MOMENT = 217.000 $1K$			

PROVIDE PROPER DRAINAGE TO ELIMINATE UPLIFT

STRESS ANALYSIS

$$\sigma = \frac{W}{A} \pm \frac{M \times Y}{I}$$

$$W = 11,140^K$$

$$A = 644$$

$$M_{CG} = \frac{11140 \times 1,5' + 385000}{16,700} = 401,700^K$$

$$\begin{aligned} &+ 533 \\ &+ 111 \\ &= 644 \end{aligned}$$

$$Y_{1,2} = 55,5, 24,5$$

$$I = \frac{15 \times 24,5^3 + 15 \times 55,5^3 - 12,5 \times 44,5^3}{3}$$

$$= \frac{15 \times (14706 + 170,953) - 12,5 \times 88121}{3} = \frac{2720,000}{3} - \frac{1,100,000}{3} = 560,000^4$$

$$\sigma_{TOE} = \frac{11,140}{644} + \frac{401,700 \times 55,5}{560,000} = 17,3 + 39,8 = 57,1^K/SF = \underline{\underline{396 PSI}}$$

$$\sigma_{HEEL} = 17,3 - 17,6 = - 0,3^K/SF = \underline{\underline{- 2 PSI}}$$

J. F. CAMILLONE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15/72 REV.


SKETCH# AR-404

TRUMBULL LAKE DAM

REQUINNOCK RIVER BASIN, CONN.

CELL DAM STUDY

ALTERNATE: BASE LENGTH = 90'-0"



1) C.G. CONC. + CELL FILL
A) HEAD SEC.
8,450 K

B) STEM INCL. BASE
 $2.5 \times 54.5 \times 150 \times 137.5 = 2810^k$

C) HEAD FOUNDATION = 400 K

D) C.G. OF A, B, C.

$$\frac{8850 \times 72.25' + 2810 \times 27.25'}{11660} = z = 61.5'$$

8850
2810
11660
716500

2) WATER PRESSURE = 8550 K

3) C.G. BASE

$$\frac{533 \times 72.25 + 136 \times 27.25}{669} = y = 63.3'$$

533
+ 136
= 669
32600
3700
42300

E) RESISTANCE AGAINST OVERTURNING

FORCE	MOMENT ARM	MOMENT "TCE"
$W_{C.B.} = 11,660$	61.5'	+ 717,000
$P_W = 8,550$	45'	- 385,000
RIGHTING MOMENT		332,000 IK

$\frac{M_{CB}}{M_W} = 1.87$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM A.P. 11
REGUONNOCK RIVER BASIN, CT
CELL DAM STUDY

STRESS ANALYSIS (90 FT BASE)

$$S = \frac{W}{A} + \frac{M \times Y}{I}$$

$$W = 11,660 \text{ K}$$

$$A = 669$$

$$M_{CG} = 11,660 \times 1,8 + 385,000 = 406,000 \text{ K'}$$

$$Y_{1,2} = 63,3', 26,7'$$

$$I = \frac{15 \times 26,7^3 + 15 \times 63,3^3 - 12,5 \times 54,5^3}{3}$$

$$= \frac{15 \times (1,9034 + 253,636) - 12,5 \times 161,878}{4,090,000} = \frac{2,920,000}{690,000}$$

0,5

$$S_{TOE} = \frac{11,660}{669} + \frac{406,000 \times 63,3}{690,000} =$$

$$17,4 + 37,2 = 54,6 \text{ K/SF} = \underline{379 \text{ PSI} +}$$

$$S_{HEEL} \quad 17,4 - 15,7 = 1,7 \text{ K/SF} = \underline{12 \text{ PSI} +}$$

PROVIDE ADEQUATE DRAINAGE NEAR
UPSTREAM FACE TO COUNTER UPLIFT

UPLIFT (NO DRAINAGE)

$$\frac{135 + 20}{2} = \frac{155}{2} = 77'$$

$$U = 62,5' \times 35,5' \times 77' \times 15' = 2560$$

$$e_0 = \frac{20 + 270 \times 35,5}{3 \times 135} = 22,1$$

$$22,1 + 54,5 = 76,6'$$

$$M = 2560 \times 76,6 = \frac{196,000 \text{ K'}}{581,000}$$

-6-

$$\frac{M_{CG}}{M_W} = \frac{7176}{5810} = 1,24$$

J. F. CAMELLERIE, P.E.
23 GREEN STREET
BURLINGTON, N. Y.

DATE: JULY 15/72 REV.


SKETCH # 118-40

TRUMBULL LAKE DAM

REGUONHOOD BASIN, CONN

CELL DAM STUDY

ALTERNATIVE LAYOUT # 1




L. E. CAMPELLERIE, P.E.
25 WATER STREET
HUNTSINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH # AR-

TRUMBULL LAKE DAM
REGUONNOCK RIVER BASIN, CONN.
CELL DAM STUDY

ALTERNATE LAYOUT # 2



NOT USED

J. F. CAMBERIE, P.E.
 23 GIBBY STREET
 HUNTINGTON, N. Y.

DATE JULY 15/72 REV.


SKETCH# AR-410

TENNISBALL LAKE DAM

PHOENIX RIVER BASIN, CONN.

CIVIL DAM STUDY

SPILLWAY SLAB



$LL = 7' \times 62.5 = 440 \text{ "/SF} \quad (7' \text{ SURCHARGE})$

$DL = 2.5 \times 150 = 375 \text{ "/SF} \quad 815 \text{ "/SF}$

CLEAR SPAN = 14'-0" , 12'-6"

C.O.C. = 16'-6" , 15'-0"

AVER. SLAB THICKNESS = 2'-6"

$d = 26"$

J. F. CAMPELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE 07/15/11 REV.

SKETCH# AR-411

TRUMBULL LAKE DAM

DEERDUNOCK RIVER BASIN COMM.

CELL DAM STUDY

$$\begin{aligned} 1/ - M \text{ TRANSV.} &= \frac{W.L.^2}{20} = \frac{0.815 \times 16.5^2}{20} = 11.1''^K \\ 2/ + M \text{ TRANSV.} &= \frac{W.L.^2}{24} = 9.25''^K \\ 3/ - M \text{ LONG.} &= \frac{W.L.^2}{24} = 7.65''^K \end{aligned} \quad \left. \begin{array}{l} \\ \\ \end{array} \right\} \begin{array}{l} 16'-0'' \\ \\ 15'-0'' \end{array}$$

$$\underline{A_{S1}} = \frac{11.1}{1.16 \times 26} = 0.242''^2 = \# 4 @ 10'' \quad \underline{0.88 \# / SF}$$

$$\underline{A_{S2}} = \frac{9.25}{45.8} = 0.2''^2 \quad \# 4 @ 12'' \quad \underline{0.73 \# / SF}$$

$$\underline{A_{S3}} = \frac{7.65}{45.8} = 0.17''^2 \quad \# 4 @ 14'' \text{ SKY } \# 4 @ 15'' \quad \underline{0.59 \# / SF \times 2}$$

$$\underline{\text{TOTAL RE. / SF}} = 2.79 \# / SF$$

$$\underline{\text{TOTAL SLAB AREA}} = 38.5' \times 240' = \underline{9,300 \text{ SF}}$$

$$\underline{\text{TOTAL REINF.}} = 9,300 \times 2.79 = 26,000'' = \underline{13 \text{ TONS}}$$

$$\sim 30 \# / CY$$

CONC. VOL. OF SPILLWAY SLAB

$$9,300 \times 2.5 = 23,200 \text{ CF} = \underline{860 \text{ CY}}$$

COST STUDY SHEETS

CELLULAR DAM

AC4 -11-

FOUNDATION CONC.

UNDER SLIDE I	150' x 37' x 16' DP. AVE. =	89,000
II	180 x 37 x 14' =	93,000
III	150 x 37 x 8' =	45,000
		<u>227,000</u>

$$227,000 \text{ CF} / 27 = 8,400 \text{ c.y.}$$

UNDER STEM (I)	54' L x 6' x 16' DP. AVE. x 6 =	31,000
(II)	54 x 6 x 14' x 6 =	27,000
(III)	54 x 6 x 8' x 5 =	13,000
		<u>71,000</u>

$$71,000 \text{ CF} / 27 = 2,600 \text{ c.y.}$$

TOTAL FDN. CONC.

$$\text{UNDER SLIDES} = 8,400 + 2,600 = \underline{11,000 \text{ c.y.}}$$

FOUNDATION FORMWORK

FACE FORMS	480' x 2 =	960 LF
TRANSV. "	37' x 17' =	630 LF
STEM "	114' x 17' =	1940 LF

$$3,530 \text{ LF} \times 13 \text{ DP} = 45,890$$

ABUTMENT FORMWORK

$$\text{TOTAL FACE FORMING} = 38 \times 7.5 \times 60 \times 2.25 = 38,550$$

$$\text{FDN. FORMS} < 480 \times 7.5 \times 2.25 = 8,000 \text{ } \phi$$

$$\text{LIFT STARTERS} = 8,000 \text{ } \phi$$

$$\text{CANTILEVER FORMS} = 22,500 \text{ } \phi$$

$$\text{TRANSV. BULKHEADS} 8 \times 7.5 \times 30 = 1,800$$

HORIZONTAL JOINT TREATMENT

$$30 \times 60 \times 30' = 54,000 \text{ } \phi$$

LIFTS AV. DP

CONC. ABUTEMENTS

ABUTEMENT #	CONC. REQ'D
91	31
94	38
90	38
89	247
88	296
87	296
83	186
82	186
78	481
77	302
74	667
73	406
69	784
68	512
64	768
63	615
59	764
58	691
54	617
53	794
50	900
49	385
45	900
42	612
39	350
41	189
56	610
52	610
48 + MISC.	585 + 300
46	63
37	312
27	544
47	225
41	491
34	225
28 + 35	316 + 424

16,760 C.Y
TOTAL

J. F. CAMBERGIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE:	REV.	SHEET NO. AD-5403
TRUMBULL LAKE DAM		
PERQUONNOCK RIVER BASIN, CONN.		
CELLULAR DAM ESTIMATE		

ROCK EXCAVATION:

AREA OF ROCK EXCAV. (ORIG. DAM.) 45,510 SF = A₁

AREA OF REDUCED ROCK EXCAV. = A_R

$$[25(43+57+66+67+68+68+62+56+51+46+43+42+41+40+39+33)]$$

$$- [6(11+12+13+13+11+6)]$$

$$+ [6(4+5+10+11+13+14+14+16)]$$

$$+ [4.5(26+16)] + [7(480)] = \underline{\underline{- 24,180 SF = A_R}}$$

VOL. EXCAV.
 ORIG. DAM

21,330 SF = A₂

$$\text{ROCK EXC.} = \left(\frac{21,330}{45,510} \right) \left(\overset{\text{EST.}}{10,000} \right) = 4700 \text{ C.Y.}$$

ADD'L EXCAV.

$$\left\{ \left[\frac{23(30)}{2} + 37(6) + \frac{15(13)}{2} \right] 36 \right.$$

$$\left. + \left[\frac{3(54)(4.5)}{2} + \frac{3(54)(6)}{2} \right] \right\} = \underline{\underline{120 \text{ CY}}}$$

TOTAL ROCK EXCAV = 4820 CY

FOUNDATION GROUTING:

50,000 S.F.

HAND CLEANING:

A₁ = 45,510 SF

A_R = 24,180 SF

A₂ = 21,330 SF

$$\left(\frac{21,330}{45,510} \right) (71,060) = \underline{\underline{33,600 \text{ S.F.}}}$$

1) CONC. VOLUME NO SPILLWAY, CELL SEC.a) SEC. I & II

LENGTH = 160 FT EA.

HEIGHT = 117 FT

$$\text{CELL WALLS} = 3 \times 160' \times 117' \times 2.5' + 11 \times 82.5' \times 117' \times 2'$$

$$140,500 + 265,000 = 405,500 \text{ CF} = \underline{15,000}$$

$$\text{FILL} = 2 \times 216,200 = 432,400 \text{ CF} = \underline{16,000}$$

b) SEC. III

LENGTH = 160 FT

HEIGHT = 94 FT

$$\text{CELL WALLS} = \frac{15,000 \times 94}{117} = \underline{12,070 \text{ CY}}$$

$$\text{FILL} = 132' \times 14' \times 94' \times 2 = 348,000 \text{ CF} = \underline{12,900 \text{ CY}}$$

c) TOTAL CONCRETE

$$2 \times 15,000 + 12,100 = \underline{42,100 \text{ CY}}$$

d) TOTAL FILL

$$16,000 \times 2 + 12,900 = \underline{44,900 \text{ CY}}$$

TOTAL CONCRETE

MASS CONC.		STRUCT. CON	
FOUNDATION	11,000 C.Y.	}	CELLS... 42,100
ABUTMENTS	16,800 C.Y.		SPILLWAY --- 800
	<u>27,800 C.Y.</u>		ROADWAY --- 600
STRUCT. CONC	44,720 C.Y.		STONE TOWER --- 600
			PUMP HOUSE --- 700
		PET. WALL --- 300	

J. F. CAMPBELL, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JUL. 15 '72 REV.

SKETCH # AD-5485

TRUMBULL LAKE DAM

PEQUONNOK RIVER BASIN

CELL DAM STUDY

CEMENT & FLYASH REQUIREMENTS

EXTERIOR CONCRETE

$$27,800 \text{ CY} \times \frac{1.83 \text{ CWT}}{20} = 2550 \text{ TONS}$$

STRUCTURAL CONCRETE

$$44,720 \text{ CY} \times \frac{5.64 \text{ CWT}}{20} = \frac{12650 \text{ TONS}}{15,200 \text{ TONS}}$$

FLYASH

$$27,800 \text{ CY} \times \frac{.78 \text{ CWT}}{20} = 1,100 \text{ TONS}$$

AGGREGATE REQUIREMENTS (BORROW)

$$\begin{array}{r} 72,500 \text{ CY} \times 1.85 \text{ TONS} = 134,000 \text{ T} \\ \text{CELL FILL } 45,000 (1.85) = 83,500 \text{ T} \\ \text{SITE WORK} \quad \quad \quad 9,000 \text{ T} \\ \hline 226,500 \text{ T} \\ \text{SLIP FORM CONC } (42,100)(1.85) = 78,000 \text{ T} \\ \hline 148,500 \text{ T} \end{array}$$

J. F. CAMELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15, 1972 REV.

SKETCH# AD-5406

TRIMMICK LAKE DAM

DECOQUICK RIVER BASIN, CANN.

CELL DAM - COST STUDY

QUARRY OPERATION 1600 TONS /SHIFT

STRAIGHT SHIFT \$.29 /TON

SHIFT COST BASED ON 24 HR PRODUCTION /DAY

FOREMAN	95 ⁵⁰	
DRAWLINE OPER.	77 ⁷⁵	
1 OILER	62 ¹⁰	
1 SPOTTER	50 ¹⁰	
	<hr/>	275.75

SUPPLIES 40⁰⁰

AGGREGATE HAUL

4 TRUCK DRIVERS	191 ⁰⁰	231.00
	<hr/>	

\$ 506.75

\$ 0.32 /TON

J. F. CAMBERLIERE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15, 1972 REV.

SKETCH# AD-6407

TRUNDLE LAKE DAM

ROCKAWAY RIVER BASIN, CONN.

CELL DAM - COST STUDY

AGGREGATE PRODUCTION (1580 TONS / SHIFT)

STRAIGHT SHIFT \$.34 / TON

SHIFT BASED ON 24 HR PRODUCTION \$.39 / TON

MIX PLANT 1000 CY / SLIP SHIFT

STRAIGHT SHIFT \$ 1.75 / CY

SHIFT BASED ON 24 HR PRODUCTION

LABOR 721⁰⁰ (641 x 98)

MISC. MAT. 300⁰⁰

\$ 1021⁰⁰

$\frac{1021^{00}}{1000} = \$1^{00} / \text{CY}$

J. F. CAMELLERIE, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH# AD-5

TRUMBULL LAKE DAM

PEQUODNOCK RIVER BASIN, CONECT

CELLULAR DAM

SLIDING FORMS

UPSTREAM FACE	_____	480 LF
DOWNSTREAM FACE	$480 - (15 \times 5 + 2 \times 3.75) =$	400
STEM ENDS	_____	80
CELL INSIDE (HORIZ)	$12.5 \times 32 \times 4 =$	1600
CELL INSIDE (VERT)	$14 \times 2 \times 64 =$	1800
STEM SIDES	$2 \times 54 \times 17 =$	1840

6200 LF

$$6200 \text{ LF CONTACT SURFACE} / 2 = \underline{3100 \text{ LF FORM}}$$

YOKES (3T) 10/BAY X 32 BAYS = 320 YOKES

14/STEM X 15 STEM = 210

7/STEM X 2 STEM = 14

END BAYS = 8

552

SAY 560 YOKES

JACK ROD (3T)

10/BAY X 20 BAYS = 200

14/STEM X 10 = 140

7/STEM X 1 = 7

END = 4

$351 \times 117' \text{ HIGH} = 41,200 \text{ LF.}$

552 TOTAL

-351

201 LEFT X 94' HIGH = 18,800 LF

60,600 LF

J. F. CAMMERER, P.E.
 23 GREEN STREET
 HUNTINGTON, N. Y.

TRUMBULL LAKE DAM
 HUDONSDOWN RIVER BASIN, CONN.
 CELLULAR DAM

<u>DECKS</u>	CELLS	12.5 x 14 x 2 x 32 =	11,300 ϕ '
	UPSTREAM	2'W x 430' L _G =	960
	DOWNSTREAM		960
	STEM SIDES	2 x 54 x 2 x 17 =	3,680
			<u>16,900 ϕ'</u>

<u>SCAFFOLDS</u>	UPSTREAM	2 x 430	960 ϕ '
	DOWN ST.		960
	STEM SIDES		3,680
			<u>5,600 ϕ'</u>

<u>RAILINGS + LADDERS</u>	480	
	480	
54 x 2 x 17 =	1,840	
	<u>2,800 LF</u>	SAY 3000 LF

<u>HYDRAULIC PIPE</u>	L.F. FORM =	3100 LF
	560 JACKS x 10' / JACK =	5600
		<u>8,700 LF</u>

<u>TOPPING-OUT RODS</u>	320 YOKES x 2 / YOKE =	640
	8 x 2 =	16
	224 x 1 / YOKE =	224
		<u>880</u>

J. F. CAMELLINE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15 '72 REV.

SKETCH PAD - 5/11

TIMMAYALL LAKE DAM

ROCKY MOUNTAIN RIVER BASIN, CONN.

CELLULAR DAM.

SLIDE CREW

TOTAL CONC. IN SLIP. = 42,100 CY.
MAX. CONC. IN 1 SLIP = 19,000 C.Y.

14 DAYS x 3 SHIFTS/DAY = 42 SHIFTS

$\frac{42,100}{42 \times 8} = 125 \text{ CY/HR.}$

CLASSIFICATION	#	HR. RATE INCL. FRINGE BENEFITS	COST / SHIFT 9/8	
HOIST OPER.	1	8.60	77	
JACK OPER.	3	8.00	216	
CARPENTER	1	9.00	81	
ELECTRICIAN	2/3	8.25	50	
FIN. FOREMAN	1	9.37	84	
FINISHERS	6	8.87	477	
FIN. HELPER	2	7.15	129	
LABORERS:				
FOREMAN	1	6.10	55	* 1 TOP
PLACING #	13	5.60	1260	MAN, 4
VIBRATING	8	5.60		CONV. MEN,
CURING	3	5.60		8 SHOVEL
CRANE OPER.	2/3	8.60	52	1 UTILITY
OILER	2/3	6.85	41	
CONV. OPER	3	7.75	209	
			<u># 2731</u>	

42 SHIFTS x # 2731 = # 114,700

J. F. CAMPELLERIE, P.E.
23 GREEN STREET
HUNTINGTON, N. Y.

DATE JULY 15/72 REV.

SKETCH # AD-5411

TRUMPULL LINE DAM

PEQUONNOCOK RIVER BASIN, CONN.

CELLULAR DAM

FINISH UPSTREAM $150(117) + (180 \times 117) + (150 \times 94) =$
 $17,600 + 21,100 + 14,100 = \underline{\underline{52,800 \phi'}}$

DOWNSTREAM $\underline{\underline{52,800}}$

STEM SIDES $54 \times 2 \times 11 \text{ STEMS} \times 117' = \underline{\underline{140,000}}$

$54 \times 2 \times 6 \quad \times 94 = \underline{\underline{61,000}}$

$\underline{\underline{306,600 \phi'}}$

VERTICAL KEYS $3 \text{ KEYS} \times 117 = 352$

$3 \quad \times 94 = \underline{\underline{283}}$

$\underline{\underline{735 \text{ LF} \times 2 = 1470 \text{ LF}}}$

JAY FOOTING $32 \times 3 = 96$

$16 \times 4 = \underline{\underline{64}}$

$\underline{\underline{160 \times 10' = 1600 \text{ LF}}}$

SPILLWAY SLAB FINISH + CURBING

$40' \text{ W} \times 240' = \underline{\underline{9600 \phi'}}$

REINFORCING STEEL

CELL = $24,000 \text{ cu ft} \times 70\# = 1,680,000\#$

$= 840 \text{ TONS}$

SAY 900 TONS

CONVEYOR SYSTEMS

CONVEYOR SYSTEM (LOWER SYSTEM)

FEEDER CONVEYOR, PLANT TO TRESTLE	1
SIDE DISCHARGE CONVEYOR ON TRESTLE	1
CONVEYORS TO MONOLITHS	<u>1</u>
	3

3 OPERATORS INCLUDED ELSEWHERE

CONVEYOR REQUIREMENTS: # 16"
 860 LF @ \$145,000 (1.67) = 100,000
 LESS SALVAGE = 50,000
 \$50,000

ERECTION = 5,000

(UPPER CONVEYOR SYSTEM)

MATERIAL TOWER TO DIST CONV.	2x 40' = 80L
LONG L. CONVEYORS	3x 180 = 540L
STEM CONVEYORS	7x 60 = <u>420L</u>
	1040L

1040 LF @ 105 = 109,000
 RAILS & ACC. 11,000
 SIDE DISC 200 (12) = 9,000
 129,000
 Less SALVAGE = 64,000
 \$65,000

(920 AV.
 (830 MIN)

ERECTION :

\$6400 X 3 = \$19,200 (3 SETS)

ADD'L SET CONVEYORS

830 @ 105 = 87,500
 RAILS & ACC = 8,500
 SIDE DISC. 9,000
 \$105,000
 LESS SALV. 50,000
 \$55,000

\$120,000

MONTH YEAR	CONSTRUCTION SCHEDULE - CELLULAR DAM											
	JAN.	FEB.	MAR.	APR.	MAY	JUNE	JULY	AUG.	SEPT.	OCT.	NOV.	DEC.
1972										STRIPPING		
										PROCUREMENT		
1973										DIVERSION-STAGE I		
										STRIPPING PLANT ERECTION		
										SLIDE SPILLWAY		
										ADUTMENTS		
1974										FOUNDATION		
										ROAD & MISC.		
										* C.D. & E.		

* CLEAN-UP, DEMOBILIZATION & ENVIRONMENT
CONTRACTURAL COMPLETION DATE DEC. 1974

POUGHKEEPSE RIVER BASIN DAM
ACCELERATED CONST. SCHED. CELLULAR DAM

ACCELERATED CONSTRUCTION SCHEDULE - CELLULAR DAM

MONTH YEAR	JAN.	FEB.	MAR.	APR.	MAY	JUNE	JULY	AUG.	SEPT.	OCT.	NOV.	DEC.
1972										STRIPPING		
										PROCUREMENT		
1973	STRIPPING	PLANT ERECTION	FOUNDATION	SLIDE	SPILLWAY							
		DIVERSION - STAGE I	ABUTMENTS	ROAD & MISC.								
	PROCUREMENT					DIVERSION STAGE II						
1974			* C. D. & E.									

* CLEAN-UP, DEMOBILIZATION & ENVIRONMENT
CONTRACTURAL COMPLETION DATE MAY 1974

AD 414

-25-

In accordance with ER 70-2-3, paragraph 6c(1)(b), dated 15 February 1973, a facsimile catalog card in Library of Congress format is reproduced below.

Camellerie (J. F.), Consulting Engineer.

Cost and feasibility study; alternate designs to permit use of slip form and other techniques to maximize economies, Trumbull Lake Dam, Pequonnock River Basin, Connecticut; final report, by J. F. Camellerie, Consulting Engineer. Vicksburg, U. S. Army Engineer Waterways Experiment Station, 1974.

1 v. (various pagings) illus. 27 cm. (U. S. Waterways Experiment Station. Miscellaneous paper C-74-15)

Prepared for U. S. Army Engineer Division, New England, Waltham, Massachusetts.

1. Concrete. 2. Concrete costs. 3. Dam construction. 4. Slip form techniques. 5. Trumbull Lake Dam. I. U. S. Army Engineer Division, New England. (Series: U. S. Waterways Experiment Station, Vicksburg, Miss. Miscellaneous paper C-74-15)
TA7.W34m no.C-74-15