

TECHNICAL REPORT HL-87-15

LIFT GATE FOR LOCKPORT LOCK ILLINOIS WATERWAY

Hydraulic Model Investigation

by

Deborah R. Cooper

Hydraulics Laboratory

DEPARTMENT OF THE ARMY Waterways Experiment Station, Corps of Engineers PO Box 631, Vicksburg, Mississippi 39180-0631





October 1987 Final Report

Approved For Public Release, Distribution Unlimited

Prepared for US Army Engineer District, Rock Island Rock Island, Illinois 61204-2004

US-CE-C Property of the United States Government

TA7 W34 no. HL- 87-15 C.4

_Unclassified			
SECURITY CLASSIFICATION	OF	THIS	PAGE

	DOCUMENTATIO	N PAGE			Form Approved OMB No. 0704-0188		
a. REPORT SECURITY CLASSIFICATION Unclassified		16 RESTRICTIVE MARKINGS					
a. SECURITY CLASSIFICATION AUTHORITY		3 DISTRIBUTION / AVAILABILITY OF REPORT					
b. DECLASSIFICATION / DOWNGRADING SCHED	DULE	Approved unlimite		c release	e; distribution		
PERFORMING ORGANIZATION REPORT NUM	BER(S)	5. MONITORING	ORGANIZATION	N REPORT NU	JMBER(S)		
Technical Report HL-87-15							
a. NAME OF PERFORMING ORGANIZATION USAEWES Hydraulics Laboratory	6b. OFFICE SYMBOL (If applicable) WESHS-S	7a. NAME OF N	ONITORING OR	GANIZATION			
PO Box 631 Vicksburg, MS 39180-0631	interior of	7b. ADDRESS (C	ity, State, and 2	ZIP Code)			
a. NAME OF FUNDING/SPONSORING ORGANIZATION USAED, Rock Island	8b. OFFICE SYMBOL (If applicable) NCRED	9. PROCUREMENT INSTRUMENT IDENTIFICATION NUMBER					
c. ADDRESS (City, State, and ZIP Code)		10. SOURCE OF	FUNDING NUM	BERS			
PO Box 2004 Clock Tower Building Rock Island, IL 61204-2004		PROGRAM ELEMENT NO.	PROJECT NO.	TASK NO.	WORK UNIT		
1. TITLE (Include Security Classification)				-			
Lift Gate for Lockport Lock, 1	Illinois Waterway	; Hydraulic	Model Inv	estigatio	no		
2. PERSONAL AUTHOR(S) Cooper, Deborah R.		1000 mm					
3a. TYPE OF REPORT 13b. TIME	COVERED 1983 TO 1984	14. DATE OF REP	ORT (Year, Mon er 1987	th, Day) 15	AGE COUNT		

	COSATI	CODES	18. SUBJECT TERMS (Continue on revers	e if necessary and identify by block number)
FIELD	GROUP	SUB-GROUP	Dynamic he		
			Hydraulic		Vibootiona
		1		ift gates	Vibrations
The closure section area, and acting of hydrauli became a loads per model in by the L	of the loo model of t id lock cha on the lift ic load ind pproximate aked and b ivestigatio	Ift gate for the chamber. The lock chamber amber was used ing cables and the cables and the cables and the cables and the cables and the cabl	This will involv ber, guard and s d to study magni nd the flow cond e exposed gate h 60 percent of th ease with increa draulic loads le	k will be eq e operation ervice gate tude and fre itions over eight increa e pool heigh sing exposed ss than the Although s	uipped to operate during emergency under dynamic heads. A 1:24-scale sills, the guard gate, approach quency of the hydraulic forces the gate. Tests indicated that the sed until the exposed gate height t. At this point, the hydraulic gate heights. This hydraulic calculated hydraulic loads provide ome gate vibrations were indicated he total load.
		LITY OF ABSTRACT		Unclassif	
I UNCLAS		ED SAME AS		Unclassif	
ZZa. NAME C	SIFIED/UNLIMIT	ED SAME AS	RPT. DTIC USERS	Unclassif 22b TELEPHONE (ied
ZZa. NAME C	SIFIED/UNLIMIT	ED SAME AS		Unclassif 22b TELEPHONE (ied (Include Area Code) 22c. OFFICE SYMBOL

PREFACE

The model investigation reported herein was authorized by the Office, Chief of Engineers, US Army, on 15 August 1983 at the request of the US Army Engineer District, Rock Island (NCR).

The study was conducted during the period August 1983 to February 1984 in the Hydraulics Laboratory (HL) of the US Army Engineer Waterways Experiment Station (WES), under the direct supervision of Messrs. H. B. Simmons and F. A. Herrmann, Jr., former and present Chiefs, HL, respectively, and under the general supervision of Messrs. J. L. Grace, Jr., Chief, Hydraulic Structures Division, and N. R. Oswalt, Chief, Spillways and Channels Branch. The project engineer for the model study was Mrs. D. R. Cooper, assisted by Messrs. B. P. Fletcher, E. L. Jefferson, R. Bryant, Jr., and T. L. Kirkpatrick, all of the Spillways and Channels Branch, and R. H. Floyd, S. Bell, and L. B. Smithhart, Instrumentation Services Division, WES. The gate was constructed by Mr. R. L. Blackwell, Engineering and Construction Services Division, WES. This report was edited by Mrs. Nancy Johnson, Information Products Division, under the Inter-Personnel Agreement Act.

During the course of the investigation, Messrs. D. McCully, R. Beach, J. A. Aidala, and J. Bartek, NCR, visited WES to discuss the program and results of model tests, observe the model in operation, and correlate these results with design studies.

COL Dwayne G. Lee, CE, is the Commander and Director of WES. Dr. Robert W. Whalin is Technical Director.

CONTENTS

	Page
PREFACE	. 1
CONVERSION FACTORS, NON-SI TO SI (METRIC)	
UNITS OF MEASUREMENT	3
PART I: INTRODUCTION	5
Prototype	
Purpose of Model Study	
Presentation of Data	
PART II: MODEL AND TEST PROCEDURE	. 7
DescriptionAppurtenances and Instrumentation	
Scale Relations	
Test Procedure	
PART III: TESTS AND RESULTS	12
Guard Gate Sill	12
Cables Comparison of Computed and Measured Water Loads	12
Acting on the Hoist Cables	14
Guard Gate	15
PART IV: CONCLUSIONS	16
TABLES 1-6	
PHOTOS 1-3	
PLATES 1-12	



CONVERSION FACTORS, NON-SI TO SI (METRIC) UNITS OF MEASUREMENT

Non-SI units of measurement used in this report can be converted to SI (metric) units as follows:

Multiply	Ву	To Obtain		
cubic feet	0.2831685	cubic metres		
degrees (angle)	0.01745329	radians		
feet	0.3048	metres		
inches	25.4	millimetres		
miles (US statute)	1.609347	kilometres		
pounds (force)	4.448222	newtons		
pounds (mass)	0.4535924	kilograms		
pounds (mass) per cubic foot	27.6799	grams per cubic centimetre		
square feet	0.0929304	square metres		
tons (2,000 pounds, mass)	907.1847	kilograms		






Figure 1. Vicinity map




Figure 2. Lockport Lock lift gate

LIFT GATE FOR LOCKPORT LOCK ILLINOIS WATERWAY

Hydraulic Model Investigation

PART I: INTRODUCTION

Prototype

1. Lockport Lock is located at river mile 291 on the Illinois Waterway, immediately west of the city of Lockport, Illinois (Figure 1). The lock is 600 ft* long by 110 ft wide and has a lift of 39 ft. The lock walls and sills are constructed of concrete masonry. Two submersible vertical lift gates, a guard gate and a service gate, are provided at the upper end of the lock. In addition, a shutter gate was located in the forebay upstream of the guard gate. The purpose of the shutter gate was to restrict flow of water through the lock during an emergency so that the guard gate could be raised into place. However, the shutter gate was removed in August 1984. The lower gates are of the miter type. Plate 1 presents the general layout and typical sections of the lock.

2. The two submersible-type lift gates are submerged on the downstream side of the sills when the gates are in the open position. The service gate is approximately 70 ft downstream of the guard gate. The two gates are iden-

tical in construction except that the guard gate is equipped with butterflytype filling valves that are necessary for the guard gate to function as an alternate to the service gate. The gates, consisting of four horizontal trusses, are horizontally framed. The horizontal trusses are framed into a vertical truss at each end. The skin plate is on the upstream side of the gate. The gates are operated by machinery located on overhead bridges carried by steel towers mounted on the lock walls (Figure 2). The weight of the gates is balanced by concrete counterweights suspended inside the framework of the towers. The gates are not provided with bearing rollers and thus cannot be operated under the flow of water. In the event an accident should occur

* A table of factors for converting non-SI to SI (metric) units of measurement is presented on page 3.

requiring closing of the gate under head, the gate could not be closed under the present system.

3. Both gates are in excellent condition. The lift towers are also in good condition. The chains for lifting the service and guard gates are a continuing and costly maintenance problem and will be replaced with cables.

Purpose of Model Study

4. The existing guard gate with its present lifting mechanism (electrically powered sprocket driving the lift chain of the counterweights) cannot be closed against a head of flowing water. The analysis of the new guard gate and service gate lifting mechanisms by the Rock Island District was presented in Design Memorandum No. 1* and Design Memorandum No. 2.** The model testing program was undertaken for the following reasons:

- To substantiate the theoretical analysis presented in Design a. Memorandum No. 2.
- To determine the lifting loads required to permit closing of the b. gate against a head of flowing water.
- c. To observe flow conditions over the gate.
- To determine the magnitude of the hydraulic forces and frequency d. of vibrations acting on the lifting cables with various gate openings and flow rates.

Presentation of Data

5. In the presentation of test results, the data are not provided in the order in which the tests were conducted. Instead, as each element of the gate and the gate lifting mechanism is considered, all tests conducted thereon are discussed. All model data are presented in terms of prototype equivalents. All tests are discussed in Part III.

* US Army Engineer District, Rock Island. 1982 (May). "General Design Memorandum, Illinois Waterway, Lockport Lock Major Rehabilitation," Design Memorandum No. 1, Rock Island, Ill.

** . 1983 (Jul). "Lift Gate Machinery Modifications; Illinois Waterway, Lockport Lock Major Rehabilitation," Design Memorandum No. 2, Rock Island, Ill.

PART II: MODEL AND TEST PROCEDURE

Description

6. The 1:24-scale model at the US Army Engineer Waterways Experiment Station (WES) (Figure 3) reproduced the 110-ft-wide lock chamber, the guard and service gate sills, a 300-ft-long section upstream of the lock chamber, and 400 ft of the lock chamber. The model gate was constructed of brass and simulated a prototype weighing 400,500 lb (dry weight). The trusses, skin plate, and walkway were reproduced to scale, and three roller bearings were attached at each end of the model gate to minimize friction in the gate slots (Figure 4). Model tests indicated that the friction forces were insignificant compared to the water loads on the gate.

7. The lock chamber was constructed of plywood, and the gate slots were fabricated of transparent plastic to allow observation of flow conditions in and around the gate slots. The gate lifting mechanism consisted of a cable at each end of the gate attached to load cells bolted into an aluminum channel that was suspended across the model (Figure 3 and Plate 2). Each model cable was sized to reproduce the elastic properties of the eight prototype cables proposed for each end of the gate.


Appurtenances and Instrumentation

Water used in the operation of the model was supplied by pumps, and 8. discharges were measured by means of venturi meters. Steel rails set to grade provided reference planes for measuring devices. Water-surface elevations were obtained with point gages. Load cells and an oscillograph recorder were used to measure and record the magnitude and frequency of the total forces acting on each end of the gate. Chart speed used during testing was 1 ips.


Scale Relations

9. The accepted equations of hydraulic similitude, based upon the Froudian relations, were used to express the mathematical relations between the dimensions and hydraulic quantities of the model and the prototype. General relations for transference of model data to prototype equivalents are presented in the following tabulation:

-7




a. Looking downstream



b. Looking upstream


Figure 3. 1:24-scale Lockport Lock lift gate model (Continued)





- c. Profile of breach
- Figure 3. (Concluded)

.



a. Upstream and plan views




Figure 4. 1:24-scale model of guard gate

Dimension	Ratio	Scale Relation
Length	$L_r = L$	1:24
Area	$A_r = L_r^2$	1:576
Velocity	$V_r = L_r^{1/2}$	1:4.899
Time	$T_r = L_r^{1/2}$	1:4.899
Discharge	$Q_r = L_r^{5/2}$	1:2,821.81
Weight	$W_r = L_r^3$	1:13,824
Force	$F_r = L_r^3$	1:13,824

Test Procedure

10. Tests were conducted in the model to measure loadings on the gate, to observe flow conditions over the gate, and to determine the magnitude and frequency of the hydraulic forces acting on the lifting cables with various gate openings and flow rates. In measuring the forces on the gate, pool elevations were held constant while the exposed gate height was varied. Tests were conducted to measure total head on the guard gate sill for discharges up to 30,000 cfs. Tests were also conducted to develop an equation for flow over the guard gate for any head on the gate and exposed gate height above the sill.

11. Test procedures were generally the same for all tests and consisted

of the following:

- a. Record test number, date, data recorder, and test conditions.
- b. Calibrate load cells.
- c. Raise gate to test position and allow upper and lower pools to stabilize.
- d. Record hoisting cable loads on the oscillograph.

- 11

- e. Record upper and lower pool elevations and other test conditions.
- f. Check load cell calibrations.

PART III: TESTS AND RESULTS

Guard Gate Sill

12. Tests were conducted to measure the total head on the guard gate sill for discharges up to 30,000 cfs. The water-surface elevation was measured using a point gage located 70 ft upstream of the guard gate sill while the gate was submerged. The velocity head of the approach flow in the section model was added to the water-surface elevation to determine the total head or energy representative of the upper pool in the prototype. An example calculation is presented and variables are defined in Plate 3. Rating curves of the breach due to the guard gate and the service gate sills (Plate 3) are presented in Plates 4 and 5. Data used to plot the curves in Plates 4 and 5 are presented in Table 1. A rating curve calculated by Rock Island District* is also shown in Plate 4.

Cables

13. Each model cable was sized to reproduce the elastic properties of the eight prototype cables proposed for each end of the gate. Tests were conducted to ensure that natural frequencies of the model cables would not influence the hydraulic force measurements. Natural frequency readings were recorded on the oscillograph for exposed gate heights of 0 and 3-18 ft in 1-ft

increments. The natural frequency of the model cables ranged from 20 Hz (unsubmerged) to 25 Hz (submerged). A comparison of the natural dynamic response of the model with the exciting hydraulic forces (2-4 Hz) indicated that the forces measured in the model would not be significantly affected by the natural frequency or damping characteristics of the model and related instrumentation. The gate hoisting cables were not subjected to a significant dynamic loading (less than 1.0 percent of total load measured and at a random frequency). Therefore, only maximum loads are tabulated in the tables and shown on the plots. A typical oscillograph record of natural frequency measurement is shown in Plate 6.

* US Army Engineer District, Rock Island. 1983 (Jul). "Lift Gate Machinery Modifications; Illinois Waterway, Lockport Lock Major Rehabilitation," Design Memorandum No. 2, Rock Island, Ill. 14. The water load F_W (Plate 3) acting on the gate and hoist cables was obtained by the following equation:

$$F_{W} = F_{T} - F_{S} \tag{1}$$

where

- F_W = maximum force due to water passing over gate (water load), 1b
- F_T = maximum total force measured in model cables, 1b
- $F_{S} = dry$ weight of gate minus weight of volume of water displaced by gate, 1b

15. Model tests for upper pools with elevations 10, 16, 18, and 25 ft above the guard gate sill were conducted for exposed gate heights of 0 and 3 through 18 ft. The first phase of testing was run with gate heights fixed. The second phase of testing was run while the gate was lifted at a rate of 2 fpm.

16. Each test with upper pool conditions fixed in the first phase of testing was repeated. The gate was raised to a given height and the pool was allowed to stabilize. The load cells were zeroed. The load (force) was measured and recorded on the oscillograph (Plate 7).

17. The gate was raised at a rate of 2 fpm in the second phase of testing and the forces recorded on the oscillograph concurrently. The pools were held constant while the gate was manually being lifted.

18. The water load increased as the exposed gate height d_r increased until d_r became approximately equal to 60 percent of the pool height. At

this point, the hydraulic loads peaked and decreased with increasing exposed gate heights (Plates 8-11). Data used to plot the curves in Plates 8-11 are presented in Tables 2-5. A maximum load of 73,400 lb occurred at $d_p = 6$ ft for the first phase and 70,300 lb at $d_p = 6$ ft for the second phase of testing with a 10-ft pool (Plate 8). The maximum loads increased to 133,900 lb at $d_p = 9$ ft during the first phase and 134,000 lb at $d_p = 9$ ft during the second phase of tests with a 16-ft pool (Plate 9). A maximum of 163,600 lb at $d_p = 10$ ft for the first phase and 164,000 lb at $d_p = 10$ ft for the second phase of testing the pool to 25 ft increased the maximum load of the first phase of testing to 319,400 lb at $d_p = 15$ ft (Plate 11). At the peak load condition, the water cascaded through the gate members rather than forming a definable nappe.

Comparison of Computed and Measured Water Loads Acting on the Hoist Cables

19. The water load F_W was calculated by Rock Island District to be approximately equal to the weight of water acting over the cross-sectional area of the top truss of the gate (see Figure 5).




Figure 5. Water-surface profile used for calculating F_W The equation used was

$$F_{W} = d_{g} \gamma A_{T} \gamma$$
 (2)

where

dg = depth of water relative to top of gate, ft Y = specific weight of water, 62.4 pcf

 A_T = cross-sectional area of top truss, ft

20. In the model, the members composing the top truss were simulated and water cascaded through the gate members as shown in Figure 6 and Photos 1-3.




Figure 6. Typical water-surface profile observed in the model

21. A comparison of d_g assumed by Rock Island District and d_g measured at WES indicated that the WES d_g value was less than the Rock Island District d_g value. Also, the maximum WES F_W values were about 28 percent less than the Rock Island District calculated F_W values.


Guard Gate

22. Tests were conducted to develop an equation for flow over the gate for any head on the gate and gate height above the sill. Discharge versus head on the gate for various depths of pool above the sill was plotted (Plate 12). Data used to plot the curves on Plate 12 are presented in Table 6. The following equation was obtained and may be used to calculate the discharge for free uncontrolled flow over the gate:

$$Q = 3.49 L H_g^{1.5}$$
 (3)

where

Q = discharge over the gate, cfs L = width of the gate, 110 ft H_g = distance from the upper pool to the top of the gate, ft



PART IV: CONCLUSIONS

23. The hydraulic model investigation of the Lockport Lock lift gate yielded hydraulic loads about 28 percent less than the calculated hydraulic loads provided by the Rock Island District. The measured depth of the gate under water, d_g (Plate 3), was less than that assumed by the Rock Island District in Design Memorandum No. 2.* The difference in d_g measured in the model and d_g used in the calculations may have caused the discrepancy between measured and calculated loads.


24. The water loads on the lifting cable increased from 73,400 lb with 10 ft of head on the gate sill to 322,900 lb with 25 ft of head on the gate sill. The lifting loads required to permit closing of the gate against a head of flowing water are dependent upon two variables: the amount of head on the gate sill H_T and the exposed height of the gate above the gate sill d_r .


25. Discharge coefficients were determined for computing the discharge through the structure with the lift gate in the lowered position, $d_r = 0$, and with the gate in various raised positions. The discharge coefficient was considerably lower with the gate lowered (2.86) than with the gate raised (3.49). This was attributed to the change in shape of the control weir with the gate lowered (guard gate sill shape) and with the gate raised (gate shape).

26. Although there was some gate vibration as indicated on the oscillograph record (Plate 7), the vibrations were random and small compared to the magnitude of the load.

* US Army Engineer District, Rock Island. 1983 (Jul). "Lift Gate Machinery Modifications, Illinois Waterway, Lockport Lock Major Rehabilitation," Design Memorandum No. 2, Rock Island, Ill.

Discharge cfs	Water- Surface e1*	<u>V</u> , fps	<u>v</u> ² /2g	V ² /2g + Water- Surface El	H _T , ft
0	558.00	0.00	0.00	558.00	0.00
5,000	564.29	1.29	0.026	564.32	6.32
7,500	566.42	1.82	0.052	566.47	8.47
10,000	568.10	2.33	0.084	568.19	10.19
12,500	569.64	2.80	0.121	569.76	11.76
15,000	571.37	3.22	0.161	571.53	13.53
17,500	572.57	3.65	0.207	572.78	14.78
20,000	573.79	4.06	0.256	574.05	16.05
22,500	574.75	4.47	0.310	575.06	17.06
25,000	575.90	4.85	0.365	576.27	18.27
27,500	576.77	5.23	0.425	577.20	19.20
30,000	577.44	5.63	0.492	577.93	19.93





* Vertical Datum (NGVD).

Table 2

Hoist Cable Loads

Y = 10 ft

		Phase I Testing										
		Te	st 1		Test 2							
d _r ft	d g ft	F _T lb	FS 1b	F _W 1b	d g ft	F _T 1b	F _S 1b	F _W 1b				
0	5.8	349,600	347,400	2,200	5.8	347,500	347,400	100				
3	3.0	373,100	347,400	25,700	2.8	366,100	347,400	18,700				
4	2.0	369,800	347,400	22,400	1.8	373,000	347,400	25,600				
5	-0.2	404,100	347,900	56,200	0	403,900	347,400	56,500				
6	-1.9	421,200	351,900	69,300	-1.7	424,500	351,100	73,400				
7	-4.6	410,800	356,900	53,900	-4.4	410,800	356,400	54,400				
8	-6.1	407,400	359,900	47,500	-5.9	410,800	359,400	51,400				
9	-7.8	400,600	363,400	37,200	-7.6	397,000	362,900	34,100				
10	-9.5	367,900	367,900	0	-9.3	366,400	366,400	0				

Pha	se II Testi	ng	Roc	Calculate	and a state of the
F _T lb	F _S lb	F _W 1b	d g ft	F _T 1b	F _W 1b
352,500	347,400	5,100		322,248	0
373,300	347,400	25,900	5.0	322,248	0
383,300	347,400	35,900	4.2	322,171	0
404,400	347,400	57,000	3.4	437,586	103,534
418,200	347,900	70,300	2.7	419,816	82,218
418,200	356,900	61,300	2.0	400,729	60,902
411,300	359,900	51,400	1.3	381,618	39,587
401,300	363,400	37,900	0.7	365,227	21,316
367,900	367,900	0	0	345,297	0

1.1

Table 3

Hoist Cable Loads

Y = 16 ft*

d g ft	F _T 1b	st 1 F _S	F		T	est 2		Die	and TT Testi	
ft	1	FS	F			est c		Phase II Testing		
40 F		_1b	F _W 1b	d g ft	F _T 1b	F _S 1b	F _W 1b	F _T 1b	F _S 1b	F _W 1b
12.5	365,500	347,400	18,200	11.3	369,500	347,400	22,100	362,900	347,400	15,500
6.4	400,600	347,400	53,200	6.4	393,600	347,400	46,200	400,900	347,400	53,500
4.2	431,700	347,400	84,300					428,600	347,400	81,200
4.1	431,700	347,400	84,300	3.4	435,000	347,400	87,600	432,000	347,400	84,600
2.8	435,000	347,400	87,600	2.6	428,100	347,400	80,700	445,800	347,400	98,400
1.1	459,500	347,400	112,100	0.9	469,500	347,400	122,100	473,500	347,400	126,100
-0.8	477,100	348,900	128,200	-1.1	483,300	349,400	133,900	483,800	349,400	134,400
				-4.2	472,900	355,900	117,000	475,300	355,900	119,400
-		-		-5.5	469,500	358,400	111,100	470,200	358,400	111,800
-7.0	449,100	361,900	87,200	-7.2	435,000	362,400	72,600	466,800	362,400	104,400
-10.2	431,700	368,400	63,300	-10.2	442,000	368,400	73,600	449,400	368,400	81,000
-11.2	370,400	370,400	0	-11.2	370,400	370,400	0	370,400	370,400	0
	6.4 4.2 4.1 2.8 1.1 -0.8 -7.0 -10.2	6.4 400,600 4.2 431,700 4.1 431,700 2.8 435,000 1.1 459,500 -0.8 477,100 -7.0 449,100 -10.2 431,700	6.4 400,600 347,400 4.2 431,700 347,400 4.1 431,700 347,400 2.8 435,000 347,400 1.1 459,500 347,400 -0.8 477,100 348,900 -7.0 449,100 361,900 -10.2 431,700 368,400	6.4 400,600 347,400 53,200 4.2 431,700 347,400 84,300 4.1 431,700 347,400 84,300 2.8 435,000 347,400 87,600 1.1 459,500 347,400 112,100 -0.8 477,100 348,900 128,200 -7.0 449,100 361,900 87,200 -10.2 431,700 368,400 63,300	6.4 $400,600$ $347,400$ $53,200$ 6.4 4.2 $431,700$ $347,400$ $84,300$ $$ 4.1 $431,700$ $347,400$ $84,300$ 3.4 2.8 $435,000$ $347,400$ $87,600$ 2.6 1.1 $459,500$ $347,400$ $112,100$ 0.9 -0.8 $477,100$ $348,900$ $128,200$ -1.1 $$ $$ $$ $$ -4.2 $$ $$ $$ $$ -5.5 -7.0 $449,100$ $361,900$ $87,200$ -7.2 -10.2 $431,700$ $368,400$ $63,300$ -10.2	6.4 $400,600$ $347,400$ $53,200$ 6.4 $393,600$ 4.2 $431,700$ $347,400$ $84,300$ $$ $$ 4.1 $431,700$ $347,400$ $84,300$ 3.4 $435,000$ 2.8 $435,000$ $347,400$ $87,600$ 2.6 $428,100$ 1.1 $459,500$ $347,400$ $87,600$ 2.6 $428,100$ -0.8 $477,100$ $348,900$ $128,200$ -1.1 $483,300$ $$ $$ $$ $$ -4.2 $472,900$ $$ $$ $$ $$ -4.2 $472,900$ $$ $$ $$ $$ -4.2 $472,900$ $$ $$ $$ $$ -4.2 $472,900$ $$ $$ $$ $$ -4.2 $472,900$ $$ $$ $$ $$ $$ -4.2 $$ $$ $$ $$ -4.2 $472,900$ $$ $$ $$ $$ $$ -4.2 $$ $$ $$ $$ $$ -4.2 $$ $$ $$ $$ $$ -4.2 $$ $$ $$ $$ -5.5 $469,500$ $$ $$ $$ $$ -5.5 $469,500$ $$ $$ $$ $$ $$ -2.2 $$ $$ $$ $$ -2.2 $435,000$ $$ $$ $$ $$ -2.2 $425,000$ <td< td=""><td>6.4$400,600$$347,400$$53,200$$6.4$$393,600$$347,400$$4.2$$431,700$$347,400$$84,300$$$$$$$$4.1$$431,700$$347,400$$84,300$$3.4$$435,000$$347,400$$2.8$$435,000$$347,400$$87,600$$2.6$$428,100$$347,400$$1.1$$459,500$$347,400$$112,100$$0.9$$469,500$$347,400$$-0.8$$477,100$$348,900$$128,200$$-1.1$$483,300$$349,400$$$$$$$$$$-4.2$$472,900$$355,900$$-0.8$$477,100$$348,900$$128,200$$-1.1$$483,300$$349,400$$$</td><td>6.4$400,600$$347,400$$53,200$$6.4$$393,600$$347,400$$46,200$$4.2$$431,700$$347,400$$84,300$$$$$$$$$$$$4.1$$431,700$$347,400$$84,300$$3.4$$435,000$$347,400$$87,600$$2.8$$435,000$$347,400$$87,600$$2.6$$428,100$$347,400$$80,700$$1.1$$459,500$$347,400$$112,100$$0.9$$469,500$$347,400$$122,100$$-0.8$$477,100$$348,900$$128,200$$-1.1$$483,300$$349,400$$133,900$$$$$$$$$$-4.2$$472,900$$355,900$$111,100$$$$$$$$$$$$-5.5$$469,500$$358,400$$111,100$$-7.0$$449,100$$361,900$$87,200$$-7.2$$435,000$$362,400$$72,600$$-10.2$$431,700$$368,400$$63,300$$-10.2$$442,000$$368,400$$73,600$</td><td>6.4$400,600$$347,400$$53,200$$6.4$$393,600$$347,400$$46,200$$400,900$$4.2$$431,700$$347,400$$84,300$$$$$$$$$$$$428,600$$4.1$$431,700$$347,400$$84,300$$3.4$$435,000$$347,400$$87,600$$432,000$$2.8$$435,000$$347,400$$87,600$$2.6$$428,100$$347,400$$80,700$$445,800$$1.1$$459,500$$347,400$$112,100$$0.9$$469,500$$347,400$$122,100$$473,500$$-0.8$$477,100$$348,900$$128,200$$-1.1$$483,300$$349,400$$133,900$$483,800$$$$$$$$$$$$$$-4.2$$472,900$$355,900$$111,100$$470,200$$$<td>6,4$400,600$$347,400$$53,200$$6.4$$393,600$$347,400$$46,200$$400,900$$347,400$$4,2$$431,700$$347,400$$84,300$$$$$$$$$$$$428,600$$347,400$$4,1$$431,700$$347,400$$84,300$$3.4$$435,000$$347,400$$87,600$$432,000$$347,400$$2.8$$435,000$$347,400$$87,600$$2.6$$428,100$$347,400$$80,700$$445,800$$347,400$$1.1$$459,500$$347,400$$112,100$$0.9$$469,500$$347,400$$122,100$$473,500$$347,400$$-0.8$$477,100$$348,900$$128,200$$-1.1$$483,300$$349,400$$133,900$$483,800$$349,400$$$<td< td=""></td<></td></td></td<>	6.4 $400,600$ $347,400$ $53,200$ 6.4 $393,600$ $347,400$ 4.2 $431,700$ $347,400$ $84,300$ $$ $$ $$ 4.1 $431,700$ $347,400$ $84,300$ 3.4 $435,000$ $347,400$ 2.8 $435,000$ $347,400$ $87,600$ 2.6 $428,100$ $347,400$ 1.1 $459,500$ $347,400$ $112,100$ 0.9 $469,500$ $347,400$ -0.8 $477,100$ $348,900$ $128,200$ -1.1 $483,300$ $349,400$ $$ $$ $$ $$ -4.2 $472,900$ $355,900$ $$ -0.8 $477,100$ $348,900$ $128,200$ -1.1 $483,300$ $349,400$ $$	6.4 $400,600$ $347,400$ $53,200$ 6.4 $393,600$ $347,400$ $46,200$ 4.2 $431,700$ $347,400$ $84,300$ $$ $$ $$ $$ $$ 4.1 $431,700$ $347,400$ $84,300$ 3.4 $435,000$ $347,400$ $87,600$ 2.8 $435,000$ $347,400$ $87,600$ 2.6 $428,100$ $347,400$ $80,700$ 1.1 $459,500$ $347,400$ $112,100$ 0.9 $469,500$ $347,400$ $122,100$ -0.8 $477,100$ $348,900$ $128,200$ -1.1 $483,300$ $349,400$ $133,900$ $$ $$ $$ $$ -4.2 $472,900$ $355,900$ $111,100$ $$ $$ $$ $$ $$ -5.5 $469,500$ $358,400$ $111,100$ -7.0 $449,100$ $361,900$ $87,200$ -7.2 $435,000$ $362,400$ $72,600$ -10.2 $431,700$ $368,400$ $63,300$ -10.2 $442,000$ $368,400$ $73,600$	6.4 $400,600$ $347,400$ $53,200$ 6.4 $393,600$ $347,400$ $46,200$ $400,900$ 4.2 $431,700$ $347,400$ $84,300$ $$ $$ $$ $$ $$ $428,600$ 4.1 $431,700$ $347,400$ $84,300$ 3.4 $435,000$ $347,400$ $87,600$ $432,000$ 2.8 $435,000$ $347,400$ $87,600$ 2.6 $428,100$ $347,400$ $80,700$ $445,800$ 1.1 $459,500$ $347,400$ $112,100$ 0.9 $469,500$ $347,400$ $122,100$ $473,500$ -0.8 $477,100$ $348,900$ $128,200$ -1.1 $483,300$ $349,400$ $133,900$ $483,800$ $$ $$ $$ $$ $$ $$ -4.2 $472,900$ $355,900$ $111,100$ $470,200$ $$ <td>6,4$400,600$$347,400$$53,200$$6.4$$393,600$$347,400$$46,200$$400,900$$347,400$$4,2$$431,700$$347,400$$84,300$$$$$$$$$$$$428,600$$347,400$$4,1$$431,700$$347,400$$84,300$$3.4$$435,000$$347,400$$87,600$$432,000$$347,400$$2.8$$435,000$$347,400$$87,600$$2.6$$428,100$$347,400$$80,700$$445,800$$347,400$$1.1$$459,500$$347,400$$112,100$$0.9$$469,500$$347,400$$122,100$$473,500$$347,400$$-0.8$$477,100$$348,900$$128,200$$-1.1$$483,300$$349,400$$133,900$$483,800$$349,400$$$<td< td=""></td<></td>	6,4 $400,600$ $347,400$ $53,200$ 6.4 $393,600$ $347,400$ $46,200$ $400,900$ $347,400$ $4,2$ $431,700$ $347,400$ $84,300$ $$ $$ $$ $$ $$ $428,600$ $347,400$ $4,1$ $431,700$ $347,400$ $84,300$ 3.4 $435,000$ $347,400$ $87,600$ $432,000$ $347,400$ 2.8 $435,000$ $347,400$ $87,600$ 2.6 $428,100$ $347,400$ $80,700$ $445,800$ $347,400$ 1.1 $459,500$ $347,400$ $112,100$ 0.9 $469,500$ $347,400$ $122,100$ $473,500$ $347,400$ -0.8 $477,100$ $348,900$ $128,200$ -1.1 $483,300$ $349,400$ $133,900$ $483,800$ $349,400$ $$ <td< td=""></td<>

Note: See Plate 3 for definition of terms.

* No calculated loads.

*// _____

٠

Table 4 Hoist Cable Loads $\underline{Y = 18 \text{ ft}}$

				Phase I	Testing							(Calculated	by
		Te	et 1			Te	st 2		Pha	ase II Test	ting	Rock	Island Dis	strict
dr	dg	FT	FS	FW	dg	FT	FS	FW	FT	FS	FW	dg	FT	FW
ft	_ft	_1b	_1b	<u></u>	ft	_1b	_1b	<u>1b</u>	<u></u>	_1b	1b	ft	<u></u> 1b	1b
0	12.5	369,800	347,400	22,400	10.3	373,000	347,400	25,600	375,400	347,400	28,000			
3	6.4	421,200	347,400	73,800	5.6	424,700	347,400	77,300	428,500	347,400	81,100	11.0	329,117	0
4	5.4	428,000	347,400	80,600					449,300	347,400	101,900	10.1	328,801	0
5	3.2	428,000	347,400	80,600					442,400	347,400	95,000	9.3	328,356	0
б	0.9	438,200	347,400	90,800	0.9	448,900	347,400	101,500	445,800	347,400	98,400	8.5	328,105	0
7	-0.1	451,900	347,700	104,200	—				456,200	347,700	108,500	7.7	327,965	0
8	-1.1	445,100	349,900	95,200					470,000	349,900	120,100	7.0	569,262	213,158
9	-1.3	452,000	350,400	101,600	-1.3	476,500	350,400	126,100	483,800	350,400	133,400	6.2	549,672	188,797
10					-1.8	514,500	350,900	163,600	514,900	350,900	164,000	5.5	532,488	167,482
11					-3.3	500,700	353,900	146,800	508,400	343,900	154,500	4.8	515,005	146,166
12	-4.6	489,600	356,900	132,700	-5.0	490,300	357,400	132,900	508,000	357,400	150,600	4.1	502,647	124,850
13					-7.2	486,900	362,400	124,500				3.4	484,429	103,534
14					-9.7	459,100	367,400	91,700				2.7	465,905	82,218
15	-11.2	480,000	370,400	109,600	-11.6	479,800	373,900	105,900	480,400	373,900	106,500	2.0	446,950	60,902
16					-13.4	466,000	374,900	91,100				1.3	427,477	39,587
17	-	-			-14.9	452,500	375,900	77,600				0.67	409,685	20,402
18	-17.8	383,400	383,400	0	-15.8	379,900	379,900	0	383,400	383,400	0	0	390,165	0

~

19.

Note: See Plate 3 for definition of terms.

~

Table 5

Hoist Cable Loads

Y = 25 ft*

				Phase I	Testing						
		Tea	st 1			T	est 2		P	hase II Test	ing
d _r	d g ft	F _T 1b	F _S 1b	F _W 1b	d g ft	F _T 1b	F _S 1b	F _W 1b	F _T 1b	F _S 1b	F _W 1b
									1000		and the second second
0	10.6	400,900	347,400	53,500	10.6	432,000	347,400	84,600	435,500	347,400	88,100
3	6.6	473,500	347,400	126,100	6.6	442,400	347,400	95,000	459,700	347,400	112,300
4	4.8	480,400	347,400	133,000	4.8	463,100	347,400	115,700	476,900	347,400	129,500
5	3.4	497,700	347,400	150,300	3.4	487,300	347,400	139,900	504,600	347,400	157,200
6	1.9	501,100	347,400	153,700	1.9	515,000	347,400	167,600	525,300	347,400	177,900
7	-0.5	525,300	348,400	176,900	-1.2	532,200	349,900	182,300	532,200	349,900	182,300
8	-2.2	542,600	352,400	190,200	-2.2	532,200	352,400	179,800	535,700	352,400	183,300
9	-4.4	546,100	356,900	189,200	-4.4	546,100	356,900	189,200	549,500	356,900	192,600
10	-4.8	525,300	357,400	167,900	-4.8	528,800	357,400	171,400	546,100	357,400	188,700
11	-5.0	539,100	357,900	181,200	-5.0	549,500	357,900	191,600	532,200	357,900	174,300
12	-5.0	573,700	357,900	215,800	-5.0	570,200	357,900	212,300	570,200	357,900	212,300
13	-5.0	642,800	357,900	284,900	-5.0	653,200	357,900	295,300	591,000	357,900	233,100
14	-6.6	656,600	360,900	295,700	-6.3	677,400	360,400	317,000	670,500	360,900	309,600
15	-8.5	684,300	364,900	319,400	-8.5	687,800	364,900	322,900	684,300	364,900	319,400
16	-9.0	684,300	365,900	318,400	-9.7	684,300	367,400	316,900	667,000	367,400	299,600
17	-11.2	677,400	370,400	307,000	-11.2	687,800	370,400	317,400	670,464	370,400	300,064
18	-12.2	615,200	372,400	242,800	-12.2	601,300	372,400	228,900	591,000	372,400	218,600


Note: See Plate 3 for definition of terms.


* No calculated loads.

1.4 2

d _r ,ft	Y = 10 ft		Y = 16 ft		Y = 18 ft		Y = 25 ft	
	H _g , ft	Q, cfs						
3	7	6,600	13	16,700	15	20,900	22	38,900
4	6	4,700			14	18,900	21	36,200
5	5	3,700	11	12,500	13	16,800	20	34,100
6	4	3,000	10	11,500	12	15,200	19	31,600
7	3	1,600	9	9,500	11	13,400	18	29,200
8	2	1,100	8	8,600	10	12,200	17	26,900
9			7	7,000	9	9,300	16	25,000
10			6	5,300	8	7,900	15	21,100
11			5	5,000	7	6,800	14	20,700
12			4	4,600	6	5,500	, 13	19,800
13					5	4,400	12	17,700
14					4	3,200	11	15,700
15							10	12,800
16							9	12,200
17							8	10,800
18							7	7,300

Table 6 Discharge Data, Model Study of Lockport Lock Liftgate





a. Downstream view








Photo 1. Unit discharge 57 cfs/ft, $d_r = 12.0$ ft, pool el 576 ft (NGVD), tailwater el 539 ft (NGVD)




Photo 2. Unit discharge 64 cfs/ft, $d_r = 9.0$ ft, pool el 574 ft (NGVD), tailwater el 539 ft (NGVD)






Photo 3. Unit discharge 27 cfs/ft, $d_r = 6.0$ ft, pool el 568 ft (NGVD), tailwater el 539 ft (NGVD)












PLATE 3







.






PLATE 7








PLATE 8












PLATE 12