



**US Army Corps
of Engineers®**
Engineer Research and
Development Center



Vicksburg District Mat Sinking Unit

Mat Sinking Unit Supply Study

Mississippi River Revetment

Julie A. Hicks, Laurin I. Yates, and Jackie S. Pettway

September 2021



The US Army Engineer Research and Development Center (ERDC) solves the nation's toughest engineering and environmental challenges. ERDC develops innovative solutions in civil and military engineering, geospatial sciences, water resources, and environmental sciences for the Army, the Department of Defense, civilian agencies, and our nation's public good. Find out more at www.erdclibrary.on.worldcat.org/discovery.

To search for other technical reports published by ERDC, visit the ERDC online library at <http://www.erdclibrary.on.worldcat.org/discovery>.

Mat Sinking Unit Supply Study

Mississippi River Revetment

Julie A. Hicks

*Geotechnical and Structures Laboratory
US Army Engineer Research and Development Center
3909 Halls Ferry Road
Vicksburg, MS 39180-6199*

Laurin I. Yates

*Coastal and Hydraulics Laboratory
US Army Engineer Research and Development Center
3909 Halls Ferry Road
Vicksburg, MS 39180-6199*

Jackie S. Pettway

*Information Technology Laboratory
US Army Engineer Research and Development Center
3909 Halls Ferry Road
Vicksburg, MS 39180-6199*

Final report

Approved for public release; distribution is unlimited.

Prepared for USACE, Vicksburg District
Vicksburg, MS 39180-3435

Under MIPR W807PM91017173

Abstract

The Mississippi Valley Division (MVD) has maintained the Mississippi River banks for over 80 years. The Mat Sinking Unit (MSU), built in 1946, was considered state-of-the-art at the time. This system is still in operation today and has placed over 1,000 miles of Articulated Concrete Mats along the Mississippi River from Head of Passes, LA, to Cairo, IL. A new MSU has been designed and is expected to be fully mission capable and operational by the 2023 season, which is expected to increase the productivity from 2,000 squares/day up to 8,000 squares/day with double shifts and optimal conditions.

This MSU supply study identifies and optimizes the supply chain logistics for increased production rates from the mat fields to the MSU. The production rates investigated for this effort are 2,000 squares/day, 4,000 squares/day, and 6,000 squares/day. RiskyProject® software, which utilizes a Monte Carlo method to determine a range of durations, manpower, and supplies based on logical sequencing is used for this study. The study identifies several potential supply and demand issues with the increased daily production rates. Distance to casting fields, number of barges, and square availability are the major issues to supply increased placement rates identified by this study.

DISCLAIMER: The contents of this report are not to be used for advertising, publication, or promotional purposes. Citation of trade names does not constitute an official endorsement or approval of the use of such commercial products. All product names and trademarks cited are the property of their respective owners. The findings of this report are not to be construed as an official Department of the Army position unless so designated by other authorized documents.

DESTROY THIS REPORT WHEN NO LONGER NEEDED. DO NOT RETURN IT TO THE ORIGINATOR.

Contents

Abstract	ii
Figures and Tables	v
Preface	vii
1 Introduction	1
1.1 Background.....	1
1.2 Purpose	8
1.3 Objective	8
1.4 Approach	9
1.4.1 <i>Data collection and information</i>	9
1.4.2 <i>MSU operation descriptions</i>	12
2 Methodology	17
2.1 Supply chain analysis.....	17
2.1.1 <i>Inputs and assumptions</i>	17
2.1.2 <i>Resources</i>	23
2.1.3 <i>Potential delay events to schedule</i>	25
2.2 Program.....	29
2.2.1 <i>Potential delay impact</i>	29
2.2.2 <i>Application of potential causes of delay percentages</i>	29
2.3 Analysis	31
2.4 Sensitivity analysis	31
2.5 Analyzed conditions.....	32
2.6 Current Condition	34
2.7 2,000 squares/day condition	35
2.8 4,000 squares/day condition	37
2.9 6,000 squares/day condition	40
3 Conclusion	43
References	45
Appendix A: Logistics Schedules	46
Appendix B: Schedules with Risks Calculated	66
Appendix C: Risk Matrices	95
Appendix D: Potential Delay Probabilities	98
Unit Conversion Factors	101
Acronyms and Abbreviations	102

Glossary..... 103

Report Documentation Page

Figures and Tables

Figures

Figure 1. Willow mats being constructed by weaving the material (courtesy of Vicksburg District [MVK]).	2
Figure 2. Willow mats being constructed by weaving the material (courtesy of MVK).	2
Figure 3. Wood and stone material used for bank protection in 1939 (courtesy of Memphis District).	3
Figure 4. Concrete slabs placed along the bank (courtesy of MVK).	3
Figure 5. Personnel assist with placement of concrete slabs (courtesy of MVK).	4
Figure 6. Mississippi River course changes.	5
Figure 7. MSU area of responsibility (AOR) along the Mississippi River.	6
Figure 8. View of the current MSU from landside prior to anchoring of mats for placement.	7
Figure 9. Workers tying mats during placement.	7
Figure 10. Graphic of new MSU (ARMOR 1) courtesy of MVK.	8
Figure 11. Vessel moving loaded stack barge to MSU.	10
Figure 12. Dozer landside anchoring ACMs.	10
Figure 13. Supply stack barge for MSU operations.	11
Figure 14. Operations on MSU for ACM placement.	11
Figure 15. ACM being offloaded from supply barge.	12
Figure 16. Aerial view of the MSU operations during ACM placement.	13
Figure 17. MV <i>William James</i> leaving Port of Vicksburg with the MSU and support barge.	14
Figure 18. MV <i>Mississippi</i> .	15
Figure 19. MV <i>Benyard</i> .	15
Figure 20. MV <i>William James</i> .	16
Figure 21. MV <i>Harrison</i> .	16
Figure 22. Schedule of MSU operations for 2019 current schedule.	19
Figure 23. Schedule of MSU operations for 2,000 squares/day.	20
Figure 24. Schedule of MSU operations for 4,000 squares/day.	21
Figure 25. Schedule of MSU operations for 6,000 squares per day.	22
Figure 26. Potential delay register for issue with barge.	30
Figure 27. Results for Current Condition placement.	35
Figure 28. Results for 2,000 squares/day placement.	37
Figure 29. Results for 4,000 squares/day placement.	40
Figure 30. Results for 6,000 squares/day placement.	42
Figure A-1. Schedule of events for 2,000 squares/day.	47
Figure A-2. Schedule of events for 4,000 squares/day.	54

Figure A-3. Schedule of events for 6,000 squares/day.....	60
Figure B-1. Schedule of events with risks calculated for the current schedule.	67
Figure B-2. Schedule of events with risks calculated for 2,000 squares/day.....	74
Figure B-3. Schedule of events with risks calculated for 4,000 squares/day.....	81
Figure B-4. Schedule of events with risks calculated for 6,000 squares/day.....	88
Figure C-1. Risk matrix for 2,000 squares/day.	95
Figure C-2. Risk matrix for 4,000 squares/day.	96
Figure C-3. Risk matrix for 6,000 squares/day.	97

Tables

Table 1. MSU supply logistics support.....	13
Table 2. List of resources used for scheduling.	23
Table 3. Potential delay register.	26
Table 4. Percentage of probability of occurrence.	28
Table 5. Sensitivity analysis of reduction of risk percentage and increase in delay times.	32
Table 6. Days required at mat field.....	33
Table 7. Estimated durations for base, minimum, mean, and maximum durations.	34
Table 8. Identified delays in schedule for 2,000 squares/day.	36
Table 9. Identified delays in schedule for 4,000 squares/day.	38
Table 10. Identified delays in schedule for 6,000 squares/day.	41
Table D-1. Potential delay register.....	98
Table D-2. Percentage of probability of occurrence.	100

Preface

This study was conducted for the US Army Corps of Engineers, Vicksburg District, under MIPR W807PM91017173.

This work was performed by the Structural Mechanics Branch of the Geosciences and Structures Division of the US Army Engineer Research and Development Center (ERDC), Geotechnical and Structures Laboratory (ERDC-GSL) the Navigation Division of the ERDC Coastal and Hydraulics Laboratory (ERDC-CHL), and the Software Engineering and Informatics Division of the ERDC Information Technology Laboratory (ERDC-ITL).

At the time of publication of this report, Mr. Bradford A. Steed was Chief, Structural Mechanics Branch, and Mr. James L. Davis was Chief, Geosciences and Structures Division. The Deputy Director of ERDC-GSL was Mr. Charles W. Ertle II, and the Director was Mr. Bartley Durst. Mr. Chad Bounds was Chief, Harbors, Entrances, and Structures Branch. Ms. Ashley Frey was Chief, Navigation Division. The Deputy Director of ERDC-CHL was Mr. Keith Flowers, and the Director was Dr. Ty V. Wamsley. The Deputy Director of ERDC-ITL was Dr. Jackie S. Pettway, and the Director was Dr. David A. Horner.

COL Teresa A. Schlosser was the Commander of ERDC, and the Director was Dr. David W. Pittman.

1 Introduction

1.1 Background

The Mississippi Valley Division (MVD) has been maintaining the Mississippi River banks for over 80 yr¹. This is accomplished by armoring the riverbanks with a protective material. Early armoring consisted of willow fascine or lumber framework mattresses wired together to form a protected mat that was placed on a graded slope. A silt backfill and rock armoring held the mattresses in position (Figure 1–Figure 3). The invention of the Articulated Concrete Mat (ACM) occurred in 1914 and was patented in 1916. The configuration of these mats and placement techniques were modified until the 1940s (Figure 4 and Figure 5). These mats provide channel stability and prevent cutting of new channels, breaching of levee systems, destruction of property, threatening of populations, interruption of navigation and commerce, disruption of agricultural interests, and endangerment of natural habitats. This allows for some control of the mighty Mississippi River. Figure 6 shows the changing Mississippi River from 1765 to present.

¹ For a full list of the spelled-out forms of the units of measure used in this document, please refer to *US Government Publishing Office Style Manual, 31st ed.* (Washington, DC: US Government Publishing Office 2016), 248-52, <https://www.govinfo.gov/content/pkg/GPO-STYLEMANUAL-2016/pdf/GPO-STYLEMANUAL-2016.pdf>.

Figure 1. Willow mats being constructed by weaving the material (courtesy of Vicksburg District [MVK]).



Figure 2. Willow mats being constructed by weaving the material (courtesy of MVK).



Figure 3. Wood and stone material used for bank protection in 1939 (courtesy of Memphis District [MVM]).



Figure 4. Concrete slabs placed along the bank (courtesy of MVK).





Figure 5. Personnel assist with placement of concrete slabs (courtesy of MVK).



Figure 6. Mississippi River course changes.



As the techniques for assembling and placing the ACM were fully developed, design began for a vessel that could be used to place the mats from the river. The Mat Sinking Unit (MSU) was built in 1946 and was considered state-of-the-art at the time. This system is still in operation today and has placed over 1,000 mi of ACM along the Mississippi River from Head of Passes, LA, to Cairo, IL (Figure 7). The operation of the MSU requires approximately 325 personnel and unique equipment such as the tying tools used to connect the ACM into the mattresses. The MSU has a mission to lay concrete mats, which form a protective overcoat to shield the riverbank from erosion and sloughing caused by channel currents and

turbulent water associated with river flood stages (Figure 8 and Figure 9). However, there are issues with safety, labor intensity, and reliability. Though this system is still utilized today, there are designs underway to develop an updated system including automation where appropriate to improve productivity and safety. A new MSU is in the fourth and final stage of design and is expected to be fully mission capable and operational by the 2023 season (Figure 10). The goal is to automate much of the work through robotics, thereby improving safety and increasing the productivity from 2,000 squares/day (on production days) to a minimum of 4,000 squares/day and possibly as high as 8,000 squares/day with double shifts and optimal conditions.

Figure 7. MSU area of responsibility (AOR) along the Mississippi River.




Figure 8. View of the current MSU from landside prior to anchoring of mats for placement.



Figure 9. Workers tying mats during placement.



Figure 10. Graphic of new MSU (ARMOR 1) courtesy of MVK.



1.2 Purpose

The purpose of this MSU Resource Assessment study is to identify and optimize the logistics of increased production rates from the mat fields to the MSU, factoring various scenarios and variables. The production rates investigated for this effort are 2,000 squares/day, 4,000 squares/day, and 6,000 squares/day.

1.3 Objective

The objective of this study is to provide the MVK with an estimate of the potential demand within the supply chain of squares to the new ARMOR 1 mat sinking unit. The system consists of a support fleet for movement of concrete squares to include barges and tows, mechanisms including cranes for loading and offloading the squares, fleet positioning requirements, and unexpected downtime. Some possible bottlenecks or drivers include, but are not limited to, manpower requirements, mobilization requirements, operational equipment, dependability and resilience of system materials, training requirements, storage requirements (including distance from stored location and equipment needed to move them), inclement weather, and maintenance and replacement tasks. Productivity limitations with recommendations for required resources are provided in this report.

1.4 Approach

1.4.1 Data collection and information

In April 2019, personnel from the US Army Engineer Research and Development Center (ERDC) held a kick-off meeting with MVK team members to discuss the MSU process. The current MSU was constructed in 1948. There currently are issues with safety, labor intensity, and reliability. The new MSU is in the fourth and final stage of design and expected to be fully mission capable and operational by the 2023 season. Robotics will automate much of the work, thereby reducing the needed labor force and increasing the productivity from 2,000 squares/day (on production days) to a minimum of 4,000 squares/day and possibly as high as 6,000 squares/day with double shifts and optimal conditions. As the new MSU comes online, there will be increased requirements on the supply logistics of the revetment process that must be analyzed. The meeting provided an opportunity for expert elicitation to gain understanding of any potential bottlenecks to the current process and identify potential pinch points as daily production is increased. An initial list of steps in the supply processes and potential risk drivers was developed by ERDC and provided to the MVK for comment. Over the following several months, historical data including revetment schedules from previous seasons and boat orders, as well as additional expert elicitations including discussion with boat captains were collected. A site visit to the MSU was requested and tentatively scheduled.

Due to river conditions, the site visit to the MSU to observe operations could not occur until 23 October 2019. Four ERDC team members traveled to Bougere in Louisiana to observe operations and conduct additional expert elicitation. Figure 11 through Figure 15 show operations observed during the site visit.

Figure 11. Vessel moving loaded stack barge to MSU.



Figure 12. Dozer landside anchoring ACMs.



Figure 13. Supply stack barge for MSU operations.



Figure 14. Operations on MSU for ACM placement.



Figure 15. ACM being offloaded from supply barge.



1.4.2 MSU operation descriptions

The process for river revetment with the MSU includes several components for success. Figure 16 provides a graphic of the MSU operation and components during ACM placement. The operation, including supply logistics, requires several vessels, barges, and ACM fields. Table 1 describes the components of the MSU operation, the capacities, and the functions. Figure 17 shows the Motor Vessel (MV) *William James* leaving the Port of Vicksburg with the MSU and support barges. There are five river vessels used to perform various tasks under the current conditions. US Army Corps of Engineers (USACE) vessels MV *Mississippi*, MV *Benyaard*, MV *William James*, and MV *Harrison* are depicted in Figure 18, Figure 19, Figure 20, and Figure 21, respectively. There are currently 43 vessels utilized for ACM transport from the three current mat fields to supply squares for the MSU operations. These mat fields are located in Richardson Landing, TN; Delta, LA; and St. Francisville, LA.

Figure 16. Aerial view of the MSU operations during ACM placement.




Table 1. MSU supply logistics support.

Component	Size/No.	Function
MV <i>Mississippi</i>	6,000 hp	Dedicated to moving stack barges to and from the MSU. The MV <i>Mississippi</i> is replaced by a contract vessel when not available such as during annual low water inspection trip.
MV <i>Benyard</i>	4,300 hp	Moves the quarter boat fleet but does help move stack loads if they can be dedicated to that task for a specific trip.
MV <i>William James</i>	3,300 hp	Dedicated to the MSU, typically.
MV <i>Harrison</i>	1,200 hp	Labor barge. When used to move stack barges, the max capacity is limited to four barges. Stays local with plant and shuttles stack barges between plant and local anchor fleet.
<i>Mary Wepfer</i>	1,400 hp	Contracted vessel primarily used for fleet tender
Anchor Barges	4	Holds barges in the current as an alternative to tying to trees. Allows barge anchorage closer to the plant. Fleet number: MVK = 2, MVM = 2.

Component	Size/No.	Function
Quarter Barges	1	Provided housing and other provisions for employees
Stack Barges	43	Barges for transporting squares. Each barge can hold 585 squares, which are stacked 113 high. Typical load operations is 3-4 per day with a maximum of 7. Loading unit shifts will often work weekends to keep up with production.
Richardson Landing, TN, casting field	1	Casts squares and loads barges for transport to MSU. Within the MVK AOR.
Delta, LA, casting field	1	Casts squares and loads barges for transport to MSU. Within Vicksburg District AOR.
St. Francisville, LA, casting field	1	Casts squares and loads barges for transport to MSU. Within New Orleans District AOR.

Figure 17. MV *William James* leaving Port of Vicksburg with the MSU and support barge.



Figure 18. MV *Mississippi*.



Figure 19. MV *Benyard*.



Figure 20. MV *William James*.



Figure 21. MV *Harrison*.



2 Methodology

A software package named RiskyProject® was used for the supply logistics analysis. This software package is an advanced project management software used for planning, scheduling, and determining how risks and uncertainties can impact project schedules or milestones. This software package was utilized in previous applications within USACE (Myrick et al. 2020).

2.1 Supply chain analysis

2.1.1 Inputs and assumptions

Analysis of historical revetment schedules and initial analysis of supply logistics resulted in the selection of three placement locations from the 2019 season farthest from the mat fields supplying the squares. Those locations are Gravolet, Rescue, and Lee Towhead. For the analysis, Gravolet was supplied by the St. Francisville mat yard, Rescue was supplied by the Delta, LA, mat yard, and Lee Towhead was supplied by the Richardson Landing mat yard. The total number of ACM placed per location was based on the actual ACM placement during the 2019 season. These three locations were used to develop a placement route to analyze the expected increase in productivity and were used as a baseline from the actual placement time to validate the initial models.

A base duration was established based on the actual time required to place the specified squares during the 2019 season at the three locations. Total squares placed at Gravolet, Rescue, and Lee Towhead during the 2019 season were 9,224; 18,694; and 8,663, respectively. The three placements were input into the model as a complete season to capture relocation of equipment and transfer of supply locations and equipment. The low and high duration is the time that it could plausibly take without any potential delays applied to the schedule and are based on experience and knowledge of the operation and environment. A reason for the low and high durations is to account for other factors that may affect the project, such as staff production levels, and an acknowledgement that the times are just estimates. These estimates are given with the understanding that future modifications to the operation or other factors not considered at this time could alter the supply logistics schedule and in turn increase probably of delays.

Figure 22 – Figure 25 show the high-level schedules for the season with placement in three locations. See Appendix A for full schedules showing all tasks and sub-tasks. The schedule shows the base duration as well as the low and high durations for the operations. Also included in the schedule are any applicable lag times. In addition to the three placement locations mentioned above, the analysis includes mobilization at the three mat yards, training, Blessing of the Fleet, and relocation between placement locations. The supply barges are captured in 12-barge tows for the analysis, and the empty barges are towed to the mat yards in 4-barge to 8-barge tows for reloading. The complete logistics process from loaded barges at the mat yards, to towing to the MSU operations, to breaking tows, moving loaded barges into place, and transporting empty barges back to the mat yards are analyzed.

Figure 22. Schedule of MSU operations for 2019 current schedule.




Figure 23. Schedule of MSU operations for 2,000 squares/day.




Figure 24. Schedule of MSU operations for 4,000 squares/day.





Figure 25. Schedule of MSU operations for 6,000 squares per day.



As the schedules for each run are examined, it is apparent that there are tasks that cannot commence until previous tasks are complete or are at least partially complete. For example, placement in a location cannot begin until the equipment has been relocated to the placement areas. Lag time is the length of time after one event occurs before the second event occurs and is listed as either start-to-start or finish-to-finish.

2.1.2 Resources

Table 2 provides the resources being used in setting the schedules for the three placement location seasons. With the exception of the ARMOR 1 Crew, all resources are assumed to have 24 hr availability. The ARMOR 1 Crew assumes 10 hr shifts for current and 2,000 squares/day conditions and 12 hr shifts for 4,000 squares/day. For the 6,000 squares/day conditions, two 8 hr shifts are operated per day.

Table 2. List of resources used for scheduling.

Resource Name	Initials
ARMOR 1 Unit	A1
ARMOR 1 Crew (current, 2,000, and 4,000 squares/day)	A1C
ARMOR 1 Crew 1 st Shift (6,000 squares/day)	A1C1
ARMOR 1 Crew 2 nd Shift (6,000 squares/day)	A1C2
Anchor Barge 1 - Vicksburg (VKS)	AB1
Anchor Barge 2 - VKS	AB2
Anchor Barge 3 - Memphis (MPH)	AB3
Anchor Barge 4 - MPH	AB4
<i>MV Mississippi</i>	M
<i>MV Harrison</i>	MVH
<i>MV Benyaurd</i>	MVB
<i>MV William James</i>	MVWJ
<i>Mary Wepfer</i>	MW
Quarter Barge	QB
Barge 1	B1
Barge 2	B2
Barge 3	B3
Barge 4	B4

Resource Name	Initials
Barge 5	B5
Barge 6	B6
Barge 7	B7
Barge 8	B8
Barge 9	B9
Barge 10	B10
Barge 11	B11
Barge 12	B12
Barge 13	B13
Barge 14	B14
Barge 15	B15
Barge 16	B16
Barge 17	B17
Barge 18	B18
Barge 19	B19
Barge 20	B20
Barge 21	B21
Barge 22	B22
Barge 23	B23
Barge 24	B24
Barge 25	B25
Barge 26	B26
Barge 27	B27
Barge 28	B28
Barge 29	B29
Barge 30	B30
Barge 31	B31
Barge 32	B32
Barge 33	B33
Barge 34	B34
Barge 35	B35
Barge 36	B36
Barge 37	B37

Resource Name	Initials
Barge 38	B38
Barge 39	B39
Barge 40	B40
Barge 41	B41
Barge 42	B42
Barge 43	B43
Dozer 1	D1
Dozer 2	D2
Dozer 3	D3
Dozer 4	D4
Dozer Crew	D
Memphis Mat Yard Crew	MYCW
Mat Yard Crane	MYC
Delta Mat Yard Crew	DYC
St. Francisville Mat Yard Crew	SFC

2.1.3 Potential delay events to schedule

A potential delay, for purposes of this analysis, is any event that may cause delays in the mat sinking unit operations. A list of potential impacts to supply logistics was developed based on historical events and expert elicitation and are provided in Table 3. Probability of occurrence for each potential delay that would result in a minor delay, moderate delay, serious delay, and critical delay. The probability of no delay was then calculated by subtracting all possible delay percentages from 100% probability.

Table 4 provides the percent probabilities for minor, moderate, serious, critical, and no delays for each possible delay.

Table 3. Potential delay register.

Possible Delays to Schedule	Description	Cause	Trigger
Barge Wreck in Tow	Barge(s) separate from tow and sink.	Lashings loosed, commercial vehicle wreck, tow strikes bridge, etc.	
Commercial Wreck	A commercial vessel wrecks in the river in the tug tow zone, shutting down river traffic.	High current, other mishap/accident causing a commercial wreck not involving USACE MSU vessels.	
Ice in River Impeding Navigation	Ice causing hazards on river leading to slowdown/stopping of tow.	Cold weather in northern reach of river.	Winter weather
Ice on Boat Deck	Ice on boat decks causing hazardous operation for personnel	Low temperatures	Weather
Issue with Barge	Barge(s) become in operable.	Damage to barge(s) rendering it in operable until repair.	
Lightning	Sustained lightning in work area.	Thunderstorm, etc.	Inclement weather warning.
Low Fuel	Vessels low on fuel, necessitating delay		
Mats Not Available	Squares not available for loading onto barges.	Production down at square-pouring plant.	
Mechanical Problems at Yard	Problems with production/loading machinery at Mat yard.	Machinery malfunction	
Mechanical Problems with ARMOR 1	Problems with ARMOR 1 unit's machinery.	Malfunctioning engines, motors, etc.	Improper usage, maintenance, force of nature, etc.
Mechanical Problems with Tow Vessel	Problems with tow vessels machinery.	Malfunctioning engines, motors, etc.	Improper usage, maintenance, force of nature, etc.
Not Enough Employees	Not enough employees to successfully operate tows, ARMOR 1 unit, or other vessels.	Weather or other delay causing employees not to arrive on time, or insufficient crews available.	

Possible Delays to Schedule	Description	Cause	Trigger
Reduced Speeds on River	Coast Guard reduces river speeds.		Wrecks, water levels, currents, etc.
Riverbank Slope/Landscape Not Complete	Delays as a result of site prep.	Additional clearing and/or bank preparation needed.	Higher than expected water elevation or failed communication with clearing and snagging
River Currents/High Water Elevation	Major delays possible with requirement to construct healing points, toggling for swift current or remote parking for quarter boat fleet	Unanticipated rise in river stages, or decision to mitigate high water with additional construction.	Weather
River Impediments to Navigation			
River Low water Elevation	Water surface elevations less than Low Water Reference Plane (LWRP) +5 for revetment design.	Seasonal drought	Weather
River Navigation Shut Down	Coast Guard stops traffic on river.	Coast Guard stops traffic from moving on river for period of time.	Wrecks, water levels, currents, etc.
Unattended Barge	Barge comes loose from tow or anchorage and travels away from site, necessitating vessels to retrieve it and re-position it.	Loosed lashings, etc. causing barge to break away from tow/anchorage/etc.	
Wind			

Table 4. Percentage of probability of occurrence.

Possible Delays to Schedule	Minor =< 1 hr Delay	Moderate =< 3 hr Delay	Serious =< 6 hr Delay	Critical > 6 hr Delay	No Delay (100% - All total % off all delays)
Barge Wreck in Tow	5%	2%	1%	1%	91.00%
Commercial Wreck	1%	1%	2%	10%	86%
Ice on Boat Deck	2%	1%	1%	5%	91%
Issue with Barge	10%	2%	1%	1%	86%
Lightning	5%	1%	1%		93%
Low Fuel	1%	1%	1%	1%	96%
Squares Not Available	1%	1%	1%	1%	96%
Mechanical Problems at Yard	5%	2%	2%	2%	89%
Mechanical Problems with ARMOR 1	5%	1%	1%	1%	92%
Mechanical Problems with Tow Vessel	5%	1%	1%	1%	92%
Not Enough Employees	10%	5%	5%	5%	75%
Riverbank Slope/Landscape Not Complete	5%	5%	2%	1%	87%
River Currents/High Water Elevation	20%	10%	5%	2%	63%
River Low Water Elevation	10%	5%	2%	2%	81%
River Navigation Shut Down	5%	1%	1%	1%	92%
Unattended Barge	2%	1%	1%	0%	97%
Wind	5%	1%	1%	1%	92%
Mission Priority Changes*				2%	98%

* The risk of a Mission Priority Change has the potential to stop work of all future tasks when the risk is applied to a schedule. Therefore, for the purpose of determining risks to supplying ACMs for placement, it will not be used in the analysis.

The outcome of that delay is input as a probability of occurrence and given a delay in minimum and maximum hours. For this study, multiple percentages were input with varying hours of delay ranging from a “minor” delay of less than 1 hr, a “moderate” delay of between 1 and 3 hr, a “serious” delay of between 3 and 6 hr, and a “critical” delay of more than 6 hr. A possible source of delay could have different outcomes applied to multiple tasks.

2.2 Program

Risky Project software was used to analyze the risk events on the deployment schedule.

2.2.1 Potential delay impact


For the potential causes of delays identified for this project, a fixed delay was assigned to each of the tasks. There is no set length of delay that such an event would produce. The authors therefore asked MVK to indicate the probability that each event would cause a minor delay, moderate delay, serious delay, or critical delay. For purposes of this analysis, a minor delay was defined as a delay of less than 1 hr; moderate delay was more than 1 hr but less than 3 hr; serious delay was more than 3 hr but less than 6 hr; and a critical delay was defined as more than 6 hr.

2.2.2 Application of potential causes of delay percentages

For each identified potential cause of delays, a set of probabilities is entered into the database. Each potential cause is then assigned to tasks that it has a potential to impact. Additionally, the potential cause of delay is also assigned to the appropriate resources. There are several possible outcomes from the potential delay. Possible types of outcomes that could be relevant to this type schedule are Fixed delay (most likely), Relative Delay (less likely), Restart Task, End Task, Cancel Task, Cancel Task plus all successors, Safety Risk, Environmental Risk, Quality Risk, Performance Risk, and Technology Risk. For the purposes of this study and its inherent types of risks, a Fixed delay was chosen. Any delay that would cause the schedule to stop or for tasks to be canceled would not show where the appropriate choke points in the schedule would occur.

The outcomes are assigned a percent probability of a specified outcome. Further, mutually exclusive alternative probabilities are also assigned. The potential delay register for barge issues is given in Figure 26.

Figure 26. Potential delay register for issue with barge.



Each task in the schedule has multiple possible delays assigned to it. Each possible delay has multiple probabilities that are assigned to the associated task(s). A task that has two mechanisms for delay assigned will actually have eight possible delay probabilities assigned. These eight probabilities are what will be used in the Monte Carlo Analysis. However, the analysis will only use one probability of a risk per 1 run out of 800.

For each task in the schedule, a potential cause of delay can be assigned to be analyzed as a Parallel Risk. That is, it will always be run parallel to the other potential causes of delay assigned to that particular task and not sequentially during the analysis calculations. This can lessen the chance of an artificially high duration outcome in the analysis.

Potential causes of delays can also be assigned to the entire schedule as a "Global Risk." The Global Risks are applied to each (sub-) task in the schedule but will not show up in the number of potential causes of delays counted for each task.

2.3 Analysis

The Monte Carlo simulations are a probabilistic calculation based on the distribution of each risk on each assigned task in the schedule. For each of the individual calculations run on the schedule, a different outcome was chosen by the program and applied to either a low, base, or high duration for that alternative. Each answer is averaged through the entire number of specified simulations. Each simulation in this study was run 800 times.

The simulations were not stopped if convergence was reached before all the simulations had been completed, giving a higher level of confidence in the results.

The Monte Carlo analysis can pick multiple potential delays assigned to a task that may or that may not ever happen simultaneously, even though they could all happen to a particular task. For instance, when a barge is being offloaded onto ARMOR 1, there are four potential delays assigned to it. Those delays are fog on the river, ice on the boat deck, lightning, and mechanical problems on ARMOR 1. The four potential delays assigned during barge offloading may not all happen simultaneously. Additionally, assignment of weather type risks may be more important based on the time of day a task is scheduled to be performed. While the weather delays have been assigned based on when the task is scheduled to occur, in the outcome of the analysis, that task may then occur later in the day when there is less potential for that particular weather delay. This may slightly increase the calculated duration.

2.4 Sensitivity analysis

Although it is not possible to quantify the accuracy of the duration estimates on the probability of a delay for a task, it is possible to measure the sensitivity of the results. One measure of sensitivity would be to repeat a series of simulations where all of the times are doubled. That is, a minor delay would be 1.0 hr to 2 hr, a moderate delay would be 2.0 hr to 6 hr, etc.

Another option is to change the likelihood of a delay occurring. Because many of the potential delays already total 100% across the range of delays, it is not possible to double the estimated chance of occurrence as provided by MVK. It is, however, possible to cut the chance of occurrence in half.

The base duration was established by the 2019 current condition analysis based on the known information. A sensitivity analysis was conducted to establish the sensitivity to changes in delay durations and chance of occurrence of the probable delays for the 2,000 squares/day analysis for ACM placement at Gravolet, Rescue, and Lee Towhead.

The resulting times for the sensitivity analysis, given in Table 5, show less than a 13% deviation in total time when doubling the delay times and less than a 7% deviation in total time when the chance of occurrence is reduced by half. The reduction in the percent probabilities when reducing the input probabilities to half is a good indicator that the 2,000 squares/day, as well as the 4,000 squares/day and 6,000 squares/day, duration of delays has a high percentage of accuracy.

Table 5. Sensitivity analysis of reduction of risk percentage and increase in delay times.

	2,000 Squares/Day (hr)	One-Half Risk % (hr)	Double Delay Time (hr)
No Risk	296.5	296.5	296.5
Minimum	285	305	300
Median	425	370	525
Maximum	2,420	2,300	2,800
% Probability			
1	310	310	330
5	332	305	345
10	343.27	305.43	356.88
20	357.72	310.9	373.98
50	415.98	336.35	481.17
80	617.13	439.25	768.25
90	936.6	621.08	1,373.48
95	2,093.67	923.27	2,429.65
99	2,234.82	2,177.13	2,606.25

2.5 Analyzed conditions

Three production rates were analyzed to simulate conditions of 2,000 squares/day, 4,000 squares/day, and 6,000 squares/day. The season consisted of placement of ACM at three locations chosen from the 2019

season based on their remoteness from the nearest mat yard in their AOR. The base duration for the placement was compared to the actual placement times for the three locations during the 2019 season serving as a validation for the supply logistics process.

The four schedules analyzed in this study are based on the three site locations and the relocation time to travel and set up the MSU. The travel time is based on information from expert elicitation and vessel capacity. Barges are scheduled to travel to the square casting yards in the AOR that they will be working in next. The time to re-load the barges at the next yard and travel time to the next site are included in the schedules. Risks causing delay to these scheduled barge transport activities can have an impact on the continuation of work at each production site.

The Current Conditions schedule was input based on the average number of squares that could have been laid during the known duration at each of the three sites in 2019. Calculations were then made to determine the number of days that would be spent at each site and the number of barges needing to be off-loaded based on the total number of squares to be placed per day. Table 6 shows the results of those calculations.

Table 6. Days required at mat field.

Days at Mat Site				
	Current Condition (days/average squares/day)	2,000	4,000	6,000
Memphis	4/2,340	4.33	2.1	1.44
Vicksburg	9/2,077	9.35	4.67	3.12
St. Francisville	7/1,320.5	4.62	2.3	1.54

The results of the risk analysis are shown in Table 7 below. Included in the table are the estimated base durations without risk applied and the low, mean, and high durations when risks are applied.

Table 7. Estimated durations for base, minimum, mean, and maximum durations.

Duration to Complete Schedule in Hours				
	Current Condition	2,000 squares/day	4,000 squares/day	6,000 squares/day
Base	281.0	296.5	198.8	190.0
Minimum	281.1	302.8	230.8	275.0
Mean	574.1	574.6	471.0	503.0
Maximum	2,482.9	2,427.5	2,189.1	2,260.0


2.6 Current Condition

The schedule for the Current Condition model was input based on the number of squares laid at the site divided by the number of days the MSU was on site in 2019. This gave an average number of squares laid per day for use in comparing actual production to the three simulated production rate schedules. The base duration for the Current Conditions and the 2,000 squares/day schedule are mathematically similar for the Memphis and Vicksburg locations, with the St. Francisville location being significantly less in duration.

The total duration is 281.0 hr. The Mat Yard Mobilization components happen concurrently with mat placement and require a total of 204.85 hr to supply the ACM for the operations. Each task includes a low, base, and high duration for completion as well as a probability for success and probability of delay. The number of possible delays is captured for each task. For further review of the full schedules and Gantt charts with risks applied, see Appendix B.

The simulated results for the current rate including base duration with probable delays applied is shown in Figure 27. With all possible delays applied, the low duration time is 281.13 hr. The mean duration time is 574.05 hr. The high duration time is 2,482.88 hr. The colored columns show the number of total possible risks impacting the tasks with colors going from dark red for tasks with the most-assigned risks to white for those with no risks.

Figure 27. Results for Current Condition placement.



2.7 2,000 squares/day condition

The total duration of the analyzed schedule for 2,000 squares/day is 302.8 hr. The Mat Yard Mobilization components happen concurrently with mat placement and require a total of 223.4 hr to supply the ACM for the operations. Each task includes a low, base, and high duration for completion as well as a probability for success and probability of delay. The analysis showed that there were extended delays caused by limited resources, distance to mat yard, and impact of risk-delay durations. Figure 28 shows the results for the 2,000 squares/day rate.

Delays in the schedule are factored in before any risks are applied. The chart below lists the inherent delays in the base schedule with no risks applied. When risks are applied to the schedule, task durations are

lengthened, and delays are then compounded further. Table 8 lists only the inherent schedule delays and what happens to that task when the risks are analyzed. For further review of the full schedules and Gantt charts with risks applied, see Appendix B.


Table 8. Identified delays in schedule for 2,000 squares/day.

Where	#	Task	When	Why	Mitigation	With Risks Applied
St. Francisville	1	Load Squares on Barges 5-16 at St. Francisville Yard	Day 18	Barges 5-16 cannot be loaded at St. Francisville until they arrive from the Memphis site.	Had more barges been available, they could have been loaded 12-13 days sooner (if pre-cast).	
Memphis	2	1st Fleet of Barges Anchored at Memphis	Day 4	Waiting arrival of Barges 1-12 from Richardson Landing.	Coordination with square casting yard needed.	Adds additional 1 day of delay.
Vicksburg	3	Land Anchors Installed - D1V	Day 14	The MSU crew has a regularly scheduled weekend off as soon as the plant arrives at the Vicksburg site. Work does not begin until the Monday morning of their return. Net 2.5-day loss.	No recommendation.	Mean duration of task is extended 5.35 hr. Subsequent tasks are delayed due to risks applied to third fleet of barges being delayed by nearly 7 days.
St. Francisville	4	Stack Anchor Barge Moored at St. Francisville	Day 29	The MSU crew has a regularly scheduled weekend off as soon as the plant arrives at the St. Francisville site. Work does not begin until the Monday morning of their return. Net 2-day loss.	No recommendation.	Delay further compounded by risks associated with relocating MSU plant to St. Francisville site. Delay of 24 days.

In Table 8, the third instance of delay during this simulation occurs on the second day of ACM placement at the Rescue location. The schedule is delayed due to the stack barge tow not arriving in time to carry out subsequent tasks. In addition, the late arrival coincides with the scheduled off days for the mat-laying crew. This effectively delays the schedule by

approximately 2–3 days without any other possible delays being applied. While this study is based on only three locations on the river being scheduled for armoring, it does show how the arrival time of stacks from the yards (especially from farthest points) can negatively affect the schedule even without risks.

Figure 28. Results for 2,000 squares/day placement.



2.8 4,000 squares/day condition

For the 4,000 squares/day condition, the ARMOR 1 crew moved to one 10 hr shift. The total duration is 198.8 hr. The Mat Yard Mobilization components happen concurrently with mat placement and require a total of 291 hr to supply the ACM for the operations. Each task includes a low, base, and high duration for completion as well as a probability for success and probability of delay.

The simulated results for the 4,000 squares/day rate are shown in Figure 29. With all possible delays applied, the low duration time is 230.8 hr. The mean duration time is 471.0 hr. The high duration time is 2,189.1 hr. This analysis showed that there were extended delays caused by limited resources, distance to mat yard, and impact of risk-delay durations.


Delays in the schedule are factored in before any risks are applied. The chart below lists the inherent delays in the base schedule with no risks applied. When risks are applied to the schedule, task durations are lengthened, and delays are then compounded further. Table 9 lists only the inherent schedule delays and what happens to that task when the risks are analyzed. For further review of the full schedules and Gantt charts with risks applied, see Appendix B.

Table 9. Identified delays in schedule for 4,000 squares/day.

Where	#	Task	When	Why	Mitigation	With Risks applied
St. Francisville	1	Load Stacks on Barges 5-16 at St. Francisville Yard	Day 15	Barges 5-16 cannot be loaded at St. Francisville until they arrive from the Memphis site.	Had more barges been available, they could have been loaded 9-10 days sooner (if pre-cast).	
Memphis	2	T1-B1 towed in place	Day 5	The first fleet of barges does not arrive until the day after the plant and dozer arrive and are setup. Work cannot begin on mat placement until barges are delivered to site. Net 1-day loss.	Suggest longer hours or additional resources at square casting field to load squares on barges.	Mean duration of task is extended approximately 2.5 hr. Task is delayed 1 day.
Memphis	3	T2-B13 towed in place	Day 7	Work delayed until arrival of the second fleet of barges. Barges 13-15 do not arrive until end of day. Work begins at regular shift next morning. Net loss of 2.5 hr at end of day.	No recommendation. Loss is negligible and may vary with travel times.	Mean duration of task is extended 4.25 hr. Task is delayed 7 days due to previous tasks of barge arrival and off-loading risk delays.

Where	#	Task	When	Why	Mitigation	With Risks applied
Memphis	4	T4-B28 towed in place	Day 14	Compounded delay. The fourth fleet of barges does not arrive to finish out day 2 at Memphis site. Loss of 2 hr at end of workday. Barges arrive on Sunday. Crew begins regularly scheduled weekend off same day that barges are delayed. Work resumes the next Monday morning.	Suggest longer hours or additional resources at square casting field to load squares on barges.	Mean duration of task is extended approximately 0.2 hr. Task is delayed 15 days due to previous tasks of barge arrival and off-loading risk delays.
St. Francisville	5	T7-B17	Day 22	Work delayed until arrival of the seventh fleet of barges. Barges 17-20 do not arrive until end of day. Work begins at regular shift next morning. Net loss of 2 hr at end of day.	No recommendation. Loss is negligible and may vary with travel times.	Mean duration of task is extended 3.75 hours. Task is delayed 32 days due to previous tasks of barge arrival and off-loading risk delays.

Figure 29. Results for 4,000 squares/day placement.



2.9 6,000 squares/day condition

There was a change to the resources of the work crew on ARMOR 1 for the 6,000 squares/day condition. Instead of working one 10 hr shift, there are two 8 hr shifts. The total duration is 190 hr. The Mat Yard Mobilization components happen concurrently with mat placement and require a total of 187.8 hr to supply the ACM for the operations. Each task includes a low, base, and high duration for completion as well as a probability for success and probability of delay. The number of possible delays is captured for each task.

The simulated results for the 6,000 squares/day rate with probable delays applied is shown in Figure 30. With all possible delays applied, the low duration time is 275.0 hr. The mean duration time is 503.0 hr. The high duration time is 2,260.0 hr.

Delays in the schedule are factored in before any risks are applied. The chart below lists the inherent delays in the base schedule with no risks applied. When risks are applied to the schedule, task durations are lengthened, and delays are then compounded further. Table 10 lists only the inherent schedule delays and what happens to that tasks when the risks are analyzed. For further review of the full schedules and Gantt charts with risks applied, see Appendix B.

Table 10. Identified delays in schedule for 6,000 squares/day.

Where	#	Task	When	Why	Mitigation	With Risks Applied
St. Francisville	1	Load squares on Barges 5-16 at St. Francisville Yard	Day 20	Barges 5-16 cannot be loaded at St. Francisville until they arrive from the Memphis site.	Had more barges been available, they could have been loaded 4-5 days sooner (if pre-cast).	
Memphis	2	First Fleet of barges anchored at Memphis	Day 5	Waiting arrival of barges 1-12 from Richardson Landing.	Coordination with square casting yard needed.	Mean duration of task is extended approximately 2.8 hr. Task is delayed 1 day.
Memphis	3	T2-B13 towed in place	Day 7	Work delayed until arrival of the second fleet of barges. Barges 13-15 do not arrive until end of day. Work begins at regular shift next morning. Net loss of 3.5 hr at end of day.	No recommendation. Loss is negligible and may vary with travel times.	Mean duration of task is extended 5.5 hr. Task is delayed 8 days due to previous tasks of barge arrival and off-loading risk delays.
Memphis	4	T4-B28 towed in place	Day 10	Compounded delay. The fourth fleet of barges does not arrive to finish out day 2 at Memphis site. Loss of 9 hr of a workday on a Thursday. Barges arrive on Sunday. Crew begins regularly scheduled weekend off same day that barges are delayed. Work resumes the next Monday morning. Net loss of almost 4 days.	Suggest longer hours or additional resources at square casting field to load squares on barges. More available barges to be pre-placed at site.	Mean duration of task is extended 2.3 hr. Task is delayed 16 days due to previous tasks of barge arrival and off-loading risk delays.

Figure 30. Results for 6,000 squares/day placement.



3 Conclusion

In conclusion, the study shows that the three analyzed schedules for 2,000, 4,000, and 6,000 squares/day of production are feasible based on comparisons of actual production during the 2019 season in the three selected locations. However, when risks are applied to the schedules, the delays can become further compounded.

There are inherent schedule delays in the three analyzed schedules that are due to the current inventory of barges, vessels, and resources. The longest delays are seen when production levels at the site require more ACMs from a production facility. The normal wait time to load barges with ACMs at the square casting yards and transit time from the square casting yard to the site are the main driving factors for duration delays when risks are applied to higher production rate schedules. It is recommended that additional barges be added to mitigate negative impacts of inherent and applied risk delays.

While only three site locations were analyzed for this study, it can be inferred that additional square supply sites added to the schedules would reduce risks of delays. The production levels at the square casting yards and the number of barges available to be utilized are reasons for delay. This study assumed that the square casting yards would have a sufficient inventory of squares cast to load onto the barges as needed. Higher production rates at the field sites are going to require that more squares are available sooner for transportation to sites. If they are not cast and available, this will further increase the delay duration of the square loading and transportation tasks in the schedule. More sites along the river to armor will only increase the demand on the yards and the time to transport barges to and from sites and yards. It is recommended that additional mat yards and/or square storage locations may be required to mitigate inherent and applied risk delays, as well as additional resources to load barges at casting yards. Also having more loaded barges available for pre-positioning at sites will decrease transportation delays due to the increased production levels.

To reduce delays due to travel time with loaded and unloaded barges, it is recommended that nearest mat yard supply be utilized rather than the AOR restriction.

The three analyzed production schedules showed some minor delays due to regularly scheduled weekend off days in conjunction with delays of stack barge transportation to sites. When the arrival of needed stack barges is delayed, this increases the non-productive hours for the crew(s) generally at the end of a workday before a weekend off, or at the beginning of the next regularly scheduled workday. Additional barges being added to the fleet and available for loading and pre-positioning will decrease these delays.


References

Myrick, G. B., J. A. Hicks, L. I. Yates, and M. C. Allison. 2020. *Operation and Deployment Risk Assessment Report (RAR) for the City of Cedar Rapids, IA; Alternative and Sequencing Optimization for Removable Flood Barriers*. ERDC TR-20-3. Vicksburg, MS: US Army Engineer Research and Development Center.


Appendix A: Logistics Schedules

Figure A-1 and Figure A-2 present the schedule of events for 2,000 squares/day and 4,000 squares/day, respectively. Figure A-3 presents the schedule of events for 6,000 squares/day.

Figure A-1. Schedule of events for 2,000 squares/day.



Task ID	Task Name	August, 2020																																		
		04	06	08	10	12	14	16	18	20	22	24	26	28	30	01	03	05	07	09	11	13	15	17	19	21	23	25	27	29	31	0				
36	2nd Fleet of Barges Anchored at Memphis																																			
37	☐ ACM Placement - 1st Day																																			
38	Land Anchors Installed - D1M																																			
39	T1-B1 towed in place																																			
40	T1-B1 Offloaded																																			
41	T1-B2 towed in place																																			
42	T1-B2 Offloaded																																			
43	T1-B3 towed in place																																			
44	T1-B3 Offloaded																																			
45	T1-B4 towed in place																																			
46	T1-B4 Offloaded (1/2)																																			
47	☐ ACM Placement - 2nd Day																																			
48	Land Anchors Installed - D2M																																			
49	T1-B4 Offloaded (1/2)																																			
50	T1-B5 towed in place																																			
51	T1-B5 Offloaded																																			
52	T1-B6 towed in place																																			
53	T1-B6 Offloaded																																			
54	T1-B7 towed in place																																			
55	T1-B7 Offloaded																																			
56	☐ ACM Placement - 3rd Day																																			
57	Land Anchors Installed - D3M																																			
58	T1-B8 towed in place																																			
59	T1-B8 Offloaded																																			
60	T1-B9 towed in place																																			
61	T1-B9 Offloaded																																			
62	T1-B10 towed in place																																			
63	T1-B10 Offloaded																																			
64	T1-B11 towed in place																																			
65	T1-B11 Offloaded (1/2)																																			
66	☐ ACM Placement - 4th Day																																			
67	Land Anchors Installed - D4M																																			
68	T1-B11 Offloaded (1/2)																																			
69	T1-B12 towed in place																																			
70	T1-B12 Offloaded																																			




Task ID	Task Name	August, 2020																																	
		04	06	08	10	12	14	16	18	20	22	24	26	28	30	01	03	05	07	09	11	13	15	17	19	21	23	25	27	29	31	0			
106	T3-B19 Offloaded (1/2)																																		
107	☐ ACM Placement - 2nd Day Vicksburg																																		
108	Land Anchors Installed - D2V																																		
109	T3-B19 Offloaded (1/2)																																		
110	T3-B20 towed in place																																		
111	T3-B20 Offloaded																																		
112	Tow Barges 16-20 to St. Francisville Yard																																		
113	T3-B21 towed in place																																		
114	T3-B21 Offloaded																																		
115	T3-B22 towed in place																																		
116	T3-B22 Offloaded																																		
117	☐ ACM Placement - 3rd Day Vicksburg																																		
118	Land Anchors Installed - D3V																																		
119	T3-B23 towed in place																																		
120	T3-B23 Offloaded																																		
121	T3-B24 towed in place																																		
122	T3-B24 Offloaded																																		
123	T3-B25 towed in place																																		
124	T3-B25 Offloaded																																		
125	T3-B26 towed in place																																		
126	T3-B26 Offloaded (1/2)																																		
127	☐ ACM Placement - 4th Day Vicksburg																																		
128	Land Anchors Installed - D4V																																		
129	T3-B26 Offloaded (1/2)																																		
130	T3-B27 towed in place																																		
131	T3-B27 Offloaded																																		
132	T4-B28 towed in place																																		
133	T4-B28 Offloaded																																		
134	T4-B29 towed in place																																		
135	T4-B29 Offloaded																																		
136	☐ ACM Placement - 5th Day Vicksburg																																		
137	Land Anchors Installed - D5V																																		
138	T4-B30 towed in place																																		
139	T4-B30 Offloaded																																		
140	T4-B31 towed in place																																		

Task ID	Task Name	August, 2020																													
		04	06	08	10	12	14	16	18	20	22	24	26	28	30	01	03	05	07	09	11	13	15	17	19	21	23	25	27	29	31
141	T4-B31 Offloaded											┆																			
142	T4-B32 towed in place											┆																			
143	T4-B32 Offloaded											┆																			
144	T4-B33 towed in place											┆																			
145	T4-B33 Offloaded (1/2)											┆																			
146	ACM Placement - 6th Day Vicksburg											┆																			
147	Land Anchors Installed - D6V											┆																			
148	T4-B33 Offloaded (1/2)											┆																			
149	T4-B34 towed in place											┆																			
150	T4-B34 Offloaded											┆																			
151	T4-B35 towed in place											┆																			
152	T4-B35 Offloaded											┆																			
153	T4-B36 towed in place											┆																			
154	T4-B36 Offloaded											┆																			
155	ACM Placement - 7th Day Vicksburg											┆																			
156	Land Anchors Installed - D7V											┆																			
157	T4-B37 towed in place											┆																			
158	T4-B37 Offloaded											┆																			
159	T4-B38 towed in place											┆																			
160	T4-B38 Offloaded											┆																			
161	T4-B39 towed in place											┆																			
162	T4-B39 Offloaded											┆																			
163	T5-B40 towed in place											┆																			
164	T5-B40 Offloaded (1/2)											┆																			
165	ACM Placement - 8th Day Vicksburg											┆																			
166	Land Anchors Installed - D8V											┆																			
167	T5-B40 Offloaded (1/2)											┆																			
168	T5-B41 towed in place											┆																			
169	T5-B41 Offloaded											┆																			
170	T5-B42 towed in place											┆																			
171	T5-B42 Offloaded											┆																			
172	T5-B43 towed in place											┆																			
173	T5-B43 Offloaded											┆																			
174	ACM Placement - 9th Day Vicksburg											┆																			
175	Land Anchors Installed - D8V											┆																			

Task ID	Task Name	August, 2020																																			
		04	06	08	10	12	14	16	18	20	22	24	26	28	30	01	03	05	07	09	11	13	15	17	19	21	23	25	27	29	31	0					
176	T5-B1 towed in place																																				
177	T5-B1 Offloaded																																				
178	T5-B2 towed in place																																				
179	T5-B2 Offloaded																																				
180	T5-B3 towed in place																																				
181	T5-B3 Offloaded																																				
182	T5-B4 towed in place																																				
183	T5-B4 Offloaded (1/2)																																				
184	☐ ACM Placement - 10th Day Vicksburg																																				
185	T5-B4 Offloaded (1/2)																																				
186	☐ Relocate Floating Plant to St. Francisville Region																																				
187	Mat Anchor Barge towed to St. Francisville Region																																				
188	Quarter Boat towed to St. Francisville Region																																				
189	ARMOR ONE Anchor Barge towed to St. Francisville Region																																				
190	ARMOR ONE Unit towed to St. Francisville Region																																				
191	Dozers towed to St. Francisville Region																																				
192	☐ St. Francisville Region																																				
193	☐ Mobilize Floating Plant at St. Francisville Region																																				
194	Mat Anchor Barge Moored in place at St. F.																																				
195	Quarter Boat Moored in Place at St. F.																																				
196	ARMOR ONE Anchor Barge Moored in place at St. F.																																				
197	ARMOR ONE unit moored in place at St. F.																																				
198	Dozers placed at St. F.																																				
199	6th Fleet of Barges Anchored at St. F.																																				
200	7th Fleet of Barges Anchored at St. F.																																				
201	☐ ACM Placement - 1st Day St. Francisville																																				
202	Land Anchors Installed - D1SF																																				
203	T6-B5 towed in place																																				
204	T6-B5 Offloaded																																				
205	T6-B6 towed in place																																				
206	T6-B6 Offloaded																																				
207	T6-B7 towed in place																																				
208	T6-B7 Offloaded																																				
209	T6-B8 towed in place																																				
210	T6-B8 Offloaded (1/2)																																				

Task ID	Task Name	August, 2020																															Se	
		04	06	08	10	12	14	16	18	20	22	24	26	28	30	01	03	05	07	09	11	13	15	17	19	21	23	25	27	29	31	0		
211	ACM Placement 2nd Day St. Francisville																	▲	▲	▲	▲	▲												
212	Land Anchors Installed - D2SF																	▼																
213	T6-B8 Offloaded (1/2)																	▼																
214	T6-B9 towed in place																	▼																
215	T6-B9 Offloaded																	▼																
216	T6-B10 towed in place																	▼																
217	T6-B10 Offloaded																	▼																
218	T6-B11 towed in place																	▼																
219	T6-B11 Offloaded																	▼																
220	ACM Placement 3rd Day St. Francisville																	▲	▲	▲	▲	▲												
221	Land Anchors Installed - D3SF																	▼																
222	T6-B12 towed in place																	▼																
223	T6-B12 Offloaded																	▼																
224	T6-B13 towed in place																	▼																
225	T6-B13 Offloaded																	▼																
226	T6-B14 towed in place																	▼																
227	T6-B14 Offloaded																	▼																
228	T6-B15 towed in place																	▼																
229	T6-B15 Offloaded (1/2)																	▼																
230	ACM Placement 4th Day St. Francisville																	▲	▲	▲	▲	▲												
231	Land Anchors Installed - D4SF																	▼																
232	T6-B15 Offloaded (1/2)																	▼																
233	T6-B16 towed in place																	▼																
234	T6-B16 Offloaded																	▼																
235	T7-B17 towed in place																	▼																
236	T7-B17 Offloaded																	▼																
237	T7-B18 towed in place																	▼																
238	T7-B18 Offloaded																	▼																
239	ACM Placement 5th Day St. Francisville																	▲	▲	▲	▲	▲												
240	Land Anchors Installed - D4SF																	▼																
241	T7-B19 towed in place																	▼																
242	T7-B19 Offloaded																	▼																
243	T7-B20 towed in place																	▼																
244	T7-B20 Offloaded																	▼																
245	End of Season																	◆																

Figure A-2. Schedule of events for 4,000 squares/day.



Task Name		August, 2020																												
		04	06	08	10	12	14	16	18	20	22	24	26	28	30	01	03	05	07	09	11	13	15	17	19	21	23	25	27	29
57	T1-B8 towed in place																													
58	T1-B8 Offloaded																													
59	T1-B9 towed in place																													
60	T1-B9 Offloaded																													
61	T1-B10 towed in place																													
62	T1-B10 Offloaded																													
63	T1-B11 towed in place																													
64	T1-B11 Offloaded																													
65	T1-B12 towed in place																													
66	T1-B12 Offloaded																													
67	Tow Barges 1-4 to Delta Yard																													
68	Tow Barges 5-12 to St. Francisville Yard from Delta Yard																													
69	T2-B13 towed in place																													
70	T2-B13 Offloaded																													
71	T2-B14 towed in place																													
72	T2-B14 Offloaded (1/2)																													
73	ACM Placement - 3rd Day																													
74	Land Anchors Installed - D3M																													
75	T2-B14 Offloaded (1/2)																													
76	T2-B15 towed in place																													
77	T2-B15 Offloaded																													
78	Tow Barges 13-15 to St. Francisville Yard from Memphis																													
79	Relocate Floating Plant to Vicksburg																													
80	Mat Anchor Barge towed to Vicksburg																													
81	Quarter Boat towed to Vicksburg																													
82	ARMOR ONE Anchor Barge towed to Vicksburg																													
83	ARMOR ONE Unit towed to Vicksburg																													
84	Dozers towed to Vicksburg																													
85	Vicksburg Region																													
86	Mobilize Floating Plant for Vicksburg Region																													
87	Mat Anchor Barge Moored in place at Vicksburg																													
88	Quarter Boat Moored in Place at Vicksburg																													
89	ARMOR ONE Anchor Barge Moored in place at Vicksburg																													
90	ARMOR ONE unit moored in place at Vicksburg																													
91	Dozers placed at Vicksburg																													


Task ID	Task Name	August, 2020																												
		04	06	08	10	12	14	16	18	20	22	24	26	28	30	01	03	05	07	09	11	13	15	17	19	21	23	25	27	29
92	3rd Fleet of Barges Anchored																													
93	4th Fleet of Barges Anchored																													
94	5th Fleet of Barges Anchored																													
95	ACM Placement - 1st Day																													
96	Land Anchors Installed - D1V																													
97	T3-B16 towed in place																													
98	T3-B16 Offloaded																													
99	T3-B17 towed in place																													
100	T3-B17 Offloaded																													
101	T3-B18 towed in place																													
102	T3-B18 Offloaded																													
103	T3-B19 towed in place																													
104	T3-B19 Offloaded																													
105	T3-B20 towed in place																													
106	T3-B20 Offloaded																													
107	<i>Tow Barges 16-20 to St. Francisville Yard</i>																													
108	T3-B21 towed in place																													
109	T3-B21 Offloaded																													
110	T3-B22 towed in place																													
111	T3-B22 Offloaded (3/4)																													
112	ACM Placement - 2nd Day																													
113	Land Anchors Installed - D2V																													
114	T3-B22 Offloaded (1/4)																													
115	T3-B23 towed in place																													
116	T3-B23 Offloaded																													
117	T3-B24 towed in place																													
118	T3-B24 Offloaded																													
119	T3-B25 towed in place																													
120	T3-B25 Offloaded																													
121	T3-B26 towed in place																													
122	T3-B26 Offloaded																													
123	T3-B27 towed in place																													
124	T3-B27 Offloaded																													
125	T4-B28 towed in place																													
126	T4-B28 Offloaded																													

	Task Name	August, 2020																												
		04	06	08	10	12	14	16	18	20	22	24	26	28	30	01	03	05	07	09	11	13	15	17	19	21	23	25	27	29
127	T4-B29 towed in place																													
128	T4-B29 Offloaded (1/2)																													
129	<input type="checkbox"/> ACM Placement - 3rd Day																													
130	Land Anchors Installed - D3V																													
131	T4-B29 Offloaded (1/2)																													
132	T4-B30 towed in place																													
133	T4-B30 Offloaded																													
134	T4-B31 towed in place																													
135	T4-B31 Offloaded																													
136	T4-B32 towed in place																													
137	T4-B32 Offloaded																													
138	T4-B33 towed in place																													
139	T4-B33 Offloaded																													
140	T4-B34 towed in place																													
141	T4-B34 Offloaded																													
142	T4-B35 towed in place																													
143	T4-B35 Offloaded																													
144	T4-B36 towed in place																													
145	T4-B36 Offloaded (1/4)																													
146	<input type="checkbox"/> ACM Placement - 4th Day																													
147	Land Anchors Installed - D4V																													
148	T4-B36 Offloaded (3/4)																													
149	T4-B37 towed in place																													
150	T4-B37 Offloaded																													
151	T4-B38 towed in place																													
152	T4-B38 Offloaded																													
153	T4-B39 towed in place																													
154	T4-B39 Offloaded																													
155	T5-B40 towed in place																													
156	T5-B40 Offloaded																													
157	T5-B41 towed in place																													
158	T5-B41 Offloaded																													
159	T5-B42 towed in place																													
160	T5-B42 Offloaded																													
161	<input type="checkbox"/> ACM Placement - 5th Day																													

	Task Name	August, 2020																												
		04	06	08	10	12	14	16	18	20	22	24	26	28	30	01	03	05	07	09	11	13	15	17	19	21	23	25	27	29
162	Land Anchors Installed - D5V																													
163	T5-B43 towed in place																													
164	T5-B43 Offloaded																													
165	T5-B1 towed in place																													
166	T5-B1 Offloaded																													
167	T5-B2 towed in place																													
168	T5-B2 Offloaded																													
169	T5-B2 towed in place																													
170	T5-B3 Offloaded																													
171	T5-B3 towed in place																													
172	T5-B4 Offloaded																													
173	Relocate Floating Plant to St. Francisville Region																													
174	Mat Anchor Barge towed to St. Francisville Region																													
175	Quarter Boat towed to St. Francisville Region																													
176	ARMOR ONE Anchor Barge towed to St. Francisville Region																													
177	ARMOR ONE Unit towed to St. Francisville Region																													
178	Dozers towed to St. Francisville Region																													
179	St. Francisville Region																													
180	Mobilize Floating Plant at St. Francisville Region																													
181	Mat Anchor Barge Moored in place at St. F.																													
182	Quarter Boat Moored in Place at St. F.																													
183	ARMOR ONE Anchor Barge Moored in place at St. F.																													
184	ARMOR ONE unit moored in place at St. F.																													
185	Dozers placed at St. F.																													
186	6th Fleet of Barges Anchored at St. F.																													
187	7th Fleet of Barges Anchored at St. F.																													
188	ACM Placement - 1st Day St. Francisville																													
189	Land Anchors Installed - D1SF																													
190	T6-B5 towed in place																													
191	T6-B5 Offloaded																													
192	T6-B6 towed in place																													
193	T6-B6 Offloaded																													
194	T6-B7 towed in place																													
195	T6-B7 Offloaded																													
196	T6-B8 towed in place																													

Task ID	Task Name	August, 2020																												
		04	06	08	10	12	14	16	18	20	22	24	26	28	30	01	03	05	07	09	11	13	15	17	19	21	23	25	27	29
197	T6-B8 Offloaded																													
198	T6-B9 towed in place																													
199	T6-B9 Offloaded																													
200	T6-B10 towed in place																													
201	T6-B10 Offloaded																													
202	T6-B11 towed in place																													
203	T6-B11 Offloaded (3/4)																													
204	ACM Placement 2nd Day St. Franisville																													
205	Land Anchors Installed - D2SF																													
206	T6-B11 Offloaded (1/4)																													
207	T6-B12 towed in place																													
208	T6-B12 Offloaded																													
209	T6-B13 towed in place																													
210	T6-B13 Offloaded																													
211	T6-B14 towed in place																													
212	T6-B14 Offloaded																													
213	T6-B15 towed in place																													
214	T6-B15 Offloaded																													
215	T6-B16 towed in place																													
216	T6-B16 Offloaded																													
217	T7-B17 towed in place																													
218	T7-B17 Offloaded																													
219	T7-B18 towed in place																													
220	T7-B18 Offloaded (1/2)																													
221	ACM Placement 3rd Day St. Francisville																													
222	Land Anchors Installed - D3SF																													
223	T7-B18 Offloaded (1/2)																													
224	T7-B19 towed in place																													
225	T7-B19 Offloaded																													
226	T7-B20 towed in place																													
227	T7-B20 Offloaded																													
228	End of Season																													

Figure A-3. Schedule of events for 6,000 squares/day.



Project Name		ARMOR 1 - 6000 Mats/day		Date: 01/11/21 13:30																											
	Task Name	August, 2020																													
		05	07	09	11	13	15	17	19	21	23	25	27	29	31	02	04	06	08	10	12	14	16	18	20	22	24	26	28	30	
56	T1-B9 towed in place																														Barge 9,MV Harrison
57	T1-B9 Offloaded																														Barge 9,ARMOR ONE CREW 2nd Shift
58	T1-B10 towed in place																														Barge 10,MV Harrison
59	T1-B10 Offloaded																														Barge 10,ARMOR ONE CREW 2nd Shift
60	T1-B11 towed in place																														Barge 11,MV Harrison
61	T1-B11 Offloaded (1/4)																														Barge 11,ARMOR ONE CREW 2nd Shift
62	ACM Placement - 2nd Day																														
63	Land Anchors Installed - D2M																														Dozer 1,Dozer 2,Dozer 3,Dozer 4,Dozer Crew - 1st shift(400%)
64	T1-B11 Offloaded (3/4)																														Barge 11,ARMOR ONE Crew 1st shift
65	T1-B12 towed in place																														Barge 12,MV Harrison
66	T1-B12 Offloaded																														Barge 12,ARMOR ONE Crew 1st shift
67	Tow Barges 1-4 to Delta Yard																														Barge 1,Barge 2,Barge 3,Barge 4,MV Mississippi
68	Tow Barges 5-12 to St. Francisville Yard from Delta Yard																														MV Mississippi,Barge 5,Barge 6,Barge 7,Barge 8,Barge 9,Barge 10,Barge 11,Barge 12
69	T2-B13 towed in place																														Barge 13,MV Harrison
70	T2-B13 Offloaded																														Barge 13,ARMOR ONE Crew 1st shift
71	T2-B14 towed in place																														Barge 14,MV Harrison
72	T2-B14 Offloaded																														Barge 14,ARMOR ONE Crew 1st shift
73	T2-B15 towed in place																														Barge 15,MV Harrison
74	T2-B15 Offloaded																														Barge 15,ARMOR ONE Crew 1st shift
75	Tow Barges 13-15 to St. Francisville Yard from Memphis																														MV Mississippi,Barge 13,Barge 14,Barge 15
76	Relocate Floating Plant to Vicksburg																														
77	Mat Anchor Barge towed to Vicksburg																														Anchor Barge 1 - VKS,Anchor Barge 2 - VKS,ARMOR ONE Crew 1st shift
78	Quarter Boat towed to Vicksburg																														Quarter Barge,ARMOR ONE Crew 1st shift,MV Benyaurd
79	ARMOR ONE Anchor Barge towed to Vicksburg																														ARMOR ONE Crew 1st shift
80	ARMOR ONE Unit towed to Vicksburg																														ARMOR ONE Crew 1st shift,ARMOR ONE Unit,MV William James
81	Dozers towed to Vicksburg																														Dozer 1,Dozer 2,Dozer 3,Dozer 4,Dozer Crew(400%)
82	Vicksburg Region																														
83	Mobilize Floating Plant for Vicksburg Region																														
84	Mat Anchor Barge Moored in place at Vicksburg																														ARMOR ONE Crew 1st shift
85	Quarter Boat Moored in Place at Vicksburg																														Quarter Barge,ARMOR ONE Crew 1st shift,MV Benyaurd
86	ARMOR ONE Anchor Barge Moored in place at Vicksburg																														ARMOR ONE Crew 1st shift
87	ARMOR ONE unit moored in place at Vicksburg																														ARMOR ONE Crew 1st shift,ARMOR ONE Unit,MV William James
88	Dozers placed at Vicksburg																														Dozer 1,Dozer 2,Dozer 3,Dozer 4,Dozer Crew(400%)
89	3rd Fleet of Barges Anchored																														Barge 16,Barge 17,Barge 18,Barge 19,Barge 20,Barge 21,Barge 22,Barge 23,Barge 24,B
90	4th Fleet of Barges Anchored																														Barge 28,Barge 29,Barge 30,Barge 31,Barge 32,Barge 33,Barge 34,Barge 35,Ba

Project Name	ARMOR 1 - 6000 Mats/day	Date: 01/11/21 13:30
--------------	-------------------------	----------------------

Task Name	August, 2020																												
	05	07	09	11	13	15	17	19	21	23	25	27	29	31	02	04	06	08	10	12	14	16	18	20	22	24	26	28	30
91 5th Fleet of Barges Anchored																													
92 <input type="checkbox"/> ACM Placement - 1st Day																													
93 Land Anchors Installed - D1V																													
94 T3-B16 towed in place																													
95 T3-B16 Offloaded																													
96 T3-B17 towed in place																													
97 T3-B17 Offloaded																													
98 T3-B18 towed in place																													
99 T3-B18 Offloaded																													
100 T3-B19 towed in place																													
101 T3-B19 Offloaded																													
102 T3-B20 towed in place																													
103 T3-B20 Offloaded																													
104 <i>Tow Barges 16-20 to St. Francisville Yard</i>																													
105 T3-B21 towed in place																													
106 T3-B21 Offloaded																													
107 T3-B22 towed in place																													
108 T3-B22 Offloaded																													
109 T3-B23 towed in place																													
110 T3-B23 Offloaded																													
111 T3-B24 towed in place																													
112 T3-B24 Offloaded																													
113 T3-B25 towed in place																													
114 T3-B25 Offloaded (1/4)																													
115 <input type="checkbox"/> ACM Placement - 2nd Day																													
116 Land Anchors Installed - D2V																													
117 T3-B25 Offloaded (3/4)																													
118 T3-B26 towed in place																													
119 T3-B26 Offloaded																													
120 T3-B27 towed in place																													
121 T3-B27 Offloaded																													
122 T4-B28 towed in place																													
123 T4-B28 Offloaded																													
124 T4-B29 towed in place																													
125 T4-B29 Offloaded																													

Project Name		ARMOR 1 - 6000 Mats/day	Date: 01/11/21 13:30																																																						
Task Name	August, 2020																																																								
	05	07	09	11	13	15	17	19	21	23	25	27	29	31	02	04	06	08	10	12	14	16	18	20	22	24	26	28	30																												
126									↓	Barge 30, MV Harrison																																															
127									↓	Barge 30, ARMOR ONE Crew 1st shift																																															
128									↓	Barge 31, MV Harrison																																															
129									↓	Barge 31, ARMOR ONE CREW 2nd Shift																																															
130									↓	Barge 32, MV Harrison																																															
131									↓	Barge 32, ARMOR ONE CREW 2nd Shift																																															
132									↓	Barge 33, MV Harrison																																															
133									↓	Barge 33, ARMOR ONE CREW 2nd Shift																																															
134									↓	Barge 34, MV Harrison																																															
135									↓	Barge 34, ARMOR ONE CREW 2nd Shift																																															
136									↓	Barge 35, MV Harrison																																															
137									↓	Barge 35, ARMOR ONE CREW 2nd Shift																																															
138	☐ ACM Placement - 3rd Day								↓																																																
139									↓	Dozer 1, Dozer 2, Dozer 3, Dozer 4, Dozer Crew(400%)																																															
140									↓	Barge 35, ARMOR ONE Crew 1st shift																																															
141									↓	Barge 36, MV Harrison																																															
142									↓	Barge 36, ARMOR ONE Crew 1st shift																																															
143									↓	Barge 37, MV Harrison																																															
144									↓	Barge 37, ARMOR ONE Crew 1st shift																																															
145									↓	Barge 38, MV Harrison																																															
146									↓	Barge 38, ARMOR ONE Crew 1st shift																																															
147									↓	Barge 39, MV Harrison																																															
148									↓	Barge 39, ARMOR ONE Crew 1st shift																																															
149									↓	Barge 40, MV Harrison																																															
150									↓	Barge 40, ARMOR ONE CREW 2nd Shift																																															
151									↓	Barge 41, MV Harrison																																															
152									↓	Barge 41, ARMOR ONE CREW 2nd Shift																																															
153									↓	Barge 42, MV Harrison																																															
154									↓	Barge 42, ARMOR ONE CREW 2nd Shift																																															
155									↓	Barge 43, MV Harrison																																															
156									↓	Barge 43, ARMOR ONE CREW 2nd Shift																																															
157									↓	Barge 1, MV Harrison																																															
158									↓	Barge 1, ARMOR ONE CREW 2nd Shift																																															
159									↓	Barge 2, MV Harrison																																															
160									↓	Barge 2, ARMOR ONE CREW 2nd Shift																																															

Project Name		ARMOR 1 - 6000 Mats/day		Date: 01/11/21 13:30																										
Task ID	Task Name	August, 2020																												
		05	07	09	11	13	15	17	19	21	23	25	27	29	31	02	04	06	08	10	12	14	16	18	20	22	24	26	28	30
161	ACM Placement - 4th Day																													
162	Land Anchors Installed - D4V																													
163	T5-B2 Offloaded (3/4)																													
164	T5-B2 towed in place																													
165	T5-B3 Offloaded																													
166	T5-B3 towed in place																													
167	T5-B4 Offloaded																													
168	Relocate Floating Plant to St. Francisville Region																													
169	Mat Anchor Barge towed to St. Francisville Region																													
170	Quarter Boat towed to St. Francisville Region																													
171	ARMOR ONE Anchor Barge towed to St. Francisville Region																													
172	ARMOR ONE Unit towed to St. Francisville Region																													
173	Dozers towed to St. Francisville Region																													
174	St. Francisville Region																													
175	Mobilize Floating Plant at St. Francisville Region																													
176	Mat Anchor Barge Moored in place at St. F.																													
177	Quarter Boat Moored in Place at St. F.																													
178	ARMOR ONE Anchor Barge Moored in place at St. F.																													
179	ARMOR ONE unit moored in place at St. F.																													
180	Dozers placed at St. F.																													
181	6th Fleet of Barges Anchored at St. F.																													
182	7th Fleet of Barges Anchored at St. F.																													
183	ACM Placement - 1st Day St. Francisville																													
184	Land Anchors Installed - D1SF																													
185	T6-B5 towed in place																													
186	T6-B5 Offloaded																													
187	T6-B6 towed in place																													
188	T6-B6 Offloaded																													
189	T6-B7 towed in place																													
190	T6-B7 Offloaded																													
191	T6-B8 towed in place																													
192	T6-B8 Offloaded																													
193	T6-B9 towed in place																													
194	T6-B9 Offloaded																													
195	T6-B10 towed in place																													

Project Name		ARMOR 1 - 6000 Mats/day	Date: 01/11/21 13:30																											
Task Name		August, 2020																												
		05	07	09	11	13	15	17	19	21	23	25	27	29	31	02	04	06	08	10	12	14	16	18	20	22	24	26	28	30
196	T6-B10 Offloaded																													
197	T6-B11 towed in place																													
198	T6-B11 Offloaded																													
199	T6-B12 towed in place																													
200	T6-B12 Offloaded																													
201	T6-B13 towed in place																													
202	T6-B13 Offloaded																													
203	T6-B14 towed in place																													
204	T6-B14 Offloaded																													
205	T6-B15 towed in place																													
206	T6-B15 Offloaded (1/4)																													
207	ACM Placement 2nd Day St. Franisville																													
208	Land Anchors Installed - D2SF																													
209	T6-B15 Offloaded (3/4)																													
210	T6-B16 towed in place																													
211	T6-B16 Offloaded																													
212	T7-B17 towed in place																													
213	T7-B17 Offloaded																													
214	T7-B18 towed in place																													
215	T7-B18 Offloaded																													
216	T7-B19 towed in place																													
217	T7-B19 Offloaded																													
218	T7-B20 towed in place																													
219	T7-B20 Offloaded																													
220	End of Season																													

Appendix B: Schedules with Risks Calculated


Figures B-1 through B-4 present schedules with risks calculated.

Figure B-1. Schedule of events with risks calculated for the current schedule.


	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020				September, 2020				October, 2020				November, 2020				December,							
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29	06	13				
1	☐ BEGINNING OF SEASON	281.13 hr	574.05 hr	2482.88 hr	0																												
2	☐ Mat Yard Mobilization	203.15 hr	306 hr	941 hr	0																												
3	☐ Memphis Yard Mobilization	51 hr	71 hr	168.07 hr	0																												
4	Tie off empty barges at Memphis Yard	2.1 hr	7.68 hr	34.68 hr	8																												
5	Lash and Prep loaded barges for transport at Memphis Yard	2.28 hr	2.3 hr	40.07 hr	8																												
6	Load Mats on Barges 1-12 at Memphis Yard	24.65 hr	31 hr	50.35 hr	18																												
7	Tow 1st Fleet of Barges from Richardson Landing to Memphis Re	20.75 hr	25.57 hr	29.58 hr	28																												
8	Load Mats on Barges 13-15 at Memphis Yard	6.58 hr	10 hr	18.97 hr	18																												
9	Tow 2nd Fleet of Barges from Richardson Landing to Memphis R	36.05 hr	39.92 hr	53 hr	28																												
10	☐ Delta Yard Mobilization	121.97 hr	175 hr	465.9 hr	0																												
11	Tie off empty barges at Delta Yard	2.53 hr	9.85 hr	36.18 hr	8																												
12	Lash and Prep loaded barges for transport at Delta Yard	2.5 hr	2.5 hr	40.3 hr	8																												
13	Load Mats on Barges 16-27 at Delta Yard	28.2 hr	35.5 hr	58.25 hr	18																												
14	Tow 3rd Fleet of Barges from Delta Yard to Vicksburg	21.42 hr	26.47 hr	40.35 hr	28																												
15	Load Mats on Barges 28-39 at Delta Yard	27.6 hr	27.6 hr	49.4 hr	18																												
16	Tow 4th Fleet of Barges from Delta Yard to Vicksburg	61.35 hr	66.45 hr	73.47 hr	28																												
17	Load Mats on Barges 40-43, 1-4 at Delta Yard	16.1 hr	21.6 hr	31.33 hr	18																												
18	Tow 5th Fleet of Barges from Delta Yard to Vicksburg	59.08 hr	66.37 hr	93.28 hr	28																												
19	☐ St. Francisville Yard Mobilization	102.15 hr	141.07 hr	400 hr	0																												
20	Tie off empty barges at St. Francisville Yard	2.15 hr	6.07 hr	10.45 hr	8																												
21	Lash and Prep loaded barges for transport at St. Francisville Yarc	2.68 hr	4.17 hr	37.02 hr	8																												
22	Load Mats on Barges 5-16 at St. Francisville Yard	28.1 hr	30 hr	45.83 hr	18																												
23	Tow 6th Fleet of Barges from St. Francisville to New Orleans	21.92 hr	25.78 hr	53.65 hr	28																												
24	Loat Mats on Barges 17-20 at St. Francisville Yard	8.7 hr	11.15 hr	24.78 hr	18																												
25	Tow 7th Fleet of Barges from St. Francisville to New Orleans	69.72 hr	73.47 hr	107.13 hr	28																												
26	☐ ACM Placement	281.13 hr	574.05 hr	2482.88 hr	0																												
27	Training	10.17 hr	11.98 hr	13.93 hr	0																												
28	Blessing of the Fleet	7.18 hr	9.02 hr	28.98 hr	0																												
29	☐ Memphis Region	83.65 hr	140.85 hr	550.63 hr	0																												
30	☐ Mobilize Floating Plant for Memphis Region	83.65 hr	140.85 hr	550.63 hr	0																												
31	Mat Anchor Barge Moored in place at Memphis	1.62 hr	4.68 hr	25.58 hr	4																												
32	Quarter Boat Moored in Place at Memphis	3.27 hr	7.08 hr	19.73 hr	8																												
33	ARMOR ONE Anchor Barge Moored in place at Memphis	4.85 hr	6.55 hr	15.6 hr	4																												
34	ARMOR ONE unit moored in place at Memphis	5.32 hr	8.3 hr	29.78 hr	4																												
35	Dozers placed at Memphis	2.18 hr	2.18 hr	30.78 hr	12																												

	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020			August, 2020			September, 2020			October, 2020			November, 2020			December,					
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22
36	1st Fleet of Barges Anchored at Memphis	3.15 hr	4.87 hr	14.63 hr	6																					
37	2nd Fleet of Barges Anchored at Memphis	3.45 hr	5.37 hr	11.5 hr	6																					
38	<input type="checkbox"/> ACM Placement - 1st Day	27.43 hr	48.75 hr	154.82 hr	0																					
39	Land Anchors Installed - D1M	0.62 hr	8.38 hr	38.92 hr	19																					
40	T1-B1 towed in place	0.3 hr	3.58 hr	24.27 hr	14																					
41	T1-B1 Offloaded	2.32 hr	2.32 hr	20.97 hr	10																					
42	T1-B2 towed in place	0.28 hr	3.48 hr	15.2 hr	12																					
43	T1-B2 Offloaded	1.68 hr	7.12 hr	25.68 hr	8																					
44	T1-B3 towed in place	0.25 hr	3.52 hr	9.68 hr	12																					
45	T1-B3 Offloaded	3.32 hr	3.32 hr	11.1 hr	8																					
46	T1-B4 towed in place	0.47 hr	3.73 hr	23.22 hr	12																					
47	T1-B4 Offloaded	1.82 hr	5.55 hr	24.82 hr	8																					
48	<input type="checkbox"/> ACM Placement - 2nd Day	12.93 hr	30 hr	119.87 hr	0																					
49	Land Anchors Installed - D2M	0.82 hr	5 hr	16.8 hr	19																					
50	T1-B5 towed in place	0.27 hr	3.75 hr	19.98 hr	14																					
51	T1-B5 Offloaded	3.22 hr	3.22 hr	21.03 hr	10																					
52	T1-B6 towed in place	0.25 hr	3.53 hr	8.97 hr	12																					
53	T1-B6 Offloaded	1.52 hr	5.05 hr	15.1 hr	8																					
54	T1-B7 towed in place	0.33 hr	3.53 hr	24.27 hr	12																					
55	T1-B7 Offloaded	2.83 hr	5 hr	22.1 hr	8																					
56	T1-B8 towed in place	0.32 hr	3.57 hr	22.8 hr	12																					
57	T1-B8 Offloaded	3.38 hr	3.38 hr	9.42 hr	8																					
58	<input type="checkbox"/> ACM Placement - 3rd Day	38.7 hr	47.97 hr	165.32 hr	0																					
59	Land Anchors Installed - D3M	0.25 hr	0.25 hr	16.33 hr	19																					
60	T1-B9 towed in place	0.27 hr	3.63 hr	22.8 hr	14																					
61	T1-B9 Offloaded	2.4 hr	2.4 hr	15.98 hr	10																					
62	T1-B10 towed in place	0.25 hr	3.55 hr	21.93 hr	12																					
63	T1-B10 Offloaded	3.18 hr	3.18 hr	21.13 hr	8																					
64	T1-B11 towed in place	0.45 hr	3.53 hr	11.42 hr	12																					
65	T1-B11 Offloaded	2.88 hr	7.12 hr	16.1 hr	8																					
66	T1-B12 towed in place	0.45 hr	3.47 hr	27.38 hr	12																					
67	T1-B12 Offloaded	2.03 hr	3.3 hr	12.27 hr	8																					
68	<i>Tow Barges 1-4 to Delta Yard</i>	46.05 hr	51.93 hr	86.65 hr	28																					
69	<i>Tow Barges 5-12 to St. Francisville Yard from Delta Yard</i>	20.23 hr	25.73 hr	47.45 hr	28																					
70	<input type="checkbox"/> ACM Placement - 4th Day	9.77 hr	26.68 hr	110.28 hr	0																					

	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020				September, 2020				October, 2020				November, 2020				December,			
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29	06	13
71	Land Anchors Installed - D4M	1.5 hr	6.68 hr	16.93 hr	19																								
72	T2-B13 towed in place	0.28 hr	3.62 hr	29.03 hr	14																								
73	T2-B13 Offloaded	2.72 hr	9.52 hr	17.42 hr	10																								
74	T2-B14 towed in place	0.38 hr	3.58 hr	40.97 hr	12																								
75	T2-B14 Offloaded	2.88 hr	5 hr	24.07 hr	8																								
76	T2-B15 towed in place	0.37 hr	3.67 hr	43.35 hr	12																								
77	T2-B15 Offloaded	1.88 hr	1.88 hr	10.75 hr	8																								
78	☐ Relocate Floating Plant to Vicksburg	12.8 hr	17.52 hr	30.58 hr	0																								
79	Mat Anchor Barge towed to Vicksburg	22.28 hr	29.1 hr	72.58 hr	22																								
80	Quarter Boat towed to Vicksburg	18.28 hr	29.1 hr	69.35 hr	22																								
81	ARMOR ONE Anchor Barge towed to Vicksburg	19.93 hr	28.77 hr	56.63 hr	18																								
82	ARMOR ONE Unit towed to Vicksburg	19 hr	29.1 hr	54.92 hr	22																								
83	Dozers towed to Vicksburg	22.02 hr	29.25 hr	54.05 hr	22																								
84	☐ Vicksburg Region	93.08 hr	290 hr	1642.13 hr	0																								
85	☐ Mobilize Floating Plant for Vicksburg Region	93.08 hr	290 hr	1642.13 hr	0																								
86	Mat Anchor Barge Moored in place at Vicksburg	1.9 hr	3.03 hr	13.13 hr	4																								
87	Quarter Boat Moored in Place at Vicksburg	4.03 hr	5.83 hr	29.45 hr	8																								
88	ARMOR ONE Anchor Barge Moored in place at Vicksburg	4.53 hr	6.43 hr	12.68 hr	4																								
89	ARMOR ONE unit moored in place at Vicksburg	5.57 hr	10 hr	26.28 hr	4																								
90	Dozers placed at Vicksburg	1.7 hr	5.4 hr	26.07 hr	12																								
91	3rd Fleet of Barges Anchored	2.03 hr	5.42 hr	25.63 hr	6																								
92	4th Fleet of Barges Anchored	3.48 hr	5.45 hr	13.17 hr	6																								
93	5th Fleet of Barges Anchored	2.23 hr	5.32 hr	18.4 hr	6																								
94	☐ ACM Placement - 1st Day	10.65 hr	108.1 hr	648.97 hr	0																								
95	Land Anchors Installed - D1V	0.23 hr	10 hr	38.87 hr	19																								
96	T3-B16 towed in place	0.25 hr	3.63 hr	30.23 hr	14																								
97	T3-B16 Offloaded	2.13 hr	5 hr	20.52 hr	10																								
98	T3-B17 towed in place	0.32 hr	3.5 hr	26.78 hr	12																								
99	T3-B17 Offloaded	2.95 hr	2.95 hr	11.38 hr	8																								
100	T3-B18 towed in place	0.28 hr	3.63 hr	43.63 hr	12																								
101	T3-B18 Offloaded	2.28 hr	4.08 hr	11.82 hr	8																								
102	T3-B19 towed in place	0.27 hr	3.6 hr	30.42 hr	12																								
103	T3-B19 Offloaded	1.93 hr	8.1 hr	11.73 hr	8																								
104	☐ ACM Placement - 2nd Day	19.35 hr	21.9 hr	132.47 hr	0																								
105	Land Anchors Installed - D2V	0.77 hr	1.9 hr	8.48 hr	19																								



	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020			August, 2020				September, 2020				October, 2020				November, 2020				December,		
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29
106	T3-B20 towed in place	0.37 hr	3.52 hr	40.58 hr	14																						
107	T3-B20 Offloaded	1.68 hr	7.93 hr	24.6 hr	10																						
108	<i>Tow Barges 16-20 to St. Francisville Yard</i>	40.47 hr	45.48 hr	70.9 hr	28																						
109	T3-B21 towed in place	0.38 hr	3.5 hr	32.92 hr	12																						
110	T3-B21 Offloaded	2.9 hr	2.9 hr	23.68 hr	8																						
111	T3-B22 towed in place	0.4 hr	3.67 hr	32.72 hr	12																						
112	T3-B22 Offloaded	1.65 hr	2.32 hr	9.48 hr	8																						
113	T3-B23 towed in place	0.35 hr	3.63 hr	27.7 hr	12																						
114	T3-B23 Offloaded	2.32 hr	2.32 hr	11.43 hr	8																						
115	ACM Placement - 3rd Day	11.92 hr	20 hr	126.52 hr	0																						
116	Land Anchors Installed - D3V	0.13 hr	0.13 hr	15.33 hr	19																						
117	T3-B24 towed in place	0.43 hr	3.65 hr	36.95 hr	14																						
118	T3-B24 Offloaded	1.65 hr	1.65 hr	20.23 hr	10																						
119	T3-B25 towed in place	0.38 hr	3.62 hr	32.57 hr	12																						
120	T3-B25 Offloaded	2.57 hr	5.42 hr	11.85 hr	8																						
121	T3-B26 towed in place	0.3 hr	3.48 hr	28.48 hr	12																						
122	T3-B26 Offloaded	3.37 hr	3.37 hr	13.62 hr	8																						
123	T3-B27 towed in place	0.42 hr	3.6 hr	28.5 hr	12																						
124	T3-B27 Offloaded	2.67 hr	6.17 hr	10.83 hr	8																						
125	ACM Placement - 4th Day	10.77 hr	30 hr	137.47 hr	0																						
126	Land Anchors Installed - D4V	0.37 hr	2.42 hr	21.33 hr	19																						
127	T4-B28 towed in place	0.33 hr	3.52 hr	34.83 hr	14																						
128	T4-B28 Offloaded	2.48 hr	2.48 hr	16.62 hr	10																						
129	T4-B29 towed in place	0.3 hr	3.5 hr	28.43 hr	12																						
130	T4-B29 Offloaded	1.62 hr	7.77 hr	17.78 hr	8																						
131	T4-B30 towed in place	0.43 hr	3.6 hr	40.68 hr	12																						
132	T4-B30 Offloaded	3.22 hr	3.22 hr	9.23 hr	8																						
133	T4-B31 towed in place	0.27 hr	3.58 hr	38.58 hr	12																						
134	T4-B31 Offloaded	1.75 hr	3.8 hr	15.42 hr	8																						
135	ACM Placement - 5th Day	9.5 hr	30 hr	156.4 hr	0																						
136	Land Anchors Installed - D5V	1.15 hr	5 hr	20.63 hr	19																						
137	T4-B32 towed in place	0.33 hr	3.75 hr	44.1 hr	14																						
138	T4-B32 Offloaded	1.18 hr	1.18 hr	24.52 hr	10																						
139	T4-B33 towed in place	0.27 hr	3.65 hr	42.67 hr	12																						
140	T4-B33 Offloaded	1.87 hr	6.73 hr	19.65 hr	8																						



	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020			August, 2020			September, 2020			October, 2020			November, 2020			December,			
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08
141	T4-B34 towed in place	0.4 hr	3.58 hr	32.57 hr	12																			
142	T4-B34 Offloaded	1.27 hr	3.95 hr	20.45 hr	8																			
143	T4-B35 towed in place	0.33 hr	3.63 hr	37.78 hr	12																			
144	T4-B35 Offloaded	2.7 hr	2.7 hr	11.82 hr	8																			
145	<input type="checkbox"/> ACM Placement - 6th Day	10.77 hr	30 hr	131.32 hr	0																			
146	Land Anchors Installed - D6V	0.77 hr	7.05 hr	10 hr	19																			
147	T4-B36 towed in place	0.35 hr	3.7 hr	38.98 hr	14																			
148	T4-B36 Offloaded	1.92 hr	1.92 hr	8.75 hr	10																			
149	T4-B37 towed in place	0.27 hr	3.55 hr	39.7 hr	12																			
150	T4-B37 Offloaded	1.8 hr	5.32 hr	12.23 hr	8																			
151	T4-B38 towed in place	0.45 hr	3.45 hr	37.53 hr	12																			
152	T4-B38 Offloaded	3.42 hr	5.78 hr	19.07 hr	8																			
153	T4-B39 towed in place	0.25 hr	3.63 hr	26.92 hr	12																			
154	T4-B39 Offloaded	1.55 hr	1.55 hr	23.13 hr	8																			
155	<input type="checkbox"/> ACM Placement - 7th Day	10.67 hr	17.58 hr	157.03 hr	0																			
156	Land Anchors Installed - D7V	0.43 hr	10 hr	21.9 hr	19																			
157	T5-B40 towed in place	0.28 hr	3.7 hr	43.12 hr	14																			
158	T5-B40 Offloaded	2.18 hr	2.18 hr	22.72 hr	10																			
159	T5-B41 towed in place	0.32 hr	3.65 hr	29.03 hr	12																			
160	T5-B41 Offloaded	2.18 hr	2.18 hr	19.22 hr	8																			
161	T5-B42 towed in place	0.28 hr	3.62 hr	43.32 hr	12																			
162	T5-B42 Offloaded	2.25 hr	2.25 hr	16.98 hr	8																			
163	T5-B43 towed in place	0.28 hr	3.6 hr	28.42 hr	12																			
164	T5-B43 Offloaded	2.58 hr	7.58 hr	25.33 hr	8																			
165	<input type="checkbox"/> ACM Placement - 8th Day	9.52 hr	32.42 hr	151.97 hr	0																			
166	Land Anchors Installed - D8V	0.17 hr	2.42 hr	11.4 hr	19																			
167	T5-B1 towed in place	0.42 hr	3.62 hr	39.13 hr	14																			
168	T5-B1 Offloaded	1.82 hr	5.77 hr	25.48 hr	10																			
169	T5-B2 towed in place	0.25 hr	3.52 hr	29.13 hr	12																			
170	T5-B2 Offloaded	2.2 hr	4.67 hr	9.07 hr	8																			
171	T5-B3 towed in place	0.42 hr	3.57 hr	40.13 hr	12																			
172	T5-B3 Offloaded	1.77 hr	1.77 hr	21.9 hr	8																			
173	T5-B4 towed in place	0.37 hr	3.5 hr	32.67 hr	12																			
174	T5-B4 Offloaded	2.47 hr	6.87 hr	22.13 hr	8																			
175	<input type="checkbox"/> Relocate Floating Plant to St. Francisville Region	25.4 hr	28.5 hr	47.87 hr	0																			

	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020			August, 2020			September, 2020			October, 2020			November, 2020			December,				
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15
176	Mat Anchor Barge towed to St. Francisville Region	60.72 hr	61.9 hr	89.68 hr	22																				
177	Quarter Boat towed to St. Francisville Region	47.9 hr	62.23 hr	89.1 hr	22																				
178	ARMOR ONE Anchor Barge towed to St. Francisville Region	49.82 hr	62.12 hr	107.68 hr	22																				
179	ARMOR ONE Unit towed to St. Francisville Region	57.42 hr	62.2 hr	79.83 hr	22																				
180	Dozers towed to St. Francisville Region	56.12 hr	62.2 hr	100.35 hr	22																				
181	☐ St. Francisville Region	75.63 hr	363.05 hr	2271.88 hr	0																				
182	☐ Mobilize Floating Plant at St. Francisville Region	75.63 hr	363.05 hr	2271.88 hr	0																				
183	Mat Anchor Barge Moored in place at St. F.	1.33 hr	1.33 hr	17.68 hr	4																				
184	Quarter Boat Moored in Place at St. F.	2.77 hr	2.92 hr	16.28 hr	8																				
185	ARMOR ONE Anchor Barge Moored in place at St. F.	2.5 hr	2.5 hr	22.83 hr	4																				
186	ARMOR ONE unit moored in place at St. F.	5.6 hr	8.57 hr	15.08 hr	4																				
187	Dozers placed at St. F.	1.4 hr	3.83 hr	17.53 hr	16																				
188	6th Fleet of Barges Anchored at St. F.	2.5 hr	5.42 hr	23.73 hr	6																				
189	7th Fleet of Barges Anchored at St. F.	2.17 hr	5.22 hr	9.2 hr	6																				
190	☐ ACM Placement - 1st Day St. Francisville	10.8 hr	240 hr	1696.68 hr	0																				
191	Land Anchors Installed - D1SF	0.33 hr	8.32 hr	30.2 hr	19																				
192	T6-B5 towed in place	0.45 hr	3.67 hr	29.68 hr	14																				
193	T6-B5 Offloaded	2.43 hr	2.43 hr	17.7 hr	10																				
194	T6-B6 towed in place	0.32 hr	3.55 hr	37.77 hr	12																				
195	T6-B6 Offloaded	2.48 hr	4.17 hr	25.25 hr	8																				
196	T6-B7 towed in place	0.33 hr	3.43 hr	27.98 hr	12																				
197	T6-B7 Offloaded (1/4)	0.95 hr	4.63 hr	17.45 hr	8																				
198	☐ ACM Placement 2nd Day St. Francisville	9.77 hr	20 hr	98.73 hr	0																				
199	Land Anchors Installed - D2SF	0.88 hr	1.83 hr	23.62 hr	19																				
200	T6-B7 Offloaded (3/4)	2.43 hr	8.15 hr	23.48 hr	10																				
201	T6-B8 towed in place	0.4 hr	3.58 hr	37.18 hr	12																				
202	T6-B8 Offloaded	2.98 hr	7.78 hr	9.32 hr	8																				
203	T6-B9 towed in place	0.27 hr	3.53 hr	33.6 hr	12																				
204	T6-B9 Offloaded (1/2)	2.8 hr	2.8 hr	15.42 hr	8																				
205	☐ ACM Placement 3rd Day St. Francisville	9.42 hr	9.42 hr	78.02 hr	0																				
206	Land Anchors Installed - D3SF	0.37 hr	0.37 hr	10.25 hr	19																				
207	T6-B9 Offloaded (1/2)	2.68 hr	2.68 hr	11.38 hr	10																				
208	T6-B10 towed in place	0.25 hr	3.7 hr	39.02 hr	14																				
209	T6-B10 Offloaded	3.43 hr	3.43 hr	16.23 hr	8																				
210	T6-B11 towed in place	0.25 hr	3.62 hr	39.97 hr	12																				





Figure B-2. Schedule of events with risks calculated for 2,000 squares/day.

	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020				September, 2020				October, 2020				November, 2020				December, 2020							
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29	06	13				
1	<input type="checkbox"/> BEGINNING OF SEASON	302.83 hr	574.63 hr	2427.53 hr	0																												
2	<input type="checkbox"/> Mat Yard Mobilization	223.38 hr	324.17 hr	1010 hr	0																												
3	<input type="checkbox"/> Memphis Yard Mobilization	50 hr	70 hr	166.5 hr	0																												
4	Tie off empty barges at Memphis Yard	2.1 hr	7.07 hr	42.07 hr	8																												
5	Lash and Prep loaded barges for transport at Memphis Yard	2.28 hr	2.93 hr	35.1 hr	8																												
6	Load Mats on Barges 1-12 at Memphis Yard	24.65 hr	30 hr	35.47 hr	18																												
7	Tow 1st Fleet of Barges from Richardson Landing to Memphis Regi	20.95 hr	25.52 hr	36.73 hr	28																												
8	Load Mats on Barges 13-15 at Memphis Yard	6.58 hr	10 hr	26.38 hr	18																												
9	Tow 2nd Fleet of Barges from Richardson Landing to Memphis Reg	36.05 hr	39.9 hr	69.48 hr	28																												
10	<input type="checkbox"/> Delta Yard Mobilization	130.97 hr	148.2 hr	287.37 hr	0																												
11	Tie off empty barges at Delta Yard	2.53 hr	10 hr	37.6 hr	8																												
12	Lash and Prep loaded barges for transport at Delta Yard	2.5 hr	2.75 hr	45.73 hr	8																												
13	Load Mats on Barges 16-27 at Delta Yard	28.2 hr	36.33 hr	47.25 hr	18																												
14	Tow 3rd Fleet of Barges from Delta Yard to Vicksburg	21.42 hr	26.4 hr	36.2 hr	28																												
15	Load Mats on Barges 28-39 at Delta Yard	27.6 hr	30.85 hr	40.9 hr	18																												
16	Tow 4th Fleet of Barges from Delta Yard to Vicksburg	61.35 hr	66.43 hr	81.28 hr	28																												
17	Load Mats on Barges 40-43, 1-4 at Delta Yard	22.52 hr	22.52 hr	41.57 hr	18																												
18	Tow 5th Fleet of Barges from Delta Yard to Vicksburg	61.07 hr	66.38 hr	86.35 hr	28																												
19	<input type="checkbox"/> St. Francisville Yard Mobilization	161.12 hr	235.02 hr	766.78 hr	0																												
20	Tie off empty barges at St. Francisville Yard	2.17 hr	2.17 hr	31.33 hr	8																												
21	Lash and Prep loaded barges for transport at St. Francisville Yard	2.85 hr	10 hr	46.1 hr	8																												
22	Load Mats on Barges 5-16 at St. Francisville Yard	25.75 hr	35 hr	37.87 hr	18																												
23	Tow 6th Fleet of Barges from St. Francisville to New Orleans	21.92 hr	25.82 hr	48.87 hr	28																												
24	Loat Mats on Barges 17-20 at St. Francisville Yard	8.7 hr	10.32 hr	18.93 hr	18																												
25	Tow 7th Fleet of Barges from St. Francisville to New Orleans	68.58 hr	73.37 hr	102 hr	28																												
26	<input type="checkbox"/> ACM Placement	302.83 hr	574.63 hr	2427.53 hr	0																												
27	Training	10.17 hr	11.98 hr	13.93 hr	0																												
28	Blessing of the Fleet	7.18 hr	8.02 hr	27.07 hr	0																												
29	<input type="checkbox"/> Memphis Region	93.53 hr	160 hr	630.38 hr	0																												
30	<input type="checkbox"/> Mobilize Floating Plant for Memphis Region	93.53 hr	160 hr	630.38 hr	0																												
31	Quarter Boat Moored in Place at Memphis	3.17 hr	7 hr	24.03 hr	8																												
32	ARMOR ONE Anchor Barge Moored in place at Memphis	3.07 hr	3.07 hr	18.13 hr	4																												
33	ARMOR ONE unit moored in place at Memphis	4.77 hr	10 hr	25.48 hr	4																												
34	Dozers placed at Memphis	1.95 hr	5 hr	26.27 hr	12																												
35	1st Fleet of Barges Anchored at Memphis	3.67 hr	4.88 hr	22.57 hr	6																												


	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020			August, 2020			September, 2020			October, 2020			November, 2020			December, 2020				
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15
36	2nd Fleet of Barges Anchored at Memphis	3.45 hr	5.25 hr	13.92 hr	6																				
37	☐ ACM Placement - 1st Day	8.95 hr	31.18 hr	180.92 hr	0																				
38	Land Anchors Installed - D1M	0.28 hr	7.3 hr	39.53 hr	19																				
39	T1-B1 towed in place	0.28 hr	3.7 hr	16.68 hr	14																				
40	T1-B1 Offloaded	2.1 hr	7.2 hr	25.42 hr	10																				
41	T1-B2 towed in place	0.32 hr	3.63 hr	24.45 hr	14																				
42	T1-B2 Offloaded	1.88 hr	1.88 hr	24.02 hr	8																				
43	T1-B3 towed in place	0.27 hr	3.7 hr	20.92 hr	12																				
44	T1-B3 Offloaded	2.48 hr	5.87 hr	14.13 hr	8																				
45	T1-B4 towed in place	0.3 hr	3.6 hr	18.53 hr	12																				
46	T1-B4 Offloaded (1/2)	1.17 hr	1.18 hr	17.83 hr	8																				
47	☐ ACM Placement - 2nd Day	10.38 hr	28.82 hr	116.17 hr	0																				
48	Land Anchors Installed - D2M	0.55 hr	8.82 hr	18.35 hr	19																				
49	T1-B4 Offloaded (1/2)	1.98 hr	1.98 hr	18.95 hr	10																				
50	T1-B5 towed in place	0.3 hr	3.65 hr	32.2 hr	14																				
51	T1-B5 Offloaded	1.72 hr	5 hr	11.63 hr	8																				
52	T1-B6 towed in place	0.48 hr	3.58 hr	15.15 hr	12																				
53	T1-B6 Offloaded	1.42 hr	6.65 hr	14.07 hr	8																				
54	T1-B7 towed in place	0.25 hr	3.62 hr	36.53 hr	12																				
55	T1-B7 Offloaded	3.68 hr	3.68 hr	17.08 hr	8																				
56	☐ ACM Placement - 3rd Day	9.73 hr	12.58 hr	135.5 hr	0																				
57	Land Anchors Installed - D3M	0.55 hr	10 hr	15.88 hr	19																				
58	T1-B8 towed in place	1.13 hr	3.33 hr	16.08 hr	14																				
59	T1-B8 Offloaded	2.27 hr	2.27 hr	14.85 hr	10																				
60	T1-B9 towed in place	0.33 hr	3.52 hr	26.95 hr	14																				
61	T1-B9 Offloaded	2.42 hr	2.42 hr	16.25 hr	8																				
62	T1-B10 towed in place	0.4 hr	3.6 hr	29.13 hr	12																				
63	T1-B10 Offloaded	2.38 hr	2.38 hr	19.07 hr	8																				
64	T1-B11 towed in place	0.35 hr	3.65 hr	41 hr	12																				
65	T1-B11 Offloaded (1/2)	0.92 hr	2.58 hr	22.33 hr	8																				
66	☐ ACM Placement - 4th Day	31.82 hr	49.47 hr	128.45 hr	0																				
67	Land Anchors Installed - D4M	0.77 hr	7.35 hr	25.97 hr	19																				
68	T1-B11 Offloaded (1/2)	0.77 hr	0.77 hr	10.33 hr	10																				
69	T1-B12 towed in place	2.13 hr	3.48 hr	23.93 hr	14																				
70	T1-B12 Offloaded	2.98 hr	3.93 hr	26.32 hr	10																				




	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020			August, 2020				September, 2020			October, 2020			November, 2020			December, 2020			
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15
71	Tow Barges 1-4 to Delta Yard	46.08 hr	51.75 hr	59.53 hr	28																				
72	Tow Barges 5-12 to St. Francisville Yard from Delta Yard	20.08 hr	25.22 hr	39.33 hr	28																				
73	T2-B13 towed in place	0.42 hr	3.65 hr	28.05 hr	12																				
74	T2-B13 Offloaded	2.32 hr	8.4 hr	12.98 hr	8																				
75	T2-B14 towed in place	0.25 hr	3.57 hr	44.27 hr	12																				
76	T2-B14 Offloaded	1.52 hr	3.12 hr	11.03 hr	8																				
77	☐ ACM Placement - 5th Day	7.5 hr	16.85 hr	60.35 hr	0																				
78	Land Anchors Installed - D5M	5.3 hr	6.85 hr	24.18 hr	19																				
79	T2-B15 towed in place	0.27 hr	3.33 hr	24.35 hr	14																				
80	T2-B15 Offloaded	1.93 hr	6.3 hr	25.82 hr	10																				
81	☐ Relocate Floating Plant to Vicksburg	12.28 hr	12.28 hr	29.33 hr	0																				
82	Mat Anchor Barge towed to Vicksburg	21.78 hr	29.07 hr	59.58 hr	22																				
83	Quarter Boat towed to Vicksburg	20.83 hr	29.1 hr	61.93 hr	22																				
84	ARMOR ONE Anchor Barge towed to Vicksburg	22.23 hr	28.83 hr	71.33 hr	18																				
85	ARMOR ONE Unit towed to Vicksburg	21.15 hr	29.17 hr	50.72 hr	22																				
86	Dozers towed to Vicksburg	20.1 hr	29.12 hr	64.82 hr	22																				
87	☐ Vicksburg Region	125.95 hr	310 hr	1711.83 hr	0																				
88	☐ Mobilize Floating Plant for Vicksburg Region	125.95 hr	310 hr	1711.83 hr	0																				
89	Mat Anchor Barge Moored in place at Vicksburg	1.88 hr	3.48 hr	8.58 hr	4																				
90	Quarter Boat Moored in Place at Vicksburg	3.62 hr	10 hr	15.4 hr	8																				
91	ARMOR ONE Anchor Barge Moored in place at Vicksburg	3.78 hr	10 hr	27.57 hr	4																				
92	ARMOR ONE unit moored in place at Vicksburg	7.03 hr	7.35 hr	15.53 hr	4																				
93	Dozers placed at Vicksburg	3.78 hr	7.48 hr	12.18 hr	12																				
94	3rd Fleet of Barges Anchored	2.77 hr	5.27 hr	11.65 hr	6																				
95	4th Fleet of Barges Anchored	2.72 hr	5.33 hr	9.63 hr	6																				
96	5th Fleet of Barges Anchored	2.4 hr	5.42 hr	22.42 hr	6																				
97	☐ ACM Placement - 1st Day Vicksburg	10.12 hr	100 hr	696.05 hr	0																				
98	Land Anchors Installed - D1V	0.4 hr	7.35 hr	39.18 hr	19																				
99	T3-B16 towed in place	0.3 hr	3.62 hr	29.5 hr	14																				
100	T3-B16 Offloaded	2.53 hr	2.53 hr	14.63 hr	10																				
101	T3-B17 towed in place	0.33 hr	3.65 hr	41.83 hr	12																				
102	T3-B17 Offloaded	1.6 hr	4.52 hr	13.95 hr	8																				
103	T3-B18 towed in place	0.45 hr	3.52 hr	27.9 hr	12																				
104	T3-B18 Offloaded	2.05 hr	5.53 hr	9.58 hr	8																				
105	T3-B19 towed in place	0.28 hr	3.5 hr	29.52 hr	12																				




	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020			August, 2020			September, 2020			October, 2020			November, 2020			December, 2020				
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15
106	T3-B19 Offloaded (1/2)	1.9 hr	1.9 hr	16.05 hr	8																				
107	☐ ACM Placement - 2nd Day Vicksburg	19.88 hr	20 hr	126.4 hr	0																				
108	Land Anchors Installed - D2V	2.03 hr	8.98 hr	18.85 hr	19																				
109	T3-B19 Offloaded (1/2)	1.23 hr	1.23 hr	19.08 hr	10																				
110	T3-B20 towed in place	0.3 hr	3.53 hr	32.55 hr	14																				
111	T3-B20 Offloaded	1.65 hr	8.18 hr	10.7 hr	10																				
112	<i>Tow Barges 16-20 to St. Francisville Yard</i>	39.2 hr	45.42 hr	69.78 hr	28																				
113	T3-B21 towed in place	0.37 hr	3.67 hr	32.02 hr	12																				
114	T3-B21 Offloaded	1.37 hr	1.37 hr	10.4 hr	8																				
115	T3-B22 towed in place	0.28 hr	3.57 hr	28 hr	12																				
116	T3-B22 Offloaded	1.78 hr	1.78 hr	22.45 hr	8																				
117	☐ ACM Placement - 3rd Day Vicksburg	11.17 hr	20 hr	128.25 hr	0																				
118	Land Anchors Installed - D3V	2.87 hr	2.87 hr	16.28 hr	19																				
119	T3-B23 towed in place	0.48 hr	3.25 hr	14.72 hr	12																				
120	T3-B23 Offloaded	1.75 hr	1.75 hr	9.53 hr	10																				
121	T3-B24 towed in place	0.45 hr	3.63 hr	35.13 hr	14																				
122	T3-B24 Offloaded	2.8 hr	5 hr	23.63 hr	8																				
123	T3-B25 towed in place	0.25 hr	3.63 hr	26.77 hr	12																				
124	T3-B25 Offloaded	1.53 hr	5 hr	21.22 hr	8																				
125	T3-B26 towed in place	0.3 hr	3.57 hr	33.83 hr	12																				
126	T3-B26 Offloaded (1/2)	0.73 hr	0.73 hr	20.7 hr	8																				
127	☐ ACM Placement - 4th Day Vicksburg	11.6 hr	30 hr	142.13 hr	0																				
128	Land Anchors Installed - D4V	2.18 hr	7.07 hr	25.57 hr	19																				
129	T3-B26 Offloaded (1/2)	2.25 hr	2.93 hr	26.65 hr	10																				
130	T3-B27 towed in place	0.4 hr	3.35 hr	22.85 hr	14																				
131	T3-B27 Offloaded	1.37 hr	5 hr	19.07 hr	8																				
132	T4-B28 towed in place	0.33 hr	3.75 hr	32.57 hr	12																				
133	T4-B28 Offloaded	1.9 hr	1.9 hr	20.75 hr	8																				
134	T4-B29 towed in place	0.3 hr	3.53 hr	37.9 hr	12																				
135	T4-B29 Offloaded	3 hr	7.07 hr	12.83 hr	8																				
136	☐ ACM Placement - 5th Day Vicksburg	9.38 hr	30 hr	118.72 hr	0																				
137	Land Anchors Installed - D5V	1.27 hr	5 hr	10.27 hr	19																				
138	T4-B30 towed in place	0.4 hr	3.8 hr	27.08 hr	14																				
139	T4-B30 Offloaded	1.75 hr	1.75 hr	9.25 hr	10																				
140	T4-B31 towed in place	0.3 hr	2.87 hr	19.73 hr	12																				



	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020			August, 2020			September, 2020			October, 2020			November, 2020			December, 2020				
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15
141	T4-B31 Offloaded	2.12 hr	8.22 hr	11.98 hr	8																				
142	T4-B32 towed in place	0.38 hr	3.58 hr	37.63 hr	12																				
143	T4-B32 Offloaded	2.07 hr	2.22 hr	18.48 hr	8																				
144	T4-B33 towed in place	0.33 hr	3.65 hr	26.72 hr	12																				
145	T4-B33 Offloaded (1/2)	0.77 hr	2.12 hr	21.55 hr	8																				
146	☐ ACM Placement - 6th Day Vicksburg	13.23 hr	30 hr	108.52 hr	0																				
147	Land Anchors Installed - D6V	3.37 hr	6.55 hr	22.87 hr	19																				
148	T4-B33 Offloaded (1/2)	0.95 hr	3.45 hr	23.85 hr	10																				
149	T4-B34 towed in place	0.35 hr	3.83 hr	21.88 hr	14																				
150	T4-B34 Offloaded	1.95 hr	6.05 hr	12.43 hr	8																				
151	T4-B35 towed in place	0.45 hr	3.57 hr	17.37 hr	12																				
152	T4-B35 Offloaded	3.57 hr	3.57 hr	25.67 hr	8																				
153	T4-B36 towed in place	0.33 hr	3.55 hr	35.33 hr	12																				
154	T4-B36 Offloaded	2.27 hr	4.73 hr	10.07 hr	8																				
155	☐ ACM Placement - 7th Day Vicksburg	14 hr	14 hr	132.75 hr	0																				
156	Land Anchors Installed - D7V	3.57 hr	7.63 hr	23.93 hr	19																				
157	T4-B37 towed in place	0.35 hr	3.55 hr	10.5 hr	14																				
158	T4-B37 Offloaded	2.25 hr	2.25 hr	21.3 hr	10																				
159	T4-B38 towed in place	0.27 hr	3.93 hr	24.37 hr	14																				
160	T4-B38 Offloaded	4.57 hr	4.57 hr	13.8 hr	8																				
161	T4-B39 towed in place	0.27 hr	3.9 hr	7.87 hr	12																				
162	T4-B39 Offloaded	1.35 hr	1.35 hr	22.12 hr	8																				
163	T5-B40 towed in place	0.42 hr	3.57 hr	40.07 hr	12																				
164	T5-B40 Offloaded (1/2)	0.97 hr	0.97 hr	12.82 hr	8																				
165	☐ ACM Placement - 8th Day Vicksburg	15.67 hr	31.43 hr	124.5 hr	0																				
166	Land Anchors Installed - DBV	2.22 hr	10 hr	22.17 hr	19																				
167	T5-B40 Offloaded (1/2)	2.87 hr	2.87 hr	19.03 hr	14																				
168	T5-B41 towed in place	0.25 hr	3.37 hr	18.27 hr	12																				
169	T5-B41 Offloaded	2.05 hr	4.52 hr	24.3 hr	8																				
170	T5-B42 towed in place	2.75 hr	3.23 hr	10.7 hr	12																				
171	T5-B42 Offloaded	2.57 hr	8.85 hr	21.55 hr	8																				
172	T5-B43 towed in place	0.25 hr	3.5 hr	15.53 hr	12																				
173	T5-B43 Offloaded	2.72 hr	2.72 hr	17.32 hr	8																				
174	☐ ACM Placement - 9th Day Vicksburg	15.33 hr	38.28 hr	111.77 hr	0																				
175	Land Anchors Installed - DBV	4.45 hr	8.4 hr	23.4 hr	19																				



	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020				September, 2020				October, 2020				November, 2020				December			
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29	06	13
176	T5-B1 towed in place	0.3 hr	4.1 hr	10.37 hr	14																								
177	T5-B1 Offloaded	2.02 hr	8.33 hr	17.42 hr	10																								
178	T5-B2 towed in place	1.25 hr	3.45 hr	21.92 hr	14																								
179	T5-B2 Offloaded	1.18 hr	4.12 hr	8.97 hr	8																								
180	T5-B3 towed in place	0.3 hr	2.9 hr	13.37 hr	12																								
181	T5-B3 Offloaded	3.5 hr	3.5 hr	13.23 hr	8																								
182	T5-B4 towed in place	0.7 hr	4.13 hr	14.92 hr	12																								
183	T5-B4 Offloaded (1/2)	1.63 hr	8.37 hr	19.08 hr	8																								
184	☐ ACM Placement - 10th Day Vicksburg	1.93 hr	1.93 hr	22.75 hr	0																								
185	T5-B4 Offloaded (1/2)	1.93 hr	1.93 hr	22.75 hr	10																								
186	☐ Relocate Floating Plant to St. Francisville Region	8.55 hr	30 hr	48.17 hr	0																								
187	Mat Anchor Barge towed to St. Francisville Region	54.02 hr	61.82 hr	79.18 hr	22																								
188	Quarter Boat towed to St. Francisville Region	56.07 hr	62.33 hr	87.47 hr	22																								
189	ARMOR ONE Anchor Barge towed to St. Francisville Region	54.85 hr	62.2 hr	107.75 hr	22																								
190	ARMOR ONE Unit towed to St. Francisville Region	58.77 hr	62.25 hr	90.53 hr	22																								
191	Dozers towed to St. Francisville Region	57.7 hr	62.23 hr	98.73 hr	22																								
192	☐ St. Francisville Region	62.83 hr	324.63 hr	2177.53 hr	0																								
193	☐ Mobilize Floating Plant at St. Francisville Region	62.83 hr	324.63 hr	2177.53 hr	0																								
194	Mat Anchor Barge Moored in place at St. F.	1.08 hr	1.17 hr	9 hr	4																								
195	Quarter Boat Moored in Place at St. F.	1.93 hr	3.15 hr	15.42 hr	8																								
196	ARMOR ONE Anchor Barge Moored in place at St. F.	1.78 hr	1.78 hr	14.43 hr	4																								
197	ARMOR ONE unit moored in place at St. F.	4.83 hr	8.65 hr	11.92 hr	4																								
198	Dozers placed at St. F.	1.28 hr	4.87 hr	13.58 hr	16																								
199	6th Fleet of Barges Anchored at St. F.	2.4 hr	5.27 hr	20.87 hr	6																								
200	7th Fleet of Barges Anchored at St. F.	2.72 hr	5.38 hr	15.72 hr	6																								
201	☐ ACM Placement - 1st Day St. Francisville	10.38 hr	230 hr	1767.7 hr	0																								
202	Land Anchors Installed - D1SF	0.55 hr	7.67 hr	33.4 hr	19																								
203	T6-B5 towed in place	0.27 hr	3.63 hr	30.67 hr	14																								
204	T6-B5 Offloaded	2.85 hr	2.85 hr	14.93 hr	10																								
205	T6-B6 towed in place	0.3 hr	3.68 hr	40.73 hr	14																								
206	T6-B6 Offloaded	1.78 hr	5.38 hr	24.1 hr	8																								
207	T6-B7 towed in place	0.37 hr	3.65 hr	41.82 hr	12																								
208	T6-B7 Offloaded	1.78 hr	1.78 hr	18.5 hr	8																								
209	T6-B8 towed in place	0.32 hr	3.5 hr	22.53 hr	12																								
210	T6-B8 Offloaded (1/2)	2.08 hr	2.08 hr	20.67 hr	8																								




	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020			August, 2020			September, 2020			October, 2020			November, 2020			December, 2020			
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08
211	<input type="checkbox"/> ACM Placement 2nd Day St. Francisville	9.53 hr	20 hr	119.43 hr	0																			
212	Land Anchors Installed - D2SF	0.65 hr	0.65 hr	22.22 hr	19																			
213	T6-B8 Offloaded (1/2)	0.98 hr	0.98 hr	22.13 hr	10																			
214	T6-B9 towed in place	0.27 hr	3.63 hr	36.12 hr	14																			
215	T6-B9 Offloaded	1.95 hr	5.53 hr	16.68 hr	10																			
216	T6-B10 towed in place	0.37 hr	3.3 hr	19.97 hr	12																			
217	T6-B10 Offloaded	2 hr	2 hr	14.87 hr	8																			
218	T6-B11 towed in place	0.35 hr	3.32 hr	7.62 hr	12																			
219	T6-B11 Offloaded	2.97 hr	7.92 hr	17.13 hr	8																			
220	<input type="checkbox"/> ACM Placement 3rd Day St. Francisville	11.73 hr	27.2 hr	103.57 hr	0																			
221	Land Anchors Installed - D3SF	0.53 hr	2.8 hr	12.95 hr	19																			
222	T6-B12 towed in place	3.35 hr	3.58 hr	21.47 hr	14																			
223	T6-B12 Offloaded	2.37 hr	2.37 hr	20.97 hr	10																			
224	T6-B13 towed in place	0.42 hr	3.72 hr	6.6 hr	14																			
225	T6-B13 Offloaded	2.3 hr	7.55 hr	25.17 hr	8																			
226	T6-B14 towed in place	1.15 hr	3.6 hr	11.7 hr	12																			
227	T6-B14 Offloaded	1.48 hr	3.88 hr	20.47 hr	8																			
228	T6-B15 towed in place	0.3 hr	3.77 hr	10.98 hr	12																			
229	T6-B15 Offloaded (1/2)	1.65 hr	4.62 hr	10.7 hr	8																			
230	<input type="checkbox"/> ACM Placement 4th Day St. Francisville	12.25 hr	26.68 hr	108.82 hr	0																			
231	Land Anchors Installed - D4SF	2.12 hr	2.8 hr	23.92 hr	19																			
232	T6-B15 Offloaded (1/2)	0.72 hr	5 hr	16.67 hr	10																			
233	T6-B16 towed in place	0.33 hr	4.03 hr	18.48 hr	14																			
234	T6-B16 Offloaded	2.47 hr	2.47 hr	20.78 hr	8																			
235	T7-B17 towed in place	0.35 hr	3.42 hr	18.43 hr	12																			
236	T7-B17 Offloaded	3.4 hr	6.65 hr	12.32 hr	8																			
237	T7-B18 towed in place	0.82 hr	3.7 hr	16.23 hr	12																			
238	T7-B18 Offloaded	2.05 hr	3.88 hr	9.52 hr	8																			
239	<input type="checkbox"/> ACM Placement 5th Day St. Francisville	8.93 hr	20.72 hr	78.02 hr	0																			
240	Land Anchors Installed - D4SF	3.62 hr	6.08 hr	8.02 hr	19																			
241	T7-B19 towed in place	0.27 hr	3.52 hr	39.88 hr	14																			
242	T7-B19 Offloaded	2.98 hr	8.47 hr	20.67 hr	10																			
243	T7-B20 towed in place	0.35 hr	4.18 hr	24.15 hr	14																			
244	T7-B20 Offloaded	1.72 hr	4.63 hr	26.3 hr	8																			
245	End of Season	0 hr	0 hr	0 hr	0																			



Figure B-3. Schedule of events with risks calculated for 4,000 squares/day.

	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020				September, 2020				October, 2020				November, 2020				Decem			
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29	06	
1	<input type="checkbox"/> BEGINNING OF SEASON	230.75 hr	471 hr	2189.12 hr	0																								
2	<input type="checkbox"/> Mat Yard Mobilization	191 hr	291 hr	921 hr	0																								
3	<input type="checkbox"/> Memphis Yard Mobilization	51 hr	71 hr	181 hr	0																								
4	Tie off empty barges at Memphis Yard	2.1 hr	7.6 hr	46.03 hr	8																								
5	Lash and Prep loaded barges for transport at Memphis Yard	2.28 hr	2.37 hr	41.25 hr	8																								
6	Load Mats on Barges 1-12 at Memphis Yard	24.65 hr	31 hr	46.25 hr	18																								
7	Tow 1st Fleet of Barges from Richardson Landing to Memphis	20.75 hr	25.43 hr	42.38 hr	28																								
8	Load Mats on Barges 13-15 at Memphis Yard	6.65 hr	10 hr	22.47 hr	18																								
9	Tow 2nd Fleet of Barges from Richardson Landing to Memphis Reg	36.05 hr	39.97 hr	56.7 hr	28																								
10	<input type="checkbox"/> Delta Yard Mobilization	121.97 hr	168.53 hr	407.47 hr	0																								
11	Tie off empty barges at Delta Yard	2.53 hr	9.22 hr	34.13 hr	8																								
12	Lash and Prep loaded barges for transport at Delta Yard	2.5 hr	2.58 hr	36.08 hr	8																								
13	Load Mats on Barges 16-27 at Delta Yard	28.2 hr	34.88 hr	43.12 hr	18																								
14	Tow 3rd Fleet of Barges from Delta Yard to Vicksburg	19.7 hr	24.15 hr	30.53 hr	28																								
15	Load Mats on Barges 28-39 at Delta Yard	26.58 hr	26.58 hr	49.58 hr	18																								
16	Tow 4th Fleet of Barges from Delta Yard to Vicksburg	59.23 hr	66.37 hr	70.75 hr	28																								
17	Load Mats on Barges 40-43, 1-4 at Delta Yard	16.32 hr	20 hr	34.43 hr	18																								
18	Tow 5th Fleet of Barges from Delta Yard to Vicksburg	60.38 hr	66.43 hr	81.2 hr	28																								
19	<input type="checkbox"/> St. Francisville Yard Mobilization	100 hr	140 hr	430 hr	0																								
20	Tie off empty barges at St. Francisville Yard	2.15 hr	2.15 hr	28.95 hr	8																								
21	Lash and Prep loaded barges for transport at St. Francisville Yard	2.68 hr	8.42 hr	40.92 hr	8																								
22	Load Mats on Barges 5-16 at St. Francisville Yard	27.82 hr	27.82 hr	40.57 hr	18																								
23	Tow 6th Fleet of Barges from St. Francisville Yard to New Orleans	18.95 hr	25.93 hr	42.37 hr	28																								
24	Load Mats on Barges 17-20 at St. Francisville	8.95 hr	15 hr	17.13 hr	18																								
25	Tow 7th Fleet of Barges from St. Francisville to New Orleans	66.15 hr	73.42 hr	92.35 hr	28																								
26	<input type="checkbox"/> ACM Placement	230.75 hr	471 hr	2189.12 hr	0																								
27	Training	10.17 hr	11.98 hr	13.93 hr	0																								
28	Blessing of the Fleet	7.15 hr	9.02 hr	29.83 hr	0																								
29	<input type="checkbox"/> Memphis Region	83.68 hr	150 hr	613.63 hr	0																								
30	<input type="checkbox"/> Mobilize Floating Plant for Memphis Region	83.68 hr	150 hr	613.63 hr	0																								
31	Mat Anchor Barge Moored in place at Memphis	1.65 hr	4.45 hr	21.78 hr	4																								
32	Quarter Boat Moored in Place at Memphis	3.27 hr	7.08 hr	29.18 hr	8																								
33	ARMOR ONE Anchor Barge Moored in place at Memphis	3.07 hr	10 hr	16.75 hr	4																								

Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020				September, 2020				October, 2020				November, 2020				Decem				
					05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29	06		
34	ARMOR ONE unit moored in place at Memphis	4.77 hr	10 hr	23.27 hr	4																								
35	Dozers placed at Memphis	1.95 hr	5.52 hr	25.03 hr	12																								
36	1st Fleet of Barges Anchored at Memphis	3.15 hr	4.93 hr	8.72 hr	6																								
37	2nd Fleet of Barges Anchored at Memphis	3.2 hr	5.35 hr	12.03 hr	6																								
38	▣ ACM Placement - 1st Day	22.7 hr	50 hr	199.33 hr	0																								
39	Land Anchors Installed - D1M	1.5 hr	9.08 hr	23.92 hr	19																								
40	T1-B1 towed in place	0.3 hr	3.7 hr	8.92 hr	14																								
41	T1-B1 Offloaded	1.47 hr	1.47 hr	18.22 hr	10																								
42	T1-B2 towed in place	0.28 hr	3.67 hr	12.82 hr	14																								
43	T1-B2 Offloaded	0.95 hr	4.92 hr	10.13 hr	8																								
44	T1-B3 towed in place	0.27 hr	3.58 hr	20.88 hr	12																								
45	T1-B3 Offloaded	2.53 hr	2.53 hr	14.78 hr	8																								
46	T1-B4 towed in place	0.57 hr	3.85 hr	13.28 hr	12																								
47	T1-B4 Offloaded	1.17 hr	5 hr	9.52 hr	8																								
48	T1-B5 towed in place	0.28 hr	3.9 hr	21.82 hr	12																								
49	T1-B5 Offloaded	1.78 hr	1.78 hr	20.87 hr	8																								
50	T1-B6 towed in place	0.28 hr	3.65 hr	17.15 hr	12																								
51	T1-B6 Offloaded	1.48 hr	7.1 hr	18.13 hr	8																								
52	T1-B7 towed in place	0.25 hr	3.55 hr	21.78 hr	12																								
53	T1-B7 Offloaded (3/4)	1.93 hr	1.93 hr	23.42 hr	8																								
54	▣ ACM Placement - 2nd Day	38.52 hr	55 hr	229.23 hr	0																								
55	Land Anchors Installed - D2M	2.3 hr	10 hr	16 hr	19																								
56	T1-B7 Offloaded (1/4)	0.7 hr	0.7 hr	21.03 hr	10																								
57	T1-B8 towed in place	0.3 hr	3.63 hr	21.98 hr	14																								
58	T1-B8 Offloaded	1.3 hr	6.62 hr	9.6 hr	10																								
59	T1-B9 towed in place	0.25 hr	3.63 hr	11.18 hr	12																								
60	T1-B9 Offloaded	1.18 hr	1.18 hr	16.18 hr	8																								
61	T1-B10 towed in place	0.33 hr	3.65 hr	21.02 hr	12																								
62	T1-B10 Offloaded	1.98 hr	1.98 hr	19.38 hr	8																								
63	T1-B11 towed in place	0.33 hr	3.52 hr	31.1 hr	12																								
64	T1-B11 Offloaded	1.47 hr	1.47 hr	16.38 hr	8																								
65	T1-B12 towed in place	0.43 hr	3.48 hr	46.73 hr	12																								
66	T1-B12 Offloaded	1.82 hr	1.82 hr	13.92 hr	8																								
67	<i>Tow Barges 1-4 to Delta Yard</i>	46.95 hr	51.3 hr	60.17 hr	28																								
68	<i>Tow Barges 5-12 to St. Francisville Yard from Delta Yard</i>	21.1 hr	26.53 hr	40.37 hr	28																								



	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020			August, 2020			September, 2020			October, 2020			November, 2020			Decem					
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22
69	T2-B13 towed in place	0.38 hr	5 hr	45.12 hr	12																					
70	T2-B13 Offloaded	1.37 hr	5 hr	14.52 hr	8																					
71	T2-B14 towed in place	0.45 hr	3.82 hr	8.95 hr	12																					
72	T2-B14 Offloaded (1/2)	1.53 hr	3 hr	8.57 hr	8																					
73	☐ ACM Placement - 3rd Day	32.55 hr	47 hr	117.83 hr	0																					
74	Land Anchors Installed - D3M	2.92 hr	7 hr	25.88 hr	19																					
75	T2-B14 Offloaded (1/2)	0.73 hr	1.52 hr	25.68 hr	10																					
76	T2-B15 towed in place	0.3 hr	3.63 hr	12.3 hr	14																					
77	T2-B15 Offloaded	1.2 hr	2.87 hr	21.53 hr	10																					
78	Tow Barges 13-15 to St. Francisville Yard from Memphis	61.73 hr	67.42 hr	77.87 hr	22																					
79	☐ Relocate Floating Plant to Vicksburg	12.4 hr	12.4 hr	18.47 hr	0																					
80	Mat Anchor Barge towed to Vicksburg	22.28 hr	29.08 hr	42.45 hr	22																					
81	Quarter Boat towed to Vicksburg	18.18 hr	29.12 hr	43.67 hr	22																					
82	ARMOR ONE Anchor Barge towed to Vicksburg	21.88 hr	28.88 hr	41.28 hr	18																					
83	ARMOR ONE Unit towed to Vicksburg	18.38 hr	29.08 hr	29.8 hr	22																					
84	Dozers towed to Vicksburg	21.92 hr	29.22 hr	31.1 hr	22																					
85	☐ Vicksburg Region	79.12 hr	200 hr	1009.92 hr	0																					
86	☐ Mobilize Floating Plant for Vicksburg Region	79.12 hr	200 hr	1009.92 hr	0																					
87	Mat Anchor Barge Moored in place at Vicksburg	2 hr	4.58 hr	11.52 hr	4																					
88	Quarter Boat Moored in Place at Vicksburg	3.82 hr	7.03 hr	17.72 hr	8																					
89	ARMOR ONE Anchor Barge Moored in place at Vicksburg	4.53 hr	6.68 hr	23.43 hr	4																					
90	ARMOR ONE unit moored in place at Vicksburg	6.48 hr	8.23 hr	16.27 hr	4																					
91	Dozers placed at Vicksburg	1.7 hr	5.48 hr	9.98 hr	12																					
92	3rd Fleet of Barges Anchored	2.22 hr	5.25 hr	12.32 hr	6																					
93	4th Fleet of Barges Anchored	3.07 hr	5.37 hr	17.37 hr	6																					
94	5th Fleet of Barges Anchored	2.23 hr	5.37 hr	9.85 hr	6																					
95	☐ ACM Placement - 1st Day	20 hr	55 hr	178.03 hr	0																					
96	Land Anchors Installed - D1V	1.2 hr	5 hr	21.47 hr	19																					
97	T3-B16 towed in place	0.25 hr	1.47 hr	9.4 hr	14																					
98	T3-B16 Offloaded	1.17 hr	5.48 hr	16.13 hr	10																					
99	T3-B17 towed in place	0.33 hr	3.63 hr	22.2 hr	14																					
100	T3-B17 Offloaded	0.9 hr	0.9 hr	12.65 hr	8																					
101	T3-B18 towed in place	0.47 hr	3.58 hr	12.5 hr	12																					
102	T3-B18 Offloaded	1.22 hr	6.5 hr	17.8 hr	8																					
103	T3-B19 towed in place	0.27 hr	3.55 hr	10.88 hr	12																					

	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020			August, 2020			September, 2020			October, 2020			November, 2020			Decem				
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15
104	T3-B19 Offloaded	1.9 hr	2.4 hr	17.57 hr	8																				
105	T3-B20 towed in place	0.32 hr	3.6 hr	24.17 hr	12																				
106	T3-B20 Offloaded	1.57 hr	2.37 hr	19.48 hr	8																				
107	<i>Tow Barges 16-20 to St. Francisville Yard</i>	39.37 hr	45.52 hr	58.87 hr	28																				
108	T3-B21 towed in place	0.35 hr	3.63 hr	11.77 hr	12																				
109	T3-B21 Offloaded	1.02 hr	6.73 hr	20.42 hr	8																				
110	T3-B22 towed in place	0.28 hr	3.57 hr	12.1 hr	12																				
111	T3-B22 Offloaded (3/4)	1.42 hr	1.42 hr	8.03 hr	8																				
112	<input type="checkbox"/> ACM Placement - 2nd Day	12.05 hr	30 hr	220.05 hr	0																				
113	Land Anchors Installed - D2V	1.52 hr	5.85 hr	9.53 hr	10																				
114	T3-B22 Offloaded (1/4)	0.8 hr	4.12 hr	10.23 hr	10																				
115	T3-B23 towed in place	0.3 hr	3.52 hr	33.02 hr	14																				
116	T3-B23 Offloaded	0.85 hr	4.97 hr	23.65 hr	10																				
117	T3-B24 towed in place	0.37 hr	3.62 hr	32.78 hr	14																				
118	T3-B24 Offloaded	1.98 hr	1.98 hr	9.27 hr	8																				
119	T3-B25 towed in place	0.27 hr	3.58 hr	27.6 hr	12																				
120	T3-B25 Offloaded	0.87 hr	0.87 hr	10.23 hr	8																				
121	T3-B26 towed in place	0.32 hr	3.55 hr	34.65 hr	12																				
122	T3-B26 Offloaded	1.35 hr	1.35 hr	17.9 hr	8																				
123	T3-B27 towed in place	0.37 hr	3.7 hr	37.18 hr	12																				
124	T3-B27 Offloaded	1.13 hr	1.13 hr	13.42 hr	8																				
125	T4-B28 towed in place	0.3 hr	0.4 hr	29.27 hr	12																				
126	T4-B28 Offloaded	1.15 hr	6.98 hr	9.55 hr	8																				
127	T4-B29 towed in place	0.35 hr	3.6 hr	32.1 hr	12																				
128	T4-B29 Offloaded (1/2)	0.4 hr	0.4 hr	8.75 hr	8																				
129	<input type="checkbox"/> ACM Placement - 3rd Day	16.25 hr	50 hr	228.18 hr	0																				
130	Land Anchors Installed - D3V	1.93 hr	8.57 hr	9.17 hr	19																				
131	T4-B29 Offloaded (1/2)	0.63 hr	1.43 hr	21.23 hr	10																				
132	T4-B30 towed in place	0.33 hr	3.6 hr	34.9 hr	14																				
133	T4-B30 Offloaded	1.28 hr	4.72 hr	15.87 hr	10																				
134	T4-B31 towed in place	0.37 hr	3.63 hr	28.4 hr	14																				
135	T4-B31 Offloaded	1.2 hr	1.2 hr	17.2 hr	8																				
136	T4-B32 towed in place	0.3 hr	3.7 hr	40.55 hr	12																				
137	T4-B32 Offloaded	1.33 hr	5.78 hr	8.55 hr	8																				
138	T4-B33 towed in place	0.33 hr	3.62 hr	38.55 hr	12																				

	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020			September, 2020				October, 2020			November, 2020				Decem	
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15
139	T4-B33 Offloaded	1.03 hr	1.03 hr	14.58 hr	8																				
140	T4-B34 towed in place	0.33 hr	3.65 hr	39.98 hr	12																				
141	T4-B34 Offloaded	1.47 hr	7.2 hr	25.9 hr	8																				
142	T4-B35 towed in place	0.28 hr	3.28 hr	23.27 hr	12																				
143	T4-B35 Offloaded	3.78 hr	3.78 hr	23.07 hr	8																				
144	T4-B36 towed in place	0.33 hr	3.72 hr	18.02 hr	12																				
145	T4-B36 Offloaded (1/4)	1.3 hr	5 hr	13.02 hr	8																				
146	☐ ACM Placement - 4th Day	14.33 hr	40 hr	217.08 hr	0																				
147	Land Anchors Installed - D4V	2.08 hr	2.08 hr	20.13 hr	19																				
148	T4-B36 Offloaded (3/4)	1.27 hr	6.27 hr	19.4 hr	10																				
149	T4-B37 towed in place	0.37 hr	3.77 hr	30 hr	14																				
150	T4-B37 Offloaded	1.28 hr	1.28 hr	10.55 hr	10																				
151	T4-B38 towed in place	0.45 hr	3.58 hr	39.08 hr	12																				
152	T4-B38 Offloaded	1.45 hr	5 hr	8.12 hr	8																				
153	T4-B39 towed in place	0.33 hr	4.02 hr	19.83 hr	12																				
154	T4-B39 Offloaded	1.45 hr	1.45 hr	16.3 hr	8																				
155	T5-B40 towed in place	0.32 hr	3.82 hr	17.67 hr	12																				
156	T5-B40 Offloaded	1.68 hr	2.47 hr	22.97 hr	8																				
157	T5-B41 towed in place	0.42 hr	3.77 hr	6.75 hr	12																				
158	T5-B41 Offloaded	1.5 hr	5.07 hr	21.35 hr	8																				
159	T5-B42 towed in place	0.3 hr	3.7 hr	34.37 hr	12																				
160	T5-B42 Offloaded	1.43 hr	1.43 hr	23.92 hr	8																				
161	☐ ACM Placement - 5th Day	10.5 hr	20 hr	146.57 hr	0																				
162	Land Anchors Installed - D5V	2.5 hr	9.97 hr	23.23 hr	19																				
163	T5-B43 towed in place	0.35 hr	3.85 hr	18.05 hr	14																				
164	T5-B43 Offloaded	1.7 hr	1.82 hr	19.77 hr	8																				
165	T5-B1 towed in place	0.3 hr	3.38 hr	23.43 hr	12																				
166	T5-B1 Offloaded	0.97 hr	3.35 hr	16.45 hr	8																				
167	T5-B2 towed in place	0.27 hr	3.45 hr	8.43 hr	12																				
168	T5-B2 Offloaded	1.93 hr	1.93 hr	24.85 hr	8																				
169	T5-B2 towed in place	0.28 hr	3.48 hr	10.37 hr	12																				
170	T5-B3 Offloaded	1.08 hr	1.08 hr	19.42 hr	8																				
171	T5-B3 towed in place	0.3 hr	3.63 hr	24.25 hr	12																				
172	T5-B4 Offloaded	0.95 hr	0.95 hr	10.25 hr	8																				
173	☐ Relocate Floating Plant to St. Francisville Region	27.18 hr	27.18 hr	40.08 hr	0																				

	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020			August, 2020			September, 2020			October, 2020			November, 2020			Decem			
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08
174	Mat Anchor Barge towed to St. Francisville Region	61.68 hr	61.8 hr	79.07 hr	22																			
175	Quarter Boat towed to St. Francisville Region	56.87 hr	62.23 hr	90.85 hr	22																			
176	ARMOR ONE Anchor Barge towed to St. Francisville Region	56.27 hr	62.12 hr	105.25 hr	22																			
177	ARMOR ONE Unit towed to St. Francisville Region	48.57 hr	62.3 hr	81.67 hr	22																			
178	Dozers towed to St. Francisville Region	68.18 hr	68.18 hr	101.47 hr	22																			
179	☐ St. Francisville Region	59.75 hr	300 hr	2018.12 hr	0																			
180	☐ Mobilize Floating Plant at St. Francisville Region	59.75 hr	300 hr	2018.12 hr	0																			
181	Mat Anchor Barge Moored in place at St. F.	1.67 hr	3.87 hr	20.68 hr	4																			
182	Quarter Boat Moored in Place at St. F.	2.18 hr	2.88 hr	20.23 hr	8																			
183	ARMOR ONE Anchor Barge Moored in place at St. F.	2.25 hr	2.38 hr	25.03 hr	4																			
184	ARMOR ONE unit moored in place at St. F.	5.53 hr	5.53 hr	15.42 hr	4																			
185	Dozers placed at St. F.	1.97 hr	6.57 hr	22.4 hr	16																			
186	6th Fleet of Barges Anchored at St. F.	3.12 hr	5.37 hr	17.35 hr	6																			
187	7th Fleet of Barges Anchored at St. F.	2.83 hr	5.35 hr	16.23 hr	6																			
188	☐ ACM Placement - 1st Day St. Francisville	26.43 hr	250 hr	1719.48 hr	0																			
189	Land Anchors Installed - D1SF	0.48 hr	7.17 hr	40.32 hr	19																			
190	T6-B5 towed in place	0.27 hr	3.57 hr	30.38 hr	14																			
191	T6-B5 Offloaded	1.05 hr	5.17 hr	15.1 hr	10																			
192	T6-B6 towed in place	0.25 hr	3.67 hr	41.87 hr	14																			
193	T6-B6 Offloaded	1.15 hr	1.15 hr	9.13 hr	10																			
194	T6-B7 towed in place	0.27 hr	3.65 hr	32.77 hr	12																			
195	T6-B7 Offloaded	2.2 hr	3.9 hr	10.4 hr	8																			
196	T6-B8 towed in place	0.28 hr	3.18 hr	14.77 hr	12																			
197	T6-B8 Offloaded	1.23 hr	5.13 hr	18.5 hr	8																			
198	T6-B9 towed in place	0.25 hr	3.97 hr	39.9 hr	12																			
199	T6-B9 Offloaded	1.97 hr	1.97 hr	10.5 hr	8																			
200	T6-B10 towed in place	0.28 hr	3 hr	16.65 hr	12																			
201	T6-B10 Offloaded	1.8 hr	5.43 hr	23.27 hr	8																			
202	T6-B11 towed in place	0.33 hr	3.78 hr	21.38 hr	12																			
203	T6-B11 Offloaded (3/4)	0.57 hr	0.57 hr	18.83 hr	8																			
204	☐ ACM Placement 2nd Day St. Francisville	26.05 hr	50 hr	213.83 hr	0																			
205	Land Anchors Installed - D2SF	1.08 hr	8.22 hr	8.7 hr	19																			
206	T6-B11 Offloaded (1/4)	1.27 hr	1.78 hr	23.27 hr	10																			
207	T6-B12 towed in place	0.27 hr	3.7 hr	30.4 hr	14																			
208	T6-B12 Offloaded	2.22 hr	6.02 hr	8.55 hr	10																			


	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020				September, 2020				October, 2020				November, 2020				Decem	
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29
209	T6-B13 towed in place	7.2 hr	7.2 hr	11.03 hr	12																						
210	T6-B13 Offloaded	1.93 hr	1.93 hr	19.7 hr	8																						
211	T6-B14 towed in place	1.17 hr	4 hr	13.92 hr	12																						
212	T6-B14 Offloaded	1.68 hr	5.55 hr	23 hr	8																						
213	T6-B15 towed in place	0.4 hr	3.78 hr	10.68 hr	12																						
214	T6-B15 Offloaded	2.47 hr	2.47 hr	14.23 hr	8																						
215	T6-B16 towed in place	0.25 hr	3.43 hr	20.67 hr	12																						
216	T6-B16 Offloaded	1.25 hr	3.83 hr	23 hr	8																						
217	T7-B17 towed in place	2.82 hr	3.9 hr	26.85 hr	12																						
218	T7-B17 Offloaded	1.22 hr	3.47 hr	18.68 hr	8																						
219	T7-B18 towed in place	0.3 hr	3.57 hr	22.52 hr	12																						
220	T7-B18 Offloaded (1/2)	2.1 hr	2.1 hr	20.37 hr	8																						
221	<input type="checkbox"/> ACM Placement 3rd Day St. Francisville	7.27 hr	7.27 hr	84.8 hr	0																						
222	Land Anchors Installed - D3SF	3.33 hr	3.33 hr	23.28 hr	19																						
223	T7-B18 Offloaded (1/2)	0.73 hr	0.73 hr	21.22 hr	10																						
224	T7-B19 towed in place	1.13 hr	3.83 hr	16.43 hr	14																						
225	T7-B19 Offloaded	0.98 hr	0.98 hr	15.35 hr	8																						
226	T7-B20 towed in place	0.37 hr	3.87 hr	19.98 hr	12																						
227	T7-B20 Offloaded	0.72 hr	0.72 hr	14.53 hr	8																						
228	End of Season	0 hr	0 hr	0 hr	0																						

Figure B-4. Schedule of events with risks calculated for 6,000 squares/day.

	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020				September, 2020				October, 2020				November, 2020				December, 2020							
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29	06	13	20			
1	☐ BEGINNING OF SEASON	275 hr	503 hr	2260 hr	0	[Gantt bar spanning from July 5 to August 23]																											
2	☐ Mat Yard Mobilization	212 hr	305 hr	942.32 hr	0	[Gantt bar spanning from July 5 to August 23]																											
3	☐ Memphis Yard Mobilization	51 hr	68 hr	190 hr	0	[Gantt bar spanning from July 5 to August 23]																											
4	Tie off empty barges at Memphis Yard	2.1 hr	8 hr	46.13 hr	8	[Task bar with risk indicator]																											
5	Lash and Prep loaded barges for transport at Memphis Yard	2.28 hr	2.28 hr	47.93 hr	8	[Task bar with risk indicator]																											
6	Load Mats on Barges 1-12 at Memphis Yard	24.65 hr	34 hr	46.45 hr	18	[Task bar with risk indicator]																											
7	Tow 1st Fleet of Barges from Richardson Landing to Memphis	20.75 hr	25.57 hr	39.2 hr	28	[Task bar with risk indicator]																											
8	Load Mats on Barges 13-15 at Memphis Yard	6.65 hr	9 hr	30.12 hr	18	[Task bar with risk indicator]																											
9	Tow 2nd Fleet of Barges from Richardson Landing to Memphis R	36.05 hr	39.93 hr	50.07 hr	28	[Task bar with risk indicator]																											
10	☐ Delta Yard Mobilization	85.68 hr	170 hr	464.48 hr	0	[Gantt bar spanning from July 5 to August 23]																											
11	Tie off empty barges at Delta Yard	2.53 hr	8.33 hr	38.62 hr	8	[Task bar with risk indicator]																											
12	Lash and Prep loaded barges for transport at Delta Yard	2.5 hr	2.5 hr	39.22 hr	8	[Task bar with risk indicator]																											
13	Load Mats on Barges 16-27 at Delta Yard	28.2 hr	38.8 hr	57.55 hr	18	[Task bar with risk indicator]																											
14	Tow 3rd Fleet of Barges from Delta Yard to Vicksburg	19.7 hr	24.02 hr	30.37 hr	28	[Task bar with risk indicator]																											
15	Load Mats on Barges 28-39 at Delta Yard	26.58 hr	26.58 hr	45.63 hr	18	[Task bar with risk indicator]																											
16	Tow 4th Fleet of Barges from Delta Yard to Vicksburg	59.23 hr	66.43 hr	83.6 hr	28	[Task bar with risk indicator]																											
17	Load Mats on Barges 40-43, 1-4 at Delta Yard	19.53 hr	27.77 hr	37.67 hr	18	[Task bar with risk indicator]																											
18	Tow 5th Fleet of Barges from Delta Yard to Vicksburg	62.95 hr	66.55 hr	87.17 hr	28	[Task bar with risk indicator]																											
19	☐ St. Francisville Yard Mobilization	112.92 hr	140.68 hr	392.1 hr	0	[Gantt bar spanning from July 5 to August 23]																											
20	Tie off empty barges at St. Francisville Yard	2.07 hr	8.68 hr	11.2 hr	8	[Task bar with risk indicator]																											
21	Lash and Prep loaded barges for transport at St. Francisville Yan	2.82 hr	2.82 hr	31.72 hr	8	[Task bar with risk indicator]																											
22	Load Mats on Barges 5-16 at St. Francisville Yard	27.75 hr	30.02 hr	38.05 hr	18	[Task bar with risk indicator]																											
23	Tow 6th Fleet of Barges from St. Francisville Yard to New Orlean	24.75 hr	28.45 hr	39.27 hr	28	[Task bar with risk indicator]																											
24	Load Mats on Barges 17-20 at St. Francisville	10.17 hr	10.17 hr	28.67 hr	18	[Task bar with risk indicator]																											
25	Tow 7th Fleet of Barges from St. Francisville to New Orleans	64.57 hr	73.6 hr	73.6 hr	28	[Task bar with risk indicator]																											
26	☐ ACM Placement	275 hr	503 hr	2260 hr	0	[Gantt bar spanning from July 5 to August 23]																											
27	Training	10.17 hr	11.98 hr	13.93 hr	0	[Task bar with risk indicator]																											
28	Blessing of the Fleet	7.18 hr	10.17 hr	28.28 hr	0	[Task bar with risk indicator]																											
29	☐ Memphis Region	92.65 hr	157.35 hr	601.2 hr	0	[Gantt bar spanning from July 5 to August 23]																											
30	☐ Mobilize Floating Plant for Memphis Region	92.65 hr	157.35 hr	601.2 hr	0	[Gantt bar spanning from July 5 to August 23]																											
31	Mat Anchor Barge Moored in place at Memphis	1.62 hr	4.57 hr	21.67 hr	4	[Task bar with risk indicator]																											
32	Quarter Boat Moored in Place at Memphis	3.27 hr	7.05 hr	27.1 hr	8	[Task bar with risk indicator]																											
33	ARMOR ONE Anchor Barge Moored in place at Memphis	4.85 hr	6.68 hr	14.8 hr	4	[Task bar with risk indicator]																											
34	ARMOR ONE unit moored in place at Memphis	5.32 hr	8.22 hr	30.68 hr	4	[Task bar with risk indicator]																											
35	Dozers placed at Memphis	2.8 hr	5.52 hr	29.82 hr	12	[Task bar with risk indicator]																											


	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020				September, 2020				October, 2020				November, 2020				December, 2020			
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29	06	13
36	1st Fleet of Barges Anchored at Memphis	3.15 hr	4.83 hr	23.62 hr	6																								
37	2nd Fleet of Barges Anchored at Memphis	3.2 hr	5.33 hr	13.05 hr	6																								
38	<input type="checkbox"/> ACM Placement - 1st Day	31.22 hr	60.12 hr	254.28 hr	0																								
39	Land Anchors Installed - D1M	0.28 hr	9.12 hr	11.43 hr	19																								
40	T1-B1 towed in place	0.3 hr	3.62 hr	22.92 hr	14																								
41	T1-B1 Offloaded	1.47 hr	4.22 hr	16.68 hr	10																								
42	T1-B2 towed in place	0.28 hr	3.7 hr	11.12 hr	14																								
43	T1-B2 Offloaded	0.95 hr	0.95 hr	12.82 hr	8																								
44	T1-B3 towed in place	0.25 hr	3.55 hr	15.17 hr	12																								
45	T1-B3 Offloaded	2.53 hr	5.9 hr	11.78 hr	8																								
46	T1-B4 towed in place	0.57 hr	3.82 hr	8.1 hr	12																								
47	T1-B4 Offloaded	1.48 hr	1.48 hr	8.48 hr	8																								
48	T1-B5 towed in place	0.67 hr	3.78 hr	18.27 hr	12																								
49	T1-B5 Offloaded	1.6 hr	3 hr	24.37 hr	8																								
50	T1-B6 towed in place	0.28 hr	3.58 hr	44.15 hr	12																								
51	T1-B6 Offloaded	0.88 hr	2.43 hr	7.98 hr	8																								
52	T1-B7 towed in place	9.05 hr	9.05 hr	13.88 hr	12																								
53	T1-B7 Offloaded	1.95 hr	4.73 hr	12.15 hr	8																								
54	T1-B8 towed in place	0.42 hr	3.52 hr	12.73 hr	12																								
55	T1-B8 Offloaded	3.17 hr	3.17 hr	15.42 hr	8																								
56	T1-B9 towed in place	0.35 hr	3.7 hr	10.97 hr	12																								
57	T1-B9 Offloaded	1.28 hr	2.92 hr	20.67 hr	10																								
58	T1-B10 towed in place	0.4 hr	3.57 hr	23.1 hr	14																								
59	T1-B10 Offloaded	2.1 hr	2.1 hr	16.88 hr	10																								
60	T1-B11 towed in place	0.72 hr	3.73 hr	12.07 hr	14																								
61	T1-B11 Offloaded (1/4)	0.7 hr	0.7 hr	11.43 hr	10																								
62	<input type="checkbox"/> ACM Placement - 2nd Day	44 hr	69.5 hr	240.42 hr	0																								
63	Land Anchors Installed - D2M	0.3 hr	5 hr	36.32 hr	19																								
64	T1-B11 Offloaded (3/4)	0.65 hr	3 hr	16.15 hr	10																								
65	T1-B12 towed in place	1.48 hr	3.52 hr	8.25 hr	14																								
66	T1-B12 Offloaded	0.83 hr	5.17 hr	20.02 hr	10																								
67	<i>Tow Barges 1-4 to Delta Yard</i>	41.45 hr	50.35 hr	65.75 hr	22																								
68	<i>Tow Barges 5-12 to St. Francisville Yard from Delta Yard</i>	13.37 hr	25.52 hr	39.45 hr	22																								
69	T2-B13 towed in place	0.25 hr	5.75 hr	21.68 hr	12																								
70	T2-B13 Offloaded	1.75 hr	2.78 hr	18.58 hr	8																								

	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020				September, 2020				October, 2020				November, 2020				December, 2020			
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29	06	13
71	T2-B14 towed in place	0.48 hr	3.93 hr	18.6 hr	12																								
72	T2-B14 Offloaded	1.67 hr	1.67 hr	25.9 hr	8																								
73	T2-B15 towed in place	0.27 hr	3.37 hr	23.35 hr	12																								
74	T2-B15 Offloaded	0.93 hr	4.02 hr	16.25 hr	8																								
75	<i>Tow Barges 13-15 to St. Francisville Yard from Memphis</i>	62.13 hr	67.12 hr	79.03 hr	22																								
76	<input type="checkbox"/> Relocate Floating Plant to Vicksburg	13.15 hr	13.15 hr	24.42 hr	0																								
77	Mat Anchor Barge towed to Vicksburg	20.83 hr	29.02 hr	41.6 hr	22																								
78	Quarter Boat towed to Vicksburg	19.12 hr	29.12 hr	37.62 hr	22																								
79	ARMOR ONE Anchor Barge towed to Vicksburg	17.73 hr	28.9 hr	55.42 hr	18																								
80	ARMOR ONE Unit towed to Vicksburg	18.22 hr	29.18 hr	38.05 hr	22																								
81	Dozers towed to Vicksburg	20.52 hr	29.1 hr	48.32 hr	22																								
82	<input type="checkbox"/> Vicksburg Region	94.15 hr	204 hr	1054.6 hr	0																								
83	<input type="checkbox"/> Mobilize Floating Plant for Vicksburg Region	94.15 hr	204 hr	1054.6 hr	0																								
84	Mat Anchor Barge Moored in place at Vicksburg	2.6 hr	4.57 hr	10.88 hr	4																								
85	Quarter Boat Moored in Place at Vicksburg	4.32 hr	7.05 hr	28.17 hr	8																								
86	ARMOR ONE Anchor Barge Moored in place at Vicksburg	4.08 hr	6.53 hr	12.68 hr	4																								
87	ARMOR ONE unit moored in place at Vicksburg	4.5 hr	8.3 hr	29.2 hr	4																								
88	Dozers placed at Vicksburg	1.97 hr	5.47 hr	15.13 hr	12																								
89	3rd Fleet of Barges Anchored	2.67 hr	5.38 hr	16.07 hr	6																								
90	4th Fleet of Barges Anchored	3.07 hr	5.48 hr	22.87 hr	6																								
91	5th Fleet of Barges Anchored	2.92 hr	5.38 hr	15.1 hr	6																								
92	<input type="checkbox"/> ACM Placement - 1st Day	19 hr	52 hr	256.08 hr	0																								
93	Land Anchors Installed - D1V	1.2 hr	1.2 hr	20.93 hr	19																								
94	T3-B16 towed in place	0.38 hr	3.62 hr	14.45 hr	14																								
95	T3-B16 Offloaded	0.85 hr	3.08 hr	9.75 hr	10																								
96	T3-B17 towed in place	0.37 hr	3.62 hr	19.02 hr	14																								
97	T3-B17 Offloaded	0.92 hr	3.48 hr	20.68 hr	10																								
98	T3-B18 towed in place	0.27 hr	3.72 hr	12.72 hr	12																								
99	T3-B18 Offloaded	2.22 hr	2.22 hr	13.3 hr	8																								
100	T3-B19 towed in place	0.37 hr	3.73 hr	17.75 hr	12																								
101	T3-B19 Offloaded	1.37 hr	6.03 hr	22.4 hr	8																								
102	T3-B20 towed in place	0.3 hr	3.52 hr	13.48 hr	12																								
103	T3-B20 Offloaded	1.17 hr	1.17 hr	8.48 hr	8																								
104	<i>Tow Barges 16-20 to St. Francisville Yard</i>	37.15 hr	44.9 hr	44.9 hr	22																								
105	T3-B21 towed in place	0.3 hr	3.65 hr	15.48 hr	12																								



	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020				September, 2020				October, 2020				November, 2020				December, 2020			
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29	06	13
106	T3-B21 Offloaded	1.47 hr	5.38 hr	14.82 hr	8																								
107	T3-B22 towed in place	0.43 hr	3.6 hr	9.17 hr	12																								
108	T3-B22 Offloaded	1.12 hr	1.12 hr	19.13 hr	8																								
109	T3-B23 towed in place	0.43 hr	4.08 hr	27.5 hr	12																								
110	T3-B23 Offloaded	1.25 hr	1.73 hr	18.15 hr	10																								
111	T3-B24 towed in place	0.48 hr	3.25 hr	39.32 hr	14																								
112	T3-B24 Offloaded	1.58 hr	1.58 hr	12.13 hr	10																								
113	T3-B25 towed in place	0.4 hr	3.5 hr	18.88 hr	14																								
114	T3-B25 Offloaded (1/4)	0.78 hr	0.78 hr	20.28 hr	10																								
115	<input type="checkbox"/> ACM Placement - 2nd Day	33 hr	52 hr	331 hr	0																								
116	Land Anchors Installed - D2V	1.92 hr	1.92 hr	23.7 hr	0																								
117	T3-B25 Offloaded (3/4)	1.05 hr	4.13 hr	8.98 hr	14																								
118	T3-B26 towed in place	0.4 hr	3.62 hr	9.18 hr	14																								
119	T3-B26 Offloaded	0.98 hr	0.98 hr	13.38 hr	10																								
120	T3-B27 towed in place	0.28 hr	3.52 hr	11.12 hr	12																								
121	T3-B27 Offloaded	1.83 hr	7.5 hr	13.45 hr	8																								
122	T4-B28 towed in place	0.27 hr	0.42 hr	43.15 hr	12																								
123	T4-B28 Offloaded	1.13 hr	6.9 hr	10.67 hr	8																								
124	T4-B29 towed in place	0.33 hr	3.55 hr	33 hr	12																								
125	T4-B29 Offloaded	1.3 hr	1.3 hr	24.12 hr	8																								
126	T4-B30 towed in place	0.43 hr	3.7 hr	12.82 hr	12																								
127	T4-B30 Offloaded	1.1 hr	3 hr	8.93 hr	8																								
128	T4-B31 towed in place	0.45 hr	3.85 hr	20.18 hr	12																								
129	T4-B31 Offloaded	0.88 hr	0.88 hr	10.27 hr	8																								
130	T4-B32 towed in place	0.4 hr	3.57 hr	33.87 hr	12																								
131	T4-B32 Offloaded	1.78 hr	5 hr	20.03 hr	8																								
132	T4-B33 towed in place	0.4 hr	3.85 hr	20.98 hr	12																								
133	T4-B33 Offloaded	1.65 hr	1.65 hr	13.5 hr	10																								
134	T4-B34 towed in place	0.28 hr	3.97 hr	9.22 hr	14																								
135	T4-B34 Offloaded	0.78 hr	6.57 hr	9.95 hr	10																								
136	T4-B35 towed in place	2 hr	3.82 hr	12.48 hr	14																								
137	T4-B35 Offloaded (1/4)	0.6 hr	1.77 hr	9.98 hr	10																								
138	<input type="checkbox"/> ACM Placement - 3rd Day	20 hr	55.97 hr	333 hr	0																								
139	Land Anchors Installed - D3V	1.43 hr	7.62 hr	13.95 hr	19																								
140	T4-B35 Offloaded (3/4)	1.13 hr	1.13 hr	17.08 hr	10																								

	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020				September, 2020				October, 2020				November, 2020				December, 2020			
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29	06	13
141	T4-B36 towed in place	0.4 hr	3.77 hr	14.8 hr	12																								
142	T4-B36 Offloaded	1.03 hr	8 hr	15.55 hr	10																								
143	T4-B37 towed in place	0.3 hr	3.85 hr	15.23 hr	14																								
144	T4-B37 Offloaded	0.85 hr	1.37 hr	15.97 hr	8																								
145	T4-B38 towed in place	0.93 hr	3.37 hr	20.55 hr	12																								
146	T4-B38 Offloaded	3.9 hr	3.9 hr	10.07 hr	8																								
147	T4-B39 towed in place	0.42 hr	4.35 hr	23.63 hr	12																								
148	T4-B39 Offloaded	1.42 hr	6.98 hr	22.63 hr	8																								
149	T5-B40 towed in place	0.28 hr	3.52 hr	20.37 hr	12																								
150	T5-B40 Offloaded	0.65 hr	2.87 hr	16.48 hr	8																								
151	T5-B41 towed in place	0.38 hr	3.87 hr	23.68 hr	12																								
152	T5-B41 Offloaded	1.2 hr	2.72 hr	25.4 hr	8																								
153	T5-B42 towed in place	0.25 hr	3.82 hr	18.13 hr	12																								
154	T5-B42 Offloaded	1.7 hr	1.7 hr	25.9 hr	8																								
155	T5-B43 towed in place	0.42 hr	3.7 hr	17.72 hr	12																								
156	T5-B43 Offloaded	1.47 hr	1.47 hr	21.73 hr	10																								
157	T5-B1 towed inplace	0.33 hr	3.65 hr	13.45 hr	14																								
158	T5-B1 Offloaded	1.05 hr	1.05 hr	12.63 hr	10																								
159	T5-B2 towed in place	2.22 hr	3.92 hr	22 hr	14																								
160	T5-B2 Offloaded (1/4)	0.78 hr	0.78 hr	21.38 hr	10																								
161	<input type="checkbox"/> ACM Placement - 4th Day	11.15 hr	22 hr	100.6 hr	0																								
162	Land Anchors Installed - D4V	2 hr	4.2 hr	25.65 hr	19																								
163	T5-B2 Offloaded (3/4)	0.68 hr	3.12 hr	17.53 hr	10																								
164	T5-B2 towed in place	9.43 hr	9.43 hr	9.43 hr	12																								
165	T5-B3 Offloaded	0.75 hr	2.1 hr	14.73 hr	8																								
166	T5-B3 towed in place	0.28 hr	3.57 hr	36.03 hr	12																								
167	T5-B4 Offloaded	1.12 hr	1.12 hr	12.6 hr	8																								
168	<input type="checkbox"/> Relocate Floating Plant to St. Francisville Region	27.85 hr	27.85 hr	38.88 hr	0																								
169	Mat Anchor Barge towed to St. Francisville Region	57.98 hr	61.83 hr	70.98 hr	22																								
170	Quarter Boat towed to St. Francisville Region	58.32 hr	62.18 hr	73.38 hr	22																								
171	ARMOR ONE Anchor Barge towed to St. Francisville Region	54.05 hr	62.15 hr	67.57 hr	22																								
172	ARMOR ONE Unit towed to St. Francisville Region	54.77 hr	62.3 hr	78.88 hr	22																								
173	Dozers towed to St. Francisville Region	63.23 hr	63.23 hr	69.97 hr	22																								
174	<input type="checkbox"/> St. Francisville Region	66.8 hr	113 hr	542.83 hr	0																								
175	<input type="checkbox"/> Mobilize Floating Plant at St. Francisville Region	66.8 hr	113 hr	542.83 hr	0																								



	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020			September, 2020				October, 2020			November, 2020			December, 2020							
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29	06	13	20
176	Mat Anchor Barge Moored in place at St. F.	1.62 hr	5.22 hr	21.12 hr	4																									
177	Quarter Boat Moored in Place at St. F.	1.65 hr	6.63 hr	11.85 hr	8																									
178	ARMOR ONE Anchor Barge Moored in place at St. F.	2.02 hr	5.8 hr	16.78 hr	4																									
179	ARMOR ONE unit moored in place at St. F.	5.38 hr	11 hr	13.47 hr	4																									
180	Dozers placed at St. F.	1.75 hr	1.85 hr	22.5 hr	16																									
181	6th Fleet of Barges Anchored at St. F.	2.2 hr	5.4 hr	8.87 hr	6																									
182	7th Fleet of Barges Anchored at St. F.	2.27 hr	5.4 hr	20.73 hr	6																									
183	<input type="checkbox"/> ACM Placement - 1st Day St. Francisville	37.6 hr	52 hr	338.65 hr	0																									
184	Land Anchors Installed - D1SF	1.93 hr	6.22 hr	24.47 hr	19																									
185	T6-B5 towed in place	0.48 hr	3.75 hr	18.78 hr	14																									
186	T6-B5 Offloaded	1.53 hr	1.53 hr	16.57 hr	10																									
187	T6-B6 towed in place	0.25 hr	3.67 hr	30.07 hr	14																									
188	T6-B6 Offloaded	1.25 hr	3.43 hr	13.5 hr	10																									
189	T6-B7 towed in place	0.37 hr	3.62 hr	27.63 hr	12																									
190	T6-B7 Offloaded	0.83 hr	3.92 hr	13.53 hr	8																									
191	T6-B8 towed in place	0.72 hr	3.2 hr	19.92 hr	12																									
192	T6-B8 Offloaded	2.37 hr	2.37 hr	13.6 hr	8																									
193	T6-B9 towed in place	0.38 hr	4.08 hr	15.45 hr	12																									
194	T6-B9 Offloaded	1.57 hr	6.57 hr	14.98 hr	8																									
195	T6-B10 towed in place	0.43 hr	3.03 hr	18.58 hr	12																									
196	T6-B10 Offloaded	1.78 hr	1.78 hr	16.78 hr	8																									
197	T6-B11 towed in place	4.08 hr	4.08 hr	33.95 hr	12																									
198	T6-B11 Offloaded	0.65 hr	0.65 hr	19.12 hr	8																									
199	T6-B12 towed in place	0.38 hr	3.57 hr	20.08 hr	12																									
200	T6-B12 Offloaded	2.75 hr	2.75 hr	8.73 hr	8																									
201	T6-B13 towed in place	1.6 hr	4.28 hr	20.08 hr	12																									
202	T6-B13 Offloaded	0.88 hr	0.88 hr	16.83 hr	8																									
203	T6-B14 towed in place	0.33 hr	3.63 hr	20.73 hr	12																									
204	T6-B14 Offloaded	2.37 hr	2.37 hr	18.78 hr	10																									
205	T6-B15 towed in place	2.65 hr	3.83 hr	18.9 hr	14																									
206	T6-B15 Offloaded (1/4)	1.23 hr	6.45 hr	18.48 hr	10																									
207	<input type="checkbox"/> ACM Placement 2nd Day St. Francisville	22 hr	42 hr	163 hr	0																									
208	Land Anchors Installed - D2SF	1.47 hr	1.47 hr	21.03 hr	19																									
209	T6-B15 Offloaded (3/4)	0.9 hr	6.32 hr	7.5 hr	10																									
210	T6-B16 towed in place	0.35 hr	3.45 hr	17.55 hr	14																									

	Task Name	Low Dur	Mean Dur	High Dur	Risks	July, 2020				August, 2020				September, 2020				October, 2020				November, 2020				December, 2020										
						05	12	19	26	02	09	16	23	30	06	13	20	27	04	11	18	25	01	08	15	22	29	06	13	20	27	04	11			
211	T6-B16 Offloaded	1.98 hr	1.98 hr	14.73 hr	10																															
212	T7-B17 towed in place	0.25 hr	3.88 hr	22.42 hr	12																															
213	T7-B17 Offloaded	2.4 hr	2.55 hr	11.2 hr	8																															
214	T7-B18 towed in place	2.92 hr	4.97 hr	17.58 hr	12																															
215	T7-B18 Offloaded	3.1 hr	3.1 hr	19.9 hr	8																															
216	T7-B19 towed in place	0.33 hr	4.85 hr	19.73 hr	12																															
217	T7-B19 Offloaded	0.92 hr	5.15 hr	27.88 hr	8																															
218	T7-B20 towed in place	0.27 hr	3.93 hr	13.48 hr	12																															
219	T7-B20 Offloaded	1.65 hr	4.02 hr	9.37 hr	8																															
220	End of Season	0 hr	0 hr	0 hr	0																															

Appendix C: Risk Matrices

Figures C-1 through C-3 present risk matrices.

Figure C-1. Risk matrix for 2,000 squares/day.



Figure C-2. Risk matrix for 4,000 squares/day.





Figure C-3. Risk matrix for 6,000 squares/day.



Appendix D: Potential Delay Probabilities

Table D-1 and Table D-2 present the potential delay register and the percentage of probability of occurrence, respectively.

Table D-1. Potential delay register.

Possible Delays to Schedule	Description	Cause	Trigger
Barge Wreck in Tow	Barge(s) separate from tow and sink.	Lashings loosed, commercial vehicle wreck, tow strikes bridge, etc.	
Commercial Wreck	A commercial vessel wrecks in the river in the tug tow zone, shutting down river traffic.	High current, other mishap/accident causing a commercial wreck not involving USACE MSU vessels.	
Ice in River Impeding Navigation	Ice causing hazards on river leading to slowdown/stopping of tow.	Cold weather in northern reach of river.	Winter weather
Ice on Boat Deck	Ice on boat decks causing hazardous operation for personnel.	Low temperatures	Weather
Issue with Barge	Barge(s) become inoperable.	Damage to barge(s) rendering it inoperable until repair.	
Lightning	Sustained lightening in work area.	Thunderstorm, etc.	Inclement weather warning.
Low Fuel	Vessels low on fuel, necessitating delay		
Squares Not Available	Squares not available for loading onto barges.	Production down at square-pouring plant.	
Mechanical Problems at Yard	Problems with production/loading machinery at square yard.	Machinery malfunction	

Possible Delays to Schedule	Description	Cause	Trigger
Mechanical Problems with ARMOR 1	Problems with ARMOR 1 unit's machinery.	Malfunctioning engines, motors, etc.	Improper usage, maintenance, force of nature, etc.
Mechanical Problems with Tow Vessel	Problems with tow vessels machinery.	Malfunctioning engines, motors, etc.	Improper usage, maintenance, force of nature, etc.
Not Enough Employees	Not enough employees to successfully operate tows, ARMOR 1 unit, or other vessels.	Weather or other delay causing employees not to arrive on time, or insufficient crews available.	
Reduced Speeds on River	Coast Guard reduces river speeds.	Coast Guard reduces speed on river.	Wrecks, water levels, currents, etc.
Riverbank Slope/Landscape Not Complete	Delays as a result of site preparation.	Additional clearing needed.	Higher than expected water elevation or failed communication with clearing and snagging
River Currents/High Water Elevation	Major delays possible with requirement to construct healing points, toggling for swift current or remote parking for quarter boat fleet.	Unanticipated rise in river stages, or decision to mitigate high water with additional construction.	Weather
River Impediments to Navigation			
River Low water Elevation	Water surface elevations less than LWRP +5 for revetment design.	Seasonal drought.	Weather
River Navigation Shut Down	Coast Guard stops traffic on river.	Coast Guard stops traffic from moving on river for period of time.	Wrecks, water levels, currents, etc.
Unattended Barge	Barge comes loose from tow or anchorage and travels away from site, necessitating vessels to retrieve it and re-position it.	Loosed lashings, etc., causing barge to break away from tow/anchorage/etc.	
Wind			

Table D-2. Percentage of probability of occurrence.

Possible Delays to Schedule	Minor =< 1 hr Delay	Moderate =< 3 hr Delay	Serious =< 6 hr Delay	Critical > 6 hr Delay	No Delay (100% - all total % off all delays)
Barge Wreck in Tow	5%	2%	1%	1%	91%
Commercial Wreck	1%	1%	2%	10%	86%
Ice on Boat deck	2%	1%	1%	5%	91%
Issue with Barge	10%	2%	1%	1%	86%
Lightning	5%	1%	1%		93%
Low Fuel	1%	1%	1%	1%	96%
Squares Not Available	1%	1%	1%	1%	96%
Mechanical Problems at Yard	5%	2%	2%	2%	89%
Mechanical Problems with ARMOR 1	5%	1%	1%	1%	92%
Mechanical Problems with Tow Vessel	5%	1%	1%	1%	92%
Not Enough Employees	10%	5%	5%	5%	75%
Riverbank Slope/Landscape not Complete	5%	5%	2%	1%	87%
River Currents/High Water Elevation	20%	10%	5%	2%	63%
River Low Water Elevation	10%	5%	2%	2%	81%
River Navigation Shut Down	5%	1%	1%	1%	92%
Unattended Barge	2%	1%	1%	0%	97%
Wind	5%	1%	1%	1%	92%
Mission Priority Changes				2%	98%

Unit Conversion Factors

Multiply	By	To Obtain
cubic feet	0.02831685	cubic meters
cubic inches	1.6387064 E-05	cubic meters
cubic yards	0.7645549	cubic meters
feet	0.3048	meters
horsepower (550 foot-pounds force per second)	745.6999	watts
inches	0.0254	meters
knots	0.5144444	meters per second
miles (nautical)	1,852	meters
miles (US statute)	1,609.347	meters
miles per hour	0.44704	meters per second
pounds (force)	4.448222	newtons
square feet	0.09290304	square meters
square inches	6.4516 E-04	square meters
square miles	2.589998 E+06	square meters
tons (2,000 pounds, mass)	907.1847	kilograms
tons (2,000 pounds, mass) per square foot	9,764.856	kilograms per square meter
yards	0.9144	meters

Acronyms and Abbreviations

ACM	Articulated Concrete Mat
AOR	Area of Responsibility
ERDC	US Army Engineer Research and Development Center
LWRP	Low Water Reference Plane
MPH	Memphis
MSU	Mat Sinking Unit
MV	Motor Vessel
MVD	Mississippi Valley Division
MVK	US Army Corps of Engineers, Vicksburg District
MVM	US Army Corps of Engineers, Memphis District
USACE	US Army Corps of Engineers
VKS	Vicksburg

Glossary

chance: Possibility or probability of a given outcome in a situation that is uncertain. See also *Probability*.

critical risk: Any risk that may endanger the project from completion.

delay: A duration in time that would be added to a schedule should a risk event occur.

duration: The amount of time associated with completing an activity, task, or element of work in a given schedule.

failure: Exceedance of a defined performance threshold or performance indicator.

mat: Sewn-together squares.

mat yard: Locations for fabrication of concrete squares.

mean duration: The average of a set of numbers, or the average of the probabilistic outcomes of durations from a Monte Carlo analysis.

mobilization: The process of communication of the warning trigger (action) level to the deployment team and the transportation of all resources required for the commencement of erection or closure operations.

Monte Carlo analysis: A simulation-driven, iterative statistical analysis of possible outcomes that generates a curve to reflect the likelihood of given time and cost parameters based on the outcomes of multiple iterations.

probability: A mathematical expression of the possibility or likelihood of occurrence, normally expressed as a percentage.

performance: The creation or achievement of something that can be valued against some stated initial aim or objective.

risk: Any event that may cause a delay in construction. Expressed as a written summary of the event, its implications, and impacts.

square: The 4 ft × 25 ft × 3 in. concrete cast with 16 linked blocks cast in repetitive courses with the final as a thirteenth course

stack: 13 squares.

trigger: An indicator of the imminent occurrence of a given risk event that serves as an immediate precursor to the occurrence of the risk.

REPORT DOCUMENTATION PAGE

Form Approved
OMB No. 0704-0188

The public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports (0704-0188), 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.
PLEASE DO NOT RETURN YOUR FORM TO THE ABOVE ADDRESS.

1. REPORT DATE September 2021		2. REPORT TYPE Final Report		3. DATES COVERED (From - To)	
4. TITLE AND SUBTITLE Mat Sinking Unit Supply Study: Mississippi River Revetment				5a. CONTRACT NUMBER	
				5b. GRANT NUMBER	
				5c. PROGRAM ELEMENT NUMBER	
6. AUTHOR(S) Julie A. Hicks, Laurin I. Yates, and Jacqueline S. Pettway				5d. PROJECT NUMBER	
				5e. TASK NUMBER	
				5f. WORK UNIT NUMBER	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) (see reverse)				8. PERFORMING ORGANIZATION REPORT NUMBER ERDC TR-21-13	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) USACE, Vicksburg District Vicksburg, MS 39180-3435				10. SPONSOR/MONITOR'S ACRONYM(S) USACE MVK	
				11. SPONSOR/MONITOR'S REPORT NUMBER(S)	
12. DISTRIBUTION/AVAILABILITY STATEMENT Approved for public release; distribution is unlimited.					
13. SUPPLEMENTARY NOTES MIPR W807PM91017173; USACE Vicksburg District					
14. ABSTRACT The Mississippi Valley Division (MVD) has maintained the Mississippi River banks for over 80 years. The Mat Sinking Unit (MSU), built in 1946, was considered state-of-the-art at the time. This system is still in operation today and has placed over 1,000 miles of Articulated Concrete Mats along the Mississippi River from Head of Passes, LA, to Cairo, IL. A new MSU has been designed and is expected to be fully mission capable and operational by the 2023 season, which is expected to increase the productivity from 2,000 squares/day up to 8,000 squares/day with double shifts and optimal conditions. This MSU supply study identifies and optimizes the supply chain logistics for increased production rates from the mat fields to the MSU. The production rates investigated for this effort are 2,000 squares/day, 4,000 squares/day, and 6,000 squares/day. RiskyProject® software, which utilizes a Monte Carlo method to determine a range of durations, manpower, and supplies based on logical sequencing is used for this study. The study identifies several potential supply and demand issues with the increased daily production rates. Distance to casting fields, number of barges, and square availability are the major issues to supply increased placement rates identified by this study.					
15. SUBJECT TERMS Concrete construction, Embankments—Mississippi River, Flood control—Mississippi River, Hydraulic engineering, Logistics, Revetments, River engineering, Shore protection—Mississippi River					
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT SAR	18. NUMBER OF PAGES 115	19a. NAME OF RESPONSIBLE PERSON Jacqueline S. Pettway
a. REPORT Unclassified	b. ABSTRACT Unclassified	c. THIS PAGE Unclassified			19b. TELEPHONE NUMBER (Include area code) 601-634-2288

7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) (continued)

Geotechnical and Structures Laboratory
US Army Engineer Research and Development Center
3909 Halls Ferry Road
Vicksburg, MS 39180-6199

Coastal and Hydraulics Laboratory
US Army Engineer Research and Development Center
3909 Halls Ferry Road
Vicksburg, MS 39180-6199

Information Technology Laboratory
US Army Engineer Research and Development Center
3909 Halls Ferry Road
Vicksburg, MS 39180-6199